

JULY 17, 2015 AS SHOWN 14009.01

AREA. ALL EROSION CONTROL MEASURES SHALL REMAIN INSTALLED AND MAINTAINED DURING ANY INACTIVE PERIOD.

SPECIFICATION 68-2.02F(3)

6" PVC RECTORSEAL

BACKWATER VALVE, OR

EQUIVALENT (HYDROMODIFICATION

─ 6" MIN. DIA. SOLID PVC PIPE

<u>FL PER PLAN</u>

(PERFORATIONS DOWN) WRAPPED IN OUTLET CONTROL STRUCTURE),

HYDROMODIFICATION BIORETENTION PLANTER

TYPICAL SECTION

NO SCALE

6" MIN. DIA. PERFORATED PIPE -

BENCH MARK

BRASS DISK STAMPED "JM 154 1969" LOCATED 3.09 MILES EAST ALONG OTAY MESA ROAD FROM INTERSECTION OF OTAY VALLEY ROAD, 20.5' SOUTH OF CENTERLINE OF OTAY MESA ROAD AND ABOUT 170' EAST OF CENTERLINE INTERSECTION OF HARVEST ROAD. STEEL FENCEPOST MARKER LIES 1' SOUTH OF DISK. RECORD FROM COUNTY OF SAN DIEGO VERTICAL CONTROL RECORD. ELEVATION: 541.10 DATUM: U.S.C.& G.S., M.S.L.

- . THIS PLAN IS PROVIDED TO ALLOW FOR FULL AND ADEQUATE DISCRETIONARY REVIEW OF A PROPOSED
- 3. A CONSTRUCTION, EXCAVATION OR ENCROACHMENT PERMIT FROM THE DIRECTOR OF PUBLIC WORKS WILL BE
- 4. ALL SLOPES OVER 3 FEET IN HEIGHT SHALL BE PLANTED IN ACCORDANCE WITH SAN DIEGO COUNTY SPECIFICATIONS.
- . THE DIRECTOR OF PUBLIC WORKS APPROVAL OF THESE PLANS DOES NOT CONSTITUTE COUNTY BUILDING OFFICIAL
- APPROVAL OF ANY FOUNDATIONS FOR STRUCTURES TO BE PLACED ON THE AREA COVERED BY THESE PLANS. NO WAIVER OF THE GRADING ORDINANCE REQUIREMENTS CONCERNING MINIMUM COVER OVER EXPANSIVE SOILS IS MADE OR IMPLIED (SECTIONS 87.403 & 87.410). ANY SUCH WAIVER MUST BE OBTAINED FROM THE DIRECTOR OF DPLU. 8. ALL SLOPES SHALL BE ROUNDED INTO EXISTING TERRAIN TO PRODUCE A CONTOURED TRANSITION FROM CUT OR FILL FACES TO NATURAL GROUND AND ABUTTING CUT OR FILL SURFACES.

A SEPARATE PERMIT MUST BE OBTAINED FOR WASTE OR IMPORT AREA. GRADING QUANTITIES ARE APPROXIMATE AND ARE PROVIDED HEREON FOR PERMIT PURPOSES ONLY. QUANTITIES ARE BASED ON THE DIFFERENCE BETWEEN THE EXISTING SURFACES AND PROPOSED PAD/SUBGRADE SURFACES. VARIATIONS DUE TO LOSS FROM CLEARING AND GRUBBING, STRIPPING, SHRINKAGE, SWELL, UNSUITABLE MATERIAL & REMEDIAL GRADING ARE NOT CONSIDERED NOR FACTORED INTO THESE QUANTITIES. CONTRACTOR SHALL VERIFY QUANTITIES WITH THEIR OWN VOLUME CALCULATIONS. CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THEIR OWN INDEPENDENT QUANTITY AND MATERIAL TAKE OFFS AND CONSTRUCT THE DESIGN INDICATED ON THESE DRAWINGS, PROJECT TO BE BID BASED

13. SPECIAL CONDITION: IF ANY ARCHAEOLOGICAL RESOURCES ARE DISCOVERED ON THE SITE OF THIS GRADING DURING GRADING OPERATIONS, SUCH OPERATIONS WILL CEASE IMMEDIATELY, AND THE PERMITTEE WILL NOTIFY THE DIRECTOR OF PUBLIC WORKS OF THE DISCOVERY. GRADING OPERATIONS WILL NOT RECOMMENCE UNTIL THE PERMITTEE HAS RECEIVED WRITTEN AUTHORITY FROM THE DIRECTOR OF PUBLIC WORKS TO DO SO.

ON CONTRACTOR'S OWN ESTIMATES.