FOODSERVICE EQUIPMENT SCHEDULE

MK.	QTY	DESCRIPTION	ELECTRICAL							WATER		WASTE		GAS		REMARKS	
			FLAMPS	KW	HP	VOLTS	PHASE	DIRECT	PLUG	COLD	HOT	DIRECT	INDIRECT	SIZE	KBTUH		STATUS
1	1	MOP AND BROOM RACK															
2	1	JANITORIAL WALL SHELF															
3	1	MOP SINK AND FAUCET								1/2"	1/2"	2"				NON-POROUS W./VACUUM BREAKER FAUCET	
4	1	WATER HEATER								3/4"				1/2"	50.0	AO SMITH BT-65, 80 GA. CAPACITY OR EQUAL PROVIDED AND INSTALLED BY PLUMBER	
5	1	BAG IN THE BOX														PROVIDED BY OTHER	
6	1	WATER FILTER															
7	1	ICE MAKER	20.0			120V	1		X	3/8"			1/2"			DRAINS TO FLOOR SINK	
8	1	ICE BIN											1 3/8"			DRAINS TO FLOOR SINK	
9	1L	LOCKERS															
10	1	REACH-IN REFRIGERATOR	9.0		1/2	120V	1		X							35/70 LBS CAPACITY, SELF-CONTAINED	
11	1	GATE															
12	1	GREASE TRAP														STAINLESS STEEL	
13	1	WALL SHELF														STAINLESS STEEL	
14	1	PREP TABLE WITH SINK											1 1/2"			STAINLESS STEEL, DRAINS TO FLOOR SINK, MEETS EHP-883	
15	1	FAUCET								1/2"	1/2"						
16	1	REACH-IN REFRIGERATOR	9.0		1/2	120V	1		X							SELF-CONTAINED	
17	1	REACH-IN FREEZER	9.0		1/2	120V	1		X							SELF-CONTAINED	
18	1	WORK TABLE														STAINLESS STEEL	
19	1	WALL SHELF														STAINLESS STEEL	
20	1	HAND SINK								1/2"	1/2"	1 1/2"				SOAP AND TOWEL DISPENSER PROVIDED BY GENERAL CONTRACTOR	
21	–	-SPARE NUMBER-															
22	–	-SPARE NUMBER-															
23	1	THREE COMPARTMENT SINK								1/2"	1/2"		1 1/2"			18"X18"X12" W/ 18"DRAINBOARD ON EACH SIDE AND A SPLASH, MEETS EHP-883, DRAINS TO FLOOR SINK	
24	1	FAUCET WITH PRE-RINSE								1/2"	1/2"						
25	2	WALL SHELF														STAINLESS STEEL	
26	1L	DRY STORAGE SHELVING														WIRE-TYPE	
27	1	COUNTER														CUSTOM MILLWORK	
28	1	ESPRESSO MACHINE	17.0			120V	1		X	1/4"			3/4"			DRAINS TO FLOOR SINK	
29	1	GRINDER	5.0			120V	1		X								
30	1	UNDERCOUNTERREFRIGERATOR	4.0		1/5	120V	1		X							SELF-CONTAINED	
31	3	CUP DISPENSERS															
32	1	WALL SHELF														CUSTOM MILLWORK	
33	1	COFFEE MAKER	15.0			120V	1		X	1/4"						SELF-CONTAINED	
34	1	JUICER	4.3			120V	1		X							SELF-CONTAINED	
35	2	MILK SHAKE MIXERS	10.0EA.			120V	1		X								
36	1	UNDERCOUNTER FREEZER	7.0		1/3	120V	1		X							SELF-CONTAINED	
37	1	EXHAUST HOOD W/ LIGHT	3.0			120V	1	X								U.L. LISTED, STAINLESS STEEL	
38	1	EXHAUST BLOWER			1.0	208V	3	X								VERIFY LOCATION ON ROOF	
39	1	MAKE-UP AIR SYSTEM			1/3	120V	1	X								VERIFY LOCATION ON ROOF	
40	1	FIRE PROTECTION				120V	1	X								KFC TO PROVIDE GAS SHUT-OFF VALVE, INSTALLED BY PLUMBER ELECTRICIAN TO PROVIDE MAGNETIC CONTACTOR	
41	–	-SPARE NUMEBER-															
42	–	-SPARE NUMBER-															
43	1	6 BURNER RANGE W/ OVEN	5.0		1/3	120V	1		X					3/4"	155.0		
44	1	WORK TABLE														STAINLESS STEEL	
45	1	FRYER												3/4"	90.0		
46	1	FRYER												3/4"	90.0		
47	1	GRIDDLE WITH STAND												3/4"	72.0		
48	1	WORK TABLE														STAINLESS STEEL	
49	1	GRIDDLE												3/4"	48.0		
50	1	WORK TABLE														STAINLESS STEEL	
51	–	-SPARE NUMBER-															
52	–	-SPARE NUMBER-															
53	1	GLASS DOOR MERCHANDISER	9.0		1/2	120V	1		X							SELF-CONTAINED	
54	1	CASH REGISTER	VER.			120V	1		X								
55	3	CUP DISPENSERS															
56	1	COUNTER														CUSTOM MILLWORK	
57	–	-SPARE NUMBER-															
58	1	SNEEZE GUARD														MEETS EHP-885	
59	1	HOT FOOD TABLE	19.2			208V	1		X				X			DRAINS TO FLOOR SINK	
60	1	PIZZA PREP TABLE	8.0		1/3	120V	1		X							SELF-CONTAINED	
61	1	CONTACT TOASTER	14.3			120V	1		X								
62	1	WATER FILLER FAUCET									1/2"					FOR ITEM# 59	
63	1	WORK TABLE														STAINLESS STEEL	
64	1	HAND SINK								1/2"	1/2"	1 1/2"				SOAP AND TOWEL DISPENSER PROVIDED BY GENERAL CONTRACTOR	
65	1	ICE/BEVERAGE DISPENSER	8.0			120V	1		X				X			SELF SERVICE, PUSH BOTTOM TYPE, DRAINS TO FLOOR SINK	
66	1	CARBONATOR	5.0			120V	1		X	1/2"			X			W. VACCUM BREAKER, RELIEF VALVE, DRAINS TO FLOOR SINK PROVIDED BY PURVEYOR	
67	1	COUNTER														CUSTOM MILLWORK	
68	1	DROP-IN COLD PAN											1"			DRAINS TO FLOOR SINK	
69	1	SELF-SERVE SNEEZE GUARD														MEETS EHP-885	
70	1	TRASH/TRAY UNIT															