
SAN DIEGO AREA

REGIONAL STANDARD DRAWINGS



STANDARD DRAWINGS FOR AGENCIES IN THE SAN DIEGO REGION

Recommended by the Regional Standards Committee
Maintained and Published by the San Diego County
Department of Public Works.
March, 1995

AMERICAN PUBLIC WORKS ASSOCIATION
ASSOCIATED GENERAL CONTRACTORS OF AMERICA
BUILDING INDUSTRY ASSOCIATION
CALIF. COUNCIL OF CIVIL ENGINEERS & LAND SURVEYORS
CARLSBAD, CITY OF
CHULA VISTA, CITY OF
CORONADO, CITY OF
DEL MAR, CITY OF
EL CAJON, CITY OF
ENCINITAS, CITY OF
ENGINEERING & GENERAL CONTRACTORS ASSOCIATION
ESCONDIDO, CITY OF
HELIX WATER DISTRICT
IMPERIAL BEACH, CITY OF
LA MESA, CITY OF
LEMON GROVE, CITY OF
NATIONAL CITY, CITY OF
OCEANSIDE, CITY OF
OTAY MUNICIPAL WATER DISTRICT
PACIFIC BELL COMPANY
POWAY, CITY OF
SAN DIEGO, CITY OF
SAN DIEGO, COUNTY OF
SAN DIEGO COUNTY ROCK PRODUCERS ASSOCIATION
SAN DIEGO GAS & ELECTRIC COMPANY
SAN MARCOS, CITY OF
SANTEE, CITY OF
SOLANA BEACH, CITY OF
VISTA, CITY OF

Regional Standards Committee

March 1995

These standard drawings have been adopted by the San Diego Regional Standards Committee for the benefit of all agencies in the San Diego area. The Regional Standards Committee membership is comprised of the County's sixteen cities, the County of San Diego, various representative districts and private industry organizations, the Pacific Telephone Company and the San Diego Gas and Electric Company as named above. The San Diego County Department of Public Works is currently providing coordination and staff support for the Regional Standards Committee.

REVISIONS

The Regional Standards Committee will continuously accept proposed revisions and/or proposed new standard drawings for review. They should be submitted to the Regional Standards staff at the Department of Public Works, County of San Diego, 5555 Overland Avenue, San Diego, California 92123, Attention Omar Moheize. Should the proposed revision be very minor in nature, i.e., a grammatical error, etc., the staff will make the necessary change without taking it to the Regional Standards Committee. Once enough proposals have been submitted to warrant a Regional Standards Committee meeting, the staff will prepare an agenda and schedule a meeting.

At the meeting the Committee will take one of three possible actions: approve the change, reject the change or recommend that a subcommittee further study the change and make recommendations to the Committee. The individual or organization who submitted the change will then be notified of the Committee action. After approval of the proposed change by the Regional Standards Committee, the staff will print and distribute the change to the governmental agencies within San Diego County.

It is intended that the standard drawing package will be reprinted and distributed periodically incorporating all the changes approved by the Regional Standards Committee since the last printing. The reprinting will take place when the Regional Standards Committee determines enough revisions have been approved to warrant issuance of an updated drawing package. It is further intended that the Regional Standards be accepted by all agencies at the earliest date possible.

Chairman, Regional Standards Committee

RSC

REVISION FOR REGIONAL STANDARDS

☐ SPECIFICATION ☐ DRAWING

DRAFT NO.

DATE

SUBMITTED BY:

NAME _____ PHONE _____

AGENCY _____

ADDRESS _____

SUBCOMMITTEE ACTION

ON _____

☐ RECOMMENDED ☐ AS MODIFIED ☐ REJECTED

REGIONAL COMMITTEE ACTION

ON _____

☐ RECOMMENDED ☐ AS MODIFIED ☐ REJECTED

TABLE OF CONTENTS

CONCRETE STRUCTURES

C-1 Masonry Retaining Wall Type 1 (Level Backfill)

C-2 Masonry Retaining Wall Type 2 (Live Load Surcharge or Sloping Backfill)

C-3 Masonry Retaining Wall Type 3 (Level Backfill)

C-4 Masonry Retaining Wall Type 4 (Live Load Surcharge or Sloping Backfill)

C-5 Masonry Retaining Wall Type 5 (Level Backfill)

C-6 Masonry Retaining Wall Type 6 (Live Load Surcharge or Sloping Backfill)

C-7 General Notes for Masonry Retaining Wall

C-8 Details for Masonry Retaining Wall

C-9 Gravity Retaining Walls

C-10 General Notes and Details for Gravity Retaining Walls

C-11 Reinforced Concrete Retaining Wall Type 1

C-12 Reinforced Concrete Retaining Wall Type 1A

C-13 Reinforced Concrete Retaining Wall Details No.1

C-14 Reinforced Concrete Retaining Wall Details No. 2

C-15 Reinforced Concrete Retaining Wall Details No. 3

DRAINAGE SYSTEMS

D-1 Curb Inlet - Type A

D-2 Curb Inlet - Type B

D-3 Curb Inlet - Type C

D-4 Curb Inlet - Type D

D-5 Curb Inlet - Type D (Details)

D-7 Catch Basin - Type F

D-8 Catch Basin - Type G

D-9 Storm Drain Cleanout - Type A

D-10 Storm Drain Cleanout - Type B

D-11 Inlets and Cleanouts - Notes and Details

D-12 Curb Inlet Opening

D-13 Welded Steel Grate Frame

D-15 Drainage Structure Grate

D-16 Corrugated Steel Pipe Inlets Types A & B

D-17 Corrugated Steel Pipe Inlets, Details

D-18 Slotted Corrugated Steel Pipe Drains 12" through 24"

D-19 Slotted Drain Connections to Standard Inlets

D-20 Concrete Apron for Curb Inlet

D-22 Asphalt Concrete Spillway

D-23 Tapered Inlet and Downdrain Flume

D-24 Entrance Taper and Downdrain Pipe

D-25 Curb Outlet - Type A

D-27 Sidewalk Underdrain Pipe

D-29 Catch Basin - Type I

TABLE OF CONTENTS

D-30 Straight Headwall - Type A (Circular Pipe)

D-31 Straight Headwall - Type A (CSP - Arch)

D-32 Straight Headwall - Type B (Circular Pipe)

D-33 Straight Headwall - Type B (CSP - Arch)

D-34 Wing and U Type Headwalls for 12" to 36" Pipe

D-35 Wing and U Type Headwalls for 42" to 84" Pipe

D-36 Type L Headwalls - Circular Pipe

D-37 L Type Headwalls - CSP Arch

D-38 Curtain Wall

D-39 Inlet Apron for Culverts Up to 42" Diameter

D-40 Rip Rap Energy Dissipator

D-41 Concrete Energy Dissipator

D-42 Concrete Energy Dissipator (Reinforcement) 18" to 30" Diameter Pipe

D-43 Concrete Energy Dissipator (Reinforcement) 36" to 72" Diameter Pipe

D-44 Pipe Culvert Headwalls, Endwalls and Warped Wingwalls

D-45 Curb Inlet - Type J Median

D-60 Pipe Bedding and Trench Backfill for Storm Drains

D-61 Rounded Pipe Ends in Drainage Structures

D-62 Pipe Collar

D-63 Concrete Lug

D-70 Minor Drainage Channel

D-71 Major Drainage Channel

D-72 Cutoff Wall for Drainage Channel

D-73 Pipe to Channel Connection

D-74 Graded Earth Channel

D-75 Drainage Ditches

D-76A Single Box Culvert, Details No. 1

D-76B Double Box Culvert, Details No. 2

D-77A Double Box Culvert, Details No. 1

D-77B Double Box Culvert, Details No. 2

D-78A Triple Box Culvert, Details No. 1

D-78B Triple Box Culvert, Details No. 2

D-79A Box Culvert Wingwall Types A, B and C, Details No. 1

D-79B Box Culvert Wingwall Types A, B and C, Details No. 2

D-80A Box Culvert Warped Wingwalls, Details No. 1

D-80B Box Culvert Warped Wingwalls, Details No. 2

D-81A Box Culvert, Miscellaneous Details No. 1

D-81B Box Culvert, Miscellaneous Details No. 2

D-82 Debris Fence

ELECTRICAL SYSTEMS

E-1 Street Lighting Standard

E-2 Grounding of Concrete Lighting Standards

E-33 Pedestal for Electrical Equipment

GENERAL SURFACE IMPROVEMENTS

G-1 Curbs and Gutters - Separate

G-2 Curbs and Gutters - Combined

G-3 Monolithic Curb, Gutter and Sidewalk

TABLE OF CONTENTS

G-4 Curb and Gutter - Rolled

G-5 Dikes - Asphalt Concrete

G-6 Curbs and Gutter - Medians

G-7 Sidewalk - Typical Sections

G-9 Sidewalk Joint Locations

G-10 Concrete Joint Details

G-11 Portland Cement Concrete Curb, Gutter, Sidewalk & Pavement Removal and Replacement

G-12 Cross Gutter

G-13 Mid-Block Cross Gutter

G-14A Concrete Driveways (Contiguous Sidewalk)

G-14B Concrete Driveways (Non-contiguous Sidewalk)

G-15 Driveway Location and Width Requirements

G-16 Driveway Location and Width Requirements

G-17 Alley Apron

G-18 Concrete Pavement, Width 40'or Less

G-19 Concrete Pavement, Width 40'to 62'

G-20 Concrete Pavement, Alley Section, Width 53' to 69'

G-21 Concrete Pavement, Alley Section, Width 40' or Less

G-22 Cutoff Wall at End of Pavement

G-23 Cutoff Wall at End of Alley Pavement

G-24 Trench Resurfacing, Types A and B

G-25 Trench Resurfacing, Types C and D

G-26 Concrete Driveway Commercial Alternate

G-27 Pedestrian Ramp Types A and B

G-28 Pedestrian Ramp Types A-1 and B-1 (For Existing Sidewalk)

G-29 Pedestrian Ramp, Type C (For Existing Sidewalk)

G-30 Pedestrian Ramp, Type C-1

G-31 Pedestrian Ramp, Type D

G-32 General Notes for Pedestrian Ramp

G-33 Narrow Trenching Types A & B, Backfill and Resurfacing

G-34 Narrow Trenching Types C & D, Backfill and Resurfacing

G-35 Narrow Trenching Types E & F, Backfill and Resurfacing

G-36 Slurry Backfill

SPRINKLER IRRIGATION SYSTEMS

I-1 Shrubbery Sprinkler Head, Fixed Spray Type

I-2 Sprinkler Head, Pop Up Spray Type

I-3 Lawn Sprinkler Head, Pop Up Rotary (With Swing Joint)

I-5 Quick Coupling valve

I-6 Hose Bibb (Garden Valve)

I-7 Backflow Preventer Atmospheric Vacuum Breaker (2" and Smaller)

I-8 Backflow Preventer Continuous Pressure Vacuum Breaker Assembly (2" and Smaller)

I-9 Backflow Preventer, Reduced Pressure Principle Assembly Larger Than 2"

I-12 Gate Valve (2" and Smaller)

I-13 Manual Valves

TABLE OF CONTENTS

I-14 Remote Control Valve

I-15 Electrical Pull Box for Direct Burial Control Wires and Splice Details

I-16 Direct Burial Control Wire

I-17 Irrigation System Electric Controller Clock Pedestal Mounting

I-18 Irrigation System Electric Controller Clock Wall Mounting

I-19 Impact Head - Above Ground Pipe Installation

I-20 Pinning of Pipe - Above Ground Pipe Installations

I-21 Manual Control Valve and Gate Valve Installation for Above Ground Pipe Installations

I-22 Quick Coupler Assembly - Above Ground Pipe Installations

I-23 Swing Joint and Pipe Installation on Slopes Above Ground Pipe Installations

I-24 Double Swing Joint - Above Ground Pipe Installations

I-25 Trench Detail P.V.C. and/or Copper Pipe (3" and Smaller)

I-26 Trench Detail - Asbestos Cement Pipe and 4" and Larger P.V.C.

I-27 Valve Well and Cover

I-28 Connection Detail for New Asbestos Cement Supply Mains

I-29 Connection Detail for Existing Supply Mains

I-30 Impact Head (With Swing Joint)

I-31 Backflow Preventer, Reduced Pressure Principle Assembly 2" and Smaller

I-32 Protective Guard Fence for Backflow Devices

I-33 Manifold Assembly, Remote Control Valve

I-34 Shrub Sprinkler Head, Rotor Type

LANDSCAPING

L-1 Tree and Shrub Planting

L-2 Tree Staking

L-3 Concrete Mowing Strip

L-4 Steel Grate Tree Well Cover

L-5 Light Pole Pad in Turf Areas

MISCELLANEOUS

M-1 24" Manhole Frame and Cover, Heavy Duty

M-2 24" Manhole Frame and Cover, Light Duty

M-3 36" Manhole Frame and Two Concentric Covers - Heavy Duty

M-4 Manhole Cover Locking Device

M-5 Chain Link Gate

M-6 Chain Link Fence

M-9 Guard Post and Barricade

M-10 Street Survey Monument

M-11 Bench Mark - Brass Plug

M-12 Datums

M-13 Survey Monuments

M-14 Metric Equivalents

M-15 Joint Trench Utilities Location

M-16 Demountable Post

M-17 Tennis Court Fence Chain Link

TABLE OF CONTENTS

M-18 Drinking Fountain

M-19 Fire Hydrant Markers

M-20 Chain Link Fence, Details

M-21 Underground Typical Location, Conversion/Replacement/Upgrade

M-22 Utility Locations in Local and Collector Streets

M-23 Utility Locations Prime Arterials and Expressways

M-24 Pedestrian Protective Railings, Details No. 1

M-25 Pedestrian Protective Railings, Details No. 2

M-26 Concrete Steps

M-27A Disabled Parking Stall(s)

M-27B Diagonal Disabled Parking Stall(s)

M-28A Disabled Parking Sign

M-28B Van Accessible Sign for Disabled Parking Space

M-29 Pavement Symbol, Disabled Parking

M-30 Guard Rail Standards

M-31 Metal Beam Guard Railing

M-32 Metal Beam Guard Railing, Hardware

M-33 Metal Beam Guard Railing, Posts and Blocks

M-34 Guard Rail Flares

M-35 Guard Rail Flares

M-36 Metal Beam Guard Railing Miscellaneous Details

M-37 Guard Rail End Anchors (Breakaway)

M-38 Guard Rail End Anchors (Breakaway Hardware)

M-39 Barrier and Guard Rail End Anchors

M-40 Guard Rail Connections to Bridge Rails, Retaining Walls and Abutments

M-41 Guard Rail Connection to Bridge Sidewalk and Curbs

M-42 Concrete Barrier Type 50

M-43 Concrete Barrier Type 50E

M-44 Temporary Railing (Type K)

SEWERAGE SYSTEMS

S-2 Manhole - 5'x 3' Diameter

S-3 Sewer Main Cleanout

S-4 Pipe Bedding and Trench Backfill for Sewers

S-6 Concrete Cradle

S-7 Concrete Easement

S-8 Concrete Backfill

S-9 Concrete Anchor

S-10 Cutoff Wall

S-11 Concrete Protection for Existing Sewer Pipe

S-12 Concrete Support for Undercut Sewer Pipe

S-13 House Connection (Sewer Lateral)

S-15 House Connection Sewer Repair

S-16 Cleanout - Force Main

S-17 Manhole - 4'x 3' Diameter (for 15" Maximum Diameter Pipe)

S-19 Metallic Tape Locator for Non-Metallic Sewer Pipe

TABLE OF CONTENTS

WATER SYSTEMS

W-1 1" Water Service

W-2 1 1/2" and 2" Water Services

W-3 1" and 2" Manual Air Releases

W-4 1" and 2" Air and Vacuum Valves

W-5 4" and 6" Air and Vacuum Valves

W-6 2" Blow-Off Assembly, Type A

W-7 2" Blow-Off Assemblies, Types B, C and D

W-8 4" and 6" Blow-Off Assemblies Type A

W-9 4" and 6" Blow-Off Assemblies Type B

W-10 Fire Hydrant with Check Valve

W-11 Fire Hydrant Locations

W-12A Valve Well Cover

W-12B Valve Well Frame and Assembly

W-13 Valve Stem Extension

W-14 Air and Vacuum Valve Enclosures

W-15 Meter Box Locations

W-16 Protection Post

W-17 Concrete Thrust Blocks

W-18 Thrust Block Bearing Areas

W-19 Concrete Valve Blocking

W-20 Anchor Block (Vertical Bend Only)

W-21 Pipe Bedding and Trench Backfill for Water Mains

W-22 Thrust Anchor for Water Main Reducer - 4" through 16"

W-23 Multiple Service Assembly Dead End Main

W-24 Split Butt Strap

W-25 Metallic Tape Locator for Non-Metallic Water Pipe

W-26 Backflow Preventer, Reduced Pressure Principle

APPENDIX A


Traffic Control Plans

INDEX


COUNTY OF S.D. DPW

DESIGN STANDARDS

CONCRETE STRUCTURES




PLAN



TYPICAL SECTION
over 5' - 4"

ELEVATION



TYPICAL SECTION
5' - 4" max

DIMENSIONS AND REINFORCING STEEL			
H (max)	3' - 8"	5' - 4"	8' - 0"
T (min)	0' - 8"	0' - 10"	1' - 0"
W (min)	2' - 4"	3' - 6"	5' - 4"
(A) bars	# 4 @ 32"	# 4 @ 32"	# 4 @ 32"
(B) bars	——	# 4 @ 32"	# 4 @ 32"
(C) bars	——	——	# 6 @ 16"
(E) bars	# 4 total 4	# 4 total 5	# 4 total 6
max soil press. (psf)	500	600	800

NOTES

1. See Standard Drawings C-7 and C-8 for additional notes and details.
2. Fill all block cells with grout.

Revision	By	Approved	Date
Title	[illegible]	M.B.	5-86
TITLE	RC	J.H.	7-88


SAN DIEGO REGIONAL STANDARD DRAWING

MASONRY RETAINING WALL TYPE 1
(LEVEL BACKFILL)


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A Kenkel — Dec. 1975
Coordinator R.C.E. 19807 — Date


DRAWING NUMBER **C-1**



PLAN




TYPICAL SECTION
over 3' - 8"



ELEVATION

Horizontal reinf. not shown



TYPICAL SECTION
3' - 8" max.

NOTES

1. See Standard Drawings C-7 and C-8 for additional notes and details.
2. Fill all block cells with grout.

DIMENSIONS AND REINFORCING STEEL		
H (max)	5' - 4"	3' - 8"
T (min)	0' - 10"	0' - 10"
W (min)	5' - 0"	3' - 9"
(A) bars	# 4 @ 16"	———
(B) bars	# 6 @ 16"	# 4 @ 16"
max. toe press. (psf)	700	550

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allen J. Kashani Dec. 1975
Coordinator R.C.E. 19807 Date

DRAWING NUMBER C-2


SAN DIEGO REGIONAL STANDARD DRAWING

MASONRY RETAINING WALL TYPE 2
(LIVE LOAD SURCHARGE OR SLOPING BACKFILL)


Revision	By	Approved	Date
REINST.	RC	A.H.	8-88




PLAN



TYPICAL SECTION
over 5' - 4"



ELEVATION



TYPICAL SECTION
5' - 4" max

NOTES

1. See Standard Drawings C-7 and C-8 for additional notes and details.
2. Fill all blockcells with grout.

DIMENSIONS AND REINFORCING STEEL			
H (max)	3' - 8"	5' - 4"	8' - 0"
T (min)	0' - 8"	0' - 10"	1' - 0"
W (min)	2' - 4"	3' - 2"	4' - 9"
(A) bars	# 4 @ 32"	# 4 @ 32"	# 4 @ 32"
(B) bars	——	# 4 @ 32"	# 4 @ 32"
(C) bars	——	——	# 6 @ 16"
(D) bars	# 4 @ 32"	# 4 @ 16"	# 6 @ 16"
(E) bars	# 4 total 4	# 4 total 5	# 4 total 6
max. soil press. (psf)	1100	1600	2200

Revision	By	Approved	Date
REINST.	JC	A.H.	8-88


SAN DIEGO REGIONAL STANDARD DRAWING

MASONRY RETAINING WALL TYPE 3
(LEVEL BACKFILL)


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A. Kashani — Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER C-3



PLAN



ELEVATION

Horizontal reinf. not shown

TYPICAL SECTION
over 3'-8"

TYPICAL SECTION
3'-8" max

NOTES
1. See Standard Drawings C-7 and C-8 for additional notes and details.
2. Fill all block cells with grout.

DIMENSIONS AND REINFORCING STEEL				
H (max)	5'-4"		3'-8"	
T (min)	0'-10"		0'-8"	
W (min)	4'-0"		3'-0"	
Ⓐ Bars	#4@16"		#4@16"	
Ⓑ Bars	#6@16"		—	
Surcharge	sloping	live load	sloping	live load
Ⓒ Bars	#6@8"	#6@16"	#6@16"	#6@16"
K (min)	1'-0"	0'-8"	1'-0"	0'-8"
Toe Press.	2700 psf	1900 psf	1700 psf	1430 psf

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Chairman R.C.E. 25902 Date 2-22-95

SAN DIEGO REGIONAL STANDARD DRAWING


MASONRY RETAINING WALL TYPE 4
(Live Load Surcharge or Sloping Backfill)

DRAWING NUMBER C-4

Revision	By	Approved	Date
Text	OM	A Mahiz	2-95



PLAN



TYPICAL SECTION
over 5'-4"

ELEVATION

Horizontal reinf. not shown

TYPICAL SECTION
3'-8" max

DIMENSIONS AND REINFORCING STEEL			
H (max)	3'-8"	5'-4"	8'-0"
T (min)	0'-8"	0'-10"	1'-0"
W (min)	2'-1"	3'-1"	4'-3"
R	0'-9"	1'-2"	1'-5"
S	0'-8 1/2"	1'-1/2"	1'-7 1/2"
K	0'-8"	0'-8"	1'-0"
Ⓐ Bars	#4@32"	#4@32"	#4@32"
Ⓑ Bars	——	#4@32"	#4@32"
Ⓒ Bars	——	——	#7@16"
Ⓓ Bars	#4@32"	#4@16"	#4@16"
Ⓔ Bars	#4 total 5	#4 total 5	#4 total 6
Max. Toe Press. (psf)	774	1,030	1,660

NOTES
1. See Standard Drawings C-7 and C-8 for additional notes and details.
2. Fill all block cells with grout.

Revision	By	Approved	Date
Text	DM	O. Mohsin	2-95


SAN DIEGO REGIONAL STANDARD DRAWING

MASONRY RETAINING WALL TYPE 5
(Level Backfill)


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Chairman R.C.E. 25902 Date 2-95

DRAWING NUMBER C-5



PLAN



ELEVATION

TYPICAL SECTION
over 3'-8"

TYPICAL SECTION
3'-8" max

DIMENSIONS AND REINFORCING STEEL		
H (max)	5'-4"	3'-8"
T (min)	0'-10"	0'-8"
W (min)	3'-10"	2'-9"
Ⓐ Bars	#4@16"	——
Ⓑ Bars	#6@16"	#4@16"
Max. Toe Press. (psf)	2,000	1,400

NOTES
1. See Standard Drawings C-7 and C-8 for additional notes and details.
2. Fill all block cells with grout.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Chairman R.C.E. 25902 Date 2-95

DRAWING NUMBER C-6

SAN DIEGO REGIONAL STANDARD DRAWING

MASONRY RETAINING WALL TYPE 6
(Live Load Surcharge or Sloping Backfill)

Revision	By	Approved	Date
Text	DPK	D. Mohrle	2-95

DESIGN CONDITIONS:

Walls are to be used for the loading conditions shown for each type wall. Design H shall not be exceeded.
Footing key is required except as shown otherwise or when found unnecessary by the Engineer.
Special footing design is required where foundation material is uncapable of supporting toe pressure listed in table.

DESIGN DATA:

Reinforced Concrete:

Fc = 1200 psi F'c = 3000 psi
Fs = 20,000 psi n = 10

Reinforced Masonry:

F'm = 600 psi Fm = 200 psi
Fs = 20,000 psi n = 50
Earth = 120 pcf and Equivalent Fluid Pressure = 36 psf per foot of height. Walls shown for 1½:1 unlimited sloping surcharge are designed in accordance with Rankline's formula for unlimited sloping surcharge with a $\emptyset = 33^\circ\ 42'$.

REINFORCEMENT:

Intermediate grade, hard grade, or rail steel deformation shall conform to ASTM A615, A616, A617. Bars shall lap 40 diameters, where spliced, unless otherwise shown on the plans. Bends shall conform to the Manual of Standard Practice, A.C.I. Backing for hooks is four diameters. All bar embedments are clear distances to outside of bar. Spacing for parallel bars is center to center of bars.

MASONRY:

All reinforced masonry retaining walls shall be constructed of regular or light weight standard units conforming to the "Standard Specifications for Public Works Construction."

JOINTS:

Vertical control joints shall be placed at 32 foot intervals maximum. Joints shall be designed to resist shear and other lateral forces while permitting longitudal movement. Vertical expansion joints shall be placed at 96 foot intervals maximum.

CONCRETE:

Footing concrete shall be 560-C-3250, using B aggregate when placing conditions permit.

BACKFILL:

No backfill material shall be placed against masonry retaining walls until grout has reached design strength or until grout has cured for a minimum of 28 days. Compaction of backfill material by jetting or ponding with water will not be permitted. Each layer of backfill shall be moistened as directed by the Engineer and thoroughly tamped, rolled or otherwise compacted until the relative compaction is not less than 90%.

FENCING:

Safety fencing shall be installed at the top of the wall as required by the agency.

INSPECTIONS:

Call for inspections as follows:

A. When the footing has been formed, with the steel tied securely in final position, and is ready for the concrete to be placed.

B. Where cleanout holes are not provided:

(1) After the blocks have been laid up to a height of 4', or full height for walls up to 5', with steel in place but before the grout is poured, and . . . . .

(2) After the first lift is properly grouted, the blocks have been laid up to the top of the wall with the steel tied securely in place but before the upper lift is grouted.

Where cleanout holes are provided:

After the blocks have been laid up to the top of the wall, with the steel tied securely in place, but before grouting.

C. After grouting is complete and after rock or rubble wall drains are in place but before earth backfill is placed.

D. Final inspection when all work has been completed.

CONCRETE GROUT AND MORTAR MIXES:

Concrete grout shall attain a minimum compressive strength of 2,000 psi in 28 days and mortar shall attain 1,800 psi in 28 days. All cells shall be filled with grout. Rod or vibrate grout within 10 minutes of pouring to insure consolidation. Bring grout to a point 2" from the top of masonry units when grouting of second lift is to be continued at another time.

MORTAR KEY:

To insure proper bonding between the footing and the first course of block, a mortar key shall be formed by embedding a flat 2 X 4 flush with and at the top of the freshly poured footing. The 2 X 4 should be removed after the concrete has started to harden (approximately 1 hour).
A mortar key may be omitted if the first course of block is set into the fresh concrete when the footing is poured, and a good bond is obtained.

WALL DRAINS:

Wall drains shall be provided in accordance with Standard Drawing C-8.

SOIL:

All footings shall extend at least 12 inches into undisturbed natural soil or approved compacted fill. Soil should be dampened prior to placing concrete in footings.

Revision	By	Approved	Date
New Des.	TRP	M.B.	10-82
Notes		M.B.	5-86
Notes	RC	A.H.	7-88


SAN DIEGO REGIONAL STANDARD DRAWING

GENERAL NOTES FOR MASONRY RETAINING WALLS


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A. Rowland — Dec. 1975
Coordinator R.C.E. 19807 — Date


DRAWING NUMBER C-7



TYPICAL SECTION



CAP DETAIL




KEY DETAIL


NOTES:

1. All masonry retaining walls shall be constructed with cap, key and drainage details as shown hereon.
2. 4" diameter drain may be formed by placing a block on it's side.


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Allen A Kershenbaum Dec. 1975 Coordinator R.C.E. 19807 Date	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
		Note 2	RC	A.H.	7/88
	DETAILS FOR MASONRY RETAINING WALL				
DRAWING NUMBER **C-8**					



TYPE–A WALL
(Applicable for all types of backfill loadings)




TYPE–B WALL



TYPE–C WALL

WALL TYPE	HEIGHT	BASE	CONC CF/FT
A	1' - 6"	1' - 0"	1.50
	2' - 0"	1' - 0"	2.00
B	3' - 0"	2' - 4"	4.99
	4' - 0"	2' - 10"	7.66
	5' - 0"	3' - 4"	10.82
	6' - 0"	3' - 10"	14.49
C	3' - 0"	1' - 6"	3.75
	4' - 0"	2' - 0"	6.00
	5' - 0"	2' - 6"	8.75
	6' - 0"	3' - 0"	12.00



TYPICAL ELEVATION

NOTE
See Standard Drawing C-10 for Section A–A, notes and details.

Revision	By	Approved	Date

SAN DIEGO REGIONAL STANDARD DRAWING

GRAVITY RETAINING WALLS

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A. Kershaw — Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER **C-9**

CONCRETE

Concrete shall be 560-C-3250.

DESIGN CONDITIONS

Walls are to be used for the loading conditions shown for each type wall. Design H may be exceeded by six inches before going to next size.

DESIGN DATA

Fc = 1200 psi F'c = 3000 psi
Earth = 120 pcf and equivalent fluid pressure = 36 psf per foot of height


Walls shown for 1 1/2:1 unlimited sloping surcharge are designed in accordance with Rankine's Formula for unlimited sloping surcharge with $\phi = 33°\ 42'$.
Note: Maximum toe pressure under wall footing = 1 1/2 tons. Special design required where footing material is incapable of supporting this pressure.

EXCAVATION AND BACKFILL


Compaction of backfill material by jetting or ponding with water will not be permitted.

Each layer of backfill shall be moistened as directed by the Engineer and thoroughly tamped, rolled or otherwise compacted until the relative compaction is not less than 90 percent.


No backfill material shall be deposited against concrete retaining walls until the concrete has developed a strength of 2,500 pounds per square inch in compression as determined by test cyclinders, or until 28 days after wall has been placed.



TYPICAL DRAINAGE
WHEN H IS GREATER THAN 4' - 0"





SECTION A–A



RUBBER WATERSTOP
Use only when watertight joint is required.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
Allan A Kashani Dec. 1975 Coordinator R.C.E. 19807 Date		Conc.	RC	M.B.	5-86
	GENERAL NOTES AND DETAILS FOR GRAVITY RETAINING WALLS				
DRAWING NUMBER C-10					





Note:
For details not shown and drainage notes see "Retaining Wall Details No. 1", drawing C-13.


Quantities apply to Design H portion and exclude the added portion above "Gutter Elevation."


TABLE OF REINFORCING STEEL DIMENSIONS AND DATA

Design H	@ 4'	6'	8'	10'	12'	14'	16'	18'	20'	22'	24'	26'	28'	30'
W	3'-2"	4'-2"	5'-2"	6'-2"	7'-2"	8'-0"	9'-0"	10'-0"	11'-0"	12'-0"	13'-3"	14'-3"	15'-3"	16'-9"
C	1'-0"	1'-4"	1'-8"	2'-0"	2'-4"	2'-8"	3'-0"	3'-4"	3'-8"	4'-0"	4'-5"	4'-9"	5'-1"	5'-5"
B	2'-2"	2'-10"	3'-6"	4'-2"	4'-10"	5'-4"	6'-0"	6'-8"	7'-4"	8'-0"	8'-10"	9'-6"	10'-2"	11'-4"
F Screed Pts.	1'-2"	1'-2"	1'-2"	1'-2"	1'-2"	1'-2"	1'-2"	1'-2"	1'-4"	1'-4"	1'-4"	1'-8"	1'-11"	2'-2"
Batter	Vg:12	Vg:12	Vg:12	Vg:12	Vg:12	Vg:12	Vg:12	Vg:12	Vg:12	Vg:12	3/16:12	3/16:12	3/16:12	3/16:12
(A) bars											#5@24	#6@17	#6@16	
(B) bars					#4@18	#6@30	#6@22	#7@22	#8@20	#8@16	#8@14	#8@12	#9@14½	#9@12
(C) bars	#5@24	#5@24	#5@16	#5@9	#6@9	#9@15	#9@11	#10@11	#11@9	#11@8	#11@7	#11@6	#11@5½	#11@5
(D) bars	#5@24	#5@24	#5@16	#4@9	#5@9	#8@15	#8@11	#10@11	#10@10	#10@8	#10@7	#10@6	#10@5½	#10@5
Total (E) bars	6-#5	6-#5	6-#5	10-#7	10-#7	10-#7	10-#7	6-#7	6-#7	6-#7	4-#7	4-#7	4-#7	4-#7
Total (F) bars				4-#7	4-#7	4-#7	4-#7	4-#7	4-#7	4-#7	2-#7	2-#7	2-#7	2-#7
2" Level Surcharge	Lbs Ft. wall	1.6	1.9	2.2	2.5	2.8	3.3	3.5	4.0	4.3	4.6	4.9	5.3	5.7	6.2
2:1 Sloping Surcharge	Lbs Ft. wall	1.1	1.5	2.0	2.5	2.7	3.3	3.6	4.2	4.7	5.5	5.9	6.5	7.1	7.5
1½:1 Sloping Surcharge	Lbs Ft. wall	1.3	1.7	2.1	2.5	2.9	3.4	3.8	4.3	4.8	5.4	5.8	6.5	7.2	7.5
Spread Footing	Steel lbs/ft	17	30	28	37	51	80	105	147	187	246	303	407	449	507
	Conc cf/ft	8.9	12.5	16.3	20.2	25.4	30.1	34.6	40.1	45.0	52.1	63.3	77.0	88.1	104.8
Pile Fig.	Steel lbs/ft	29	52	41	70	84	113	140	172	212	270	322	427	469	528
	Conc cf/ft	10.2	12.7	16.7	20.8	25.2	30.1	34.8	40.6	45.7	53.1	64.7	78.6	89.9	107.0

Note:
Reinforcement detailed is to be placed in addition to that shown for spread footing. All piles not shown, see Pile Layout on plans.

● For pile footing Design H=4' use same footing dimensions as Design H=6'





Revision	By	Approved	Date


SAN DIEGO REGIONAL STANDARD DRAWING

REINFORCED CONCRETE RETAINING WALL TYPE 1

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Coordinator R.C.E. 19667 — Dec. 1975 Date

DRAWING NUMBER C-11



SPREAD FOOTING SECTION

Place concrete in toe against undisturbed material, except as permitted by the Engineer.




DESIGN

For drainage notes and other details, see "Retaining Wall Details No 1," drawing C-13

Note:
Quantities apply to Design H portion and exclude the added portion above "Gutter Elevation."

TABLE OF REINFORCING STEEL DIMENSIONS AND DATA

Design H		⑧ 4'	6'	8'	10'	12'
W		3'-2"	4'-2"	5'-2"	6'-2"	7'-2"
C		1'-0"	1'-4"	1'-8"	2'-0"	2'-4"
B		2'-2"	2'-10"	3'-6"	4'-2"	4'-10"
ⓒ bars		#5 @ 24	#5 @ 22	#5 @ 11	#6 @ 9	#7 @ 7½
ⓓ bars		#5 @ 24	#5 @ 22	#5 @ 22	#7 @ 18	#8 @ 15
Total ⓔ bars		6 - #6	6 - #6	6 - #6	10 - #7	10 - #7
Total ⓕ bars					4 - #7	4 - #7
CASE I - Toe Press. psf		1590	1930	2240	2550	2840
CASE II - Toe Press. psf		1060	1460	1860	2280	2700
Spread Footing	Steel lbs/ft	15	21	27	46	70
	Conc CF/ft	8.6	11.8	14.9	18.1	21.3
Pile Ftg	Steel lbs/ft	25	32	38	75	101
	Conc CF/ft	9.9	11.9	15.3	18.8	22.2



ELEVATION

Note:
Reinforcement detailed is to be placed in addition to that shown for spread footing. All piles not shown, see Pile Layout on plans.

⑧ For pile footing Design H=4' use same footing dimensions as Design H=6'

NOTES

Design Conditions


Design H may be exceeded by 6" before going to the next size. Footing key is required except when found unnecessary by the Engineer. Special footing design is required where foundation material is incapable of supporting toe pressure loads listed in table.

Design Data


f_c = 1300 psi f'_c = 3250 psi f_s = 24,000 psi
n = 10 earth = 120 pcf

Case I Equivalent fluid pressure = 36 psf max for determination of toe pressure. 27 psf min for determination of heel pressure.

Case II - Earth pressure determined from Rankine's formula with ϕ = 33°-42'.



45T PILE FOOTING SECTION



Note:
Bar cut-offs may be varied in increments of 6".

TYPICAL LAYOUT EXAMPLE

For joints required, see Details 3-3 and 3-4, drawing C-15

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Coordinator R.C.E. 19807 — Date: Dec. 1975

DRAWING NUMBER **C-12**


SAN DIEGO REGIONAL STANDARD DRAWING

REINFORCED CONCRETE RETAINING WALL TYPE 1A


Revision	By	Approved	Date




20' VC AT TOP OF WALL SLOPE CHANGE
WHERE SHOWN ON THE PLANS




FOOTING STEP




DESIGN AND DRAINAGE



PLAN



PLAN




PLAN



PLAN


½" premolded expansion joint filler and waterstop as shown when required



ELEVATION

RETURN WALL TYPE 'A'


Use where H = 8' or less



ELEVATION

RETURN WALL TYPE 'B'


Use where H = 10' or more on offset walls



ELEVATION

RETURN WALL TYPE 'C'


Use where H = 10' or more on straight walls



ELEVATION


RETURN WALL TYPE 'D'

Use where H = 6' or less



PLAN OF WALL WITH DETAIL 3-4 (drawing C-15)

PLAN OF WALL WITH EXPANSION JOINT ONLY



APPROX. WALL OFFSET VALUES

Values for offsetting forms to be determined by the Engineer

NOTES:

Design Conditions:

Design H may be exceeded by 6" before going to the next size.
Footing key is required except when found unnecessary by the Engineer.
Special footing design is required where foundation material is incapable of supporting toe pressure loads listed in table.
Return wall not required unless shown elsewhere.

Design Data:

f'c = 1300 psi fc = 3250 psi fs = 24,000 psi n = 10 earth = 120 pcf
2' Surcharge:
Equivalent fluid pressure = 36 pcf max. for determination of toe pressure.
27 pcf min. for determination of heel pressure

Earth pressures for 2:1 unlimited slope, 1½:1 slope, and 1½:1 unlimited slope, determined from Rankine's formula with Ø = 33°-42'.

Revision	By	Approved	Date
Title	EC	M.B.	5-86


SAN DIEGO REGIONAL STANDARD DRAWING

REINFORCED CONCRETE RETAINING WALL DETAILS NO. 1

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allen A. Kershaw — Dec. 1975
Coordinator R.C.E. 19807 — Date

DRAWING NUMBER C-13




RETAINING WALL
FACE OF WALL OUTLET

RETAINING WALL
GUTTER OUTLET



OUTLET DETAIL–SECTION B-B




PLAN
OFFSET WALL


PLAN
CONTINUOUS WALL

DRAIN THROUGH RETURN WALL


SECTION A–A



WALL DRAIN DETAIL




TYPICAL GUTTER DETAIL



WALL DRAINAGE
WHERE GUTTER NOT REQUIRED



GRATE DETAIL
Sizes to fit Standard Hubs



RETAINING WALL–UTILITY OPENING
To be used in conjunction with the Retaining Wall Type 1" sheet
Max. size of Opening (A)=48"

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A Kruckeberg — Dec. 1975
Coordinator R.C.E. 19807 — Date

DRAWING NUMBER **C-14**

SAN DIEGO REGIONAL STANDARD DRAWING


REINFORCED CONCRETE RETAINING WALL DETAILS NO. 2


Revision	By	Approved	Date
Title		M.B.	5-80



WEEP HOLE AND PERVIOUS BACKFILL

DETAIL 3-1





WEAKENED PLANES

DETAIL 3-2


Notes:

A. 4"ϕ drains @ 25' max. center to center (9'c-c for Type 3 and 9'-3" c c for Type 4 Retaining Walls) For walls adjacent to sidewalks or curbs, provide 4" cast iron or asbestos cement pipe under the sidewalk to discharge thru curb face. Exposed wall drains shall be located 3"± above finished grade.

B. 6" square aluminum or galvanized steel wire 4 mesh hardware cloth (Min wire diameter 0.03") Anchor firmly to backface.


C. One cubic foot pervious backfill material in a burlap sack, securely tied.

D. Pervious backfill material continuous behind retaining wall.




WALL EXPANSION JOINTS AND WEAKENED PLANES

DETAIL 3-3



WALL EXPANSION JOINT

DETAIL 3-4



Waterstop to have 5 or more pairs of raised ribs to provide 0.1 sq. in. min. rib cross-section area on each half of the waterstop. Height of ribs to be 3/32" min.

Holes will be permitted in the outer 1/2" of the web for wire, rings, etc. Tie web to #3 reinforcing bars @ 12" max. intervals to support the waterstop in proper position during concrete placement. Alternative detail may be submitted for approval of the Engineer

WATERSTOP

DETAIL 3-6

Revision	By	Approved	Date
Title	SC	M.B.	5-86

SAN DIEGO REGIONAL STANDARD DRAWING

REINFORCED CONCRETE RETAINING WALL DETAILS NO. 3


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan O Kenkel Dec. 1975

Coordinator R.C.E. 19807 Date

DRAWING NUMBER C-15

DRAINAGE SYSTEMS






NOTES:

1. See Standard Drawings D-11 & D-12 for additional notes and details.
2. Types are designated as follows: (no wing) A, (one wing) A-1, (two wings) A-2.
3. Exposed edges of concrete shall be rounded with a radius of 1/2".
4. When V exceeds 4' steps shall be installed. See Standard Drawing D-11 for details.
5. Concrete gutter to match adjacent gutters.
6. An expansion joint shall be placed at the ends of the inlet where the curb is to adjoin.
7. Provide 1/4" tooled groove in top slab in line with back of adjacent curb.
8. Surface of top slab shall be sidewalk finished to drain toward street at a slope of 1/4" per foot.
9. Maintain 1 1/2" clear spacing between reinforcing and surface unless otherwise noted.

LEGEND ON PLANS
15' Type A-1 inlet



Revision	By	Approved	Date
Reference	TRP	M.B.	10-81
Rebar		M.B.	5-86


SAN DIEGO REGIONAL STANDARD DRAWING

CURB INLET - TYPE A

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Coordinator R.C.E. 19807 — Date: Dec. 1975

DRAWING NUMBER **D-1**




PLAN

SECTION B–B



SECTION C–C




SECTION A–A

NOTES:

1. See Standard Drawings D-11 & D-12 for additional notes and details.
2. Types are designated as follows: (no wing) B, (one wing) B-1, (two wings) B-2.
3. Exposed edges of concrete shall be rounded with a radius of 1/2".
4. When V exceeds 4' steps shall be installed. See Standard Drawing D-11 for details.
5. Concrete gutter to match adjacent gutters.
6. An expansion joint shall be placed at the ends of the inlet where the curb is to adjoin.
7. Provide 1/4" tooled groove in top slab in line with back of adjacent curb.
8. Surface of top slab shall be sidewalk finished to drain toward street at a slope of 1/4" per foot.
9. Maintain 1 1/2" clear spacing between reinforcing and surface unless otherwise noted.

LEGEND ON PLANS

15' Type B-1 inlet



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen A Kashani Dec. 1975


Coordinator R.C.E. 19807 Date

DRAWING NUMBER **D-2**

SAN DIEGO REGIONAL STANDARD DRAWING

CURB INLET - TYPE B

Revision	By	Approved	Date
Notes	[illegible]	D.S.	7-79
Reference	TRP	M.B.	10-82
Rebar	[illegible]	M.E.	5-86
Dash line	[illegible]	A.H.	7-88




NOTES:

1. See Standard Drawings D-11 through D-15 for additional notes and details.
2. Types are designated as follows: (no wing) C, (one wing) C-1, (two wings) C-2.
3. Exposed edges of concrete shall be rounded with a radius of 1/2".
4. When V exceeds 4 ft. steps shall be installed. See Standard Drawing D-11 for details.
5. Concrete gutter to match adjacent gutters.
6. An expansion joint shall be placed at the ends of the inlet where the curb is to adjoin.
7. Provide 1/4" tooled groove in top slab in line with back of adjacent curb.
8. Surface of top slab shall be sidewalk finished to drain toward street at a slope of 1/4" per foot.
9. Maintain 1 1/2" clear spacing between reinforcing and surface unless otherwise noted.
10. Where inlet is to be constructed on grade and Standard Drawing D-20 concrete apron is required, lift down-grade end of grate as shown on D-20.

LEGEND ON PLANS

15' Type C-1 Inlet



Revision	By	Approved	Date
Notes		D.S.	7-79
Reference	TRP	M.B.	10-82
Note 11		M.B.	5-86

SAN DIEGO REGIONAL STANDARD DRAWING

CURB INLET - TYPE C


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Coordinator R.C.E. 19807 — Date: Dec. 1975


DRAWING NUMBER D-3


DIMENSIONS

T = 8" if V is less than 8'.
T = 10" if V is 8' or more.
V = 5' unless otherwise specified.
V = D + 32" minimum.
W = 7' unless otherwise specified.
Y = 5' unless otherwise specified.
Width of driveway, W, shall be 10' unless otherwise specified.
Elevation of point N shall be 13" below point H unless otherwise specified.



TOP SLAB REINFORCING PLAN






PT	A	B	C	D	E	F	G	H	K	M
F.C.	4½"	5¼"	6"	7½"	9"	9"	9"	9"	9"	8"

TABLE A

NOTES

1. Steel Plate should be of one continuous piece with curve portion a circular arc. Length = Width + 18" + circular arc.
2. # 4 rebar 30" long, 1' O.C. shall be installed in top of walls for ties to top and gutters.
3. The reinforcing steel in the top slab shall be # 3 bars 6" O.C. unless otherwise specified. Clearance shall be 1 1/2" from the bottom of the slab.
4. Concrete for the inlet top to be placed at the same time as the s/w curb and gutter.
5. Concrete shall be 560-C-3250
6. Exposed edges of concrete shall be rounded with a radius of 1/2".
7. Surface of top slab shall be sidewalk finished to drain toward street at a slope of 1/4" per foot.



SECTION A–A

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allen A Kenkel — Dec. 1975
Coordinator R.C.E. 19807 — Date

DRAWING NUMBER **D-4**

SAN DIEGO REGIONAL STANDARD DRAWING

CURB INLET - TYPE D


Revision	By	Approved	Date
Conc.		M.B.	5-86



DETAIL–A

NOTES

1. A plain, round steel protection bar 1" in dia. shall be installed. Bar shall be embedded 5" at each end.
2. Leave 8" hole blocked out in bottom placing of concrete for bolts placed at same time as gutter.
3. All exposed metal parts shall be galvanized.
4. All galvanizing damaged by welding shall receive two coats of aluminum paint.
5. Support bolts shall be spaced at not more than 5' - 0" O.C.
6. Adjusting nuts to be tightened and secured in place when steel plate is in proper position.



SECTION B–B

SECTION A–A MODIFIED

Revision	By	Approved	Date
Rebar	TRM	M.B.	10-82
Lap	TRM	M.B.	5-86


SAN DIEGO REGIONAL STANDARD DRAWING

CURB INLET - TYPE D (DETAILS)

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A. Kashani Dec. 1975
Coordinator R.C.E. 19807 Date

DRAWING NUMBER D-5



SECTION A–A

SECTION B–B




PLAN

NOTES

1. See Standard Drawing D-11 for additional notes and details.
2. When V exceeds 4' steps shall be installed. See Standard Drawing D-11 for details.
3. Exposed edges of concrete shall be rounded with a radius of 1/2".
4. Openings on both sides unless otherwise shown on plans.
5. Maintain 1 1/2" clear spacing between reinforcing and surface.

LEGEND ON PLANS



Revision	By	Approved	Date
Rebar	TRF	M.B.	10-82
Lap		M.B.	5-96


SAN DIEGO REGIONAL STANDARD DRAWING

CATCH BASIN - TYPE F

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Coordinator R.C.E. 19807 — Date: Dec. 1975


DRAWING NUMBER D-7



ELEVATION

NOTES

1. See Standard Drawing D-11 for additional notes and details.
2. When V exceeds 4', steps shall be installed. See Standard Drawing D-11 for details.
3. Maintain 1 1/2" clear spacing between reinforcing and surface.
4. Increase in allowable depth subject to approval by Agency.
5. Section A–A shows 3 sizes and shall not imply that an interior wall is to be built for the structures with double or triple frame and grate.
6. Exposed edges of concrete shall be rounded with a radius of 1/2".
7. Designate types as follows: Single G-1, Double G-2 and Triple G-3.
8. Only end bearing grates shall be used. See Std. Drawing D-15.



SECTION A–A

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Coordinator R.C.E. 19807 — Date: Dec. 1975

DRAWING NUMBER D-8

SAN DIEGO REGIONAL STANDARD DRAWING


CATCH BASIN - TYPE G

Revision	By	Approved	Date
Reference	TRP	M.B.	10-82
Lap	RC	M.B.	5-86



PLAN

TYPE	PIPE DIA	X	Y	Z
A 4	up to 39"	4'	4'	6'
A 5	42" to 48"	5'	4'	6'
A 6	51" to 60"	6'	4'	6'
A 7	63" to 72"	7'	4'	7'
A 8	75" to 84"	8'	4'	8'




SECTION A–A

NOTES

1. See Standard Drawing D-11 for additional notes and details.
2. Concrete base shall be 560-C-3250
3. All precast components shall be reinforced with 1/4" diameter steel, wound spirally on 4" centers.
4. All joints shall be set in Class C mortar.
5. Maintain 1 1/2" clear spacing between reinforcing and surface unless otherwise noted.
6. Exposed edges of concrete shall be rounded with a radius of 1/2".

LEGEND ON PLANS



Revision	By	Approved	Date
Lap	[illegible]	M.B.	5-86


SAN DIEGO REGIONAL STANDARD DRAWING

STORM DRAIN CLEANOUT - TYPE A

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan O Kashmark — Coordinator R.C.E. 19807 — Dec. 1975 — Date

DRAWING NUMBER **D-9**



PLAN

TYPE	PIPE DIA	X	Y	Z
B 5	up to 51"	4'	5'	5'
B 6	54" to 60"	4'	6'	6'
B 7	63" to 69"	4'	7'	7'
B 8	72" to 81"	4'	8'	8'
B 9	84" to 90"	4'	9'	9'




SECTION A–A

NOTES

1. See Standard Drawing D-11 for additional notes and details.
2. All joints shall be set in Class C mortar.
3. All precast components shall be reinforced with 1/4" diameter steel wound spirally on 4" centers.
4. Maintain 1 1/2" clear spacing between reinforcing and surface.
5. Concrete base shall be 560-C-3250.
6. Exposed edges of concrete shall be rounded with a radius of 1/2".
7. Manhole cover to be designated "Storm Drain".

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allen A. Kashani — Dec. 1975
Coordinator R.C.E. 19807 — Date

DRAWING NUMBER **D-10**


SAN DIEGO REGIONAL STANDARD DRAWING

STORM DRAIN CLEANOUT - TYPE B

Revision	By	Approved	Date
Lap	[illegible]	[illegible]	5-86
Note 7	JM	[illegible]	5-92



TYPICAL BOX SECTION



STEP DETAIL

BOX SECTION REINFORCEMENT			
MAXIMUM SPAN X or Y	DEPTH V	THICK-NESS T	HOR. & FLR. REINF.
3' - 0" to 4' - 0"	4' - 0"	6"	# 4 @ 18"
4' - 1" to 7' - 0"		6"	# 4 @ 12"
7' - 1" to 8' - 0"		6"	# 4 @ 8"
3' - 0" to 4' - 0"	4' - 1" to 8' - 0"	6"	# 4 @ 18"
4' - 1" to 5' - 0"		6"	# 4 @ 12"
5' - 1" to 6' - 0"		6"	# 4 @ 8"
6' - 1" to 8' - 0"		6"	# 4 @ 6"
3' - 0" to 4' - 0"	8' - 1" to 12' - 0"	6"	# 4 @ 15"
4' - 1" to 5' - 0"		8"	# 4 @ 12"
5' - 1" to 6' - 0"		8"	# 4 @ 8"
6' - 1" to 8' - 0"		8"	# 4 @ 6"
3' - 0" to 4' - 0"	12' - 1" to 16' - 0"	6"	# 4 @ 12"
4' - 1" to 5' - 0"		8"	# 4 @ 12"
5' - 1" to 6' - 0"		8"	# 4 @ 8"
6' - 1" to 7' - 0"		8"	# 4 @ 6"
7' - 1" to 8' - 0"		8"	# 5 @ 8"
3' - 0" to 4' - 0"	16' - 1" to 20' - 0"	8"	# 4 @ 12"
4' - 1" to 5' - 0"		10"	# 4 @ 12"
5' - 1" to 6' - 0"		10"	# 4 @ 8"
6' - 1" to 7' - 0"		10"	# 4 @ 6"
7' - 1" to 8' - 0"		10"	# 5 @ 8"
3' - 0" to 4' - 0"	20' - 1" to 24' - 0"	8"	# 4 @ 12"
4' - 1" to 5' - 0"		10"	# 4 @ 12"
5' - 1" to 6' - 0"		10"	# 4 @ 8"
6' - 1" to 7' - 0"		10"	# 4 @ 6"
7' - 1" to 8' - 0"		12"	# 5 @ 8"

NOTES

1. Concrete shall be 560-C-3250 unless otherwise noted.
2. Reinforcing steel shall comply with this drawing unless otherwise specified.
3. Reinforcing steel shall be intermediate grade deformed bars conforming to latest ASTM specifications.
4. Bends shall be in accordance with latest ACI code.
5. Minimum splice length for reinforcing shall be 30 diameters.
6. Floor shall have a wood trowel finish and, except where used as junction boxes, shall have a minimum slope of 1" per foot toward the outlet.
7. Depth V is measured from the top of the structure to the flowline of the box.
8. Wall thickness and reinforcing steel required may be decreased in accordance with table above.
9. Wall thickness shall be stepped on the outside of the box.
10. When the structure depth V exceeds 4', steps shall be cast into the wall at 15 inch intervals from 15" above floor to within 12 inches of top of structure. Where possible place steps in wall without pipe opening, otherwise over opening of smallest diameter.
11. Alternate step may be an approved steel reinforced polypropylene step.

Revision	By	Approved	Date
Notes	JC	D.S.	7-79
Conc.	JC	M.R.	5-86


SAN DIEGO REGIONAL STANDARD DRAWING

INLETS AND CLEANOUTS NOTES AND DETAILS

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen O Kenkel — Dec. 1975
Coordinator R.C.E. 19807 — Date


DRAWING NUMBER **D-11**




NOTES:

1. Face angle shall be cast into structure continuous for the full length "L".
2. All exposed metal parts to be hot-dipped galvanized after fabrication.
3. When curb inlet opening height (H) exceeds 6" install 1" ϕ steel protection bar.
4. Install additional bars at 3 1/2" clear spacing above first bar when opening exceeds 13".
5. When curb inlet opening length exceeds 8' install 1" ϕ steel support bolts, spaced at not more than 5' o.c.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
Coordinator R.C.E. 19807 — Date: Dec. 1975		Angle	JC	D.S.	7-79
		Note 3	TRP	M.B.	10-82
	CURB INLET OPENING	Angle	TRP	M.B.	10-82
DRAWING NUMBER D-12					



PLAN



SECTION A–A

NOTES

1. Hot dip galvanize all parts after fabrication.

Revision	By	Approved	Date
Note 1	SC	M.B.	5-86

SAN DIEGO REGIONAL STANDARD DRAWING


WELDED STEEL GRATE FRAME

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allen A Kershaw — Coordinator R.C.E. 19807

Dec. 1975 — Date


DRAWING NUMBER **D-13**



PLAN



SECTION A



SECTION B

NOTES
1. Hot dip galvanize all parts after fabrication.
2. Dimensions to centerline of bars unless otherwise noted.
3. Weight: 141 pounds.
4. Not to be used in pedestrian areas.

NET OPENING : A = 3.6 SF

Revision	By	Approved	Date
Note #4	DH	D. Robins	2-95


SAN DIEGO REGIONAL STANDARD DRAWING

DRAINAGE STRUCTURE GRATE

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Chairman R.C.E. 25902 Date 2-95

DRAWING NUMBER D-15




SECTION A-A

TYPE A




SECTION C-C


TYPE B



DETAIL "A"



DETAIL "B"



SECTION F-F

NOTES

1. All components shall be galvanized.
2. Inlet and outlet pipes shall be set at factory and positioned as shown on plans.
3. Ladders and Steps: None required where "H" is 3'-6" or less. Where "H" is between 3'-6" and 4'-11" place one step +16" above the floor. If "H" is 5'-0" or more install a ladder placing the lowest rung 16" above the floor and the highest rung not more than 14" below top of inlet. Place single step or ladder in wall without wall opening.
4. See Standard Drawing D-17 for additional details.
5. Grate to be provided when specified.
6. Grate detail shall be as shown on drawing D-17 unless otherwise approved by Agency.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Coordinator R.C.E. 19807 — Dec. 1975 Date

SAN DIEGO REGIONAL STANDARD DRAWING


CORRUGATED STEEL PIPE INLETS TYPES A AND B

DRAWING NUMBER D-16


Revision	By	Approved	Date
Notes	sc	0.5	7-79



GRATE DETAILS




ALTERNATIVE CAST NODULAR IRON GRATE OR CAST STEEL



3/8"ø Cross bars may be fillet welded, resistance welded or electroforged to bearing bars.


CROSS BAR DETAIL
GRATE (WELDED STEEL)




CROSS BAR DETAIL
ALTERNATIVE CAST NODULAR IRON GRATE OR CAST STEEL GRATE


GRATE BAR SPACING TABLE


TYPE	NO. BARS	CLEAR BAR SPACING	X	y	
				4"SPACING	6"SPACING
welded	15	2	9/16	3 3/4"	5 3/4"
Cast	13	2	2 1/8	3 3/4	5 3/4





STEP DETAIL
H = 3' - 6" to 4' - 11"





LADDER DETAIL
H = 5' - 0" or GREATER

Revision	By	Approved	Date


SAN DIEGO REGIONAL STANDARD DRAWING

CORRUGATED STEEL PIPE INLETS DETAILS


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan O Kashani — Coordinator R.C.E. 19807 — Dec. 1975 Date


DRAWING NUMBER **D-17**




ELBOW




TEE




TEE–SAG CONDITION




OVERSIDE DRAIN



RISER




BAND PLUG




SECTION D–D


GRATE SLOT DETAIL




SECTION E–E



METAL CAP DETAIL



GRATE SLOT WELDING DETAIL



GRATE SLOT DRAIN

NOTES

1. Drain seams may be riveted or resistance spotwelded at equal centers, continuous helical lock seam or helical welded seam.
2. Each drain section shall be assembled with standard coupling bands.
3. Cross bar spacer of grate shall be pressure fusion or plug welded to bearing bars in such a manner as to develop the strength of the cross bar spacer.
4. Cross bar spacer (Section E–E) may differ from that shown provided section area is equal or greater.
5. Grate material shall be a weldable grade of steel complying to the requirements of ASTM A 36.
6. The maximum variance from a straight line from the extreme top corners of the bearing bar shall be 1/2" in 20 feet.
7. Installation lengths shall be 10 feet or multiples thereof.
8. Either field joint sealed with a pliable mixture of sand, portland cement and emulsified asphalt (Mixture of 1 part portland cement, 3 - 5 parts sand and 1 1/2 parts SSI emulsified asphalt), or continuous weld.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan O Kashani Dec. 1975
Coordinator R.C.E. 19807 Date

DRAWING NUMBER D-18

SAN DIEGO REGIONAL STANDARD DRAWING


SLOTTED CORRUGATED STEEL PIPE DRAIN 12" THROUGH 24"

Revision	By	Approved	Date
Sect. D-D	TRP	M.B.	10-82





SECTION A–A

CATCH BASIN




C.S.P. INLET





SECTION B–B



ALTERNATE SECTION B–B

INLETS

NOTES

1. Either field joint with a pliable mixture of sand, portland cement and emulsified asphalt (mixture of 1 part portland cement, 3 - 5 parts sand, and 1 1/2 parts SSI emulsified asphalt), or continuous weld.
2. See Standard Drawing D - 18 for additional notes and details.

Revision	By	Approved	Date

SAN DIEGO REGIONAL STANDARD DRAWING


SLOTTED DRAIN CONNECTIONS TO STANDARD INLETS

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A. Kashani — Dec. 1975

Coordinator R.C.E. 19807 — Date


DRAWING NUMBER **D-19**



PLAN



SECTION A–A




SECTION B–B

NOTES:

1. Curb and apron to be placed monolithically.
2. Use of false header at valleys and slope break line is optional.
3. Extend vertical steel from inlet structure into concrete apron as required.
4. Screed Direction ⟷
5. Concrete shall be 520-C-2500

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allen A Kershenbaum — Dec. 1975
Coordinator R.C.E. 19807 — Date

DRAWING NUMBER **D-20**


SAN DIEGO REGIONAL STANDARD DRAWING

CONCRETE APRON FOR CURB INLET


Revision	By	Approved	Date
Conc.	[illegible]	M.B.	5-86



PLAN




SECTION A–A



NOTE
Cross - sectional area of ditch may be rounded, or trapezoidal.

SECTION B–B




ALTERNATE SECTION B–B

NOTES

1. A.C. spillway may be used when fill is 10' or less, and where fill slope is 1 1/2:1 or flatter.
2. Use 10' min. length of gutter transition on each side of downdrain in sag condition.

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Coordinator R.C.E. 19807 — Date: Dec. 1975

DRAWING NUMBER D-22


SAN DIEGO REGIONAL STANDARD DRAWING

ASPHALT CONCRETE SPILLWAY


Revision	By	Approved	Date
Plan	C	D. S.	7-79




PLAN



TAPERED INLET



SECTION A–A



ANCHOR · DETAIL

NOTES

1. Downdrain flume may be used where fill slope is 1 1/2 : 1 or flatter.
2. Use 10' min length of gutter transition on each side of downdrain in sag location.
3. All metal parts to be galvanized after fabrication.

LEGEND ON PLANS



Revision	By	Approved	Date


SAN DIEGO REGIONAL STANDARD DRAWING

TAPERED INLET AND DOWNDRAIN FLUME


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Coordinator R.C.E. 19807 — Dec. 1975 Date


DRAWING NUMBER **D-23**



PLAN



SECTION A–A



Material to be ¼" plate galvanized after fabrication.


PLATE DETAIL

Dimensions to be as tabulated below for Assembly.

Dia	A	B	C	D	E	F	G	L
8"	16"	25 1/2"	15"	4 3/4"	5"	6"	18"	10'
12"	18"	25 1/2"	19"	3 3/4"	5"	9"	20"	15'
18"	24"	36"	26"	6"	6"	12"	24"	25'

NOTES

1. All metal parts for anchor assemblies shall be galvinized after fabrication.
2. One anchor assembly required per length of pipe. When final length exceeds 10 ft. two anchors shall be required.




Bulkhead and Taper of same thickness as Tail Pipe with 0.079" Max. Tail Pipe of same thickness as Downdrain Pipe.

ENTRANCE TAPER– TYPE 1 ALTERNATIVE A




Tail Pipe of same thickness as Downdrain Pipe.

ENTRANCE TAPER–TYPE 1 ALTERNATIVE B



Cables and Cable Clamps to be used when specified.

ANCHOR ASSEMBLY ALTERNATIVE–A



Cables and cable clamps to be used when specified.

ANCHOR ASSEMBLY ALTERNATIVE–B

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen A. Kashani Dec. 1975


Coordinator R.C.E. 19807 Date

DRAWING NUMBER **D-24**


SAN DIEGO REGIONAL STANDARD DRAWING

ENTRANCE TAPER AND DOWNDRAIN PIPE


Revision	By	Approved	Date




PLAN



SECTION A–A



SECTION B–B




ANCHOR DETAIL

NOTES

1. Concrete shall be 560-C-3250
2. D=inside diameter of pipe or depth of channel.
3. Section to be sloped laterally with top conforming to the grades of the existing sidewalk and curb.
4. Manhole frame and cover may be deleted with open channel.
5. Trowel finish top surface and reproduce markings of existing sidewalk and curb.
6. Trowel finish floor of outlet.

LEGEND ON PLANS



Revision	By	Approved	Date
Bar Size		D.S.	7-79
Conc.		M.B.	5-86
Slope		G.L.	5A2

SAN DIEGO REGIONAL STANDARD DRAWING


CURB OUTLET - TYPE A

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A Kenkel — Dec. 1975

Coordinator R.C.E. 19807 — Date


DRAWING NUMBER **D-25**



SECTION




SECTION B–B



SECTION A–A

APPROVED DRAIN PIPE SIZES	
3"	6" to 8" CURB FACE
4"	8" CURB FACE
6"	10" CURB FACE



Drain shall not occupy
the hatched area

BLOCK CORNER

NOTES

1. Pipe shall be one continuous length from property line to curb line.
2. Multiple pipes to be set a minimum distance of D/2 apart. (MIN. 2")
3. Concrete shall be 520-C-2500
4. Pipe shall be circular asbestos cement, cast iron or rigid plastic.

Revision	By	Approved	Date
Modif.	[illegible]	M.B.	5-86


SAN DIEGO REGIONAL STANDARD DRAWING

SIDEWALK UNDERDRAIN PIPE


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A Kenkel — Coordinator R.C.E. 19807 — Dec. 1975 Date


DRAWING NUMBER **D-27**



PLAN



SECTION A-A



SECTION B-B

NOTES

1. See Standard Drawing D-11 for additional notes and details.
2. When "V" exceeds 4', steps shall be installed.

LEGEND ON PLANS



Revision		Approved	Date
Reference	TRP	M.B.	10-82
Modif.		M.B.	5-86


SAN DIEGO REGIONAL STANDARD DRAWING

CATCH BASIN - TYPE I

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Coordinator R.C.E. 25291 — Date July 1979

DRAWING NUMBER D-29



ELEVATION DOUBLE HEADWALL

ELEVATION SINGLE HEADWALL




SECTION

D	H	SINGLE			DOUBLE		
		L	Steel Lbs.	Conc C. Y.	L	Steel Lbs.	Conc C. Y.
12"	2'-8"	5'-0"	35	0.60	8'-0"	50	0.94
15"	2'-11"	6'-0"	40	0.75	9'-6"	60	1.17
18"	3'-2"	7'-0"	50	0.91	10'-6"	75	1.35
21"	3'-5"	7'-6"	60	1.02	11'-6"	90	1.52
24"	3'-8"	8'-6"	75	1.20	12'-6"	100	1.72
27"	3'-11"	9'-6"	85	1.39	14'-0"	115	2.00
30"	4'-2"	10'-0"	85	1.52	15'-0"	126	2.21
33"	4'-5"	11'-0"	100	1.73	16'-0"	130	2.42
36"	4'-8"	12'-0"	105	1.95	17'-0"	145	2.65
39"	4'-11"	12'-6"	130	2.09	18'-0"	170	2.88
42"	5'-2"	13'-6"	140	2.34	19'-0"	185	3.13
45"	5'-5"	14'-6"	150	2.60	20'-0"	195	3.38
48"	5'-8"	15'-0"	160	2.75	21'-0"	200	3.64
51"	5'-11"	16'-0"	180	3.03	22'-6"	225	4.02
54"	6'-2"	17'-0"	190	3.31	23'-6"	240	4.30

NOTES

1. Concrete shall be 560-C-3250
2. All reinforcing steel # 4 bars. All vertical and horizontal tie bars 18" maximum spacing.

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allen A Kashani — Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER **D-30**

SAN DIEGO REGIONAL STANDARD DRAWING


STRAIGHT HEADWALL - TYPE A (CIRCULAR PIPE)

Revision	By	Approved	Date
Conc.	[illegible]	M.B.	5-86
Dim. lines	[illegible]	A.H.	7-88



ELEVATION DOUBLE HEADWALL

ELEVATION SINGLE HEADWALL




SECTION

C.S.P. ARCH SIZE	H	SINGLE			DOUBLE		
		L	Steel Lbs	Conc Cu. Yds.	L	Steel Lbs	Conc Cu. Yds.
18" x 11"	2'-7"	5'-6"	37	0.64	8'-0"	52	.91
21" x 15"	2'-11"	6'-6"	45	0.80	10'-0"	60	1.22
24" x 18"	3'-2"	7'-6"	50	0.96	11'-6"	70	1.45
28" x 20"	3'-4"	8'-6"	60	1.12	13'-6"	90	1.76
35" x 24"	3'-8"	10'-6"	85	1.47	15'-6"	120	2.16
42" x 29"	4'-1"	12'-6"	110	1.76	18'-0"	145	2.57
49" x 33"	4'-5"	14'-6"	130	2.26	21'-0"	170	3.13
57" x 38"	4'-10"	17'-0"	155	2.81	24'-6"	210	3.86
64" x 43"	5'-3"	19'-0"	175	3.31	27'-0"	230	4.42
71" x 47"	5'-7"	21'-0"	195	3.81	30'-0"	255	5.09

NOTES
1. Concrete shall be 560-C-3250
2. All reinforcing steel # 4 bars. All vertical and horizontal tie bars 18" maximum spacing.

LEGEND ON PLANS



Revision	By	Approved	Date
Conc.		M.B.	5-86


SAN DIEGO REGIONAL STANDARD DRAWING

STRAIGHT HEADWALL - TYPE A (C.S.P.-ARCH)


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Coordinator R.C.E. 19807 — Date: Dec. 1975


DRAWING NUMBER **D-31**



DOUBLE PIPE ELEVATION



SECTION A–A




SINGLE PIPE ELEVATION

D	A	B	H	SINGLE		DOUBLE	
				L	Conc C.Y.	L	Conc C.Y.
12"	2'-0"	1'-0"	4'-0"	4'-0"	.45	5'-8"	.62
15"	2'-0"	1'-1"	4'-3"	5'-0"	.63	7'-1"	.85
18"	2'-0"	1'-2"	4'-6"	6'-0"	.83	8'-6"	1.12
24"	2'-6"	1'-5"	5'-6"	8'-0"	1.54	11'-4"	2.09
30"	2'-6"	1'-9"	6'-0"	10'-0"	2.41	14'-2"	3.26
36"	3'-0"	2'-0"	7'-0"	12'-0"	3.74	17'-0"	5.05

NOTES

1. Concrete shall be 560-C-3250
2. Exposed corners to be chamfered 3/4".

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Coordinator H.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER **D-32**


SAN DIEGO REGIONAL STANDARD DRAWING

STRAIGHT HEADWALL - TYPE B (CIRCULAR PIPE)


Revision	By	Approved	Date
Conc.	[illegible]	M.B.	5-86



DOUBLE PIPE ELEVATION



SECTION A–A




SINGLE PIPE ELEVATION

C.S.P. ARCH SIZE	A	B	H	SINGLE		DOUBLE	
				L	Conc C.Y.	L	Conc C.Y.
18"x 11"	2'-0"	1'-2"	3'-11"	6'	0.83	7'-3"	0.97
21"x 15"	2'-0"	1'-4"	4'-1"	7'	1.08	9'-8"	1.46
24"x 18"	2'-0"	1'-6"	4'-4"	8'	1.41	11'-6"	1.98
28"x 20"	2'-6"	1'-8"	5'-0"	9'	1.97	12'-6"	2.66
35"x 24"	2'-6"	2'-0"	5'-4"	10'	2.56	14'-5"	3.60

NOTES

1. Concrete shall be 560-C-3250
2. Exposed corners to be chamfered 3/4".

LEGEND ON PLANS



Revision	By	Approved	Date
Conc.	[illegible]	M.B.	5-86


SAN DIEGO REGIONAL STANDARD DRAWING

STRAIGHT HEADWALL - TYPE B (C.S.P. ARCH)


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen A. Kershaw — Coordinator R.C.E. 19807 — Dec. 1975 Date


DRAWING NUMBER **D-33**




U TYPE PLAN WING TYPE




SECTION A–A



WING WALL REINFORCING



ELEVATION



SECTION B–B




ALT. DETAIL C

DIA OF PIPE	DIMENSIONS			SINGLE PIPE					DOUBLE PIPE				
					U TYPE		WING TYPE			U TYPE		WING TYPE	
	L	E	F	W	CONC C. Y.	STEEL LBS.	CONC C. Y.	STEEL LBS.	W	CONC C. Y.	STEEL LBS.	CONC C. Y.	STEEL LBS.
18"	2'-3 1/8"	1'-3"	1'-10 1/2"	2'-0"	0.55	35	0.63	43	As shown on plans	0.82	53	0.90	61
24"	3'-1 7/8"	1'-9"	2'-7 1/2"	2'-6"	0.79	47	0.93	60		1.22	73	1.36	86
30"	4'-0 5/8"	2'-3"	3'-4 1/2"	3'-0"	1.05	71	1.29	85		1.66	109	1.92	123
36"	4'-11 1/2"	2'-9"	4'-1 1/2"	3'-6"	1.33	88	1.69	114		2.19	136	2.55	162

NOTES:

1. Concrete shall be 560-C-3250
2. Exposed corners to be chamfered 3/4".
3. Multiple pipes to be set a distance of D/2, with a 1' minimum between outside diameters of pipes.
4. Top of headwall shall be placed approximately parallel to profile grade when the grade is 3% or more.
5. Skewed pipes: Dimension W to be increased in width or length due to skew or multiple pipes.
6. For pipe wall thickness greater than 3" use alternate Detail–C.

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A Kashuba Dec. 1975
Coordinator R.C.E. 19807 Date


DRAWING NUMBER **D-34**

SAN DIEGO REGIONAL STANDARD DRAWING


WING AND U TYPE HEADWALLS FOR 12" TO 36" PIPES

Revision	By	Approved	Date
Conc.	RC	M.B.	5-86







SECTION A–A




ELEVATION



SECTION B–B



WING WALL REINFORCING



ALT. DETAIL C


DIA. OF PIPE	DIMENSIONS			SINGLE PIPE					DOUBLE PIPE				
					U TYPE		WING TYPE			U TYPE		WING TYPE	
	L	E	F	W	CONC. C.Y.	STEEL LBS.	CONC. C.Y.	STEEL LBS.	W	CONC. C.Y.	STEEL LBS.	CONC. C.Y.	STEEL LBS.
42"	3'-7 1/4"	2'-0"	3'-0"	4'-0"	1.57	117	1.90	135	AS SHOWN ON PLANS	2.69	190	3.16	214
48"	4'-6"	2'-6"	3'-9"	4'-6"	1.97	153	2.48	184		3.43	252	4.06	288
54"	5'-4 7/8"	3'-0"	4'-6"	5'-0"	2.41	190	3.07	246		4.24	319	5.06	368
60"	6'-3 3/4"	3'-6"	5'-3"	5'-6"	2.88	239	3.75	294		5.13	386	6.17	442
66"	7'-2 1/2"	4'-0"	6'-0"	6'-0"	3.38	294	4.52	356		6.08	454	7.20	516
72"	8'-1 3/8"	4'-6"	6'-9"	6'-6"	3.93	368	5.52	417		7.11	522	8.30	588
78"	9'-0"	5'-0"	7'-6"	7'-0"	4.50	444	6.70	503		8.20	595	9.50	693
84"	9'-10 3/4"	5'-6"	8'-3"	7'-6"	5.21	540	8.15	619		9.50	687	10.80	786

Note: Dimensions E and L apply to wing type only.

NOTES

1. Skewed Pipes: Dimension W to be increased to take care of increased width or length due to skew of multiple pipes.
2. Tops of headwalls, on grade culverts, shall be placed parallel to profile grade when the grades are 3% or more.
3. Concrete shall be 560-C-3250
4. Exposed corners shall be chamfered 3/4".
5. Multiple pipes shall be set a distance of D/2, with a 1' minimum, between outside diameters of pipes.
6. For pipe wall thickness greater than 3" use Alternate Detail-C.

LEGEND ON PLANS



Revision	By	Approved	Date
Conc.	EC	M.B.	5-86


SAN DIEGO REGIONAL STANDARD DRAWING

WING AND U TYPE HEADWALLS FOR 42" TO 84" PIPES


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen A Kenkel — Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER **D-35**



ELEVATION SECTION




CORNER STEEL DETAIL

D	H	L/2	LENGTH OF W									
			3' - 4"		4' - 10"		6' - 4"		7' - 10"		9' - 4"	
			Steel lbs.	Conc C. Y.	Steel lbs.	Conc C. Y.	Steel lbs.	Conc C. Y.	Steel lbs.	Conc C. Y.	Steel lbs.	Conc C. Y.
12"	2' - 8"	2' - 6"	50	.79	60	.98						
15"	2' - 11"	3' - 0"	55	.91	65	1.11						
18"	3' - 2"	3' - 6"	65	1.04	75	1.25						
21"	3' - 5"	3' - 9"	75	1.15	90	1.36						
24"	3' - 8"	4' - 3"	85	1.29	100	1.51	110	1.74				
27"	3' - 11"	4' - 9"	90	1.44	105	1.67	115	1.91				
30"	4' - 2"	5' - 0"	95	1.55	110	1.80	120	2.05	135	2.29		
33"	4' - 5"	5' - 6"	105	1.71	120	1.97	135	2.23	150	2.48		
36"	4' - 8"	6' - 0"	110	1.88	125	2.15	140	2.41	155	2.68	170	2.95
39"	4' - 11"	6' - 3"			150	2.28	170	2.56	185	2.84	200	3.12
42"	5' - 2"	6' - 9"			155	2.42	175	2.76	190	3.05	210	3.34
45"	5' - 5"	7' - 3"					180	2.97	200	3.27	215	3.57
48"	5' - 8"	7' - 6"					190	3.13	216	3.44	230	3.75
51"	5' - 11"	8' - 0"							220	3.67	235	3.99
54"	6' - 2"	8' - 6"							235	3.91	250	4.24

NOTES

1. Concrete shall be 560-C-3250
2. All reinforcing steel # 4 bars. All vertical and horizontal tie bars 18" maximum spacing.
3. When multiple pipes are used, the distance between pipes shall be D/2 (1' min.). Dimension L/2 is from the center of the pipe nearest to the end of the headwall as shown.

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A Kenkel Dec. 1975
Coordinator R.C.E. 19807 Date

DRAWING NUMBER **D-36**


SAN DIEGO REGIONAL STANDARD DRAWING

L TYPE HEADWALLS CIRCULAR PIPES

Revision	By	Approved	Date
Conc.	RC	M.B.	5-86



ELEVATION



SECTION




CORNER STEEL DETAIL

C.S.P. ARCH SIZE	H	L/2	LENGTH OF W									
			3' - 4"		4' - 10"		6' - 4"		7' - 10"		9' - 4"	
			Steel lbs.	Conc C. Y.	Steel lbs.	Conc C. Y.	Steel lbs.	Conc C. Y.	Steel lbs.	Conc C. Y.	Steel lbs.	Conc C. Y.
18"x 11"	2'-7"	2'-9"	50	0.84	60	1.03	70	1.21	80	1.39	90	1.57
21"x 15"	2'-11"	3'-3"	60	1.00	65	1.18	75	1.38	90	1.58	100	1.77
24"x 18"	3'-2"	3'-9"	60	1.07	70	1.32	80	1.53	95	1.74	110	1.94
28"x 20"	3'-4"	4'-3"	70	1.26	80	1.47	90	1.68	100	1.90	115	2.11
35"x 24"	3'-8"	5'-3"	100	1.51	110	1.74	120	1.97	140	2.20	155	2.42
42"x 29"	4'-1"	6'-3"	115	1.82	130	2.06	140	2.31	155	2.55	170	2.83
49"x 33"	4'-5"	7'-3"	130	2.12	145	2.37	155	2.64	170	2.90	185	3.15
57"x 38"	4'-10"	8'-6"	145	2.52	160	2.79	175	3.07	190	3.35	205	3.61
64"x 43"	5'-3"	9'-6"	185	2.89	200	3.11	215	3.48	235	3.77	250	4.06
71"x 47"	5'-7"	10'-6"	200	3.25	215	3.56	235	3.86	250	4.17	270	4.48

NOTES

1. Concrete shall be 560-C-3250
2. All reinforcing steel # 4 bars. All vertical and horizontal tie bars 18" maximum spacing.
3. When multiple pipes are used, the distance between pipes shall be S/2 (1' min.). The dimension L/2 is from the center of the pipe nearest to the end of the headwall as shown.

LEGEND ON PLANS



Revision	By	Approved	Date
Elev.	RC	D.S.	7-79
Conc.	RC	M.B.	5-86


SAN DIEGO REGIONAL STANDARD DRAWING

L TYPE HEADWALLS
(C.S.P. ARCH)


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen O Kuchenal — Dec. 1975
Coordinator R.C.E. 19807 — Date

DRAWING NUMBER D-37



FACE ELEVATION




SIDE ELEVATION

PIPE DIAMETER	X	Y	Z
12" to 24"	1' - 0"	2' - 0"	10"
21" to 36"	1' - 6"	2' - 6"	12"
39" to 48"	2' - 0"	3' - 0"	12"
51" to 60"	2' - 6"	3' - 0"	14"
63" & Larger	3' - 0"	3' - 0"	14"

NOTES:

1. A curtain wall shall be used in place of a headwall at culvert ends where extension of the culvert is considered imminent or no fill is retained.
2. Concrete shall be 560-C-3250
3. Keep the pipe-end clear of obstructions to permit easy placing of culvert extension.

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER **D-38**


SAN DIEGO REGIONAL STANDARD DRAWING

CURTAIN WALL


Revision	By	Approved	Date
Conc.	EC	M.B.	5-86



PLAN



SECTION A–A



SECTION B–B

SECTION C–C

NOTES

1. When more than one pipe is used the profile view shown shall hold for the distance across all pipe openings. Sections A-A and B-B shall be from the outermost pipe. The distance between pipes shall be D/2 for round and Span/3 for arch pipe. (12" minimum)
2. Culvert shall be cut off even with apron surface when required by the Agency.
3. Use Inlet Apron only where a flared end section can not be utilized.
4. Place weep holes when required by the Agency.

LEGEND ON PLANS



Revision	By	Approved	Date
Sec. A-A	[illegible]	D.S.	7-79
Sect. B-B	TRP	M.B.	10-82
Conc.	[illegible]	M.B.	5-96


SAN DIEGO REGIONAL STANDARD DRAWING

INLET APRON FOR CULVERTS UP TO 42" DIAMETER

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A. Kershaw — Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER D-39




PLAN

D = Pipe Diameter
W = Bottom Width of Channel



SECTION A–A




SECTION B–B

NOTES:


1. Plans shall specify:
   A) Rock class and thickness (T).
   B) Filter material, number of layers and thickness.
2. Rip rap shall be either quarry stone or broken concrete (if shown on the plans.) Cobbles are not acceptable.
3. Rip rap shall be placed over a filter blanket which may be either granular material or plastic filter cloth.
4. See standard special provisions for selection of rip rap and filter blanket.
5. Rip rap energy dissipators shall be designated as either Type 1 or Type 2. Type 1 shall be with concrete sill; Type 2 shall be without sill.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Allen O Kushmal Dec. 1975 Coordinator R.C.E. 19807 Date	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
		Sill, filter	TKP	M.B.	10-82
DRAWING NUMBER D-40	RIP RAP ENERGY DISSIPATOR				




PLAN


Note: Riprap not shown.



PICTORIAL VIEW



SECTION A—A



SECTION B—B

NOTES

1. Design:
   Equivalent Fluid Pressure = 60 p.c.f.
   Maximum Outlet Velocity = 35 f.p.s.
2. Concrete shall be 560-C-3250
3. Reinforcing shall conform to ASTM designation A615 and may be grade 40 or 60. Reinforcing shall be placed with 2" clear concrete cover unless noted otherwise. Splices shall not be permitted except as indicated on the plans.
4. For pipe grades not exceeding 20%, inlet box may be omitted.
5. If inlet box is omitted, construct pipe collar as shown.
6. Unless noted otherwise, all reinforcing bar bends shall be fabricated with standard hooks.
7. Five foot high chain link fencing, embed post 18" deep in walls and encase with Class B mortar.
8. In Sandy and Silty soil:
   a) Riprap and aggregate base cutoff wall required at the end of rock apron.
   b) Filter cloth (Polyfilter X or equivalent) shall be installed on native soil and base, minimum of 1 ft. overlaps at joints.
9. Rip rap and subbase classification shall be as shown on plans.

Pipe Dia (in)	18	24	30	36	42	48	54	60	72
Area (sq.ft.)	1.77	3.14	4.91	7.07	9.62	12.57	15.90	19.63	28.27
Max. Q (cfs)	21	38	59	85	115	151	191	236	339
W	5' - 6"	6' - 9"	8' - 0"	9' - 3"	10' - 6"	11' - 9"	13' - 0"	14' - 3"	16' - 6"
H	4' - 3"	5' - 3"	6' - 3"	7' - 3"	8' - 0"	9' - 0"	9' - 9"	10' - 9"	12' - 3"
L	7' - 4"	9' - 0"	10' - 8"	12' - 4"	14' - 0"	15' - 8"	17' - 4"	19' - 0"	22' - 0"
a	3' - 3"	3' - 11"	4' - 7"	5' - 3"	6' - 0"	6' - 9"	7' - 4"	8' - 0"	9' - 3"
b	4' - 1"	5' - 1"	6' - 1"	7' - 1"	8' - 0"	8' - 11"	10' - 0"	11' - 0"	12' - 9"
c	2' - 4"	2' - 10"	3' - 4"	3' - 10"	4' - 5"	4' - 11"	5' - 5"	5' - 11"	6' - 11"
d	0' - 11"	1' - 2"	1' - 4"	1' - 7"	1' - 9"	2' - 0"	2' - 2"	2' - 5"	2' - 9"
e	0' - 6"	0' - 6"	0' - 8"	0' - 8"	0' - 10"	0' - 10"	1' - 0"	1' - 0"	1' - 3"
f	1' - 6"	2' - 0"	2' - 6"	3' - 0"	3' - 0"	3' - 0"	3' - 0"	3' - 0"	3' - 0"
g	2' - 1"	2' - 6"	3' - 0"	3' - 6"	3' - 11"	4' - 5"	4' - 11"	5' - 4"	6' - 2"
Tf	8"			10"		12"			
Tb	7"			9 1/2"		10 1/2"			
Tw	7"			9 1/2"		10 1/2"			
Ta	7"			8"					

Revision	By	Approved	Date
Note 9		D.S	7-79
Conc.		M.B.	5-86


SAN DIEGO REGIONAL STANDARD DRAWING

CONCRETE ENERGY DISSIPATOR


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen A Kashani — Coordinator R.C.E. 19807 — Dec. 1975 Date


DRAWING NUMBER **D-41**




END SILL ELEVATION



HEADWALL ELEVATION




SECTION A–A



SECTION C–C


NOTES

1. Place reinforcing, as noted, at center wall (or slab).
2. Match location of reinforcing with that in headwall, end sill and foundation slab.
3. All reinforcing shall be placed with 2" concrete cover, unless noted otherwise.




SECTION D–D


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Allan D Kenkel Dec. 1975 Coordinator R.C.E. 19807 Date	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
DRAWING NUMBER D-42	**CONCRETE ENERGY DISSIPATOR (REINFORCEMENT) 18" TO 30" DIAMETER PIPE**				




HEADWALL ELEVATION




END SILL ELEVATION



SECTION A–A



SECTION C–C



SECTION D–D

NOTES

1. Match location of sidewall reinforcing.
2. Dowels having same size and spacing as wall reinforcing may be used in lieu of continuous bars at contractors option.
3. Match location of headwall or end sill reinforcing.

Pipe dia. (in.)	36	42	48	54	60	72
A bar	# 5 @ 12"		# 6 @ 12"		# 7 @ 12"	
B bar	# 5 @ 12"		# 6 @ 12"			
C bar	# 4 @ 12"		# 5 @ 12"			
D bar	# 4 @ 12"		# 5 @ 12"		# 6 @ 12"	
E bar	# 4 @ 12"		# 5 @ 12"			
F bar	# 4 @ 9"		# 5 @ 9"		#6@9"	
G bar	# 7			# 11		

Revision	By	Approved	Date


SAN DIEGO REGIONAL STANDARD DRAWING

CONCRETE ENERGY DISSIPATOR (REINFORCEMENT) 36" TO 72" DIAMETER PIPE

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan O Kashani — Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER **D-43**




END ELEVATION

If at upstream end, fillet is not shown




PLAN




PART LONGITUDINAL SECTION


Note: R.C.P. shown. Metal pipe similar except eliminate the expansion joint and use hook bolts @ 19"± spacing. Size and length provided by manufacturer.



SECTION A-A




SECTION B-B




ALTERNATIVE WARPED WINGWALL

Use where additional protection at toe of embankment is required. If at upstream end, fillet is not shown.




SECTION C-C

Where abrasion is anticipated, increase apron thickness to 7" min to provide 2" min. reinforcement coverage



DETAIL E



SECTION F-F

WARPED WINGWALLS

WALL DIMENSIONS AND REINFORCING

Element Slope	"H"	8' or less	10'	12'	14'	16'	18'	20'
1/4:1	Front face reinf	#4 @ 12	#4 @ 7	#5 @ 7	#5 @ 5	#6 @ 6	#7 @ 7	#7 @ 6
	Rear face reinf	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 12
3/4:1	Front face reinf	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 10	#5 @ 8	#4 @ 6
	Rear face reinf	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 10	#4 @ 7	#5 @ 6	#5 @ 8
1 1/4:1	Front face reinf	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 12
	Rear face reinf	#4 @ 8	#4 @ 8	#4 @ 5	#5 @ 6	#6 @ 7	#6 @ 6	#7 @ 6
"D" at Cut-off Wall		6"	6"	6"	7½"	8"	9½"	11"
"D" at Headwall / Endwall		6"	6"	6"	8"	9½"	11"	1'-1"

STIFFENING BEAM DIMENSIONS AND REINFORCING

"H" max.	12'	14'	16'	18'	20'	25'	30'	35'	40' or more
6'	No beam. Place 3-#5 in each face along top of wall								
8'	"A" = 1'-0" "B" = 9" Tot 6'-6"								
10'		"A" = 1'-6" "B" = 1'-0" Tot 6'-7"				A = 1'-10" "B" = 1'-0" Tot 6'-8"		"A" = 2'-0" "B" = 1'-6" Tot 8'-9"	
12'									
14'									
16'									
18'									
20'									

Notes: Walls designed for 2' surcharge; earth load = 120#/cu. ft., equivalent fluid pressure = 36#/cu. ft. Vary "D" at warped wall uniformly from that at cut-off wall to that at headwall or endwall, for max "H" > 12'. Dimensions "L", "W", "H", "M", "N", Elev "a", "Angle of flare", and end "Slope" (as apply) are shown on the plans.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Coordinator R.C.E. 19807 — Date: Dec. 1975

DRAWING NUMBER **D-44**


SAN DIEGO REGIONAL STANDARD DRAWING

PIPE CULVERT-HEADWALLS, ENDWALLS & WARPED WINGWALLS


Revision	By	Approved	Date



PLAN



SECTION A–A




SECTION B–B

NOTES:

1. See Standard Drawings D-11 & D-12 for additional notes and details.
2. Dimension shown becomes 2'-0" when opening on both sides. Adjust manhole as required.
3. Exposed edges of concrete shall be rounded with a radius of 1/2".
4. When V exceeds 4' steps shall be installed. See Standard Drawing D-11 for details.
5. Concrete gutter to match adjacent gutters.
6. An expansion joint shall be placed at the ends of the inlet where the curb is to adjoin.
7. Provide 1/4" tooled groove in top slab in line with back of adjacent curb.
8. Maintain 1 1/2" clear spacing between reinforcing and surface unless otherwise noted.

LEGEND ON PLANS

4' Type J Inlet



Revision		Approved	Date
Rebar	RC	M.B.	5-86

SAN DIEGO REGIONAL STANDARD DRAWING


CURB INLET-TYPE J MEDIAN

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Harry R. Holt Oct 1982

Chairman R.C.E. C13768 Date


DRAWING NUMBER D-45




SECTION

NOTES
1. For trenching on improved streets see Standard Drawing G–24 or G–25 for resurfacing details.
2. (*) indicates minimum relative compaction.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Chairman R.C.E. 25902 Date	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
		Rock Sz	DM	O. Robertson	2-95
DRAWING NUMBER D–60	PIPE BEDDING AND TRENCH BACKFILL FOR STORM DRAINS				



R = Thickness of pipe



R = Inside diameter of pipe / 10

NOTE

The rounded areas may be built up of cement mortar or poured in place with the drainage structure.

Revision	By	Approved	Date
Note	JC	O.S.	7-79


SAN DIEGO REGIONAL STANDARD DRAWING

ROUNDED PIPE ENDS IN DRAINAGE STRUCTURES


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen A Kashani — Coordinator R.C.E. 19807 — Dec. 1975 — Date

DRAWING NUMBER D-61



ELEVATION



SECTION A–A

NOTES:

1. Pipe collar does not have to be finished if covered.
2. Concrete shall be 560-C-3250.
3. Where gap exceeds 3" but is not more than 6" an internal form shall be used.

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A Kenkel — Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER **D-62**


SAN DIEGO REGIONAL STANDARD DRAWING

PIPE COLLAR


Revision	By	Approved	Date
Conc.	[illegible]	M.B.	5-86
Overlap	[illegible]	A.H.	7-88
Note 3	JP	G.R.	5-92




PLAN
SKEWED CONNECTION



PLAN



SECTION A–A




SECTION B–B

NOTES

1. The end of connecting pipe shall not project into the waterway of the larger pipe.
2. The larger pipe shall not be less than 24" I.D.
3. The smaller pipe shall not be more than 2/3 the size of the larger pipe.
4. Concrete shall be 470 - C - 2000.

LEGEND ON PLANS



Revision	By	Approved	Date


SAN DIEGO REGIONAL STANDARD DRAWING

CONCRETE LUG


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Coordinator R.C.E. 19807 — Dec. 1975 Date


DRAWING NUMBER **D-63**




TYPICAL SECTION



DETAIL



WEAKENED PLANE JOINT




EXPANSION JOINT

NOTES

1. A.C. or clay pipe may be substituted for plastic pipe at weep holes.
2. Weakened plane joints shall be placed every 12' to 15'. Expansion joints shall be placed at all changes of section and at ends of curves.
3. Cutoff walls shall be constructed at each end of the channel along the full width of section. See Standard Drawing D-72.
4. Chainlink fence shall be as required by Agency.
5. For bottom widths greater than 8 feet see Standard Drawing D-71.
6. Reinforcement shown is minimum.

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A Kenkel — Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER **D-70**


SAN DIEGO REGIONAL STANDARD DRAWING

MINOR DRAINAGE CHANNEL


Revision	By	Approved	Date
Conc.		M.B.	5-86




TYPICAL SECTION




DETAIL A



ALT. CONTINUOUS DRAIN



WEAKENED PLANE JOINT




EXPANSION JOINT

NOTES

1. A.C. or clay pipe may be substituted for plastic pipe at weep holes.
2. Weakened plane joints shall be placed every 12' to 15'. Expansion joints shall be placed at all changes of section and at ends of curves.
3. Cutoff walls shall be constructed at each end of the channel along the full width of section. See Standard Drawing D-72.
4. Chainlink fence shall be as required by Agency.
5. Reinforcement shown is minimum.

LEGEND ON PLANS



Revision	By	Approved	Date
Conc.	[illegible]	M.B.	5-86


SAN DIEGO REGIONAL STANDARD DRAWING

MAJOR DRAINAGE CHANNEL


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen A Kenkel — Coordinator R.C.E. 19807 — Dec. 1975 — Date

DRAWING NUMBER **D-71**



ELEVATION




SECTION A–A

NOTES

1. Thickness and wall depth shall be as shown on plan.
2. Reinforcing in cutoff wall shall be the same as that required in channel.
3. Concrete shall be 560-C-3250

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A. Kershaw — Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER **D-72**


SAN DIEGO REGIONAL STANDARD DRAWING

CUTOFF WALL FOR DRAINAGE CHANNEL

Revision	By	Approved	Date
Conc.	RC	M.B.	5-86



PLAN




ELEVATION

NOTES

1. Concrete shall be 560-C-3250
2. Pipe shall connect to channel as high as possible.
3. The maximum angle of connection is 60° downstream.
   In no case shall a pipe angle upstream.

LEGEND ON PLANS



Revision	By	Approved	Date
Conc.	JC	M.B.	5-86


SAN DIEGO REGIONAL STANDARD DRAWING

PIPE TO CHANNEL CONNECTION

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen A Kenkel — Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER **D-73**




TYPICAL SECTION

NOTE


The following shall be as required by Agency:

a) Low flow channel
b) Filter blanket
c) Cutoff wall
d) Fence

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
Coordinator R.C.E. 19807 — Dec. 1975 Date					
DRAWING NUMBER D-74	GRADED EARTH CHANNEL				



TYPE A

A = 1.25 SF


$Q_{2\%}$ = 9 cfs

BROW DITCH

TYPE B

A = 1.57 SF

$Q_{2\%}$ = 14 cfs



TYPE C

A = 2.05 SF

$Q_{2\%}$ = 21 cfs

TERRACE DITCH

TYPE D

A = 2.06 SF

$Q_{2\%}$ = 20 cfs

NOTES

1. Longitudinal slope of lined ditch shall be 2% minimum.
2. Over slope down ditches shall employ 6" thickened edge section at both sides of ditch.

LEGEND ON PLANS

Revision	By	Approved	Date
Ditch type	EC	D.S.	7-79
A.P.C.	TRP	M.B.	10-82
B height	EC	A.H.	7-88

SAN DIEGO REGIONAL STANDARD DRAWING

DRAINAGE DITCHES

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Coordinator R.C.E. 19807 — Date: Dec. 1975

DRAWING NUMBER D-75

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Coordinator R.C.E. 13807 Date 1975

DRAWING NUMBER **D-76A**

SAN DIEGO REGIONAL STANDARD DRAWING

SINGLE BOX CULVERT

DETAILS NO. 1

Revision	By	Approved	Date
Enlarged			8-88


SPAN	2'		3'		4'					5'										6'																			7'					
HEIGHT	1'-6	2'	2'	3'	2'	3'		4'		2'	3'	4'		5'				2'	3'	4'		5'				6'																			
STRENGTH CLASSIFICATION	A	A	A	A	A	B	A	B	C	A	B	A	B	A	B	C	D	A	B	C	D	A	B	A	B	A	B	C	A	B	C	D	A	B	C	D	E	A	B	C	D	E
MAX FILL OVER TOP	66		38	38	66	28	28	37	28	37	50	12	27	12	27	11	26	35	46	11	25	35	46	10	18	10	18	10	18	25	36	45	9	17	25	36	45	9	17	25	36	45
Conc Top Slab T_1	6	6	6¼	6¼	8	7	7	8	7	8	9	7½	8	7¼	8	7½	8	9¼	10½	7½	8	9½	10½	8¼	8¼	8¼	8¼	8¼	8¼	9¼	11	8¼	8¼	9¼	11	12	8¼	8¼	9¼	11	12	8¼	8¼	9¼	11	12
Conc Bottom Slab T_2	6	6	6¼	6¼	8	7	7	8	7	8	9	6	8	6	8	6	8	10	10¾	6	8	10	10¾	6¼	8	6¼	8	6½	8	9¾	11¼	7¼	8¼	10	11¼	12¼	7¼	8¼	10½	11¼	12¼	7¼	8¼	10½	11¼	12¼
Conc Sidewalls T_3	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6
Reinforcing Steel "a" Size: Bar #	4	4	4	4	5	5	5	5	5	5	6	5	5	5	5	5	5	6	6	5	5	6	6	5	5	5	5	5	5	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6
Reinforcing Steel "a" Spacing	3½	3½	3½	3½	4	5	5	4½	5	4½	5	4	4	4	4	4	4	5	4½	4	4	5	4½	4	4	4	4	4	4	5	4½	4	4	5	5½	5	4	4	5	5½	5	4	4	5	5½	5
Reinforcing Steel "a" Length	3-2	3-2	4-2	4-2	4-3	5-3	5-3	5-3	5-3	5-3	5-2	6-3	6-3	6-3	6-3	6-3	6-3	6-2	6-2	6-3	6-3	6-2	6-2	7-3	7-3	7-3	7-3	7-3	7-3	7-2	7-2	7-3	7-3	7-2	7-3	7-5	7-6	7-3	7-3	7-2	7-3	7-5	7-6	7-3	7-3	7-2	7-3	7-5	7-6
Reinforcing Steel "d" Dist. Top Slab-No of	2	2	3	3	2	5	5	3	5	3	3	7	3	7	3	7	3	3	3	7	3	3	3	7	4	7	4	7	4	4	4	7	4	4	4	4	4	7	4	4	4	4	4	7	4	4	4	4	4
Reinforcing Steel Bars Bottom Slab-No of	2	2	2	2	2	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	3	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4
Reinforcing Steel "e" Bars Spacing	18	18	18	18	V2¼	18	18	18	17	13	9¼	18	18	18	18	18	17	13	11	18	12	8½	6½	18	18	18	18	18	18	17	18	V5½	11½	8½	17	10½	7½	6	5	12	7½	7	5	4½
Spacers Number	12	12	12	12	12	14	14	14	14	14	14	14	14	14	14	14	14	16	16	14	14	16	16	12	12	14	14	14	14	14	14	16	16	16	16	16	16	18	18	18	18	18	18	18	18	18	18	18	18
Quan. Concrete: C.Y. per lin ft	17	18	23	27	31	29	33	36	36	40	43	32	37	36	41	40	44	51	54	43	48	55	57	40	42	43	46	47	50	58	52	54	60	66	56	59	65	71	78	59	61	70	78	88					
Quan. Reinf lbs per lin ft	27	29	34	36	46	44	45	47	49	52	64	57	56	59	57	61	60	68	75	63	65	77	87	64	63	66	65	69	67	74	70	70	80	91	73	78	92	112	127	81	90	99	126	139					

SPAN	7'									8'										10'																									
HEIGHT	3'		4'		5'			6'			7'			3'		4'		5'		6'		7'			8'			4'		5'		6'		7'		8'			9'			10'		
STRENGTH CLASSIFICATION	A	B	A	B	A	B	C	A	B	C	A	B	C	A	B	A	B	A	B	A	B	C	A	B	C	A	B	C	A	B	A	B	A	B	A	B	C	A	B	C	A	B	C	A	B	C
MAX FILL OVER TOP	16	26	16	26	16	26	35	16	26	35	16	26	35	13	21	13	21	13	21	13	21	31	13	21	31	13	21	31	9	18	9	18	9	18	9	18	8	18	28	8	18	28	8	18	28
Conc Top Slab T_1	7¼	8¼	7¼	8¼	7¼	8¼	9¾	7¼	8¼	9¾	7¼	8¼	9¾	7¼	8¼	7¼	8¼	7¼	8¼	7¼	8¼	10¼	7¼	8¼	10¼	7¼	8¼	10¼	8	9¼	8¼	9¾	8¼	9¾	8¼	9¾	8¼	9¾	12¼	8½	9¾	12¼	8½	9¾	12¼
Conc Bottom Slab T_2	7½	8¾	7½	8¾	7½	8¾	10¼	7½	8¾	10¼	7½	8¾	10¼	7¼	9¼	7¼	9¼	7¼	9¼	7½	9¼	11¼	7¼	9¼	11½	7½	9¼	11½	8¼	10¼	9	10¾	9	10¾	9¼	11	9¼	11	13¼	9¼	11	13¼	9¼	11	13¼
Conc Sidewalls T_3	6	7	6	7	6	7	8½	6	7	8½	6	7	8½	6½	7½	6½	7½	6½	7½	6½	7½	9¾	6½	7½	9¾	6½	7½	9¾	7¼	9¼	7¼	9¼	7¼	9¼	7¼	9¼	7¼	9¼	11½	8	9½	11½	9	9½	11½
Reinforcing Steel "a" Size: Bar #	5	5	5	5	5	5	6	5	5	6	5	5	6	5	5	5	5	5	5	5	5	6	5	5	6	5	5	6	6	6	6	6	6	6	6	6	7	6	6	7	6	6	7	6	6	7
Reinforcing Steel "a" Spacing	9	7	9	7	9	7	9	9	7	9	9	7	9	9	7	9	7	9	7	9	7	8	9	7	8	9	7	8	5	5	6	5	5	6	5	5	6	6	6	6	6	6	6	6	6	6
Reinforcing Steel "a" Length	6-8	6-9	6-8	6-9	6-8	6-9	6-10	6-8	6-9	6-10	6-8	6-9	6-10	7-7	7-8	7-7	7-8	7-7	7-8	7-7	7-8	7-10	7-7	7-8	7-10	7-7	7-8	7-10	9-5	9-8	9-5	9-8	9-5	9-8	9-5	9-8	9-5	9-8	9-9	9-6	9-8	9-9	9-7	9-8	9-9
Reinforcing Steel "b" Size: Bar #	5	5	5	5	5	5	6	5	5	6	5	5	6	5	5	5	5	5	5	5	5	6	5	5	6	5	5	6	5	6	6	6	6	6	6	6	7	6	6	7	6	6	7	6	6	7
Reinforcing Steel "b" Spacing	9	7	9	7	9	7	9	9	7	9	9	7	9	9	7	9	7	9	7	9	7	8	9	7	8	9	7	8	5	5	6	5	5	6	5	5	6	6	6	6	6	6	6	6	6	6
Reinforcing Steel "b" Dimension "X"	1-3	1-4	1-3	1-4	1-3	1-4	1-8	1-3	1-4	1-8	1-3	1-4	1-8	1-6	1-7	1-6	1-7	1-6	1-7	1-6	1-7	1-8	1-6	1-7	1-8	1-6	1-7	1-8	2-0	2-0	2-0	2-0	2-0	2-0	2-0	2-0	2-0	2-0	2-6	2-0	2-0	2-6	2-0	2-0	2-6
Reinforcing Steel "b" Length	3-1	3-2	3-1	3-2	3-1	3-2	3-10	3-1	3-2	3-10	3-1	3-2	3-10	3-4	3-5	3-4	3-5	3-4	3-5	3-4	3-5	3-10	3-4	3-5	3-10	3-4	3-5	3-10	3-10	4-2	3-10	4-2	3-10	4-2	3-10	4-2	3-10	4-2	4-8	3-10	4-2	4-8	3-10	4-2	4-8
Reinforcing Steel "c" Size: Bar #	5	5	5	5	5	5	6	5	5	6	5	5	6	5	5	5	5	5	5	5	5	6	5	5	6	5	5	6	5	6	5	6	5	6	6	5	6	6	6	5	6	6	5	6	6
Reinforcing Steel "c" Spacing	9	7	9	7	9	7	9	9	7	9	9	7	9	9	7	9	7	9	7	9	7	8	9	7	8	9	7	8	5	5	6	5	5	6	5	5	6	6	6	6	6	6	6	6	6	6
Reinforcing Steel "c" Dimension "Y"	1-10	1-11	1-10	1-11	1-10	1-11	2-3	1-10	1-11	2-3	1-10	1-11	2-3	2-0	2-5	2-0	2-5	2-0	2-5	2-0	2-5	2-8	2-0	2-5	2-8	2-0	2-5	2-8	2-8	3-4	2-8	3-4	2-8	3-4	2-8	3-4	3-6	2-8	3-4	3-6	2-8	3-4	3-6	2-8	3-4	3-6
Reinforcing Steel "c" Length	3-2	3-4	3-2	3-4	3-2	3-4	4-0	3-2	3-4	4-0	3-2	3-4	4-0	5-4	5-10	6-4	6-10	7-4	7-10	8-4	8-10	9-3	9-4	9-10	10-3	10-4	10-10	11-3	6-11	7-10	8-1	8-10	9-1	9-10	10-1	10-10	11-1	11-10	12-3	12-1	12-10	13-3	13-1	13-10	14-3
Reinforcing Steel "d" Top Slab-No of	7	4	7	4	7	4	4	7	4	4	7	4	4	7	5	7	5	7	5	7	5	5	7	5	5	7	5	5	9	5	9	5	9	5	9	5	5	9	5	5	9	5	5	9	5	5
Reinforcing Steel Bars Bottom Slab-No of	4	4	4	4	4	4	4	4	4	4	4	4	4	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5	5
Reinforcing Steel "e" Bars Spacing	18	18	18	18	18	16	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18
Spacers Total Number	24		28		28			32			36			28		32		32		36			40			40			32		34		36		40			40			44			48		
Quan. Concrete: C.Y. per lin. ft.	.47	.56	.51	.60	.55	.64	.78	.58	.68	.84	.62	.73	.89	.52	.63	.56	.70	.60	.74	.65	.79	1.00	.69	.83	1.06	.73	.88	1.12	.75	.94	.82	1.02	.86	1.08	.92	1.15	.97	1.21	1.50	1.06	1.26	1.57	1.18	1.32	1.65
Quan. Reinf. lbs per lin. ft	107	130	114	138	118	143	168	123	150	176	132	158	184	118	146	125	154	129	159	136	167	211	143	174	220	147	179	225	143	221	148	228	154	235	160	244	164	250	265	170	259	273	178	267	281

SPAN	12'														
HEIGHT	6'		7'		8'		9'			10'			12'		
STRENGTH CLASSIFICATION	A	B	A	B	A	B	A	B	C	A	B	C	A	B	C
MAX FILL OVER TOP	5	16	5	16	5	16	5	16	24	5	16	24	5	16	24
Conc Top Slab T_1	8¾	11¼	8¾	11¼	8¾	11¼	9	11¼	13¼	9	11¼	13½	9	11¼	13¼
Conc Bottom Slab T_2	8¾	12¼	8¾	12¼	8¾	12¼	9	12¼	14¾	9	12¼	14¾	9	12¼	14¾
Conc Sidewalls T_3	7½	10½	7½	10½	7½	10½	8	10½	12½	9	10½	12½	9	10½	12½
Reinforcing Steel "a" Size: Bar #	6	7	6	7	6	7	6	7	7	6	7	7	6	7	7
Reinforcing Steel "a" Spacing	11	10	11	10	11	10	11	10	8	11	10	8	11	10	8
Reinforcing Steel "a" Length	11-3	11-6	11-3	11-6	11-3	11-6	11-4	11-6	11-8	11-5	11-6	11-8	11-5	11-6	11-8
Reinforcing Steel "b" Size: Bar #	6	7	6	7	6	7	6	7	7	6	7	7	6	7	7
Reinforcing Steel "b" Spacing	11	10	11	10	11	10	11	10	8	11	10	8	11	10	8
Reinforcing Steel "b" Dimension "X"	2-8	3-0	2-8	3-0	2-8	3-0	2-8	3-0	3-0	2-8	3-0	3-0	2-8	3-0	3-0
Reinforcing Steel "b" Length	4-10	5-7	4-10	5-7	4-10	5-7	4-10	5-7	5-7	4-10	5-7	5-7	4-10	5-7	5-7
Reinforcing Steel "c" Size: Bar #	6	7	6	7	6	7	6	7	7	6	7	7	6	7	7
Reinforcing Steel "c" Spacing	11	10	11	10	11	10	11	10	8	11	10	8	11	10	8
Reinforcing Steel "c" Dimension "Y"	3-9	3-9	3-9	3-9	3-9	3-9	3-9	3-9	3-9	3-9	3-9	3-9	3-9	3-9	3-9
Reinforcing Steel "c" Length	10-2	10-4	11-2	11-4	12-2	12-4	13-2	13-4	13-8	14-2	14-4	14-6	16-2	16-4	16-6
Reinforcing Steel "d" Top Slab-No of	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6
Reinforcing Steel Bars Bottom Slab-No of	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6
Reinforcing Steel "e" Bars Spacing	18	18	18	18	18	18	18	18	18	18	18	18	18	18	18
Spacers Total Number	36		44		44		44			48			52		
Quan. Concrete: C.Y. per lin. ft.	.99	1.38	1.03	1.44	1.08	1.52	1.18	1.58	1.90	1.30	1.65	1.98	1.41	1.78	2.13
Quan. Reinf. lbs per lin. ft	203	293	213	304	218	311	223	317	387	231	326	397	243	341	415

Note:

For boxes of height less than that shown in table, use next greater table height slabs, wall dimensions and reinforcing steel, and make necessary changes in bar lengths, number of spacers and quantities




TYPICAL SECTIONS 2' THRU 6' SPANS



DETAIL "A"

Ⓐ For reinforcement clearance, except at bottom, see "Miscellaneous Details."



TYPICAL SECTION 7' THRU 12' SPANS



FLAT INVERT V INVERT TRAPEZOIDAL INVERT

ALTERNATIVE INVERTS

(When shown)

Revision	By	Approved	Date
Enlarged	[illegible]	AH	8-88

SAN DIEGO REGIONAL STANDARD DRAWING

SINGLE BOX CULVERT DETAILS NO. 2

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A. Kershaw — Dec. 1975

Coordinator R.C.E. 19807 — Date

DRAWING NUMBER **D-76B**

SPAN		4'												5'												6'					
HEIGHT		2'			3'				4'					2'			3'			4'				5'				3'			4'		
STRENGTH CLASSIFICATION		A	B	C	A	B	C	D	A	B	C	D		A	B	C	A	B	C	A	B	C	D	A	B	C	D	A	B	C	A	B	C
MAX. FILL OVER TOP		11	21	32	11	23	34	46	11	23	34	46		6	24	36	6	24	36	6	23	34	46	6	23	34	46	4	20	34	4	20	34
Conc	Top Slab T_1	6½	6½	7¼	6½	6½	7½	8½	6½	6½	7½	8½		6½	7⅝	9¼	6½	7⅝	9¼	6½	7⅝	9	10¼	6½	7⅝	9¼	10¼	7¼	8¼	10¼	7¼	8¼	10¼
	Bottom Slab T_2	6	7¼	8½	6	7½	8½	9½	6	7½	8½	9½		6½	8⅝	10¼	6½	8⅝	10¼	6½	8⅝	10	11¼	6½	8⅝	10¼	11¼	7¼	9¼	11½	7¼	9½	11½
	Sidewalls T_3	6	6	6	6	6	6	6	6	6	6	6		6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6
Steel	a Size Bar #	5	4	4	5	4	4	4	5	4	4	4		5	4	4	5	4	4	5	4	4	4	5	4	4	4	5	4	4	5	4	4
	a Spacing	11	11	9	11	10½	8½	7½	11	10½	8½	7½		10	8½	10	10	8½	10	10	8½	10	9	10	8½	10½	9	9½	11	8½	9½	11	8½
	a Length	10-3	10-2	10-2	10-3	10-2	10-2	10-2	10-3	10-2	10-2	10-2		12-3	12-2	12-2	12-3	12-2	12-2	12-3	12-2	12-2	12-2	12-3	12-2	12-2	12-2	14-3	14-2	14-2	14-3	14-2	14-2
	b or b1 Size Bar #	5	5	5	5	5	5	5	5	5	5	5		5	5	6	5	5	6	5	5	6	6	5	5	6	6	5	6	6	5	6	6
	b or b1 Spacing	11	11	9	11	10½	8½	7½	11	10½	8½	7½		10	8½	10	10	8½	10	10	8½	10	9	10	8½	10½	9	9½	11	8½	9½	11	8½
	b Length "b"	9-4	9-4	9-6	9-4	9-4	9-6	9-7	9-4	9-4	9-6	9-7		11-5	11-6	11-7	11-5	11-6	11-7	11-5	11-6	11-7	11-8	11-5	11-6	11-7	11-8	13-6	13-6	13-6	13-6	13-6	13-6
	b1 Length "b1"	9-4	9-5	9-6	9-4	9-5	9-6	9-7	9-4	9-5	9-6	9-7		11-4	11-6	11-7	11-4	11-6	11-7	11-4	11-6	11-7	11-8	11-4	11-6	11-7	11-8	13-5	13-7	13-8	13-5	13-7	13-8
	c Size Bar #	4	5	5	4	5	5	5	4	5	5	5		4	5	6	4	5	6	4	5	6	6	4	5	6	6	4	6	6	4	6	6
	c Spacing	11	11	9	11	10½	8½	7½	11	10½	8½	7½		10	8½	10	10	8½	10	10	8½	10	9	10	8½	10½	9	9½	11	8½	9½	11	8½
	c Length	4-6	4-6	4-6	4-6	4-6	4-6	4-6	4-6	4-6	4-6	4-6		5-6	5-6	5-6	5-6	5-6	5-6	5-6	5-6	5-6	5-6	5-6	5-6	5-6	5-6	6-6	6-6	6-6	6-6	6-6	6-6
Reinforcing	"d" Dist Bars Top Slab-Tot No.	10	6	6	10	6	6	6	10	6	6	6		12	6	6	12	6	6	12	6	6	6	12	6	6	6	12	6	6	12	6	6
	Bottom Slab-Tot No.	6	6	6	6	6	6	6	6	6	6	6		6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6
	"e" Bars Size Bar #	4	4	4	4	4	4	4	4	4	4	5		4	4	4	4	4	4	4	4	4	5	4	4	5	6	4	4	4	4	4	4
	Bars Spacing	18	18	18	18	18	16	12	18	12	9	10		18	18	18	18	18	16	18	12	10	10½	18	8½	9	9	18	18	16	18	14	8½
	Spacers \ Number	23			26				29					23			26			29				32				30			33		
Quan	Concrete: C.Y. per lin. ft	047	051	057	053	057	063	069	059	063	069	075		058	069	080	063	075	086	069	080	089	098	074	086	097	104	077	090	108	082	096	113
	Reinf. Lbs. per lin. ft	81	74	84	84	79	91	101	87	85	99	111		99	100	109	103	104	112	106	109	119	133	109	116	126	148	121	119	147	125	124	155

SPAN		6'								8'														10'						
HEIGHT		5'				6'				4'			5'			6'			7'				8'				5'		6'		
STRENGTH CLASSIFICATION		A	B	C	D	A	B	C	D	A	B	C	A	B	C	A	B	C	A	B	C	D	A	B	C	D	A	B	C	A	B	C
MAX FILL OVER TOP		4	19	33	43	4	19	33	43	3	14	25	3	14	25	3	14	25	3	14	25	37	3	14	25	37	2	17	30	2	17	30
Conc	Top Slab T_1	7¼	8¼	10½	12	7¼	8¼	10¼	12	8½	9½	12	8½	9½	12	8½	9½	12	8½	9½	12	14¼	8½	9½	12	14¼	8¾	12¾	16	8¾	12¾	16
	Bottom Slab T_2	7¼	9½	11½	12¾	7¼	9½	11½	12¾	7½	10½	12¾	7½	10½	12¾	7½	10½	12¾	7½	10½	12¾	13	15	7½	10¾	13	15¼	8¼	13½	16½	8¼	13½	16½
	Sidewalls T_3	6	6	6	6	6	6	6	7¼	6	6	6	6	6	6	6	6	6	7	7	7	8	7	7	8	8½	6	6	6	6	6	6
Steel	a Size Bar #	5	4	4	4	5	4	4	4	6	4	4	6	4	4	6	4	4	6	4	4	4	6	4	4	4	6	4	4	6	4	4
	a Spacing	9½	11	8½	10½	9½	11	8½	10½	12	9½	10½	12	9½	10	12	9½	10	11½	9½	10	8½	11½	9½	10	8½	11	10	10	11	9½	10
	a Length	14-3	14-2	14-2	14-2	14-3	14-2	14-2	14-2	18-4	18-4	18-2	18-2	18-4	18-2	18-2	18-4	18-2	18-2	18-5	18-5	18-5	18-6	18-7	18-5	18-8	18-8	22-4	22-2	22-2	22-4	22-2	22-2
	b or b1 Size Bar #	5	6	6	7	5	6	6	7	6	6	7	6	6	7	6	6	7	6	6	7	7	6	6	7	7	6	7	8	6	7	8
	b or b1 Spacing	9½	11	8½	10½	9½	11	8½	10½	12	9½	10½	12	9½	10	12	9½	10	11½	9½	10	8½	11½	9½	10	8½	11	10	10	11	9½	10
	b Length "b"	13-6	13-6	13-8	13-9	13-5	13-6	13-8	14-2	17-7	17-8	17-9	17-7	17-8	17-9	17-7	17-8	17-9	17-7	17-10	17-10	18-0	18-5	17-10	17-10	18-3	18-5	21-7	21-10	22-0	21-7	21-10	22-0
	b1 Length "b1"	13-5	13-6	13-8	13-9	13-5	13-6	13-8	14-2	17-5	17-8	17-9	17-5	17-8	17-9	17-5	17-8	17-9	17-5	17-8	17-8	18-0	18-5	17-8	17-11	18-0	18-7	21-5	21-10	22-0	21-5	21-10	22-0
	c Size Bar #	4	6	6	7	4	6	6	7	4	6	7	4	6	7	4	6	7	4	6	7	7	4	5	7	7	6	7	8	6	7	8
	c Spacing	9½	11	8½	10½	9½	11	8½	10½	12	9½	10½	12	9½	10	12	9½	10	11½	9½	10	8½	11½	9½	10	8½	11	10	10	11	9½	10
	c Length	6-6	6-6	6-6	6-6	6-6	6-6	6-6	6-6	8-5	8-5	8-6	8-6	8-6	8-6	8-6	8-6	8-6	8-7	8-7	8-7	8-8	8-7	8-7	8-8	8-9	10-6	10-6	10-6	10-6	10-6	10-6	10-6
Reinforcing	"d" Dist Bars Top Slab-Tot No	12	6	6	6	12	6	6	6	8	8	8	16	8	8	16	8	8	16	8	8	8	16	8	8	8	18	10	10	18	10	10
	Bottom Slab-Tot No	6	6	6	6	6	6	6	6	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	8	10	10	10	10	10	10
	"e" Bars Size Bar #	4	4	5	5	4	5	6	6	4	4	4	4	4	5	4	5	6	4	5	6	7	4	5	7	7	4	4	5	4	4	5
	Bars Spacing	18	10	9½	7	18	11	9	6	18	18	10½	18	12	10	18	11½	10	14	9½	7½	8½	11½	8½	7½	8	18	10	10	18	6	8½
	Spacers \ Number	36				36				41			44			44			47				56	50		60	48			48		
Quan	Concrete: C.Y. per lin. ft	088	101	119	130	093	107	125	147	108	130	155	114	137	161	119	142	166	132	156	183	214	139	162	199	227	140	205	246	145	207	248
	Reinf. Lbs. per lin. ft	128	131	164	175	129	137	177	201	169	173	200	172	181	218	173	188	229	185	199	248	299	191	207	284	314	236	254	310	236	274	324

SPAN		10'											12'																			
HEIGHT		7'			8'				10'				6'			7'			8'			9'				10'				12'			
STRENGTH CLASSIFICATION		A	B	C	A	B	C	D	A	B	C	D	A	B	C	A	B	C	A	B	C	A	B	C	D	A	B	C	D	A	B	C	D
MAX FILL OVER TOP		2	17	30	2	16	29	36	2	16	29	36	2	14	26	2	14	26	2	14	26	2	14	26	36	2	14	26	36	2	14	26	36
Conc	Top Slab T_1	8¾	12¾	16	8¾	12¾	16	17¼	8¾	12¾	16	17¼	10	14	17½	10	14	17½	10¼	14¼	17¾	20¾	10¼	14¼	17¾	20¾	10¼	14¼	17¾	20¾	10¼	14¼	18¼	21¼
	Bottom Slab T_2	8¼	13¾	16¼	8¾	13½	16½	18¼	8¾	13½	16½	18½	9¼	14¾	18	9¼	15	18¼	9¾	15	18¼	21¼	10	15¼	18¾	21¼	10¼	15¼	19¾	21¼	10¼	15¼	19¼	22
	Sidewalls T_3	6	6½	7	7	7	7½	8½	8	8	9	10	6	6	6½	7	7	7	8	8	8½	9	9	9	10	9	9	9½	11	9	10	11	12
Steel	a Size Bar #	6	4	4	6	4	4	4	6	4	4	4	6	4	4	6	4	4	6	4	4	4	6	4	4	4	6	4	4	4	6	8	8	9
	a Spacing	11	9½	10	11	10	10	9	11	10	10	9	9	11½	9	9	11½	9	9	11	8½	9	11	8½	9	9	11	8½	9	9	11	8½	9	9
	a Length	22-4	22-4	22-5	22-7	22-5	22-7	22-11	22-10	22-9	22-11	23-2	26-4	26-2	26-4	26-7	26-5	26-5	26-10	26-9	26-10	27-1	26-11	26-11	27-1	27-1	26-11	27-3	27-5	27-1	27-2	27-5	27-8
	b or b1 Size Bar #	6	7	8	6	7	8	8	6	7	8	8	6	8	8	6	8	8	6	8	8	9	6	8	8	9	6	8	8	9	6	8	8	9
	b or b1 Spacing	11	9½	10	11	10	10	9	11	10	10	9	9	11½	9	9	11½	9	9	11	8½	9	11	8½	9	9	11	8½	9	9	11	8½	9	9
	b Length "b"	21-7	21-11	22-3	21-10	22-1	22-4	22-9	22-1	22-4	22-9	23-1	25-8	25-10	26-3	25-11	26-1	26-4	26-2	26-4	26-9	26-5	26-8	26-10	27-1	26-11	26-11	27-1	27-5	27-2	27-5	27-8	27-11
	b1 Length "b1"	21-5	21-11	22-3	21-9	22-0	22-4	22-9	22-0	22-4	22-9	23-0	25-6	25-10	26-3	25-9	26-1	26-4	26-1	26-5	26-9	26-4	26-8	26-11	27-1	26-11	26-11	27-1	27-5	27-1	27-5	27-8	27-11
	c Size Bar #	6	7	8	6	7	8	8	6	7	8	8	5	8	8	5	8	8	5	8	8	9	5	8	8	9	5	8	8	9	5	8	8	9
	c Spacing	11	9½	10	11	10	10	9	11	10	10	9	9	11½	9	9	11½	9	9	11	8½	9	11	8½	9	9	11	8½	9	9	11	8½	9	9
	c Length	10-6	10-7	10-7	10-7	10-7	10-9	10-9	10-8	10-8	10-9	10-10	12-6	12-6	12-7	12-7	12-7	12-7	12-8	12-8	12-9	12-9	12-9	12-9	12-10	12-11	12-9	12-9	12-10	12-11	13-0	13-0	13-0	13-0
Reinforcing	"d" Dist Bars Top Slab-Tot No	18	10	10	18	10	10	10	18	10	10	10	24	10	10	24	10	10	24	10	10	24	10	10	10	24	10	10	10	24	10	10	10	
	Bottom Slab-Tot No	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	10	
	"e" Bars Size Bar #	4	4	6	4	5	6	7	4	6	6	7	4	4	5	4	4	5	4	4	5	4	5	7	8	4	7	8	8	6	7	8	9	
	Bars Spacing	14	6	8	11	8½	6	6	7½	7	5½	5	18	8	8	15	6	6½	12	5½	8	9	7½	8½	9	8½	11	8½	9	12	8	7	7	
	Spacers \ Number	51			54			64	68				32			35			68				68				72			76			
Quan	Concrete: C.Y. per lin. ft	151	218	264	168	227	274	304	192	251	309	341	184	259	316	197	277	328	219	293	359	415	238	315	369	425	259	348	423	492	267	353	430	492
	Reinf. Lbs. per lin. ft.	243	280	339	252	278	355	430	279	327	400	475	309	317	401	316	330	415	336	363	460	345	374	485	578	351	394	519	582	371	427	567	673	

Note:

For boxes of height less than that shown in table, use next greater table height slabs, wall dimensions and reinforcing steel and make necessary changes in bar lengths, number of spacers and quantities. Number of "d" bars in table is slab total for both cells.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A. Kashani Dec. 1975


Coordinator R.C.E. 19807 Date

DRAWING NUMBER **D-77A**

SAN DIEGO REGIONAL STANDARD DRAWING

DOUBLE BOX CULVERT DETAILS NO. 1

Revision	By	Approved	Date
Enlarge	JL	O.H.	9-88




Reinforcement for interior walls under 8."

TYPICAL SECTION

(Showing reinforcement for interior walls 8" and over.)

⊛ For reinforcement clearance, except at bottom, see "Miscellaneous Details."



"FLAT INVERT" ALTERNATIVE

(When shown)

Revision	By	Approved	Date
Enlarge	SC	Q.H	9/88

SAN DIEGO REGIONAL STANDARD DRAWING

DOUBLE BOX CULVERT DETAILS NO. 2

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A Kashani — Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER **D-77B**

SPAN		4'									5'															6'								
HEIGHT		2'			3'			4'			2'			3'			4'			5'					3'			4'			5'		
STRENGTH CLASSIFICATION		A	B	C	A	B	C	A	B	C	A	B	C	A	B	C	A	B	C	D	A	B	C	D	A	B	C	A	B	C	A	B	C
MAX FILL OVER TOP		10	24	38	10	24	38	10	24	38	8	17	26	8	17	26	8	17	26	35	8	17	26	35	3	13	23	3	13	23	3	13	23	30
Conc	Top Slab T_1	6½	6¼	7¼	6¼	6¼	7¼	6¼	6¼	7¼	6¼	6¾	7½	6¾	6¾	7½	6¾	6¾	7½	8½	6¾	6¾	7½	8½	7½	7½	8¼	7½	7½	8¼	7½	7½	8¼	9¼
	Bottom Slab T_2	6	7	8¼	6	7	8¼	6	7	8¼	6¼	7¼	8½	6¼	7¼	8½	6¼	7¼	8½	9½	6¼	7¼	8½	9½	6	7¾	9¼	6	7¾	9¼	6	8	9¼	10
	Sidewalls T_3	6	6	6	6	6	6	6	6	6	5	6	6	5	6	6	5	6	6	6	5	6	6	6	6	6	6	6	6	6	6	6	6	6
Steel	a — Size Bar #	5	4	5	5	4	5	5	4	5	5	4	5	5	4	5	5	4	5	5	5	4	5	5	6	5	5	6	5	5	6	6	6	6
	a — Spacing	11	11½	13	11	11½	13	11	11½	13	10	11½	13	10	11½	13	10	11	13	11½	10	11	13	11½	13	14	11½	13	14	11½	13	14	11½	10
	a — Length	14-9	14-8	14-9	14-9	14-9	14-8	14-9	14-9	14-8	14-9	17-9	17-8	17-9	17-9	17-8	17-9	17-9	17-8	17-9	17-9	17-9	17-8	17-9	17-9	20-0	20-0	20-9	20-9	20-0	20-0	20-9	20-9	20-9
	b or b_1 — Size Bar #	5	5	6	5	5	6	5	5	6	5	5	6	5	5	6	5	5	6	6	5	5	6	6	6	6	6	6	6	6	6	6	6	6
	b or b_1 — Spacing	11	11½	13	11	11½	13	11	11½	13	10	11½	13	10	11½	13	10	11	13	11½	10	11	13	11½	13	14	11½	13	14	11½	13	14	11½	10
	b or b_1 — Length "b"	14-2	14-2	14-3	14-2	14-2	14-3	14-2	14-2	14-2	14-3	17-3	17-3	17-3	17-3	17-3	17-3	17-3	17-3	17-3	17-5	17-3	17-3	17-5	17-5	20-3	20-3	20-5	20-5	20-3	20-3	20-5	20-5	20-6
	b or b_1 — Length "b_1"	14-0	14-2	14-3	14-0	14-2	14-3	14-0	14-2	14-3	17-0	17-2	17-4	17-0	17-2	17-4	17-0	17-2	17-4	17-5	17-0	17-2	17-4	17-5	17-5	20-0	20-2	20-5	20-0	20-2	20-5	20-0	20-3	20-5
	c — Size Bar #	4	5	6	4	5	6	4	5	6	4	5	6	4	5	6	4	5	6	6	4	5	6	6	6	4	6	6	4	5	6	6	6	6
	c — Spacing	11	11½	13	11	11½	13	11	11½	13	10	11½	13	10	11½	13	10	11	13	11½	10	11	13	11½	13	14	11½	13	14	11½	13	14	11½	10
	c — Length	9-0	9-0	9-0	9-0	9-0	9-0	9-0	9-0	9-0	11-0	11-0	11-0	11-0	11-0	11-0	11-0	11-0	11-0	11-0	11-0	11-0	11-0	11-0	13-0	13-0	13-0	13-0	13-0	13-0	13-0	13-0	13-0	13-0
Reinforcing	"d" Dist Bars — Top Slab-Tot No	15	9	9	15	9	9	15	9	9	18	9	9	18	9	9	18	9	9	9	18	9	9	9	18	9	9	18	9	9	18	9	9	9
	"d" Dist Bars — Bottom Slab-Tot No	9	9	9	9	9	9	9	9	9	9	9	9	9	9	9	9	9	9	9	9	9	9	9	18	9	9	18	9	9	18	9	9	9
	"e" Bars — Size Bar #	4	4	4	4	4	4	4	4	5	4	4	4	4	4	4	4	4	5	4	4	4	4	4	6	4	4	4	4	4	4	4	5	5
	"e" Bars — Spacing	18	18	18	18	18	13	18	11½	13	18	18	18	18	18	18	18	17	11½	11½	18	11	7	11½	18	18	18	18	18	11½	18	11½	12	10
	Spacers — Number	34			38			42			34			38			38			42					40			40			52			
Quan	Concrete C.Y. per lin ft	067	0.71	0.81	075	0.79	0.89	082	0.86	0.96	082	0.87	0.98	090	095	105	097	102	113	123	104	111	120	131	105	115	129	1.12	1.23	137	1.19	1.32	1.44	155
	Reinf Lbs per lin ft	122	110	133	127	115	138	131	122	147	150	126	153	155	130	157	157	136	161	181	161	143	171	192	181	168	196	183	170	200	187	177	209	235

SPAN		6'				8'																10'									
HEIGHT		6'				4'		5'			6'			7'			8'				5'			6'			7'		
STRENGTH CLASSIFICATION		A	B	C	D	A	B	C	A	B	C	A	B	C	A	B	C	D	A	B	C	D	A	B	C	A	B	C	A	B	C
MAX FILL OVER TOP		3	13	23	30	2	11	20	2	11	20	2	11	20	2	11	20	28	2	11	20	28	2	11	20	2	11	20	2	11	20
Conc	Top Slab T_1	7½	7¼	8¼	9¼	8¼	8¼	10¼	8¼	8¼	10¼	8¼	8¼	10¼	8¼	8¼	10¼	11½	8¼	8¼	10¼	11½	9	10	12	9	10	12	9	10	12
	Bottom Slab T_2	6	8	9¼	10¼	6½	9	11	6½	9¼	11	6½	9¼	11	6¾	9¼	11	12¼	6¾	9¼	11	12¼	7½	10¼	13	7½	10¾	13	7½	10¾	13
	Sidewalls T_3	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6	6½	6½	7	7	6	6	6	6	6	6	6	6	6½
Steel	a — Size Bar #	6	5	5	5	6	5	5	6	5	5	6	5	5	6	5	5	6	6	6	6	6	6	6	6	6	6	6	6	6	6
	a — Spacing	13	14	11½	10	11½	12	12	11½	12	12	11½	12	12	11½	12	12	10½	11½	11½	12	10½	10½	13	10	10½	13	10	10½	13	10
	a — Length	20-0	20-5	20-9	20-9	20-9	26-0	26-5	26-9	26-9	26-0	26-5	26-9	26-9	26-0	26-5	26-9	26-9	26-0	26-5	26-9	26-9	26-1	27-4	27-2	27-1	27-7	32-7	32-0	32-10	32-0	32-10	32-0	33-0
	b or b_1 — Size Bar #	6	6	6	6	6	6	7	6	6	7	6	6	7	6	6	7	7	6	6	7	7	6	7	7	6	7	7	6	7	7
	b or b_1 — Spacing	13	14	11½	10	11½	12	12	11½	12	12	11½	12	12	11½	12	12	10½	11½	11½	12	10½	10½	13	10	10½	13	10	10½	13	10
	b or b_1 — Length "b"	20-3	20-3	20-5	20-5	26-5	26-5	26-7	26-5	26-5	26-7	26-5	26-5	26-7	26-5	26-5	26-7	27-7	26-5	26-5	26-9	27-7	27-3	27-7	27-7	27-7	32-7	32-6	32-7	32-10	32-6	32-7	32-10	33-0
	b or b_1 — Length "b_1"	20-0	20-0	20-5	20-7	26-0	26-4	26-7	26-0	26-5	26-7	26-0	26-5	26-7	26-0	26-5	26-7	27-7	26-5	26-5	26-9	27-7	27-3	27-7	27-7	27-7	32-6	32-7	32-10	32-6	32-7	32-10	32-6	33-0
	c — Size Bar #	4	6	6	5	4	5	7	4	6	7	4	6	7	4	6	7	7	4	6	7	7	5	7	7	5	7	7	5	7	7
	c — Spacing	13	14	11½	10	11½	12	12	11½	12	12	11½	12	12	11½	12	12	10½	11½	11½	12	10½	10½	13	10	10½	13	10	10½	13	10
	c — Length	13-0	13-0	13-0	13-0	17-0	17-0	17-0	17-0	17-0	17-0	17-0	17-0	17-0	17-0	17-0	17-0	17-1	17-3	17-2	17-2	17-5	21-0	21-0	21-0	21-0	21-0	21-0	21-0	21-0	21-1
Reinforcing	"d" Dist Bars — Top Slab-Tot No	18	9	9	9	24	12	12	24	12	12	24	12	12	24	12	12	12	24	12	12	12	27	15	15	27	15	15	27	15	15
	"d" Dist Bars — Bottom Slab-Tot No	9	9	9	9	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	12	15	15	15	15	15	15	15	15	15
	"e" Bars — Size Bar #	4	4	6	6	4	4	4	4	4	5	4	5	6	4	6	7	7	4	6	7	7	4	4	5	4	5	6	4	6	7
	"e" Bars — Spacing	18	9	12	10	18	18	12	18	12	12	18	12	12	11½	12	12	10½	11½	11½	12	10½	18	13	10	18	13	10	13	13	10
	Spacers — Number	48				58		62			62			56			70			88			68			68			72		
Quan	Concrete C.Y. per lin ft	127	139	152	164	147	167	199	154	176	206	162	184	214	171	191	226	257	190	210	246	279	198	240	282	206	246	290	213	255	303
	Reinf Lbs per lin ft	192	187	221	249	261	250	301	266	257	310	267	264	320	276	277	336	409	283	295	347	441	358	372	470	359	379	482	367	391	502

SPAN		10'								12'																			
HEIGHT		8'				10'				6'			7'			8'			9'				10'				12'			
STRENGTH CLASSIFICATION		A	B	C	D	A	B	C	D	A	B	C	A	B	C	A	B	C	A	B	C	D	A	B	C	D	A	B	C	D
MAX FILL OVER TOP		2	11	20	28	2	11	20	28	2	10	18	2	10	18	2	10	18	2	11	20	30	2	11	20	30	2	11	20	30
Conc	Top Slab T_1	9	10	12	14½	9	10¼	12½	14½	10¼	11½	14	10¼	11½	14	10¼	11½	14	10¼	12	14¾	17¾	10¼	12	14¾	17¾	10¼	12	14¾	17¾
	Bottom Slab T_2	7¾	11	13	15	8	11	13½	15	8¼	12	14¼	8½	12	14¾	8½	12	14¾	8¾	12¼	15½	18¼	8¾	12¼	15½	18¼	9	12¾	15¾	18¼
	Sidewalls T_3	7	7	7½	8½	8	8½	9	10	6	6	6½	6	6	7	7	7	7½	8	8	9	10	8	8	9	10½	9	9	10½	12
Steel	a — Size Bar #	6	6	6	7	6	6	6	7	7	6	7	7	6	7	7	6	7	7	6	7	8	7	6	7	8	7	6	7	8	9
	a — Spacing	10½	13	10	11	10½	13	10	11	12	11	11½	12	11	11½	12	11	11½	12	10½	11	11½	12	10¼	11	11½	12	10½	11	11½
	a — Length	33-2	33-2	33-4	33-8	33-6	33-8	33-10	34-2	39-1	38-10	39-3	39-1	38-10	39-5	39-5	39-6	39-7	39-9	39-6	40-1	40-0	40-3	39-9	39-6	40-1	40-0	40-3	39-10	40-7	41-6
	b or b_1 — Size Bar #	6	7	7	8	6	7	7	8	7	7	8	7	7	8	7	7	8	7	7	8	9	7	7	8	9	7	7	8	9
	b or b_1 — Spacing	10½	13	10	11	10½	13	10	11	12	11	11½	12	11	11½	12	11	11½	12	10½	11	11½	12	10¼	11	11½	12	10½	11	11½
	b or b_1 — Length "b"	32-10	32-11	33-4	33-11	33-2	33-5	33-11	34-5	38-7	38-9	39-3	38-7	38-9	39-5	38-11	39-1	39-7	39-3	39-6	40-2	41-0	39-7	39-6	40-2	41-0	39-7	39-10	40-8	41-6
	b or b_1 — Length "b_1"	32-6	32-11	33-5	33-11	32-11	33-5	33-11	34-5	38-3	38-7	39-2	38-3	38-9	39-5	38-7	39-1	39-7	39-0	39-6	40-2	41-0	39-3	39-6	40-2	41-0	39-3	39-10	40-8	41-6
	c — Size Bar #	5	7	7	8	5	7	7	8	6	7	8	6	7	8	6	7	8	6	7	8	9	6	7	8	9	6	7	8	9
	c — Spacing	10½	13	10	11	10½	13	10	11	12	11	11½	12	11	11½	12	11	11½	12	10½	11	11½	12	10½	11	11½	12	10½	11	11½
	c — Length	21-2	21-2	21-3	21-5	21-4	21-5	21-6	21-8	25-0	25-0	25-1	25-0	25-0	25-2	25-2	25-2	25-3	25-4	25-4	25-6	25-8	25-4	25-4	25-6	25-9	25-6	25-6	25-9	26-0
Reinforcing	"d" Dist Bars — Top Slab-Tot No	27	15	15	15	27	15	15	15	36	15	15	36	15	15	36	15	15	36	15	15	15	36	15	15	15	36	15	15	15
	"d" Dist Bars — Bottom Slab-Tot No	15	15	15	15	15	15	15	15	15	15	15	15	15	15	15	15	15	15	15	15	15	15	15	15	15	15	15	15	15	15
	"e" Bars — Size Bar #	4	6	7	8	5	6	8	8	4	4	6	4	4	6	4	4	5	4	6	7	8	5	7	8	8	6	7	9	9
	"e" Bars — Spacing	10½	12	10	11	10½	9	10	9	11	12	5¾	11½	12	5½	9	10	10½	11	11½			12	10½	11	6½	12	9	11	9	
	Spacers — Number	76			94		102			76			80			84			104				110				116				
Quan	Concrete C.Y. per lin ft	234	277	323	378	268	318	373	422	260	318	382	270	326	398	288	345	413	313	379	461	545	323	389	472	565	362	428	524	618	
	Reinf Lbs per lin ft	377	402	514	590	421	453	577	632	489	505	628	497	516	637	505	527	654	536	582	719	872	548	606	745	939	575	636	793	963	

Note:

For boxes of height less than that shown in table, use next greater table height slabs, wall dimensions and reinforcing steel and make necessary changes in bar lengths, number of spacers and quantities. Number of "d" bars in table is slab total for all three cells.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A. Kashani — Dec. 1975


Coordinator R.C.E. 19807 — Date

DRAWING NUMBER **D-78A**

SAN DIEGO REGIONAL STANDARD DRAWING


TRIPLE BOX CULVERT DETAILS NO. 1

Revision	By	Approved	Date
Enlarge		A.H.	9-88



TYPICAL SECTION

⊛ For reinforcement clearance, except at bottom, see "Miscellaneous Details."



"FLAT INVERT" ALTERNATIVE

(When shown)

Revision	By	Approved	Date
Enlarge	JC	U.H.	9-88

SAN DIEGO REGIONAL STANDARD DRAWING


TRIPLE BOX CULVERT DETAILS NO. 2


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A Kashani — Dec. 1975


Coordinator R.C.E. 19807 — Date


DRAWING NUMBER **D-78B**

















RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER **D-79A**


SAN DIEGO REGIONAL STANDARD DRAWING

BOX CULVERT WINGWALL TYPES A, B & C DETAILS NO. 1

Revision	By	Approved	Date
Enlarge		A.H.	9-88



TYPICAL SECTION
H=4' THRU 12'



TYPICAL SECTION
H=13' THRU 16'


Design Notes:

Unit Stresses: $f_s = 20{,}000$ p.s.i, $f_c = 1200$ p.s.i, $n = 10$

Maximum Toe Pressure = 1½ Tons/sq. ft.

Elevations, length and angle of flare of wings may be varied by the Engineer to suit conditions encountered in the field. Walls designed for 2' liveload surcharge, 1½:1 sloping surcharge not to exceed 5' in elevation plus 2' liveload surcharge, or unlimited 2:1 surcharge.


Dimensions "H", "L", "M", "N", Elev "a" and "Angle of flare" (as apply) are shown on the plans.



REINFORCED CONCRETE WINGWALLS

"H"	4'	5'	6'	7'	8'	9'	10'	11'	12'	13'	14'	15'	16'
W	3'-2"	3'-8"	4'-2"	4'-8"	5'-2"	5'-8"	6'-2"	6'-8"	7'-2"	7'-8"	8'-2"	8'-8"	9'-2"
C	1'-0"	1'-2"	1'-4"	1'-6"	1'-8"	1'-10"	2'-0"	2'-2"	2'-4"	2'-6"	2'-8"	2'-10"	3'-0"
B	2'-2"	2'-6"	2'-10"	3'-2"	3'-6"	3'-10"	4'-2"	4'-6"	4'-10"	5'-2"	5'-6"	5'-10"	6'-2"
F	1'-2"												
Batter	None									½:12			
S	1'-0"	1'-0"	1'-0"	1'-0"	1'-0"	1'-0"	1'-0"	1'-0"	1'-0"	1'-6½"	1'-7"	1'-7½"	1'-8"
"c" Bars	#4@24	#4@18	#5@20	#5@14	#5@10	#5@7	#6@7½	#7@8	#7@6	#9@15	#10@15	#10@13	#10@11
"d" Bars	#4@24	#4@18	#5@20	#5@14	#5@10	#6@14	#7@15	#8@16	#7@12	#8@15	#9@15	#9@13	#9@11
Conc. $C_{Y}/L.F.$	0.32	0.38	0.44	0.49	0.55	0.61	0.67	0.73	0.79	1.02	1.10	1.18	1.26
Reinf. $lbs/L.F.$	13	16	19	25	30	37	49	62	76	73	90	104	125

Quantities do not include that portion above the design "H" limit.



TYPICAL LAYOUT EXAMPLE

Revision	By	Approved	Date
Enlarge	[illegible]	A.H.	9-88


SAN DIEGO REGIONAL STANDARD DRAWING

BOX CULVERT WINGWALL TYPES A, B & C DETAILS NO. 2


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A. Kershaw — Coordinator R.C.E. 19807 — Dec. 1975 Date


DRAWING NUMBER **D-79B**



PLAN




PART LONGITUDINAL SECTION




END ELEVATION


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Coordinator R.C.E. 19807 — Date: Dec. 1975	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
		Enlarge	SC	A.H.	9-88
DRAWING NUMBER D-80A	BOX CULVERT WARPED WINGWALL DETAILS NO. 1				



SECTION C-C



SECTION B-B



ALTERNATIVE WARPED WINGWALL

Use where additional protection to toe of embankment is required

WARPED WINGWALLS

WALL DIMENSIONS AND REINFORCING

Element Slope	"H"	8' or less	10'	12'	14'	16'	18'	20'
¼ : 1	Front face reinf	#4 @ 12	#4 @ 7	#5 @ 7	#5 @ 5	#6 @ 6	#7 @ 7	#7 @ 6
	Rear face reinf.	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 12
¾ : 1	Front face reinf	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 10	#4 @ 8	#4 @ 6
	Rear face reinf.	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 10	#4 @ 7	#4 @ 6	#5 @ 8
1¼ : 1	Front face reinf.	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 12	#4 @ 12
	Rear face reinf.	#4 @ 8	#4 @ 8	#4 @ 5	#5 @ 6	#6 @ 7	#6 @ 6	#7 @ 6
"D" at Cut-off Wall		6"	6"	6"	7½"	8"	9½"	11"
"D" at Culvert		6"	6"	6"	8"	9½"	11"	1'-1"

STIFFENING BEAM DIMENSIONS AND REINFORCING

"H" max. \ "L"	12'	14'	16'	18'	20'	25'	30'	35'	40' or more
6'	No beam. Place 2-#6 in each face along top of wall								
8'									
10'	"A" = 1'-0"								
12'	"B" = 9"								
14'	Tot. 6-#6		"A" = 1'-6"						
16'			"B" = 1'-0"		"A" = 1'-10"				
18'		Tot. 6-#7		"B" = 1'-0"		"A" = 2'-0"			
20'			Tot. 6-#8			"B" = 1'-6"			
				Tot. 8-#9					

Notes : Walls designed for 2' surcharge; earth load = 120 #/cu. ft.; equivalent fluid pressure = 36 #/cu ft.
Vary "D" of warped wall uniformly from that at cut-off wall to that at culvert, for max "H" > 12'.
Where abrasion is anticipated increase apron thickness to 7" min. to provide 2" min. reinforcement coverage.
Dimensions "L", "W", "H", "M", "N", Elev "a", "Angle of flare", and end "Slope" (as apply) are shown on the plans.
Concrete shall be class 560-B-3250.

Revision	By	Approved	Date
Enlarge		A.H.	9-88

SAN DIEGO REGIONAL STANDARD DRAWING

BOX CULVERT WARPED WINGWALL DETAILS NO. 2

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen A Kashani — Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER **D-80B**

GENERAL NOTES

QUANTITIES: QUANTITIES ARE FOR THE SLOPED INVERT SLAB AND DO NOT INCLUDE SPLICES IN LONGITUDINAL BARS, NOR TEMPERATURE REINFORCEMENT FOR EXPOSED TOP CULVERT, NOR CONCRETE OR REINFORCEMENT FOR PARAPETS OR CUTOFF WALLS.

SPECIAL COVERAGE: BOX STANDARD PLANS ARE NOT TO BE USED FOR CULVERTS IN A CORROSIVE ENVIRONMENT OR WHERE THERE IS A SEVERE ABRASIVE FLOW CONDITION.

DESIGNATION: SHOW ON PLANS AS SPAN X HEIGHT – STRENGTH CLASSIFICATION X LENGTH THUS 4 x 4 -A x 60', FOLLOWED BY ALTERNATIVES

ALTERNATIVES: INVERT WILL BE SLOPED UNLESS "TRAPEZOIDAL INVERT", "FLAT INVERT" OR "V INVERT" IS INCLUDED IN DESIGNATION. ENDS OF CULVERT WILL BE ROUNDED UNLESS "SQUARE ENDS" ARE DESIGNATED. PARAPETS WILL BE AS SHOWN UNLESS "— FT. PARAPET" IS DESIGNATED IN PLANS. SUCH DESIGNATIONS MAY BE DIFFERENT FOR INLET AND OUTLET ENDS.

REINF. PLACEMENT: MAIN REINFORCEMENT IS POSITIONED TRANSVERSE OR, FOR CURVED CULVERTS, RADIAL. WHEN RADIAL, REINFORCING SPACING IS MEASURED ALONG THE ℄

CONSTRUCTION NOTES

CONCRETE:

BOTTOM SLAB & WALLS SHALL BE CLASS 560-B-3250

TOP SLAB SHALL BE CLASS 560-C-3250

EXPANSION JOINTS:

BOTTOM SLAB – NO EXPANSION JOINTS SHALL BE PLACED.


TOP SLAB AND WALLS – WHEN COVER IS LESS THAN SPAN LENGTH, PLACE ½" EXPANSION JOINT FILLER AT 50'± CENTERS OUTSIDE THE PAVED ROADWAY LANES AND PLACE BRIDGE DETAIL 3-2 AT 50'± CENTERS UNDER PAVED ROADWAY LANES.
WHEN COVER IS MORE THAN SPAN LENGTH, PLACE ½" EXPANSION JOINT FILLER AT 30'± CENTERS AND ADDITIONAL ½" EXPANSION JOINTS AT LOCATIONS OF CHANGE IN FOUNDATION CHARACTER, AS DIRECTED BY THE ENGINEER.

CONSTRUCTION LOADS:

NOT PERMITTED UNTIL CONCRETE HAS REACHED A STRENGTH OF 3,000 PSI OR AGE OF 28 DAYS, WHICHEVER OCCURS FIRST, AND FALSEWORK PLANS HAVE BEEN SUBMITTED BY THE CONTRACTOR, TO THE ENGINEER, AND APPROVED.

CONSTRUCTION JOINTS:

TEMPORARY JOINTS MAY BE PERMITTED IF NORMAL (OR RADIAL) TO ℄ OF RCB. OTHERWISE, THE CONTRACTOR IS TO SUBMIT A PROPOSAL FOR CONSIDERATION



BRIDGE DETAIL 3-2
(Portion)

See Standard Drawing C-15

DESIGN NOTES

SPECIFICATIONS:

DESIGN: A A S H O DATED 1973 WITH REVISIONS AND AS SUPPLEMENTED BY STATE OF CALIFORNIA BRIDGE PLANNING AND DESIGN MANUAL.

SECTIONS DESIGNED FOR CULVERT IN A TRENCH ON HARD FOUNDATION, OR CULVERT UNTRENCHED ON YIELDING FOUNDATION. FOR CULVERTS ON PILES OR ROCK FOUNDATIONS, SPECIAL DESIGN WILL BE REQUIRED

LOADING

LIVE LOAD: FOR LEGAL HIGHWAY LOADS, USE HS20-44 OR ALTERNATIVE, WITH 30% IMPACT FOR ALL COVER DEPTHS NO IMPACT ON INVERT

COVER LESS THAN 2' – WHEEL LOAD DISTRIBUTION ON THE TOP SLAB IS E=0.175S+3.2' LONGITUDINALLY AND CONCENTRATED ALONG THE SPAN. WHEEL LOAD DISTRIBUTION ON THE INVERT SLAB IS 7.5' LONGITUDINALLY AND UNIFORMLY OVER THE BREATH OF THE CULVERT

COVER 2' OR MORE – WHEEL LOADS DISTRIBUTED UNIFORMLY OVER A SQUARE, THE SIDES OF WHICH ARE 1.75 TIMES THE DEPTH OF COVER, BUT NOT LESS LONGITUDINALLY THAN E ON THE TOP SLAB, OR 7.5' ON THE INVERT SLAB WHEN SUCH AREAS FROM SEVERAL WHEEL CONCENTRATIONS OVERLAP, THE TOTAL LOAD SHALL BE CONSIDERED AS UNIFORMLY DISTRIBUTED OVER THE AREA DEFINED BY THE OUTSIDE LIMITS OF THE INDIVIDUAL AREAS, BUT THE OVERALL LONGITUDINAL DIMENSION SHALL NOT EXCEED THE TOTAL LENGTH OF THE SUPPORTING SLAB. NEGLECT LIVE LOAD, ON SINGLE SPANS WHEN COVER IS MORE THAN 8' AND EXCEEDS SPAN, AND ON MULTIPLE SPANS WHEN COVER EXCEEDS DISTANCE BETWEEN EXTERIOR WALLS.

DEAD LOAD: EARTH LOAD OF 120 PCF AND AN EQUIVALENT FLUID PRESSURE OF 36 PCF, REDUCED TO 84 PCF AND 25 PCF RESPECTIVELY FOR CLEAR SPANS OF 20' OR LESS.

UNIT STRESSES: F_s = 20,000 PSI, N=10

F_c = 1,200 PSI

REINFORCEMENT EMBEDMENT IS 1½ DIA. CLEAR, MIN 1" AND IN ¼" INCREMENTS, EXCEPT AS NOTED

DISTRIBUTION "d" BARS EXPRESSED AS A % OF MAIN POSITIVE REINFORCEMENT

CLASSIFICATION "A" TOP SLAB = $\frac{100}{\sqrt{S_{PAN}'}}$, MAX 50% (UNLESS TRAFFIC LONGITUDINAL)


BOTTOM SLAB = #4 @ 18" MAX

CLASSIFICATION "B" TO "E": TOP AND BOTTOM SLABS #4 @ 18" MAX.

USE OF STANDARD DRAWING

"STRENGTH CLASSIFICATION", SYMBOLIZED BY THE LETTERS "A", "B", "C" ETC., AT THE TOP OF THE DATA TABLE IS MERELY A CONVENIENT DESIGNATION FOR A PARTICULAR STRUCTURAL SECTION FOR A CULVERT OF ANY GIVEN OPENING IT IS DICTATED BY THE COVER OR DEPTH OF FILL OVER THE TOP SLAB.

LIVE LOAD & RCB DIRECTIONAL TERMINOLOGY



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A. Kashani Dec. 1975
Coordinator R.C.E. 19887 Date

DRAWING NUMBER D-81A

SAN DIEGO REGIONAL STANDARD DRAWING


BOX CULVERT MISCELLANEOUS DETAILS NO. 1

Revision	By	Approved	Date
Enlarge	[illegible]	G. H.	10/2
JOINT	DM	O. Hatwig	2/95



PART SECTION


⊛ h = S', 6" min.




PART PLAN - SKEWED

PARAPET DETAILS FOR SINGLE SPAN CULVERTS

PARAPET "f" BAR NOS.			
SKEW ANGLE / SPAN	0° TO 15°	16° TO 30°	31° TO 45°
4'	#4	#4	#4
6'	#4	#4	#5
8'	#4	#5	#6
10'	#5	#6	#7
12'	#6	#7	#8
14'	#7	#8	#9




PART SECTION




PART PLAN - SKEWED


PARAPET DETAILS FOR MULTIPLE SPAN CULVERTS



PARAPET DETAIL FOR SKEWED CULVERTS W/O WINGWALLS



COVER: 1' AND GREATER



COVER: EXPOSED TOP AND GREATER

CULVERT EXTENSION

20° SKEW MAXIMUM

Revision	By	Approved	Date
Enlarge	[illegible]	A.H.	10/88


SAN DIEGO REGIONAL STANDARD DRAWING

BOX CULVERT MISCELLANEOUS DETAILS NO. 2


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A. Kaufman — Coordinator R.C.E. 18807 — Dec. 1975 Date

DRAWING NUMBER **D-81B**



ELEVATION



SECTION

NOTES:


1. Fence fabric shall be 2" mesh, 9 gage galvanized wire, chainlink placed on the upstream side of the posts and tension cables.
2. Tension cable shall be 5/16" diameter steel at 18" c/c secured at ends with cable clamps. Secure fence to cable with No. 12 galv. steel wire looped at 6" c/c.
3. Posts shall be 3" diameter steel pipe, 5.79 lb./ft. Fill with mortar after placing.
4. Fence fabric shall be secured to posts with 9 gage wire clips at 9" c/c.

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Harry R. Holt Oct 1982 Chairman R.C.E. C13768 Date	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
DRAWING NUMBER D-82	DEBRIS FENCE				


ELECTRICAL SYSTEMS



DIRECT BURIAL FOUNDATION

ANCHOR BASE FOUNDATION

POLE HEIGHT	MOUNTING HEIGHT	LAMP SIZE (WATTS)
25' ± 2'	27' ± 1'	170 M.V. 100 H.P.S. 90 L.P.S.
28' ± 2'	30' ± 1'	400 M.V. 250 H.P.S. 180 L.P.S.
23' – 0"	26' – 9"	70 H.P.S.
26' – 6"	30' – 0"	150 H.P.S.



Revision	By	Approved	Date
Table	[illegible]	M.B.	5-86


SAN DIEGO REGIONAL STANDARD DRAWING

STREET LIGHTING STANDARD


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A Kenkel — Coordinator R.C.E. 19807 — Dec. 1975 — Date

DRAWING NUMBER **E-1**




STEEL CONDUIT




NON–METALLIC CONDUIT

DIRECT BURIAL FOUNDATION



STEEL CONDUIT



NON–METALLIC CONDUIT


ANCHOR BASE FOUNDATION

(1) 3/4"x 8' copper covered steel ground rod.

(2) Alternate Ground: 15' no. 4 bare stranded copper wire, coiled.

(3) Approved non-metallic conduit.

(4) Steel conduit.



DETAIL A

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Coordinator R.C.E. 19807 — Date: Dec. 1975

DRAWING NUMBER E-2

SAN DIEGO REGIONAL STANDARD DRAWING


GROUNDING OF CONCRETE LIGHTING STANDARDS

Revision	By	Approved	Date



PLAN

NOTE:
Concrete shall be class 560-C-3250



SECTION A–A
STEEL & CONCRETE DIMENSIONS

SECTION B–B
CONDUIT & EQUIPMENT

Revision	By	Approved	Date
Conc.		M.B.	5-86

SAN DIEGO REGIONAL STANDARD DRAWING


PEDESTAL FOR ELECTRICAL EQUIPMENT

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen A Kenkel — Dec. 1975
Coordinator R.C.E. 19807 — Date


DRAWING NUMBER E-33

GENERAL SURFACE IMPROVEMENTS




6" CURB

Area = 0.89 SQ. FT.



8" CURB

Area = 1.09 SQ. FT.



GUTTER

NOTES:

1. Concrete shall be 520-C-2500.
2. See Standard Drawing G-10 for joint details.
3. Slope top of curb 1/4" per foot toward street.

LEGEND ON PLANS

6" curb

Revision	By	Approved	Date
Conc.	[illegible]	M.B.	5-86
Note 3	[illegible]	A.H.	7-88


SAN DIEGO REGIONAL STANDARD DRAWING

CURBS AND GUTTER - SEPARATE

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A. Kershaw — Coordinator R.C.E. 19807 — Dec. 1975 — Date

DRAWING NUMBER **G-1**



TYPE G & H CURB

TYPE	W	* AREA SQ. FT.
G	24"	1.34
H	30"	1.61

* with 6" Curb Face

NOTES:

1. Concrete shall be 520-C-2500.
2. See Standard Drawing G-10 for joint details.
3. Slope top of curb 1/4" per foot toward street.

LEGEND ON PLANS

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A. Kashani Dec. 1975
Coordinator R.C.E. 19807 Date

DRAWING NUMBER **G-2**

SAN DIEGO REGIONAL STANDARD DRAWING

CURB AND GUTTER - COMBINED

Revision	By	Approved	Date
Conc.	[illegible]	M.B.	5-86
Note 3	[illegible]	A.H.	7-88



NOTES

1. Concrete shall be 520-C-2500.
2. See Standard Drawing G-10 for joint details.
3. Monolithic curb, gutter and sidewalk is to be used with Agency approval only.

LEGEND ON PLANS

Revision	By	Approved	Date
Thickness	SC	D S	7-79
Thickness	SH	M.B.	6-82
Conc.	SC	MB	5-86


SAN DIEGO REGIONAL STANDARD DRAWING

MONOLITHIC CURB, GUTTER AND SIDEWALK

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen A Kenchmark — Coordinator R.C.E. 19807 — Dec. 1975 — Date

DRAWING NUMBER G-3



CURB AREA
(2.23 sq. ft.)

NOTES:

1. Transition to type G curb at all curb returns, except where sidewalk ramps are provided, and at all cul-de-sacs with drainage structures.
2. See Standard Drawing D-6.1 for Rolled Curb Inlet.
3. Concrete shall be 520-C-2500.
4. See Standard Drawing G-10 for joint details.

LEGEND ON PLANS

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Coordinator H C E 19807 — Dec. 1975 Date

DRAWING NUMBER G-4


SAN DIEGO REGIONAL STANDARD DRAWING

CURB AND GUTTER-ROLLED


Revision	By	Approved	Date
X-Sect.	TRP	M.B.	10-82
Conc.		M.B.	5-86




TYPE A–SECTION




TYPE B–SECTION




TYPE C–SECTION




TYPE D–SECTION



TYPE E–SECTION



TYPE F–SECTION



Slope end of dike 1:1 when not joining other improvements

ALL TYPES – SIDE VIEW

APPROX. DIKE QUANTITIES	
TYPE	TONS/LIN. FT.
A	0.0250
B	0.0375
C–6"	0.0375
C–8"	0.0583
C–9"	0.0702
D	0.0062
E	0.0194
F	0.0452

NOTES:

1. Dike is to be placed on a minimum 2" of A.C. road surfacing, extending throughout the width of the dike.
2. AR–8000 grade asphalt to be used for all dikes.
3. A.C. dikes may be shaped and compacted with an extrusion machine or other equipment capable of shaping and compacting the material to the required cross section.

LEGEND ON PLANS

Type A Dike

Revision	By	Approved	Date
Type E	JC	GH	10/88
Type F	JC	G.H.	10/88
~~Type E~~	~~JC~~	J. Hohertz	2/95

SAN DIEGO REGIONAL STANDARD DRAWING


DIKES - ASPHALT CONCRETE

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan G. Kaukeinen — Dec. 1975

Coordinator R.C.E. 19807 — Date

DRAWING NUMBER G-5



NOTES

1. Expansion Joints ———— at curb returns, adjacent to structures and at 45' intervals. (See Standard Drawing G-10).
2. Weakened Plane Joints - - - - - - - at mid point of curb return, when required, and at 15' intervals from P.C.R.'s (See Standard Drawing G-10).
3. 1/4" grooves ———— with 1/4" radius edges at 5' intervals.

Revision	By	Approved	Date
Note 4	LC	M.B.	5-86


SAN DIEGO REGIONAL STANDARD DRAWING

SIDEWALK JOINT LOCATIONS


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Coordinator R.C.E. 19807 — Date: DEC. 1975


DRAWING NUMBER G-9




EXPANSION JOINT




CONTACT JOINT



WEAKENED PLANE JOINT
GUTTER AND PAVEMENT




WEAKENED PLANE JOINT
CURB AND SIDEWALK




KEYED JOINT


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Chairman R.C.E. 25902 Date 2-95	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
		Spelling	OM	O. Mohaidat	2-95
DRAWING NUMBER G-10	CONCRETE JOINT DETAILS				




SIDEWALK PLAN




SIDEWALK SECTION



CURB PLAN



PAVEMENT SECTION



SECTION
Showing Cut

NOTE

When distance from, "Area to be removed", to existing joint, edge or score mark is less than minimum shown, "Area to be removed" shall be extended to that joint, edge or score mark.

Revision	By	Approved	Date
Pvmt. min.	[illegible]	M.B.	5-86
Notes	[illegible]	G.H.	9/88


SAN DIEGO REGIONAL STANDARD DRAWING

PORTLAND CEMENT CONCRETE CURB, GUTTER, SIDEWALK AND PAVEMENT REMOVAL AND REPLACEMENT


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen A. Kashani — Dec. 1975
Coordinator R.C.E. 19807 — Date

DRAWING NUMBER **G-11**



PLAN



SECTION A–A

NOTES:

1. Concrete shall be 560-C-3250.
2. - - - - - - - - - - - - =Weakened plane joints.
3. ← ← =Typical flowlines.
4. o =Elevations to be shown on plans.
5. Return segments to be 7" Thick.
6. Curb between P.C.R.s shall be considered as part of cross gutter.
7. In all cases subgrade shall be compacted to 95% min relative compaction to a depth of 12".

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allen A. Kashani Dec. 1975
Coordinator R.C.E. 19807 Date


DRAWING NUMBER G-12

SAN DIEGO REGIONAL STANDARD DRAWING

CROSS GUTTER

Revision	By	Approved	Date
Thickness	JC	O.S.	7-79
Note 1	TKP	M.B.	10-82
Note 6	JC	M.B.	5-86
Note 7	DP	G.L.	5-92






NOTES:

1. Cross gutter to be constructed where the drainage is carried across street.
2. Minimum allowable cross slope is 0.5 %.
3. Concrete shall be 560-C-3250.
4. In all cases subgrade shall be compacted to 95% minimum relative compaction to a depth of 12".

LEGEND ON PLANS



Revision	By	Approved	Date
Thickness	[illegible]	05	7-79
Conc.	TRP	M.B.	10-82
Thickness	JT	G. L.	5-92


SAN DIEGO REGIONAL STANDARD DRAWING

MID-BLOCK CROSS GUTTER


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen A Kenkel — Dec. 1975
Coordinator R.C.E. 19807 — Date


DRAWING NUMBER G-13



PLAN




ELEVATION




SECTION

NOTES
1. No concrete shall be be placed until forms and subgrade are inspected by the Agency.
2. Concrete shall be 520-C-2500.
3. See Standard Drawings G-15 and G-16 for width and location requirements
4. Driveway ramp to extend to 10 feet from curb face or to property linr whichever is less. (For commercial driveways only)
5. See Standard Drawings G-2 and G-10 for curb and joint details.


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Chairman R.C.E. 25902 Date 2-95	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
		New Dwg	DA	O. Hoheisz	2-95
DRAWING NUMBER G-14A	CONCRETE DRIVEWAY (Contiguous Sidewalk)				



PLAN



ELEVATION



SECTION

NOTES
1. No concrete shall be placed until forms and subgrade are inspected by the Agency.
2. Concrete shall be 520-C-2500.
3. See Standard Drawings G-15 and G-16 for width and location requirements
4. Driveway ramp to extend to 10 feet from curb face or to property linr whichever is less. (For commercial driveways only)
5. See Standard Drawings G-2 and G-10 for curb and joint details.

Revision	By	Approved	Date
New Dwg	DH	RLM	2/95


SAN DIEGO REGIONAL STANDARD DRAWING

CONCRETE DRIVEWAYS (Non-contiguous Sidewalk)

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARD COMMITTEE


Chairman R.C.E. 25902 Date 2-95

DRAWING NUMBER G-14B




REQUIREMENT 1

No portion of any curb opening shall be permitted within 6' of the intersection of the prolonged property lines and the curb as shown by arc A.




REQUIREMENT 2

No portion of any curb opening shall be permitted in the curb return where the radius of curb is 25' or less, as shown by arc B.



REQUIREMENT 3

On all curb returns where the radius is more than 25', curb openings may encroach upon each end of the return a distance equal to 12 1/2% or 1/8 of the total length of the arc on the curb return, thus leaving at least 75% of the length of arc on the return face free from driveway encroachment, provided Requirement 1 is met.



REQUIREMENT 4

No portion of any curb opening shall be permitted in the curb return where a seperate turning movement is provided, as shown by arc C

Revision	By	Approved	Date
Reqmt. 3	JC	M.B.	5-86


SAN DIEGO REGIONAL STANDARD DRAWING

DRIVEWAY LOCATION - ADJACENT TO CURB RETURNS AND STREET LINES

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen A Kenkel — Coordinator R.C.E. 19807 — Dec. 1975 — Date

DRAWING NUMBER **G-15**



NOTES

1. Curb openings, except for joint-use driveways and drive ways on lots having 21 - foot frontage or less, shall be located at least 3 feet from the side property line extended.
2. Not more than 40% of the property frontage on residential lots, nor 60% of the property frontage on commercial lots may be allocated for driveway curb openings, except that lots having frontage of less than 45' are entitled to one 12'driveway (18 foot curb opening).
3. All driveways and curb openings shall be a minimum of 3 feet from any obstruction, i.e., poles, hydrants, etc.
4. No portion of any driveway shall be allowed across a line extending normal to the roadway from the front corner of the property, except that joint-use driveways may be permitted in special instances where written approval of both property owners is filed with the Agency.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A. Kashani Dec. 1975
Coordinator R.C.E. 19807 Date

DRAWING NUMBER G-16


SAN DIEGO REGIONAL STANDARD DRAWING

DRIVEWAY LOCATION AND WIDTH REQUIREMENTS

Revision	By	Approved	Date
Note 2	JP		5-92



TYPICAL PLAN




℄ SECTION

NOTES

1. Sidewalk ramps shall be installed as required by Agency.
2. D = distance shown on plans.
3. R = radius shown on plans (3 ft. minimum).
4. O = elevations shown on plans (top of curb, and gutter elev).
5. — — — = 1/2" expansion joints.

LEGEND ON PLANS



Revision	By	Approved	Date
Thickness	JC	D.S.	7-79
Conc.	JC	M.B.	5-86
Note 5	JC	G.H.	7-88


SAN DIEGO REGIONAL STANDARD DRAWING

ALLEY APRON


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan O Kurland — Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER G-17



TYPICAL SECTION




TYPICAL PLAN


NOTES

1. Concrete shall be 560-C-3250.
2. See Standard Drawing G-10 for joint details.
3. Adjust 15' interval between Transverse Joints to match adjacent existing improvements.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Coordinator R.C.E. 19807 — Dec. 1975 Date	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
		Conc.	RC	M.B.	5-86
	CONCRETE PAVEMENT, WIDTH 40' OR LESS				
DRAWING NUMBER G-18					



TYPICAL SECTION



TYPICAL PLAN

NOTES

1. Concrete shall be 560-C-3250.
2. See Standard Drawing G-10 for joint details.
3. Adjust 15' interval between Transverse Joints to match adjacent existing improvements.

Revision	By	Approved	Date
Conc.	[illegible]	M.B.	5-96


SAN DIEGO REGIONAL STANDARD DRAWING

CONCRETE PAVEMENT WIDTH 40' TO 62'


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen A. Kashani — Coordinator R.C.E. 19807 — Dec. 1975 — Date

DRAWING NUMBER G-19



TYPICAL SECTION




TYPICAL PLAN


NOTES

1. Concrete shall be 560-C-3250.
2. See Standard Drawing G-10 for Joint Details.
3. Adjust 15' interval between Transverse Joints to match adjacent existing improvements.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Coordinator R.C.E. 19807 — Date: Dec. 1975	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
		Conc.		M.C.	5-86
DRAWING NUMBER G-20	CONCRETE PAVEMENT WIDTH 53' TO 69'				



TYPICAL SECTION



TYPICAL PLAN

NOTES

1. Concrete shall be 560-C-3250
2. See Standard Drawing G-10 for joint details.
3. Adjust 15' interval between Transverse Joints to match adjacent existing improvements.

Revision	By	Approved	Date
Conc.	[illegible]	M.B.	5-16


SAN DIEGO REGIONAL STANDARD DRAWING

CONCRETE PAVEMENT, ALLEY SECTION, WIDTH 40' OR LESS


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A. Kashani — Coordinator R.C.E. 19807 — Dec. 1975 — Date

DRAWING NUMBER **G-21**




ELEVATION




SECTION A–A


LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Allan O Kaufman Dec. 1975 Coordinator R.C.E. 19807 Date	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
		Conc.		M.B.	5-86
DRAWING NUMBER G-22	CUTOFF WALL AT END OF PAVEMENT				



ELEVATION



SECTION A–A

LEGEND ON PLANS



Revision	By	Approved	Date
Conc.	[illegible]	M.B.	5-86


SAN DIEGO REGIONAL STANDARD DRAWING

CUTOFF WALL AT END OF ALLEY PAVEMENT

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen A Kaufman — Coordinator R.C.E. 19807 — Dec. 1975 — Date


DRAWING NUMBER G-23



NOTES

1. Trench edges to be cut a minimum of 6" wider than trench for trenches 3' wide or less, and 12" wider for trenches over 3' wide.
2. Existing A.C. shall be cut and removed in such a manner so as not to tear, bulge or displace adjacent pavement. Edges shall be clean and vertical. All cuts shall be parallel or perpendicular to street centerline, when practical.
3. Base material shall be replaced to depth of existing base. A.C. may be substituted for base material.
4. A tack coat of asphaltic emulsion or paving asphalt shall be applied to existing A.C. at all contact surfaces, prior to resurfacing.
5. Asphalt Concrete Resurfacing:
   a) Minimum total thickness shall be one inch greater than existing A.C.
   b) A.C. shall be hot plant mix.
   c) Finish course for Type B resurfacing shall be laid down using a spreader box.
6. All A.C. resurfacing shall be seal coated with an emulsified asphalt and covered with sand. Chip sealing shall be applied as required by Agency.
7. Type B shall not be used on lateral crossings.
8. Sloughing of trench under pavement shall be cause for requiring additional pavement and base.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
Chairman R.C.E. 25902 Date 2-95		Notes	OM	RJM	3/95
DRAWING NUMBER G-24	TRENCH RESURFACING TYPES A & B				



TYPE C

TYPE D

GENERAL NOTES

1. Existing A.C. shall be cut and removed in such a manner so as not to tear, bulge or displace adjacent pavement. Edges shall be clean and vertical. All cuts shall be parallel or perpendicular to street centerline, when practical.
2. Sloughing of trench under pavement shall be cause for requiring additional pavement and base.
3. Trench edges shall be cut a minimum of 6" wider than trench for trenches 3' wide or less, and 12" wider for trenches over 3' wide.

NOTES TYPE-C

1. Concrete shall be colored black where required to match existing pavement, method to be specified by Agency.
2. Minimum concrete thickness:
   Alleys and local residential street ----------5 inches
   Major streets and highway ----------7 inches
   Trench resurfacing in P.C.C. pavement shall have the above minimum thickness or match the existing concrete thickness plus one inch, whichever is greater.

NOTES TYPE-D

1. A.C. shall be hot plant mix.
2. A tack coat of asphaltic emulsion or paving asphalt shall be applied to the existing A.C. at all contact surfaces and to portland cement concrete prior to placing new A.C.
3. A.C. resurfacing shall be seal coated with an emulsified asphalt and covered with sand. Chip sealing shall be applied as required by Agency.

Revision	By	Approved	Date
NOTES	DM	RLM	2/95


SAN DIEGO REGIONAL STANDARD DRAWING

TRENCH RESURFACING TYPES C & D


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Chairman R.C.E. 25902 Date 2-95


DRAWING NUMBER G-25



PLAN



ELEVATION




SECTION

NOTES

1. No concrete shall be placed until forms and subgrade are inspected by the Agency.
2. Concrete shall be 520-C-2500.
3. See Standard Drawing G-15 and G-16 for width and location requirements.
4. See Standard Drawings G-2 and G-10 for curb and joint details.

LEGEND ON PLANS



℄ of Alt. Commercial Driveway

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Harry R. Holt Oct 1982
Chairman R.C.E. C13768 Date


DRAWING NUMBER G-26

SAN DIEGO REGIONAL STANDARD DRAWING

CONCRETE DRIVEWAY COMMERCIAL ALTERNATE

Revision	By	Approved	Date
Conc.	[illegible]	M.B.	5-86
Note 4	[illegible]	A.H.	7-88


X	Y	Z	CT
Curb Height	Ramp Length	Side Slope	Curb Transition
1"	0' - 6"	1' - 6"	0' - 0"
2"	1' - 6"	1' - 6"	0' - 0"
3"	2' - 6"	1' - 8"	0' - 0"
4"	3' - 6"	2' - 4"	0' - 0"
5"	4' - 6"	3' - 0"	0' - 0"
6"	5' - 6"	3' - 0"	0' - 0"
7"	5' - 6"	3' - 0"	1' - 0"
8"	5' - 6"	3' - 0"	2' - 0"




TYPE A


CONSTRUCTION NOTES

1. Set false header for back of ramp at curb height above gutter grade to maximum 6".
2. Where shown on the plans, construct monolithic curb for retention of street drainage or to meet adjacent improvements.



TYPE B





SECTION A–A

NOTE
See Standard Drawing G-32 for general notes.

Revision	By	Approved	Date
Notes		a.H.	9/88


SAN DIEGO REGIONAL STANDARD DRAWING

PEDESTRIAN RAMP TYPES A AND B (NEW CONSTRUCTION)


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

M. Bahmani 4-25-86
Coordinator R.C.E. C21133 Date


DRAWING NUMBER G-27



PLAN VIEW



ELEVATION



SECTION A-A

TABLE A			
X	Y	Z	Z1
CURB HEIGHT	RAMP LENGTH (12:1)	SIDE SLOPE (8:1)	SIDE SLOPE (12:1)
1"	0'-6"	1'-6"	1'-6"
2"	1'-6"	1'-6"	1'-6"
3"	2'-6"	1'-8"	2'-6"
4"	3'-6"	2'-4"	3'-6"
5"	4'-6"	3'-0"	4'-6"
6"	5'-6"	3'-8"	5'-6"
7"	6'-6"	4'-4"	6'-6"
8"	7'-6"	5'-0"	7'-6"

NOTES

1. If inadequate R/W exists to provide 4' landing, side slopes shall be increased to 12:1 per side slope "Z1" in Table A. Landing shall be 3' minimum in all other cases.
2. See Standard Drawing G-32 for general notes.
3. Type A-1 is a designation for ramp at curb return.
4. Type B-1 is a designation for ramp at straight curb.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Chairman R.C.E. 25902 Date 2-95


DRAWING NUMBER G-28

SAN DIEGO REGIONAL STANDARD DRAWING

PEDESTRIAN RAMP TYPES A-1 AND B-1 (For Existing Sidewalk)

Revision	By	Approved	Date
ADA Rgmt	OA	RLM	2/95





SECTION A–A

NOTES

1. Type C ramps are only to be used to mitigate existing conditions where inadequate right of way exists to use standard drawing G-27, G-28 or G-30 and are not to be used in new construction.
2. See Standard Drawing G-32 for general notes.

X* Curb Height	Y* Ramp Length
4"	1' - 6"
5"	2' - 6"
6"	3' - 6"
7"	4' - 6"
8"	5' - 6"
9"	6' - 6"
10"	7' - 6"
11"	8' - 6"
12"	9' - 6"
13"	10' - 6"

Revision	By	Approved	Date
NOTES	JC	A.H.	8-88
Y* dim.	JP	MH	5-92


SAN DIEGO REGIONAL STANDARD DRAWING

PEDESTRIAN RAMP TYPE C


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

M. Bahmanyar 4-25-86
Coordinator R.C.E. C21133 Date


DRAWING NUMBER G-29



PLAN VIEW



ELEVATED VIEW



SECTION A–A

See Detail–B
Std. Dwg. G–32

TABLE A			
X	Y	Z	CT
DESIGN CURB HEIGHT	RAMP LENGTH (12:1)	SIDE SLOPE (8:1)	CURB TRANS.
1"	0'–6"	1'–6"	(SEE NOTE NO. 3)
2"	1'–6"	1'–6"	
3"	2'–6"	1'–8"	
4"	3'–6"	2'–4"	
5"	4'–6"	3'–0"	
6"	5'–6"	3'–8"	
7"	6'–6"	4'–4"	
8"	7'–6"	5'–0"	

NOTES

1. See Standard Drawing G–32 for general notes.
2. X= Design Curb Height as shown on plans.
3. Curb transition (CT) shall be 1'–0" for each one inch difference between existing curb height and design curb height.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

2-95


Chairman R.C.E. 25902 Date

DRAWING NUMBER G–30

SAN DIEGO REGIONAL STANDARD DRAWING

PEDESTRIAN RAMP TYPE C–1 (For Existing Sidewalk)


Revision	By	Approved	Date
ADA Rqmt	DH	RLR	2/95




TYPICAL PLAN

X	Y	Z
CURB HEIGHT	RAMP LENGTH (12:1)	SIDE SLOPE (8:1)
1.0"	1'-6"	1'-6"
1.5"	1'-6"	1'-6"
2.0"	1'-6"	1'-6"
2.5"	2'-0"	1'-6"
3.0"	2'-6"	1'-8"
3.5"	3'-0"	2'-0"
4.0"	3'-6"	2'-4"
4.5"	4'-0"	2'-8"
5.0"	4'-6"	3'-0"
5.5"	5'-0"	3'-4"
6.0"	5'-6"	3'-8"
6.5"	6'-0"	4'-0"
7.0"	6'-6"	4'-4"
7.5"	7'-0"	4'-8"
8.0"	7'-6"	5'-0"

MAX. 5'6" per AMM 10/15/86



PLAN VIEW



SECTION A-A

NOTE
See Standard Drawing G-32 for general notes.

Revision	By	Approved	Date
ADA Rgmt	OA	RLM	4/96

SAN DIEGO REGIONAL STANDARD DRAWING


PEDESTRIAN RAMP TYPE D

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Chairman R.C.E. 25902 Date 2-95

DRAWING NUMBER G-31


1. The removal of existing concrete curb, gutter, sidewalk and pavement for pedestrian ramp installation shall comply with Standard Drawing G-11.
2. Areas shown thus:  shall have a heavy broom "ripple" texture finish, transverse to axis of ramp contrasting visually with adjoining surfaces.
3. Areas shown thus:  are the minimum required for a complete ramp installation and shall be concrete class 520-C-2500.
4. If obstructions such as inlets, utility poles, fire hydrants, etc., are encountered, the ramp locations may be adjusted upon the approval of the Resident Engineer.
5. Ramp slope shall be a minimum grade of 15:1.
6. The ramp slopes will be measured relative to the sidewalk slope, see Detail A below. Adjoining slope beyond ramp shall not exceed 20:1 (5%).



Slope = X:Y
Where X is level plane




DETAIL A



DETAIL B

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Chairman R.C.E. 25902 Date 2-95	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
		Notes	DM	RLM	2/95
	GENERAL NOTES FOR PEDESTRIAN RAMPS	Detail			
DRAWING NUMBER G-32					



NOTES

1. Concrete encasement or sand cement slurry backfill shall have a maximum slump of 4 inches.
2. Concrete encasement and sand cement slurry backfill shall be thoroughly consolidated to encase conduits. Tampers or vibrators shall be used.
3. Concrete shall be screeded off to match existing pavement grade and floated to assure proper edge match.
4. A tack coat shall be applied to the concrete and existing asphalt pavement prior to placing the new asphalt pavement wearing surface.
5. Existing A.C. pavement will not require sawcutting when using rockwheel for excavation.
6. Concrete trench cover shall be a minimum 5 1/2 inches thick in alleys or local residential streets and 7 inches thick in all other streets.
7. Allow concrete backfill or concrete trench cover seven calendar days minimum but no longer than thirty calendar days to cure and dry before applying the asphalt concrete wearing surface.
8. In major or prime arterial streets, an approved set accelerating admixture, such as Calcium Chloride, may be used only with prior approval of the agency's Engineer.
9. Only type A shall be permitted for supply cables of 750 volts or less. See California Public Utility Commission General Order No. 128, Rule 33.4 D. (1) (b).
10. Select material with a minimum sand equivalent of 50 shall be backfilled to 3" min. above the conduit. Sand cement slurry backfill (100-E-100) may be substituted for select material.

Revision	By	Approved	Date
Notes	[illegible]	[illegible]	9/00
Notes 8,10	JP	[illegible]	5-92


SAN DIEGO REGIONAL STANDARD DRAWING

NARROW TRENCHING TYPES A & B BACKFILL & RESURFACING

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

M. Bahm 4-25-96
Coordinator R.C.E. C21133 Date

DRAWING NUMBER G-33



TYPE C

TYPE D

NOTES

1. Cement Slurry Backfill:
   a. Cement slurry backfill shall have a maximum slump of 4 inches.
   b. Cement slurry backfill shall be thoroughly consolidated to encase conduits. Tampers or vibrators shall be used.
   c. Cement slurry backfill shall be as follows:
      Alleys and local residential streets . . . . Class (190-E-400)
      All other streets . . . . . Class (380-E-800)
2. A tack coat shall be applied to the cement slurry backfill and existing asphalt pavement prior to placing the new asphalt surface.
3. Asphaltic Concrete Resurfacing:
   Type C
   a. Allow cement slurry backfill 24 hours minimum to cure before resurfacing.
   b. Thickness shall match the existing A.C. with a minimum of 2 inches.
   c. A.C. shall be hot mix.
   Type D
   a. Allow cement slurry backfill seven days minimum to cure before planing.
   b. Plane existing asphalt pavement and slurry backfill 1 inch minimum or one half thickness of existing A.C. not to exceed 2 inches.
   c. A.C. shall be hot mix.
4. A.C. resurfacing shall be sealed or chip sealed when required by the agencies Engineer.
5. Existing A.C. pavement will not require sawcutting when using rockwheel for excavation.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


M. Bahmanyar 4-25-86
Coordinator R.C.E. C21133 Date

DRAWING NUMBER G-34

SAN DIEGO REGIONAL STANDARD DRAWING

NARROW TRENCHING TYPES C & D BACKFILL & RESURFACING

Revision	By	Approved	Date
NOTES	JC	A.H.	8-88



TYPE E

TYPE F

NOTES

1. Concrete backfill or sand cement slurry backfill shall have a maximum slump of 4 inches.
2. Concrete backfill and sand cement slurry backfill shall be thoroughly consolidated to encase conduits. Tampers or vibrators shall be used.
3. Concrete shall be screeded off to match existing pavement grade and floated to assure proper edge match.
4. Concrete trench cover shall be a minimum of 5½ inches thick in alleys or local residential streets and 7 inches thick in all other streets.
5. Existing concrete pavement will not require sawcutting when using rockwheel for excavation.
6. In major or prime arterial streets, an approved set accelerating admixture, such as Calcium Chloride, may be used only with prior approval of the agency's Engineer.
7. Only Type E shall be permitted for supply cables of 750 volts or less. See California Public Utility Commission General Order No. 128, Rule 33.4 D. (1) (b).
8. Select material with a minimum sand equivalent of 50 shall be backfilled to 3"min. above the conduit. Sand cement slurry backfill (100-E-100) may be substituted for select material.

Revision	By	Approved	Date
Notes 7, 8	[illegible]	G.H.	9/88
Notes 6, 9	JP	[illegible]	5-92


SAN DIEGO REGIONAL STANDARD DRAWING

NARROW TRENCHING TYPES E & F BACKFILL & RESURFACING

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

M. Bahmanyar 4-25-86
Coordinator R.C.E. C21133 Date

DRAWING NUMBER G-35




NOTES:


1. Trench resurfacing shall be done according to governmental (permitting) Agency's requirements.
2. The sand used for the slurry backfill shall meet the requirements for fine aggregate Subsection 400–1.3 listed in the Standard Specifications for Public Works Construction. Slurry must be firm prior to trench resurfacing.
3. Slurry backfill may be used in permeable soils and shall not be used where it will impede subsurface drainage.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
Chairman SEPT. 1988 Date					
DRAWING NUMBER G-36	SLURRY BACKFILL				


SPRINKLER IRRIGATION SYSTEMS



PLAN VIEW



LOCATION OF SPRINKLER HEADS ADJACENT TO EXISTING IMPROVEMENTS



ELEVATION

NOTES

1. Teflon tape, 3/4" wide, shall be used on all threaded connections.
2. Close nipples shall not be used.

LEGEND ON PLANS

Show a number to indicate type head.

Revision	By	Approved	Date
Anti-Drain	JP	G.L.	5-92


SAN DIEGO REGIONAL STANDARD DRAWING

SHRUBBERY SPRINKLER HEAD FIXED SPRAY TYPE


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A Kenkel — Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER I-1



PLAN



ELEVATION


NOTES

1. All fittings shall be P.V.C. Sch. 40.
2. Teflon tape, 3/4" wide, shall be used on all threaded connections.
3. Short nipples shall not be used.
4. Anti-drain/Excess Flow Valve shall be installed under all heads unless heads have a "Built-in" Anti-drain or check valve.


LEGEND ON PLANS

Show a number to indicate type head ◯

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Allan A Kashmal Dec. 1975 Coordinator R.C.E. 19807 Date	SAN DIEGO REGIONAL STANDARD DRAWING	Revision / By / Approved / Date Alt. Instl. / TRP / M.B. / 10-82 VALVE / RC / GH / 8-88 Swing joint / JP / GH. / 5-92
DRAWING NUMBER 1-2	SPRINKLER HEAD POP UP SPRAY TYPE	



PLAN



ELEVATION

NOTES

1. All fittings shall be P.V.C. Sch. 40.
2. All nipples shall be P.V.C. Sch. 80.
3. Teflon tape, 3/4" wide, shall be used on all threaded connections.
4. Short nipples shall not be used.
5. Anti-drain/Excess Flow Valve shall be installed under all heads unless heads have a "Built-in" Anti-drain or check valve.

LEGEND ON PLANS

Show a number to indicate type head ○

Revision	By	Approved	Date
Valve	JC	GH	9/88


SAN DIEGO REGIONAL STANDARD DRAWING

LAWN SPRINKLER HEAD
POP UP ROTARY (WITH SWING JOINT)

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan O Kashmar — Dec. 1975
Coordinator R.C.E. 19807 — Date

DRAWING NUMBER I-3




PLAN

COUPLER KEY-
SINGLE LUG





KEY FOR
LOCK TOP



ELEVATION

NOTES

1. Quick coupling valves in lawn areas shall be set to grade.
2. Quick coupling valves in shrub areas shall be set 2 inches above grade.
3. Dimensions of concrete anchors are minimum.
4. Close nipples shall not be used.

LEGEND ON PLANS

Q.C.V.

Revision	By	Approved	Date
Note 2	TRP	M.B.	10-82


SAN DIEGO REGIONAL STANDARD DRAWING

QUICK COUPLING VALVE

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Coordinator R.C.E. 19807 — Date: Dec. 1975

DRAWING NUMBER 1-5




NOTES

1. Hose bibb shall be loose key operated, all brass or bronze construction, angle pattern with removable bonnet and stem assembly, replaceable seat washers and stem packing glands.
2. Unless otherwise specified, the hose connection thread shall be 3/4" male hose thread (pacific coast), and the riser opening thread shall be 3/4" female I.P.S. Discharge opening shall be 90° to riser opening.

LEGEND ON PLANS

■

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Allen A Kershaw Dec. 1975 Coordinator R.C.E. 19807 Date	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
		Set Back	TRF	M.B.	10-82
	HOSE BIBB (GARDEN VALVE)				
DRAWING NUMBER I-6					



NOTES

1. Atmospheric vacuum breakers shall be installed approximately 6" above the finished grade and above a sufficient number of sprinkler heads closest to the vacuum breaker so that at no time will it be subjected to back pressure or drainage.
2. Close nipples shall not be used.
3. All fittings, including the atmospheric vacuum breaker, shall not be of smaller size than the valve.
4. Teflon tape, 3/4" wide, shall be used on all threaded connections.
5. For use on lines 2 inches and smaller.

LEGEND ON PLANS

Revision	By	Approved	Date
Union	TRP	M.B.	10-82


SAN DIEGO REGIONAL STANDARD DRAWING

BACKFLOW PREVENTER ATMOSPHERIC VACUUM BREAKER (2" & SMALLER)

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A. Kershaw — Coordinator R.C.E. 19807 — Dec. 1975 — Date

DRAWING NUMBER I-7




NOTES

1. Continuous pressure vacuum breakers shall be installed approximately 12 inches above finished grade and at the highest point in the line.
2. Continuous pressure vacuum breakers shall not be subjected to back pressure or drainage.
3. Teflon tape 3/4" wide shall be used on all threaded connections.
4. Close nipples shall not be used.

LEGEND ON PLANS

(V)(⊗)

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
Allan A. Kashuba Dec. 1975		Note 1	[illegible]	D.S.	7-79
Coordinator R.C.E. 19807 Date	BACKFLOW PREVENTER · CONTINUOUS PRESS. VAC. BREAKER ASSY. (2" & SMALLER)	Reference	TRP	M.B.	10-82
DRAWING NUMBER I-8					



NOTES:

1. All fittings on assembly shall be flanged.
2. Buried cast iron pipe and fittings shall be polyethylene wrapped with 2 inch wide plastic backed adhesive tape (8 mil thickness). Use 1/2 inch overlap.
3. Cast iron pipe and fittings shall be cement mortar lined.
4. All exposed cast iron shall be painted with one coat of primer and two coats of exterior enamel.
5. Concrete pad shall be 24 inches wide.
6. Backflow preventer assembly shall be tested upon installation by a certified backflow device tester. Contractor shall provide Engineer with written test results completed by certified backflow tester prior to the backflow preventer assembly's acceptance by Engineer.
7. Adapt inlet and outlet fittings to main as required.

LEGEND ON PLANS

Revision	By	Approved	Date
New Dwg.	BC	A.H.	10/88


SAN DIEGO REGIONAL STANDARD DRAWING

BACKFLOW PREVENTER REDUCED PRESSURE PRINCIPLE ASSEMBLY-LARGER THAN 2"


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Chairman — Date: SEPT. 1988

DRAWING NUMBER I-9



STANDARD INSTALLATION



ALTERNATE PIPE
SLEEVE INSTALLATION


NOTES

1. All valves shall be furnished with a standard manual control valve bronze cross handle.
2. All valves shall be installed within 12" of the water main, unless otherwise shown on the plans.
3. Close nipples shall not be used.


LEGEND ON PLANS

⊗ G.V.


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Allan D Kenkel Dec. 1975 Coordinator R.C.E. 19807 Date	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
		Union	JRP	M.B.	10-82
	GATE VALVE (2" AND SMALLER)				
DRAWING NUMBER I-12					



ANGLE VALVE



GLOBE VALVE
(special cases only)



ALTERNATE PIPE
SLEEVE INSTALLATION

NOTES

1. All Manual Valves shall be furnished with a standard manual control valve bronze cross handle.
2. All valves shall be installed with 12" of the water main, unless otherwise shown on the plans.
3. All Manual Valves shall be furnished with a removable bonnet and packing gland nut.
4. Close Nipples shall not be used.
5. Locking cap shall be mounted flush with finish grade in turf areas & 1 inch above finish grade in shrub areas.

LEGEND ON PLANS

M.C.V.

Revision	By	Approved	Date
Union	TRF	M.B.	10-82
Note 5	SC	M.B.	5-86


SAN DIEGO REGIONAL STANDARD DRAWING

MANUAL VALVES

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A. Kershaw — Coordinator R.C.E. 19807 — Dec. 1975 — Date

DRAWING NUMBER I-13



TYPICAL ELEMENTARY DIAGRAM FOR WIRING ELECTRICAL REMOTE CONTROL VALVE

PLAN



ELEVATION


NOTES:


1. Splicing shall be made in valve boxes and pull boxes only. See Standard Drawing I-15 for splice details.
2. Close nipples shall not be used.
3. Spare wires terminating in valve boxes shall have their ends insulated, the same as for a splice.
4. When two or more valves are installed in the same location, they shall be in manifold using red brass fittings, with a globe valve installed at the start of the manifold.
5. All valves shall be installed with a union on the downstream side of the valve. The union shall be P.V.C.
6. Valve/controller identification shall be painted on the valve boxes. Use only aluminum asphaltic base water proof paint.
7. Clearance between piping and valve box shall be 1" to 2" typical.

LEGEND ON PLANS

▼ R.C.V

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Chairman RCE 25902 Date 5-11-92	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
DRAWING NUMBER I-14	REMOTE CONTROL VALVE				





NOTES

1. Install pull boxes as shown on plans.
2. At junctions where runs combine, splice common ground in pull box.
3. Pull box cover shall be permanently marked "ELECTRIC".
4. Conductors for each controller clock shall be harnessed separately and at sufficient intervals to maintain a definite bundle.
5. All splices shall be made with a properly set mechanical splice connector entirely enclosed in self-curing resin and shall be completely water-proof.
6. All spare wire ends shall be insulated in the same manner as wire splices.
7. If specified, all splices shall be soldered with metallic alloy solder prior to installing connectors.
8. Wire bundles inside pull boxes shall be at least 4 inches from the under side of the box cover. Minimum size pull box shall be as shown above. Larger boxes may be necessary to meet 4 inch clearance requirement.

LEGEND

P.B.

Revision	By	Approved	Date
Notes	SC	A.H.	10/88


SAN DIEGO REGIONAL STANDARD DRAWING

ELECTRICAL PULL BOX FOR DIRECT BURIAL CONTROL WIRES AND SPLICE DETAILS

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Coordinator R.C.E. 19807 — Date: Dec. 1975

DRAWING NUMBER I-15



NOTE
See Standard Drawing I-25 or I-26 for water line trench details.

NORMAL LOCATIONS OF CONTROL WIRES




ALTERNATE LOCATION OF CONTROL WIRES

NOTES:

1. Bedding material shall have a sand equivalent of 50, minimum
2. Place a 3" wide red continuous plastic tape trench marker, 9" to 12" below finish grade, directly above the direct burial control wires.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Coordinator R.C.E. 19807 — Date: Dec. 1975	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
		Reference	JRP	M.B.	10-82
		MARKER	JC	O.H.	3-88
	DIRECT BURIAL CONTROL WIRE				
DRAWING NUMBER **I-16**					



NOTES:

1. Install in each enclosure, one 25 watt incandescent lamp in a two–prong plug in light socket. Install in receptacle.
2. A 15 amp (minimum) circuit is required at each double receptable (120 V).
3. Each controller shall have a power ON–OFF switch, with lock–out. tag–out facility.

LEGEND ON PLANS



Revision	By	Approved	Date


SAN DIEGO REGIONAL STANDARD DRAWING

IRRIGATION SYSTEMS
ELECTRIC CONTROLLER CLOCK
PEDESTAL MOUNTING


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Chairman RCE 25902 Date 5-1-92

DRAWING NUMBER I-17



SIDE VIEW



ELEVATION

NOTES

1. For location of supply conduit and conductor, refer to the plans.
2. Controller shall be grounded at power supply by ground wire.
3. Make all electrical connections inside controller cabinet.
4. Each controller shall have a power on/off switch, with lock-out, tag-out facility.

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A. Kershaw — Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER I-18


SAN DIEGO REGIONAL STANDARD DRAWING

IRRIGATION SYSTEMS ELECTRIC CONTROLLER CLOCK WALL MOUNTING

Revision	By	Approved	Date
Note 4	JP	S.K.	5-92



LEVEL INSTALLATION



SLOPE INSTALLATION

LEGEND ON PLANS

Show a number to indicate type head ○

Revision	By	Approved	Date
Stake	TRP	M.B.	10-82
Clamps	JP	S. A.	5-92


SAN DIEGO REGIONAL STANDARD DRAWING

IMPACT HEAD ABOVE GROUND PIPE INSTALLATIONS

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A Kenkel — Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER 1-19




ELEVATION

SIDE VIEW

NOTE

Stake shall be placed no greater than 15' apart and at each riser.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Coordinator R.C.E. 19867 — Dec. 1975 Date	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
DRAWING NUMBER I-20	PINNING OF PIPE ABOVE GROUND PIPE INSTALLATIONS				



NOTE

All Galvanized Pipe, Nipples and Fittings installed underground shall be wrapped with 2" wide plastic backed adhesive tape, use ½" overlap.

LEGEND ON PLANS

M.C.V.

G.V.

Revision	By	Approved	Date
Note	JC	D.S.	7-74

SAN DIEGO REGIONAL STANDARD DRAWING


MANUAL CONTROL VALVE AND GATE VALVE INSTALLATION FOR ABOVE GROUND PIPE INSTALLATIONS

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A. Kershaw — Dec. 1975

Coordinator R.C.E. 19807 — Date

DRAWING NUMBER I-21



PLAN



ELEVATION

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A Kershaw Dec. 1975
Coordinator R.C.E. 19807 Date

DRAWING NUMBER I-22

SAN DIEGO REGIONAL STANDARD DRAWING


QUICK COUPLER ASSEMBLY ABOVE GROUND PIPE INSTALLATIONS

Revision	By	Approved	Date



SWING JOINT DETAIL

PLAN




ELEVATION

NOTE

Swing Joints shall be used at each change of grade.

LEGEND ON PLANS



Revision	By	Approved	Date

SAN DIEGO REGIONAL STANDARD DRAWING


SWING JOINT AND PIPE INSTALLATION ON SLOPES ABOVE GROUND PIPE INSTALLATIONS

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A. Kenkel — Dec. 1975

Coordinator R.C.E. 19807 — Date

DRAWING NUMBER I-23



PLAN



ELEVATION

NOTES

1. Double swing joint shall be used where changes of grade and alignment occur simultaneously.
2. Double swing joint shall be used for expansion joint on long runs of galvanized pipe. (300' maximum runs)

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A. Kershaw — Coordinator R.C.E. 19807 — Dec. 1975 Date


DRAWING NUMBER I-24

SAN DIEGO REGIONAL STANDARD DRAWING

DOUBLE SWING JOINT ABOVE GROUND PIPE INSTALLATIONS

Revision	By	Approved	Date





Details not shown are same as above.

MULTIPLE PIPE INSTALLATION DETAIL

(non–pressure pipe only, see Note 6 for pressure pipe)

NOTES

1. Backfill material shall be compacted to a relative compaction of 90% or more.
2. All P.V.C. pipe shall lay free in the trench with no induced strain and with sufficient allowance for expansion and contraction as recommended by the manufacturer.
3. Teflon tape, 3/4" wide shall be used on all threaded connections.
4. The letter W shall be stamped or chiseled on the improvement (curb–sidewalk) directly above the pressure pipeline.
5. All plastic pipe under pavement shall be installed in a P.V.C. sleeve.
6. Minimum clearance between pressure pipes shall be 2 inches.

Revision	By	Approved	Date
TEXT	DM	O. Nahrig	2-95


SAN DIEGO REGIONAL STANDARD DRAWING

TRENCH DETAIL P.V.C. AND/OR COPPER PIPE (3" AND SMALLER)

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Chairman R.C.E. 25902 Date 2-95


DRAWING NUMBER I–25




NOTES

1. Backfill material shall be compacted to a relative compaction of 90% or more.
2. All pipeline fittings shall be cast iron, short body, Class 250, cement mortar lined and polyethylene wrapped. All fittings shall have thrust blocks or anchors.
3. The letter W shall be stamped or chiseled on the improvement (curb–sidewalk) directly above the pressure pipeline.
4. No P.V.C. pressure pipeline shall be installed within 3' of any line, unless otherwise specified.


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Allen A Kenkel Dec. 1975 Coordinator R.C.E. 19807 Date	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
		Title	TRP	M.B.	10-82
	TRENCH DETAIL — ASBESTOS CEMENT PIPE AND 4" AND LARGER P.V.C.	Title	RC.	J. H.	7-88
DRAWING NUMBER 1-26					



PLAN



ELEVATION



CAST IRON
VALVE WELL CAP

LEGEND ON PLANS

Revision	By	Approved	Date
Dimension	[illegible]	A.H.	7-88

SAN DIEGO REGIONAL STANDARD DRAWING


VALVE WELL AND COVER

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A. Kashuba — Coordinator R.C.E. 19807

Dec. 1975 — Date

DRAWING NUMBER **I-27**



PLAN



ELEVATION


NOTES

1. Close nipples shall not be used.
2. Cast iron tapped tee shall be short body, class 250, cement mortar lined and polyethylene wrapped.
3. All tapped tees shall have a type - A support block. See Standard Drawing W-19.

LEGEND ON PLANS




RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Allan A Kashmar Dec. 1975 Coordinator R.C.E. 19807 Date	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
		Reference	TRP	M.B.	10-82
	CONNECTION DETAIL FOR NEW ASBESTOS CEMENT SUPPLY MAINS				
DRAWING NUMBER I-28					



PLAN

May Be: Bronze, double strap service clamp; cast iron tapped clamp coupling with stainless steel bolts; cast iron boltless tapping sleeve; or cast iron (cement mortar lined) cutting in tapped tee.



ELEVATION

NOTE
Close nipples shall not be used.

LEGEND ON PLANS



Revision	By	Approved	Date
Reference	TRP	M. B.	10-82


SAN DIEGO REGIONAL STANDARD DRAWING

CONNECTION DETAIL FOR EXISTING SUPPLY MAINS


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan O Kenkel — Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER I-29



PLAN



ELEVATION


NOTES

1. All fittings shall be P.V.C. Sch. 40 (except as noted).
2. All nipples shall be P.V.C. Sch. 80 (except as noted).
3. Teflon tape, 3/4" wide, shall be used on all threaded connections.
4. Short nipples shall not be used.

LEGEND ON PLANS

Show a number to indicate type head

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Coordinator R.C.E. 25291 Date July 1979	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
		Notes	JP	[illegible]	5-92
	IMPACT HEAD (WITH SWING JOINT)				
DRAWING NUMBER I-30					



NOTES:

1. All risers, unions, elbows and nipples shall be red brass.
2. Close nipples shall not be used.
3. Teflon tape 3/4" wide shall be used on all threaded connections.
4. Concrete pad shall be 18" wide.
5. Backflow preventer assembly shall be tested upon installation by a certified backflow device tester. Contractor shall provide the Engineer with written test results completed by certified backflow tester prior to the backflow preventor assembly's acceptance by the Engineer.

LEGEND ON PLANS



Revision	By	Approved	Date


SAN DIEGO REGIONAL STANDARD DRAWING

BACKFLOW PREVENTER REDUCED PRESSURE PRINCIPLE ASSEMBLY - 2" AND SMALLER

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Chairman RCE 25702 Date 5-1-92


DRAWING NUMBER I-31



NOTES:

1. All pipes shall be 1 1/2–inch diameter galvanized schedule 40 steel.
2. X dimension shall be sized to accomodate type of backflow device being protected.
3. Paint entire fence with one coat metal primer and two coats of exterior yellow colored enamel.
4. Guard fence shall be centered on backflow device.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Chairman SEPT. 1988 Date	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
	PROTECTIVE GUARD FENCE FOR BACKFLOW DEVICE				
DRAWING NUMBER **I-32**					



NOTES

1. Typical remote control valve assembly : All nipples, risers,tees and elbows are to be red brass.
2. Install largest remote control valve adjacent to gate valve and maintain uniform decrease.
3. Close nipples are not allowed.
4. Install individual valve boxes for each remote control valve.
5. Locations of Quick Coupler valves shall be as shown on plans.
6. Tee vertically from Mainline intersection to reach the 15" maximum depth.

Revision	By	Approved	Date

SAN DIEGO REGIONAL STANDARD DRAWING


REMOTE CONTROL VALVE MANIFOLD ASSEMBLY

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

George [illegible] 5-11-92
Chairman Date

RCE 25902

DRAWING NUMBER I-33



NOTES:

1. All fittings shall be P.V.C. Sch. 40 (except as noted).
2. All nipples shall be P.V.C. Sch. 80 (except as noted).
3. Teflon tape, 3/4" wide, shall be used on all threaded connections.
4. Short nipples shall not be used.

LEGEND ON PLANS

Show a number to indicate head type

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Chairman RCE 25902 Date 5-11-93


DRAWING NUMBER I-34

SAN DIEGO REGIONAL STANDARD DRAWING

SHRUB SPRINKLER HEAD ROTARY TYPE


Revision	By	Approved	Date

LANDSCAPING



TREE PLANTING - SLOPES

TREE PLANTING - LEVEL GROUND



SHRUB PLANTING - SLOPES

SHRUB PLANTING - LEVEL GROUND

Revision	By	Approved	Date

SAN DIEGO REGIONAL STANDARD DRAWING


TREE AND SHRUB PLANTING

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A Kenkel Dec. 1975

Coordinator R.C.E. 19807 Date


DRAWING NUMBER L-1



PLAN



2 stakes and 2 ties. Tie tree trunk 6" above bending moment of tree. Tie should provide flexibility of trunk but not allow rubbing of trunk against stake. Cut stakes off 6" above ties. For single stake trees, place stake on windward side of tree.



TREE STAKING – SLOPES

TREE STAKING – LEVEL GROUND

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan O Kenkel Dec. 1975


Coordinator R.C.E. 19807 Date

DRAWING NUMBER L-2

SAN DIEGO REGIONAL STANDARD DRAWING


TREE STAKING

Revision	By	Approved	Date
Plan	BC	O. S.	7.79



TYPE A
SHRUB AREAS

TYPE B
UNDER FENCES



WEAKENED PLANE JOINT
MAX. 20 FT. O. C.

EXPANSION JOINT
MAX. 120 FT. O. C.

NOTES:

1. Rebar shall be continuous with 12 inch overlap at splices.
2. Concrete shall be class 520-C-2500 and same color as any adjacent concrete.
3. Install weakened plane joints at each fence post.
4. Install expansion joints where the mowing strip abuts any concrete improvement.

Revision		Approved	Date
Conc.	C	M.B	5-86

SAN DIEGO REGIONAL STANDARD DRAWING

CONCRETE MOWING STRIP


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Harry R. Holt Oct 1982
Chairman R.C.E. C13768 Date


DRAWING NUMBER L-3

NOTES:


1. The location and species of each tree shall have prior approval of the Agency.
2. Sidewalk to be removed for each tree planting shall be saw cut full depth.
3. Fill below grate with 3/4" x No.4 clean crushed rock. If the grate is used for security, all bolts, nuts and washers shall be hot dipped galvanized. All steel items shall be hot dipped galvanized after fabrication.
4. Grate shall be two separate pieces, 2' x 4' in size, unless otherwise specified on the plans. Slot openings in grate design shall have 3/8" maximum width. Grates are to be designed in accordance with the latest edition of the Uniform Building Code, with a minimum uniform live load of 250 pounds per square foot in sidewalks, and have a method of symmetrical interior expandable rings/openings (detailed on the plans) as selected and approved by the agency.
5. Immediate notification shall be given to the Engineer of any below grade improvements encountered.




TREE SIZE




ELEVATION





PLAN



SECTION A–A

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Chairman REES5/92 Date 5-11-92

DRAWING NUMBER L-4

SAN DIEGO REGIONAL STANDARD DRAWING

STEEL GRATE TREE WELL COVER

Revision	By	Approved	Date



NOTES;

1. See Electric Plans for fixture/pole/footing details.
2. Use monolithic pour for new construction.
3. Poles shall be 6'–0" from face of curb, where applicable.
4. Pole pads shall drain at 2% minimum in same direction as sidewalk.
5. Concrete for pad shall be the same as specified for sidewalk.

Revision	By	Approved	Date

SAN DIEGO REGIONAL STANDARD DRAWING


LIGHT POLE PAD IN TURF AREAS

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Chairman — Date: SEPT. 1988

DRAWING NUMBER **L-5**

MISCELLANEOUS



MANHOLE COVER FRAME



DETAIL

MANHOLE COVER

NOTES:

1. Frame and cover shall be cast iron. Cast iron shall conform to ASTM 48, Class 35B.
2. Weights: Frame 166 - 193 lbs.
   Cover 147 - 171 lbs.
3. Machine all matching surfaces and seats of frame and cover to prevent rocking.
4. Imported frames and covers shall have the country of origin marked in compliance with federal regulations.

FOR	MARK
Sewer Projects	Sewer
Storm Drain Projects	Storm Drain
Water Projects	Water

Revision	By	Approved	Date
Note 3	SC	A.H.	7-88
Note #2	DM	D. Moheiji	2-95


SAN DIEGO REGIONAL STANDARD DRAWING

24" MANHOLE FRAME AND COVER HEAVY DUTY


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A. Kaufman — Coordinator R.C.E. 19807 — Dec. 1975 Date


DRAWING NUMBER M-1




TOP OF FRAME & COVER




SECTION THROUGH RIM




SECTION THROUGH FRAME & COVER



SECTION THROUGH LUG



BOTTOM OF COVER



SECTION THROUGH RIB AT MID RADIUS

NOTES:

1. Frame and cover shall be cast iron. Cast iron shall conform to ASTM 48, Class 30.
2. Frame and cover for use in non-traffic area only.
3. Weights: Frame 29 - 33 lbs.
   Cover 95 - 110 lbs.
4. Imported frames and covers shall have the country of origin marked in compliance with federal regulations.

FOR	MARK
Sewer Projects	Sewer
Storm Drain Projects	Storm Drain
Water Projects	Water

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A Kashmar Dec. 1975
Coordinator R.C.E. 19807 Date

DRAWING NUMBER **M-2**


SAN DIEGO REGIONAL STANDARD DRAWING

24" MANHOLE FRAME AND COVER LIGHT DUTY


Revision	By	Approved	Date
Note 4	RC	A.H	7/88
Note #3	DH	O. Hoheisel	2/95



HALF PLAN FRAME & COVER



HALF SECTION FRAME & COVER



DETAIL

NOTES:

1. Frame and cover shall be cast iron. Cast iron shall conform to ASTM 48, Class 35B.
2. Weights:

Frame	314 - 363 lbs.
outer Cover	285 - 330 lbs.
Inner Cover	147 - 171 lbs.

3. Machine all matching surfaces and seats of frame and cover to prevent rocking.
4. Imported frames and covers shall have the country of origin marked in compliance with federal regulations.

Revision	By	Approved	Date
Note 5	LC	G.H.	7-88
Note #1	DH	D. Mohajir	2-95


SAN DIEGO REGIONAL STANDARD DRAWING

36" MANHOLE FRAME AND TWO CONCENTRIC COVERS HEAVY DUTY


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A Kenkel — Coordinator R.C.E. 19807 — Dec. 1975 — Date


DRAWING NUMBER **M-3**




M-1 Detail:
COVER TO FRAME




M-3B Detail:
OUTER COVER TO FRAME



M-3A Detail:
INNER COVER TO OUTER COVER



NEOPRENE O-RING
GROOVE DETAIL



M-1 COVER AND FRAME
BOLT PLACEMENT
(See Note 3)

M-3 CONCENTRIC COVERS AND FRAME
BOLT PLACEMENT
(See Note 3)

NOTES:

1. 0.625" X 20 UNC THREAD, 316 STAINLESS STEEL SOCKET HEAD CAP SCREW AND 1.50" O.D. X 0.687" I.D. X 0.078 THICK 316 STAINLESS STEEL WASHER.
2. 0.25" NEOPRENE O-RING GASKET SHALL BE GLUED INTO MACHINED GROOVE. GLUE SHALL MEET THE REQUIREMENTS OF MIL-M-81288 (AMEND. 1)
3. BOLTDOWN PATTERNS:
   - M-1 DETAIL (24" COVER & FRAME): INSTALL TWO (2) BOLTS AT 180 DEGREES.
   - M-3A DETAIL (CONCENTRIC COVERS): BETWEEN INNER AND OUTER COVERS INSTALL TWO (2) BOLTS AT 180 DEGREES.
   - M-3B DETAIL (OUTER COVER & FRAME): BETWEEN OUTER COVER & FRAME INSTALL FOUR (4) BOLTS AT 90 DEGREES.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

2-95


Chairman R.C.E. 25902 Date

DRAWING NUMBER M-4

SAN DIEGO REGIONAL STANDARD DRAWING

MANHOLE COVER LOCKING DEVICE


Revision	By	Approved	Date
New Dwg	DM	RLM	2/95




HALF ELEVATION DOUBLE SWING GATE

NOTES

1. All footings shall be 520-C-2500 concrete.
2. The following items shall be furnished and installed only when shown on the plans and/or called for in the special provisions:
   a. Barbed wire
   b. Extension post
3. Chain link fence shall conform to Section 206-6 of the Standard Specifications for Public Works Construction unless specifically noted on this drawing.



EXTENSION POST AND BARBED WIRE



WALK GATE

LEGEND ON PLANS

Revision	By	Approved	Date
Walk gate	TRA	M.B.	10-82
Conc.	[illegible]	M.B.	5-86


SAN DIEGO REGIONAL STANDARD DRAWING


CHAIN LINK GATE

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan O Kenkel — Dec. 1975
Coordinator R.C.E. 19807 — Date

DRAWING NUMBER M-5





EXTENSION ARM AND BARBED WIRE

NOTES

1. All footings shall be 520-C-2500 concrete.
2. The following items shall be furnished and installed only when shown on the plans and/or called for in the special provisions:
   a. Barbed Wire
   b. Extension Arm
   c. Top Horizontal Rail
3. Chain link fence shall conform to Section 206-6 of the Standard Specifications for Public Works Construction unless specifically noted on this drawing.
4. See Standard Drawing M-20 for additional details.

LEGEND ON PLANS

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Coordinator R.C.E. 19807 — Date: Dec. 1975

DRAWING NUMBER **M-6**


SAN DIEGO REGIONAL STANDARD DRAWING

CHAIN LINK FENCE

Revision	By	Approved	Date
Note 3	TRP	M.B.	10-82
Notes	&	M.B.	5-86
Notes	&	A.H.	7-88




Top View




Front View

End View
(Both Barricades)

CONTINUOUS BARRICADE



Front View
SEPARATE BARRICADE



Front View
GUARD POST

NOTES

1. Posts to be structural grade redwood or pressure treated (with wood preservative) Douglas Fir, surfaced four sides; cross pieces to be 2"x 8" select grade Douglas Fir, surfaced four sides.
2. All exposed portions of barricades shall be painted with two coats of white exterior enamel over prime coat.
3. Connections shall be made with 3/8"x 6" galvanized lag screws with one (1) washer each. Reflector sign fasteners to be 3/8"x 1½" galvanized lag screws.
4. Reflector signs - California Type N. Size 18"x 18" - Yellow with nine (9) - 3¼" reflectors (center mount).
   a. Reflectors shall be red for use on dead end streets, in all other cases they shall be yellow. Reflector material shall be plastic or other approved reflectorized material.
   b. Sign material shall be aluminum alloy 6061-T6 or 5052-H38, aluminum thickness 0.063 inches.
5. Six foot long hat section metal post per Caltrans Std. Plan A74-A optional for guard post.

LEGEND ON PLANS



Revision	By	Approved	Date
Cont. Barric.	[illegible]	D.S.	7-79
Post	TRP	M.B.	10-82


SAN DIEGO REGIONAL STANDARD DRAWING

GUARD POST AND BARRICADE


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A Kashmal — Coordinator R.C.E. 19807 — Dec. 1975 Date


DRAWING NUMBER M-9



PLAN–IN UNPAVED AREA




RISER RING



TYPICAL MONUMENT SECTION
IN PAVED AREA

NOTES


1. Cover and frame to be cast integrally with pipe box.
2. Monument base may be cast in place or precast.
3. Form and taper exposed upper 6" of cast in place base to a top diameter of 5". (Precast base shall be sand backfilled).
4. Monument marker shall be a domed brass, 3" in diameter.
5. Monument Location:
   a) Set on all centerline intersections unless actual location is modified by the Agency and shown in modified location on map. When centerline intersection is impractical, offset 5 feet on centerline of major street, (see detail at right). If neither centerline can be occupied, two monuments will be set in line around the front on the perimeter of a 10-foot diameter circle, whose center is the point.
   b) Set on centerline at intervals not exceeding 1000 feet on straight runs.
   c) Set on centerline at points of curvature.
   d) Set on center at center points of cul-de-sacs.
   e) Set on centerline when center point of cul-de-sac is offset from centerline.
   f) These standards may be modified at the discretion of the Agency in cases where strict compliance therewith results in more monuments than it considers necessary. The following technique for reducing the number of monuments will be routine.
   g) Substitution of one monument on the "Point of Intersection" for monuments at the "Beginning of Curve" and the "Ending of Curve" when the "Point of Intersection" falls within the pavement area.
   h) Deletion of any monument otherwise required by these standards when its position can be determined by turning one angle from a point on a straight line between two other monuments, providing such point is not more than 300 feet from the point on which the deleted monument would have been placed.



Alternate location of monument. Tie distances shown on final subdivision map if alternate location is used.


LOCATION OF STREET
SURVEY MONUMENT

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Coordinator R.C.E. 19807 — Dec. 1975 Date	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
		Notes	JC	O.S.	7-79
		Section	JC	M.B.	5-86
	STREET SURVEY MONUMENT	Taper	JM	S.K.	5-92
DRAWING NUMBER M-10					



TYPE–A TYPE–B

ELEVATION



INSTALLATION IN EXISTING CONCRETE

(Typical for Type A or B)

NOTES

1. Material - Brass A.S.T.M. B-16. All machine tolerances 1/64"±, machine finish.
2. May be installed in fresh concrete at time of installation of concrete structure.
3. Location–in most stable, permanent location in vicinity, such as in base for street light standard or traffic signal (behind sidewalk), in curb (not near joint, on curve or near trees), on top of drainage headwall, in foundation for building or retaining wall or in concrete pads for transformers, pump stations etc.

Revision	By	Approved	Date


SAN DIEGO REGIONAL STANDARD DRAWING

BENCH MARK-BRASS PLUG

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan O Kenkel — Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER **M-11**



LEGEND

U.S.C. & G.	=	United States Coast and Geodetic Survey.
U.S.G.S.	=	United States Geological Survey.
MEAN HIGH WATER	=	Mean of all high water in San Diego Bay.
MEAN HIGHER WATER	=	Mean of all higher water in San Diego Bay. Bay charts and topography up to the mean high tide based on zero at the mean lower low water.

SOURCE

Data based on U.S.C. & G. "Sea Level Datum of 1929".

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER **M-12**

SAN DIEGO REGIONAL STANDARD DRAWING

DATUMS

Revision	By	Approved	Date

FOUND MONUMENTS

Found monuments must denote the character of the monument, how it is identified and the record, or no record as applicable.

SET MONUMENTS - Criteria for Locating and Character

On subdivision boundaries, permanent monuments are required; and must be shown on the map at intervals as specified by the local agency. The location of such points that are inacceptable or will be destroyed by contruction may be established by ties to permanent reference monuments shown on the final map.

A permanent monument shall be no less substantial than the following:

a. An iron pipe of minimum two inch diameter not less than two feet in length placed upright in the ground so that the top of said pipe is flush with the surface. Said pipe shall be filled with a metal or cement plug at least three inches in depth and centered with a metal tack and disc; or

b. A metal plug with tack and disc set flush with the surface in portland cement conrete sidewalk, curb or pavement; or other monument satisfactory to the City Engineer or County Surveyor. The metal plug shall be anchored 1" deep in sidewalk.

Lot corners and points of curves along street and alley right of way lines where portland cement concrete sidewalks, curbs or pavement exist, or will be constructed as part of the subdivision requirements, shall be identified with tack and disc set flush with the surface along an extension of the lot line at an approved offset, to be measured radially or at right angles to the right of way line in said sidewalk, curb or pavement. In case the sideline of the lot is not radial or at right angles to the right of way line a disc shall be set along an extension of the sideline at an offset to be measured radially or at right angles to the right of way line. Where no such concrete work exists, and none will be required to be constructed, all lot corners, angle points and points of curve shall be marked with a monument no less substantial than a one-half inch steel rod or pipe, 18 inches long, set flush with the surface.

LEGEND

- ● Fd 2" Iron Pipe Marked RCE XXXX or per Map XXX unless otherwise noted
- ▲ Fd Street Survey Monument Stamped RCE XXXX or LS XXXX
- ◎ Set 2" x 24" Iron Pipe Marked RCE XXXX or LS XXXX
- □ Set Lead and Disc Stamped RCE XXXX or LS XXXX
- ○ Set ½" x 18" Iron Pipe Marked RCE XXXX or LS XXXX
- △ Set Street Survey Monument Stamped RCE XXXX or LS XXXX per Standard Drawing M-10

The addition of other symbols is permissible where such will result in a clearer map.

The following notes should be used in the legend where applicable.


Unless otherwise shown on this map:

1. All lot corners except as described below will be monumented by a ½ inch by 18 inch iron pin stamped (RCE or LS number).

2. Lot corners along the sideline of dedicated street right of way will be monumented by a disc stamped (RCE or LS number), set along an extension of the lot line at an offset of ___ in the (curb, sidewalk). The offset shall be measured radially, or at right angles, to the right of way line. (See example below.)

3. All points of curve of the sidelines of dedicated streets will be monumented by a disc stamped (RCE or LS number), set at an offset of ___ in the (curb, sidewalk). The offset shall be measured radially.

EXAMPLE OF OFFSET DISCS



Revision	By	Approved	Date
Notes	RC	[illegible]	7-79
Notes	JT	[illegible]	5-92

SAN DIEGO REGIONAL STANDARD DRAWING

SURVEY MONUMENTS

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER **M-13**

WEIGHT

1 Gram	= 15.4324 grains	1 Grain	= 0.0648 g.
1 Gram	= 0.0353 oz.	1 Ounce	= 28.3495 g.
1 Kg.	= 2.2046 lb.	1 Pound	= 0.4536 kg.
1 Kg.	= 0.0011 ton	1 Ton	= 907.1848 kg.
1 Ton (met)	= 1.1023 ton	1 Ton	= 0.9072 ton (met)

AREA

1 Sq. cm.	= 0.1550 sq. in.	1 Sq. in.	= 6.4516 sq. cm.
1 Sq. m.	= 10.7639 sq. ft.	1 Sq. ft.	= 0.0929 sq. m.
1 Sq. m.	= 1.1960 sq. yd.	1 Sq. yd.	= 0.8361 sq. m.
1 Hectare	= 2.4710 acres	1 Acre	= 0.4047 hectare
1 Sq. km.	= 0.3861 sq. mile	1 Sq. mile	= 2.5900 sq. km.
1 Sq. km.	= 247.10 acres	1 Acre	= 0.0040 sq. km.

VOLUME

1 Cu. cm.	= 0.0610 cu. in.	1 Cu in.	= 16.3872 cu. cm.
1 Cu. m.	= 35.3134 cu. ft.	1 Cu ft.	= 0.0283 cu. m.
1 Cu. m.	= 1.3079 cu. yd.	1 Cu yd.	= 0.7646 cu. m.

CAPACITY

1 Liter	= 61.0250 cu. in.	1 Cu. in.	= 0.0164 liter
1 Liter	= 0.0353 cu. ft.	1 Cu ft.	= 28.3162 liters
1 Liter	= 0.2642 gal. (U.S.)	1 Gal.	= 3.7853 liters
1 Liter	= 0.0284 bu. (U.S.)	1 Bu.	= 35.2383 liters

LENGTH

1 MM.	= 0.0394 in.	1 In.	= 25.4000 mm.
1 CM.	= 0.3937 in	1 In.	= 2.5400 cm.
1 Meter	= 3.2808 ft.	1 Ft.	= 0.3048 m.
1 Meter	= 1.0936 yd.	1 Yd.	= 0.9144 m.
1 Km.	= 0.6214 mile	1 Mile	= 1.6093 km.

METRIC PREFIX

MULTIPLE	PREFIX	MULTIPLE	PREFIX
1000000	mega	1/10	deci
1000	kilo	1/100	centi
100	hecto	1/1000	milli
10	deka	1/1000000	micro

TEMPERATURE

Degrees Farenheit = 9/5 (Degrees Celcius) + 32

Degrees Centigrade = 5/9 (Degrees Fahrenheit - 32)

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen A Kenkel — Dec. 1975


Coordinator R.C.E. 19807 — Date

DRAWING NUMBER M-14


SAN DIEGO REGIONAL STANDARD DRAWING

METRIC EQUIVALENTS


Revision	By	Approved	Date
Equation	BC	D.J.	7-79




TYPE A




TYPE B




TYPE C




TYPE D



TYPE E



TYPE F



TYPE G

SERVICE TRENCH ON PUBLIC PROPERTY

	LEGEND	MIN.COVER
GM	Gas Main	30"
GS	Gas Service	30"
P	Primary Electric	42"
S	Secondary Electric	30"
ES	Electric Service	30"
ME	Multiple Electric (P, S or ES in Spacers) Concrete Encased	24"
SL	Street Light (not series)	30"
U	CATV	24"
	TELCO	24"

NOTES:

1. All dimensions are typical unless otherwise noted.
2. Generally utilities are to be installed under the applicable specifications for the particular utility and the specifications of the owner Agency.
3. The location of utilities as shown by the Standard Drawing shall in no way violate existing codes or regulations applicable to individual utilities.
4. Installation of sewer and/or water utilities are not permitted in the joint trench shown above.
5. Minimum depth of gas pipe may, subject to gas company inspectors approval, be reduced to 24" where necessary to clear structure crossings.
6. Depth and width of trench varies.
7. CATV main or trunk line conduit required along all streets, except cul-de-sac streets less than 1000' in length which may be served by feeder lines only.
8. CATV 1 1/2" feeder conduit shall run across streets with each power service line and capped at edge of sidewalk.
9. All CATV terminals and conduits shall be terminated at generally accepted locations and marked. A map shall be filed with the appropriate agency showing the locations of the CATV system.
10. In no case shall CATV conduits be placed within 12" of gas lines. Also conduits are not to be placed directly over gas lines.
11. CATV conduit may be placed with the TELCO conduit provided the TELCO minimum depth is held.

Revision	By	Approved	Date
New Dwg.	JC	A.H.	10/88


SAN DIEGO REGIONAL STANDARD DRAWING


JOINT TRENCH UTILITIES LOCATION

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Chairman — Date: SEPT. 1988

DRAWING NUMBER M-15





HASP DETAIL
(Showing Welds)

NOTES

1. Chain to be ¼" proof coil chain galvanized steel. Weld four links to post and three links to pipe sleeve.
2. All metal to be hot-dip galvanized after fabrication.

LEGEND ON PLANS

○

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


David L. Johnson July 4, 1979
Coordinator R.C.E. 25291 Date

DRAWING NUMBER M-16

SAN DIEGO REGIONAL STANDARD DRAWING

DEMOUNTABLE POST

Revision	By	Approved	Date



*For Edge Beam, Slab, and Select Fill details, see plans.

ELEVATION

DESCRIPTION	MIN. SIZE IN INCHES	MIN. WEIGHT PER LIN FT IN LBS
Line Post	2.375 O.D.	3.65
Terminal Post	2.875 O.D.	5.79
Top Rail	1.660 O.D.	2.27
Bracing	1.660 O.D.	2.27
Gate Frame	1.660 O.D.	2.27

NOTE:
Chain link fabric shall be erected on the interior side of the courts.

CAUTION:
This Standard Drawing is not to be used if any wind screen is to be applied to the fence.

Revision		Approved	Date
Fabric	X	M.B.	5-86
Caution	X	A.H.	7-88


SAN DIEGO REGIONAL STANDARD DRAWING

TENNIS COURT FENCE CHAIN-LINK


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Coordinator R.C.E. 25291 July 1979 Date

DRAWING NUMBER M-17




1. Drinking Fountain - Haws model 3376 or approved equal.
2. 3/8" dia. expansion anchors with flat (recessed heads) screws 4 places.
3. 1¼" P.V.C. pipe with sweep 90° ell connection to fountain drain.
4. 9½" x 16" concrete yard box with hinged locking top (Brooks No. 3HL or equal) set on red brick foundation.
5. 4" x 40 lin. ft. perforated underdrain pipe, encased in crushed rock (3/4" size). Pipe to be A.D.S. or equal.
6. 1" gate valve with red brass cross handle and union. Install as per Std. Dwg. I-12
7. 2" dia. galv. pipe sleeve with red brass lock cap per Std. Dwg. I-12
8. Rigid copper pipe from gate valve to fountain assembly connection.
9. Concrete pavement.



SECT B-B

NOTES

1. Install fountain so that right hand side faces prevailing wind.
2. Hand form a concrete bowl at bottom of yard box to facilitate sand clean out.
3. Perforated drain pipe and trench are to drain away from fountain at 1% min. slope. Keep drain in lawn areas.
4. Item no. 6 is a one inch gate valve. Use red brass bushing reducers to adapt to feed pipe.




TYPICAL PLAN

LEGEND ON PLANS




OMMENDED BY THE SAN DIEGO ONAL STANDARDS COMMITTEE Harry R. Holt Oct 1982 Chairman R.C.E. C13768 Date	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
DRAWING NUMBER M-18	DRINKING FOUNTAIN				

STREET LOCATIONS



FREEWAY LOCATION



DETAIL

MARKERS – Shall be blue 2-way stimsonite lifelite 88AB or equal.

ADHESIVE – An ample amount of two part (A&B) epoxy or equal.

SURFACES – Clean and dry prior to installation per manufacturer's recommendations. Install markers with reflective surfaces facing oncoming vehicles and offset 2" from lane lines toward fire hydrant.

NOTES:

1. Fire Department will provide location(s) for all markers in PRD's, Commercial Lots and other areas outside of Public Right of Way.
2. Markers must be installed at all new and relocated hydrants and within all resurfacing projects.
3. For streets without lane lines or streets with raised pavement markers and no painted lane lines, install markers 6" from centerline or existing markers.

LEGEND ON PLANS

Marker ■

Fire Hydrant

Revision		Approved	Date
Frwy loc.	R	M.B.	5-84

SAN DIEGO REGIONAL STANDARD DRAWING


FIRE HYDRANT MARKERS

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Harry R. Holt Oct 1982

Chairman R.C.E. C13768 Date


DRAWING NUMBER M-19



END AND CORNER POST ASSEMBLY



LINE POST BRACING



GATE ASSEMBLY

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

M. Behm 4-25-86


Coordinator R.C.E. C21133 Date

DRAWING NUMBER **M-20**


SAN DIEGO REGIONAL STANDARD DRAWING

CHAIN LINK FENCE DETAILS


Revision	By	Approved	Date



SIDEWALK NEXT TO CURB



SIDEWALK NEXT TO PROPERTY LINE



SIDEWALK NEXT TO CURB AND PROPERTY LINE

NOTES:

1. Sidewalk shall have a minimum of four (4) foot clear area (path, not including curb) passing pedestals, pullboxes and other structures.
2. See Standard Drawing M–15 for joint trench.

Revision	By	Approved	Date


SAN DIEGO REGIONAL STANDARD DRAWING

UNDERGROUND TYPICAL LOCATION CONVERSION/REPLACEMENT/UPGRADE


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Chairman — Date: SEPT. 1988

DRAWING NUMBER **M-21**



MAJOR STREET




TYPICAL STREET
NEW CONSTRUCTION


NOTES

1. At catch basin locations, joint trench shall be 4 ft. minimum from back of curb to inside wall of trench. See Standard Drawing M–15 for configuration of utilities in joint trench.
2. Sewer and reclaimed water mains shall be designed to cross under potable water mains. The vertical separation between potable water and reclaimed water shall be a minimum of 12 inches.
3. Sewer and reclaimed water laterals shall cross under potable water main, with a minimum vertical separation of 12 inches.
4. Sewer and reclaimed water mains shall maintain a 10 ft. minimum horizontal separation, O.D to O.D., with any potable water or sewer/reclaimed main. This separation may be reduced utilizing special construction, with special approval from the Agency and the County Health Dept. For sewer or reclaimed water mains less than 24 inches in diameter, only Agency approval is required.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE 2-95 Chairman R.C.E. 25902 Date	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
		New Dwg	DM	RLM	2/95
DRAWING NUMBER M–22	UTILITY LOCATIONS LOCAL AND MAJOR STREETS				



PRIME ARTERIAL



EXPRESSWAY

NOTES

1. At catch basin locations, joint trench shall be 4 ft. minimum from back of curb to inside wall of trench. See Standard Drawing M–15 for configuration of utilities in joint trench.
2. Sewer and reclaimed water mains shall be designed to cross under potable water mains. The vertical separation between potable water and reclaimed water shall be a minimum of 12 inches.
3. Sewer and reclaimed water laterals shall cross under potable water main, min. vertical separation of 12 inches.
4. Sewer and reclaimed water mains shall maintain a 10 ft. minimum horizontal separation, O.D to O.D., with any potable water or sewer/reclaimed main. This separation may be reduced utilizing special construction, with special approval from the Agency and the County Health Dept. For sewer or reclaimed water mains less than 24 inches in diameter, only Agency approval is required.

Revision	By	Approved	Date
New Dwg	DM	RLM	2/95

SAN DIEGO REGIONAL STANDARD DRAWING


UTILITY LOCATIONS PRIME ARTERIALS AND EXPRESSWAYS


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


2-9-95

Chairman R.C.E. 25902 Date

DRAWING NUMBER M–23







RAILING NOTES

1. 1/4" Expansion joints @ 16'± centers.
2. Weld and grind smooth all connections.
3. All railing to be hot dip galvanized after fabrication.
4. Pipe shall seamless steel ASTM A53 Grade B.
5. Maximum Δ =4". Guardrails and handrails for stairs and ramps more than 30" above grade shall have intermediate rails equally spaced such that a sphere 4" in diameter cannot pass through.
6. Handrail extension for stairs, at all bottom risers, shall be 12" plus one tread width.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Chairman R.C.E. 25902 Date 2-95

DRAWING NUMBER M-24

SAN DIEGO REGIONAL STANDARD DRAWING


PEDESTRIAN PROTECTIVE RAILING

Revision	By	Approved	Date
ADA Rqmt	OH	RLM	2/95




X IS THE MINIMUM HANDRAIL EXTENSION OF 12 INCHES PLUS THE WIDTH OF ONE TREAD AT EACH BOTTOM RISER.

NOTE: INNER HANDRAIL AT LANDINGS OF STAIRS THAT DOUBLE BACK OR IMMEDIATELY TURN SHALL BE CONTINUOUS, AND SHALL NOT EXTEND ONTO LANDING OR PATH OF TRAVEL.




TYPE A
GUARDRAIL EXTENSION



STAIR HANDRAILS

PROVIDE GUARDRAIL EXTENSIONS AS FOLLOWS:

1. TYPE A ON OPEN SIDE OF ALL LANDINGS MORE THAN 30 INCHES ABOVE GRADE OR FLOOR BELOW.
2. TYPE B ON OPEN SIDE OF STAIRS (INCLUDING LANDINGS) WHEN SPECIFIED.



TYPE B
GUARDRAIL EXTENSION

GENERAL NOTES

1. Post type guardrails, and handrails for stairs or landings 30 inches or less above grade or floor below shall have only one intermediate rail centered between the step nosing limit (or if specified the top of curb) and top of railing.
2. Post type guardrails, and handrails for stairs or landings more than 30 inches above grade or floor below shall have intermediate rails equally spaced such that a sphere 4 inches in diameter cannot pass through.
3. Where handrail extensions interfere with transverse walkways the horizontal portions shall not encroach but be turned away from stairs and parallel to walkway.
4. The top of guardrails for stairways, exclusive of their landings, may have a height as specified for handrails.

Revision	By	Approved	Date
ADA Rqmt	DA	RLM	2/95


SAN DIEGO REGIONAL STANDARD DRAWING

PEDESTRIAN PROTECTIVE RAILING DETAIL No.2

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Chairman R.C.E. 25902 Date 2-95

DRAWING NUMBER M-25




NOTES

1. Broom finish on treads, trowel finish on all other exposed surfaces.
2. 1/4" per 1' slope on treads for drainage.
3. Locate handrails on both sides.
4. Handrail may project into the required width a distance of 3-1/2" from each side of stairway.



SECTION A-A

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE 25 25902 2-95	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
		ADA Rqmt	DH	RLM	2/95
DRAWING NUMBER M-26	CONCRETE STEPS				



NOTES:

1. Provide for adequate drainage.
2. For appropriate ramp alternate to conform to topographical conditions, see Std. Dwg. G-27 through G-31.
3. Slope shall not exceed 2% in any direction unless there is equivalent facilitation.
4. Blue color should match color No. 15090 in the Federal Standard 595a as specified in Section 522(b)2.

Revision	By	Approved	Date
ADA Rqmt	DH	D. Mahuit	2-95


SAN DIEGO REGIONAL STANDARD DRAWING

DISABLED PARKING STALL(S)

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Chairman R.C.E. 25902 Date 2-95

DRAWING NUMBER M-27A



NOTES:

1. Provide for adequate drainage
2. See Std: Dwg G-27 through G-31. For appropriate ramp alternate to conform to topographical conditions.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Chairman R.C.E. 25902 Date 2-95

DRAWING NUMBER M-27B

SAN DIEGO REGIONAL STANDARD DRAWING

DIAGONAL DISABLED PARKING STALL(S)

Revision	By	Approved	Date
ADA Rqmt	DM	RLM	2/95





Sign Detail

NOTES:

1. Sign shall be constructed of a minimum 0.062" thick aluminum.
2. Lettering, symbol and border shall be reflectorized white, on a blue background.
3. Lettering shall be 1 inch and 2 inches high.
4. Where space is designed for van accessibility, a sign "VAN ACCESSIBLE" shall be installed.
5. Minimum van accessible vertical clearance is 8'-2".

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Chairman R.C.E. 25902 Date 2-95

SAN DIEGO REGIONAL STANDARD DRAWING

DISABLED PARKING SIGN

DRAWING NUMBER M-28A

Revision	By	Approved	Date
ADA Rgmt	OR	RLM	2/95



NOTES:

1. Sign shall be constructed of aluminum, 0.062" minimum thickness.
2. Colors: Background—Reflectorized Blue
   Border and letters— Reflectorized White
   Blue color shall match color No. 15090 in the
   Federal Standard 595a as specified in Section 522(b)2.

Revision	By	Approved	Date
ADA Rgmt	DH	RLM	2/95


SAN DIEGO REGIONAL STANDARD DRAWING

VAN ACCESSIBLE SIGN FOR DISABLED PARKING SPACE


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Chairman R.C.E. 25902 Date 2-95

DRAWING NUMBER M-28B



(a) SYMBOL PROPORTIONS



INTERNATIONAL SYMBOL OF ACCESSIBILITY

(b) DISPLAY CONDITIONS

NOTES:

1. Pavement symbol shall be painted white on a blue background.
2. Blue color should match color No. 15090 in the Federal Standard 595a as specified in Section 522(b)2.

Revision	By	Approved	Date
ADA RQMT	OA	O. Mehiry	2-95


SAN DIEGO REGIONAL STANDARD DRAWING

PAVEMENT SYMBOL DISABLED PARKING

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Chairman R.C.E. 25902 Date 2-95

DRAWING NUMBER M-29




SECTION A-A

TYPICAL FOR ABOVE GROUND OBSTRUCTIONS-4:1 SIDEWALK TRANSITIONS TYPICAL FOR USE WITH G-7



DETAIL OF POST KNOCKOUT



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

5-11-92
Chairman RCE 25902 Date

DRAWING NUMBER M-30

SAN DIEGO REGIONAL STANDARD DRAWING

GUARD RAIL STANDARDS

Revision	By	Approved	Date


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

COORDINATOR R.C.E. 25902 DATE 4-20-87


SAN DIEGO REGIONAL STANDARD DRAWING

METAL BEAM GUARD RAILING

DRAWING NUMBER M-31




PLAN




ELEVATION

METAL BEAM GUARD RAIL WITH WOOD POST AND BLOCKS




PLAN




ELEVATION

METAL BEAM GUARD RAIL WITH W6x8.5 OR W6x9 STEEL POSTS AND BLOCKS




SECTION A-A

* Where bolt is reversed or ⅝" threaded rod is used to mount rail, no more than ½" of thread may be exposed on traffic side of rail.




SECTION B-B



RAIL SPLICE DETAIL

ELEVATION VIEW

Splice the overlapped ends of the rail elements with ⅞"x 1¼" button head oval shoulder bolts and ⅞"x 1¼" recessed hex nut in the ⅞"x 1⅛" slots. Total 8 per rail splice; 4 per terminal section and end section. Lap rail elements in direction of traffic.



SECTION THRU RAIL ELEMENT

NOTES

1. For details of standard hardware used to construct guard railing, see Standard Dwg. M-32.
2. For details of posts and blocks used to construct guard railing, see Standard Dwg. M-33.
3. Guard railing post spacing to be 6'-3" center to center, except as otherwise noted.
4. Top of rail to be 27" above the ground line or shoulder surfacing under the rail element.
5. For guard railing approach flares, see Standard Dwg. M-34 and M-35.
6. For embankment widening details to accommodate guard railing approach flares, see Standard Dwg. M-36.
7. For guard railing end anchor details, see Standard Dwg. M-37 and M-39.
8. For guard railing connection details to bridge railing, retaining walls and abutments, see Standard Dwg. M-40.
9. For guard railing connection details to bridge sidewalks and curbs, see Standard Dwg. M-41.
10. For dike positioning with guard railing installations, see Standard Dwg. M-36.
11. Direction of traffic indicated by →

REVISION	BY	APPROVAL	DATE

DRAWING NUMBER

M-32

SAN DIEGO REGIONAL STANDARD DRAWING


METAL BEAM GUARD RAILING STANDARD

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


COORDINATOR R.C.E. 25902 DATE 4-20-92

NOTES


1. Terminal sections will not be installed on the trailing end of guard railing placed adjacent to one-way roadways.
2. Back-up plate to be used between guard rail element and steel block on steel post where there is no rail element splice. See Standard Dwg. M-31.
3. For end section details, see Standard Dwg. M-40.
4. For terminal section Type C, see Standard Dwg. M-38.




RETURN SECTION




TERMINAL SECTION
TYPE A




TERMINAL SECTION
TYPE B



SECTION THRU
RAIL ELEMENT




⅝" Ø RECESS NUT




⅝" Ø BUTTON HEAD BOLT

L	THREAD LENGTH
1 1/4"	full thread length
2"	1 1/2" Min thread length
2½"	1 3/4" Min thread length
L	2½" Min thread length



BACK-UP PLATE
See Note 2



FLAT PLATE WASHER

REVISION	BY	APPROVAL	DATE

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

COORDINATOR R.C.E. 25902 DATE

SAN DIEGO REGIONAL STANDARD DRAWING


METAL BEAM GUARD RAILING POSTS AND BLOCKS

DRAWING NUMBER


M-33

NOTES


1. All holes in wood posts and blocks shall be 3/4" 0 ±1/16".
2. All holes in steel posts and blocks shall be 13/16" 0 maximum.
3. Contractor may submit alternative steel post details for Engineer's approval.
4. Dimensions shown for wood post are nominal.




W6x15 STEEL POST




W6x8.5 OR W6x9 STEEL POST




6" x 8" DOUGLAS FIR POST




10" x 10" DOUGLAS FIR POST




6"x6"x1'-2" (0.1875" THICK) TUBULAR STEEL BLOCK



W6x8.5 OR W6x9 STEEL BLOCK



6" x 8" DOUGLAS FIR BLOCK



8" x 8" DOUGLAS FIR BLOCK

REVISION	BY	APPROVAL	DATE

DRAWING NUMBER

M-34


SAN DIEGO REGIONAL STANDARD DRAWING

GUARD RAIL FLARES


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

COORDINATOR R.C.E. 25902 DATE 4-20-92


CAA = Cable Anchors Assembly
ETW = Edge of Traveled Way




TYPE 4 FLARE
See Note 3




DETAIL A




TYPE 3 FLARE
See Note 3



37'-6" PARABOLIC OFFSETS




TYPE 2 FLARE
(See Note 3)




TYPICAL PARABOLIC LAYOUT

NOTES

1. Post, blocks and hardware to be used are shown on Standard Dwg. M-32 and M-33.
2. Guard rail post spacing to be 6'-3" center to center, except as otherwise noted.
3. Except as noted, posts shown are 6" X 8" DF, W6 X 8.5 or W6 X 9 steel posts and blocks may be specified for 6" X 8" DF posts and blocks where applicable. Where 10" X 10" DF posts and 8" X 8" DF blocks are shown, W6 X 15 steel posts and Tubular Steel 6" X 6" X 1'-2" (0.1875" thick) blocks may be specified where applicable.
4. Top of rail to be 27" above ground line or shoulder surfacing under the rail element.
5. Direction of traffic indicated by →
6. For connection details see Standard Dwg. M-40 or M-41.
7. For end anchor details see Standard Dwg. M-37 and M-39.
8. Terminal Sections will not be installed on trailing end of guard rail placed adjacent to one-way roadways.
9. Parabola portion of Type I Flare used at approach end of guard railing for embankment installations.
10. For embankment widening details to accommodate approach flares, see Standard Dwg. M-36.
11. Sand filled crash cushion, as approved by the Engineer is required for Type 2, 3, and 4 flares, when the end of the guard rail is within 30 feet of the edge of traveled way (ETW) of approaching traffic.



TYPE IFLARE
(STEEL POST INSTALLATION)
See Note 9



TYPE I FLARE
(WOOD POST INSTALLATION)
See Note 9

REVISION	BY	APPROVAL	DATE

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

COORDINATOR R.C.E. 25902 DATE 4-30-97

SAN DIEGO REGIONAL STANDARD DRAWING


GUARD RAIL FLARES

DRAWING NUMBER


M 25

NOTES


1. Post, blocks and hardware to be used are shown on Standard Dwg. M-31 and M-32.
2. Guard rail post spacing to be 6'-3" center to center, except as noted.
3. Except as noted, posts shown are 6" X 8" DF, W6 X 8.5 or W6 X 9 steel posts and blocks may be specified for 6" X 8" DF posts and blocks where applicable. Where 10" X 10" DF posts and 8" X 8" DF blocks are shown, W6 X 15 steel posts and Tubular Steel 6" X 6" X 1'-2" (0.1875" thick) blocks may be specified where applicable.
4. Top of rail to be 27" above ground line or shoulder surfacing under the rail element.
5. A 4' minimum clearance is required between face of rail and a fixed object located directly behind a guard rail post. A fixed object located behind the rail but not behine a guard rail post requires a 3' minimum clearance. Where minimum clearance cannot be obtained use approach railing transition details for fixed objects.
6. Direction of traffic indicated by →
7. For connection details see Standard Dwg. M-40.
8. For end anchor details see Standard Dwg. M-37 and M-39.
9. Terminal Sections will not be installed on trailing end of guard rail placed adjacent to one-way roadways.
10. Type 7 flare has been deleted.
11. Sand filled crash cushion, as approved by the Engineer is required for Type 5 and 6 flares, when the end of the guard rail is within 30 feet of the edge of traveled way (ETW) of approaching traffic.




DETAIL A




TYPICAL PARABOLIC LAYOUT




37'-6" PARABOLIC OFFSETS



TYPE 9 FLARE




TYPE 8 FLARE




Use with Type 5, 6, and 8 flares when guard rail is less than 4' from fixed object. See Note 5. For a series of columns, additional 10"x10"x5'-4" DF post at 3'-1½" center to center spacing to be used between columns. Where 10"x10" DF posts and 8"x8" DF blocks are shown, W6x15 steel posts and Tubular Steel 6"x6"x1'-2" (0.1875" thick) blocks may be specified where applicable. Where 6"x8" DF posts and blocks are shown, W6x8.5 or W6x9 steel posts and blocks may be specified where applicable.

APPROACH RAILING TRANSITION DETAIL FOR FIXED OBJECT



TYPE 5 FLARE



TYPE 6 FLARE

CAA = Cable Anchors Assembly
ETW = Edge of Traveled Way


REVISION	BY	APPROVAL	DATE

DRAWING NUMBER


M-36

SAN DIEGO REGIONAL STANDARD DRAWING


METAL BEAM GUARD RAILING MISCELLANEOUS




EMBANKMENT WIDENING AND DIKE PLACEMENT DIAGRAM
See Note land 2




DIKE POSITIONING
(See Note 2)



GUARD RAILING DELINEATION
See Note 4



DETAIL A



DETAIL B

Form socket in concrete to receive 6"x8" post or place concrete around 6"x8" post wrapped with one layer of ½" thick expanded polystyrene foam sheeting. Do not nail polystyrene to post. Post to be centered in concrete footing.

POST FOOTINGS
(See note 3)

Use where standard embedment of railing post is restricted by underground concrete facilities such as footing of walls, columns, etc. Use Detail A where embedment of post is less than 1'-9". Use Detail B where embedment of post is between 1'-9" and 3'-0".

NOTES

1. For guard rail flare details, see Standard Dwg. M-34 and M-35.
2. When necessary to place dike in front of guard rail, only Type "C" dike may be used. For dike details see Standard Dwg. G-5.
3. For standard railing post embedment see Standard Dwg. M-31.
4. Guard railing delineation to be used when required by special provisions.
5. Direction of traffic indicated by →

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

COORDINATOR R.C.E. 25902 DATE 4-30-92

REVISION	BY	APPROVAL	DATE


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

COORDINATOR R.C.E. 25902 DATE 4-20-92


SAN DIEGO REGIONAL STANDARD DRAWING

GUARD RAIL END ANCHORS (BREAKAWAY)

DRAWING NUMBER M 27




PLAN




ELEVATION

CABLE ANCHOR ASSEMBLY

(BREAKAWAY, TYPE B)



PLAN




ELEVATION

CABLE ANCHOR ASSEMBLY


(BREAKAWAY, TYPE A)

END PLATE DETAIL

Form socket in concrete to receive 6"x8" post or place concrete around 6"x8" post wrapped with one layer of ½" thick expanded polystyrene foam sheeting. Do not nail polystyrene to post. Post to be centered in concrete footing.



PLAN



ELEVATION

BREAKAWAY END ANCHORS

NOTES

1. For typical use of cable anchor assembly (Breakaway, Type A), see Standard Dwg. M-34 and M-35.
2. Cable anchor assembly (Breakaway, Type B) is typically used on the trailing end of guard railing for embankment installations except two-way road beds less than 80 feet in width.
3. Direction of traffic indicated by →
4. For details of Terminal Section Type C, anchor plate and 3/4" cable, see Standard Dwg. M-38.
5. Do not use flat plate washers under head of rail mounting bolt at the second anchor post of Type A anchors and next five line posts. Use flat plate washers on other line posts and at the first anchor post of Type A anchor and at the Type B anchor post.
6. For trailing end of guard rail adjacent to one-way roadway omit terminal section.

REVISION	BY	APPROVAL	DATE

DRAWING NUMBER

M-38

SAN DIEGO REGIONAL STANDARD DRAWING


GUARD RAIL END ANCHORS
(BREAKAWAY HARDWARE)

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


COORDINATOR R.C.E. 25902 DATE 4-20-22

NOTES

1. See Standard Drawing M-37 for Breakaway End Anchor details.




TERMINAL SECTION TYPE C-ELEVATION VIEW




TERMINAL CONNECTOR FOR
OPTIONAL DESIGN TERMINAL SECTION TYPE C

DETAIL C




TERMINAL SECTION TYPE C

DETAIL A




OPTIONAL DESIGN TERMINAL SECTION TYPE C

DETAIL B




ANCHOR CABLE WITH
SWAGED FITTING AND STUD

DETAIL E




ANCHOR PLATE DETAIL



SECTION A-A
(ALTERNATIVE TYPE 1)

SECTION A-A
(ALTERNATIVE TYPE 2)



DETAIL D

REVISION	BY	APPROVAL	DATE

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

COORDINATOR R.C.E. 25902 DATE 4-20-82


SAN DIEGO REGIONAL STANDARD DRAWING

BARRIER AND GUARD RAIL END ANCHORS


DRAWING NUMBER M-29

NOTES


1. For typical use of end anchors shown on this plan, See Standard Drawings M-34 and M-35.
2. Anchor cable to be parallel to guard rail for straight runs of rail. Anchor cable may have angle point at anchor plate if guard rail is curved.
3. 5'-6" with terminal section. May be less than with return sections if separate rods connect to concrete anchor.
4. Anchor rod hooks to be in contact with anchor reinforcement when concrete is placed. Wire ties may be used to position anchor rods.
5. Cable clip connection (Detail A) or clevis and bolt connection (Detail B) to be used with wood post guard railing installation. For steel post guard railing installations, clevis and bolt connection (Detail B) is to be used. Other alternative for attaching cable to anchor rod must be approved by the Engineer.



PLAN




PLAN



ELEVATION

CABLE ANCHOR ASSEMBLY


(W000 POST GUARD RAIL SHOWN)



CABLE CLIP CONNECTION

DETAIL A

See Note 5




ELEVATION

CLEVIS AND BOLT CONNECTION


DETAIL B

(STEEL POST GUARD RAIL SHOWN)

See Note 5




CLEVIS




OPTIONAL SINGLE ANCHOR ROD END DETAILS

Not to be used for double anchors



DOUBLE ANCHOR SINGLE ANCHOR

ANCHOR RODS




SECTION A-A

(ALTERNATIVE TYPE 1)

SECTION A-A


(ALTERNATIVE TYPE 2)

ANCHOR PLATE DETAILS




ANCHOR CABLE WITH SWAGED FITTING AND STUD


DETAIL E




DETAIL D




DETAIL G



BURIED POST ANCHOR



SECTION B-B



DETAIL F


REVISION	BY	APPROVAL	DATE

DRAWING NUMBER


M-40

SAN DIEGO REGIONAL STANDARD DRAWING


GUARD RAIL CONNECTIONS TO BRIDGE RAILS,




GUARD RAIL CONNECTION TO BRIDGE RAILING




STRAIGHT METAL BOX SPACER
See Note 6
Use when approach guard rail is not tapered




TAPERED METAL BOX SPACER
See Note 6
Use when approach guard rail is tapered







GUARD RAIL CONNECTION TO WALL OR ABUTMENT FACE




END SECTION DETAILS






APPROACH RAILING TRANSITION
WOOD POSTS



APPROACH RAILING TRANSITION
STEEL POSTS



See Notes 9 and 10

GUARD RAIL ANCHORAGE TO WALL OR ABUTMENT

NOTES

1. These connection details apply to bridge rails, abutments and retaining walls. For additional connection details for bridge railing, see the project plans.
2. Where 10" X 10" DF post and 8" X 8" DF blocks are shown, W6 X 15 steel posts and tubular steel 6" X 6" X 1'-2" (0.1875" thick) blocks may be specified where applicable.
3. Additional details of post, blocks and hardware are shown on Standard Dwg. M-32 and M-33.
4. Direction of traffic indicated by →
5. For approach railing details, see Type I Flare on Standard Dwg. M-34 and transition details on this plan.
6. When metal box spacer is installed, place 1-1/4" X 5" and 1-1/4" X 4" pipe spacers on 1" bolts passing through interior of tapered box spacer and 1-1/4" X 5-1/4" pipe spacers on 1" bolts passing through interior of straight box spacer.
7. Terminal Sections will not be installed on trailing end of guard rail placed adjacent to one-way roadways. When terminal section is not installed, use backup plate between rail element and metal box spacer. See Standard Dwg. M-32 for backup plate details.
8. This type of connection may be used for both the approach and departing ends of structures on roadways 28 feet or less in width.
9. Use timber shims without posts where rail to wall or abutment clearance is less than 15 inches.
10. Do Not attach rail to bridge columns. Use separate posts as shown on Standard Dwg. M-35.
11. End sections may be cut from Type B terminal section or fabricated.

REVISION	BY	APPROVAL	DATE

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

COORDINATOR R.C.E. 25902 DATE 4-30-92

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


COORDINATOR R.C.E. 25902 DATE 4-30-92


SAN DIEGO REGIONAL STANDARD DRAWING


GUARD RAIL CONNECTION TO BRIDGE SIDEWALK AND CURBS


DRAWING NUMBER

M-41












ANCHOR POST DETAILS
(FOR CONNECTION DETAIL A)


NOTES


1. Connection Details A and B apply to the traffic approach end of bridges. For departure end of bridges, see Connection Detail C.
2. When curb or sidewalk depth is less than 9", use Connection Detail B.
3. Direction of traffic indicated by →
4. For approach railing details, see Type I Flare on on Standard Dwg. M-34.
5. Terminal sections will not be installed on the trailing end of approach guard rail placed adjacent to one-way roadways.
6. Where 10" X 10" DF posts and 8" X 8" DF blocks are shown, W6 X 15 steel post and Tubular Steel 6" X 6" X 1'-2" (0.1875" thick) blocks may be specified where applicable.
7. Rail post assembly to be galvanized after fabrication.
8. Terminal section Type A to be used where pedestrian traffic is present.
9. For additional connection details for bridge barrier railings, see the project plans.























ANCHOR POST DETAILS
(FOR CONNECTION DETAIL B)

REVISION	BY	APPROVAL	DATE

DRAWING NUMBER


M-42

SAN DIEGO REGIONAL STANDARD DRAWING


CONCRETE BARRIER TYPE 50

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


COORDINATOR R.C.E. 25902 DATE




CONCRETE BARRIER
TYPE 50D
Details similar to Type 50 except as noted




CONCRETE BARRIER
TYPE 50C



CONCRETE BARRIER
TYPE 50A
Details similar to Type 50 except as noted
See Note 7




CONCRETE BARRIER
TYPE 50



ELEVATION


CONNECTION TO STRUCTURE

Details similar to Type 50 except as noted
Barrier End Anchor when necessary




ELEVATION

BARRIER END ANCHOR
See Note 9



MEDIAN BARRIER DELINEATION
See Notes 11 and 12



CONCRETE BARRIER DELINEATION
(For barriers not located in median)
See Note 11

NOTES

1. See Standard Dwg. M-32 for concrete barrier transitions at bridge column and sign pedestals.
2. Opening into existing drainage inlets shall not extend above the 3-inch vertical face at bottom of the barrier.
3. Where the barrier is added to the face of an existing concrete structure, matching existing weep holes.
4. Contractor may submit alternative details for Engineer's approval.
5. Footing monolithic or doweled with 2-#8X0'-8"@ 24. Required at barrier ends and at interruptions in barrier.
6. See Standard Dwg. M-33 for glare screen details.
7. Expansion joints in concrete barrier shall be located at all deck, pavement and principal wall joints. Expansion joint filler material shall be the same size as joint or 1/2" minimum.
8. 10" Barrier footing extends 10' back from structure.
9. For transition to TBB see Standard Dwg. M-34.
10. Where roadway offset is greater than 1-1/2", see Concrete Barrier Type 50C.
11. Barrier delineation to be used when required by the special provisions.
12. Spacing of barrier markers to match spacing of raised pavement markers on the adjacent median edgeline pavement delineation.

REVISION	BY	APPROVAL	DATE


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

COORDINATOR R.C.E. 25902 DATE 4-20-92


SAN DIEGO REGIONAL STANDARD DRAWING

CONCRETE BARRIER TYPE 50E

DRAWING NUMBER M 43




SECTION A-A




TRANSITION AT BRIDGE COLUMN
CONCRETE BARRIER TYPE 50E

NOTES


1. See Standard Dwg. M-31 for Concrete barrier Type 50.
2. See Standard Dwg. M-33 for Headlight glare Screen Details.
3. Contractor options for fill between barrier walls:
   A: Place 4" PCC at base between barrier walls.
   B: Place 12" of granular material at base between walls,
   C: Place granular material from base to bottom of 4" cap.
   Forming material for 4" cap may remain in place.
4. Reinforcing steel shall extend continuous through construction joints.
5. See "Overhead Sign" plans for sign pedestal elevations on new construction.
6. Adjust height of barier on low side of offset or superelevated roadways to provide level grade across top of Type 50E Barrier.
7. 4" PCC vertical walls at existing sign pedestals.



TRANSITION AT SIGN PEDESTAL
CONCRETE BARRIER TYPE 50E



SECTION B-B



SECTION C-C

REVISION	BY	APPROVAL	DATE

DRAWING NUMBER


M-44

SAN DIEGO REGIONAL STANDARD DRAWING

TEMPORARY RAILING (TYPE K)

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

COORDINATOR R.C.E. 25902 DATE 4-20-92




TYPICAL PANEL

Weight: 3.9 tons per panel


ELEVATION

NOTES


1. For end treatment, layout and crash cushions, where needed, see Project Plans or Special Provisions.
2. All 3-1/2" gaps at removable panels are to be backed at the base with # 8X10" dowel or 1"ø pin each side of joint. See Section K-K.
3. Alternative details for lifting the precast concrete panels of the Temporary Railing may be submitted by the Contractor for the Engineer's approval.
4. Where Temporary Railing (Type K) is placed on curves and radii that are too severe to connect panels with balled joints, the railing is to be backed continuously with earth fill. See Section H-H.
5. Attach units to deck slabs when required by Plans.




SECTION E-E




SECTION A-A




SECTION H-H




MIN EDGE DISTANCE




ELEVATION



VIEW F-F




CURVED LAYOUT




ELEVATION

TYPICAL OPENING DETAIL



SECTION K-K (*)


* Section K-K is for P.C.C. pavement. Alternative detail, 1"ø pins 2'-0" long driven in A.C. or firm soil permitted, minimum 1'-6" deep.



ALTERNATIVE HEAD DETAIL

SECTION G-G

BOLT CONNECTION DETAIL




REMOVABLE PANEL GROOVE DETAILS

REVISION	BY	APPROVAL	DATE

NOTES

1. Structural steel tubing used for post & sleeves shall be galvanized 12 gauge cold rolled steel, of the nominal dimensions shown hereon and meet the requirements of ASTM A446 Grade A.
2. Galvanizing shall be per ASTM A525. Posts & sleeves shall have 7/16" dia. holes spaced 1" o.c. ±1/8" & shall have no more variation in straightness than 1/16" in 3'. Posts shall be square within ±0.014", have twist no greater than 0.062" in 3' and have corner radii of 5/32" ±1/64".
3. The signs shall be mounted on posts in accordance with Section 56, "Signs" of the State Standard Specifications. All fastening hardware is to be provided by the Contractor.
4. Maximum sign size 5.2 sq. ft.



Revision	By	Approved	Date
New Dwg		RLM	2/95

SAN DIEGO REGIONAL STANDARD DRAWING

BREAK–AWAY SIGN POST


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

2-95


Chairman R.C.E. 25902 Date

DRAWING NUMBER M–45


SEWERAGE SYSTEMS



SECTION A – A



STEP DETAIL



SECTION B – B

NOTES:

1. Manhole frame and all joints shall be set in Class "C" mortar.
2. All precast components shall be manufactured in accordance with ASTM C-478.
3. Vertical wall of cone shall be on the upstream side of the manhole.
4. Concrete base shall be 560-C-3250 .
5. Approved water stop required for plastic pipe connectors.
6. Precast sections shall be used within dimension "A" as required, in order of preference listed:
   - A. Cone (notched for pipe if dimension "A" is less then 3').
   - B. 6" to 18" of 3' diameter grade rings/and/or risers.
   - C. 5' diameter shaft variable height.
   - D. Top step to be 15" Max. from top of frame and cover.
7. Flexible pipe joints shall be required within 12" of inside face of manhole except for plastic pipe.
8. All patching within manhole base shall be epoxy mortar.
9. Prior approval of precast base is required by the Agency.

LEGEND ON PLANS

M.H. No. 2

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A Kashmal Dec. 1975
Coordinator R.C.E. 19807 Date

DRAWING NUMBER S-2

SAN DIEGO REGIONAL STANDARD DRAWING

MANHOLE 5'x 3' DIAMETER

Revision	By	Approved	Date
Note 7	TRP	M.B.	10-82
Conc.	JC	M.B.	5-86
Notes	JC	J.H	9-88
Conc base	JP	GA	5-92




TYPE A

TYPE B

NOTES

1. Gate cap shall be labeled "Sewer".
2. Cleanouts may be used for either V.C.P. or plastic sewer mains.
3. Riser to be same diameter as sewer main.



GATE CAP
(Heavy Duty)

LEGEND ON PLANS

Revision	By	Approved	Date
Conc.	[illegible]	M.B.	5-86

SAN DIEGO REGIONAL STANDARD DRAWING

SEWER MAIN CLEANOUT

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A. Kashmal — Dec. 1975
Coordinator R.C.E. 19807 — Date

DRAWING NUMBER **S-3**

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Coordinator R.C.E. 19807 — Date Dec. 1975

DRAWING NUMBER S-4


SAN DIEGO REGIONAL STANDARD DRAWING

PIPE BEDDING AND TRENCH BACKFILL FOR SEWERS


Revision	By	Approved	Date
A, B, & C	RC	M.B.	5-76



TYPE A
STANDARD INSTALLATION




TYPE B
ROCK TO SPRINGLINE



TYPE C
ROCK ENVELOPE

NOTES

1. For trenching in improved streets, see Standard Drawings G-24 or G-25 for trench resurfacing.
2. (*) indicates minimum relative compaction.
3. Minimum depth of cover from the top of pipe to finish grade for all sanitary sewer installations shall be 3 feet. For cover less than 3 feet, see Standard Drawing S-7 for concrete encasement.
4. See Type A installation for details not shown for Types B and C.



SECTION

LEGEND ON PLANS

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan O Kashani Dec. 1975


Coordinator R.C.E. 19807 Date

DRAWING NUMBER S-6

SAN DIEGO REGIONAL STANDARD DRAWING

CONCRETE CRADLE

Revision	By	Approved	Date



SECTION

NOTE:

Encase pipe to the nearest flexible joint.

LEGEND ON PLANS

Revision	By	Approved	Date
Note	TRP	M.B.	10-82


SAN DIEGO REGIONAL STANDARD DRAWING

CONCRETE ENCASEMENT

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allen A Kashmar — Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER S-7



SECTION

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Chairman R.C.E. 25902 Date 2-95

DRAWING NUMBER S–8


SAN DIEGO REGIONAL STANDARD DRAWING

CONCRETE BACKFILL


Revision	By	Approved	Date
Rock Sz	OM	A. Mohije	2-95



PLAN



FRONT ELEVATION



SIDE ELEVATION

LEGEND ON PLANS



Revision	By	Approved	Date
Expan. jt.	TRP	M.B.	10-82


SAN DIEGO REGIONAL STANDARD DRAWING

CONCRETE ANCHOR

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan O Kaufman — Coordinator R.C.E. 19807 — Dec. 1975 — Date

DRAWING NUMBER S-9




Blocks to be laid as tightly as possible to downstream side of notch.

PLAN


NOTES

Type B:


1. No vertical joints permitted.
2. Horizontal joints must overlay by 2 corrugations.
3. Corrugations to run horizontally.
4. Front Elevation and Plan views similar to Type A.



FRONT ELEVATION



SIDE ELEVATION




ELEVATION


TYPE A

TYPE B

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Allan A Kenkel Dec. 1975 Coordinator R.C.E. 19807 Date	SAN DIEGO REGIONAL STANDARD DRAWING	Revision / By / Approved / Date	
		Type A / BC / D. S. / 7-79	
		Chg. notes / TRP / M.B. / 10-82	
DRAWING NUMBER S-10	CUTOFF WALL		



SECTION

LEGEND ON PLANS

Revision	By	Approved	Date


SAN DIEGO REGIONAL STANDARD DRAWING

CONCRETE PROTECTION FOR EXISTING SEWER PIPE


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen A Kashani — Coordinator R.C.E. 19887 — Dec. 1975 — Date

DRAWING NUMBER S-11



TYPICAL SECTION



SECTION A–A

LEGEND ON PLANS



NOTE

For water line construction encasement shall extend to first joint beyond 2 feet at both sides of trench or to a distance of 4 feet, whichever is less.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A Kershaw — Dec. 1975


Coordinator R.C.E. 19807 — Date

DRAWING NUMBER **S-12**


SAN DIEGO REGIONAL STANDARD DRAWING

CONCRETE SUPPORT FOR UNDERCUT SEWER PIPE


Revision	By	Approved	Date
Conc.	[illegible]	M.B.	5-86



PLAN



ELEVATION




Detail showing the manner of connecting opposite laterals to a sewer main. Two connections shall not be made in the same length of pipe.

NOTES

1. In no case shall a lateral connect to the sewer main directly on top of the pipe.
2. Sewer laterals shall have a minimum slope of 2%.
3. All joints on sewer lateral pipe shall be compression type or approved solvent weld.
4. Lateral shall extend to property line unless otherwise shown on plans.

LEGEND ON PLANS



Revision	By	Approved	Date


SAN DIEGO REGIONAL STANDARD DRAWING

HOUSE CONNECTION (SEWER LATERAL)

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allen A Kershaw — Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER S-13




NOTE
All joints on sewer lateral pipe shall be compression type or approved solvent weld.

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
Allen A Kenkel Dec. 1975 Coordinator R.C.E. 19807 Date	DEEP CUT HOUSE CONNECTION (SEWER LATERAL)				
DRAWING NUMBER S-14					



TYPICAL SECTION

NOTE

For water line construction repair pipe shall extend to first joint beyond 2 ft. at both sides of trench or to a distance of 4 ft., whichever is less.

Revision	By	Approved	Date

SAN DIEGO REGIONAL STANDARD DRAWING


HOUSE CONNECTION SEWER REPAIR

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen J. Kashani — Dec. 1975

Coordinator R.C.E. 19807 — Date

DRAWING NUMBER **S-15**



NOTES

1. Similar poly vinyl chloride components may be used in accordance with A.S.T.M. Standard Specification D-3033.
2. Concrete slab to be 560-C-3250
3. Use heavy duty manhole frame and cover, Std. Dwg. M-1, in areas subject to vehicular traffic; use light duty manhole frame and cover, Std. Dwg. M-2, in all other locations.

LEGEND ON PLANS

C.O.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Coordinator R.C.E. 25291 Date July 1979

DRAWING NUMBER S-16


SAN DIEGO REGIONAL STANDARD DRAWING

CLEANOUT - SEWER FORCE MAIN

Revision	By	Approved	Date
Conc., slab	[illegible]	M.B.	5-86




SECTION B–B




HALF SECTION SHALLOW MANHOLE


* Either Concentric or Eccentric Cone may be used.



SECTION C–C



STEP DETAIL



SECTION A -A

LEGEND ON PLANS

M.H. No. 2

NOTES

1. Manhole frame and all joints shall be set in Class "C" mortar.
2. All precast components shall be manufactured in accordance with ASTM C-478 except step spacing.
3. Vertical wall of cone shall be on the upstream side of the manhole.
4. Concrete base shall be 560-C-3250.
5. Approved water stop required for plastic pipe connections.
6. Flexible pipe joints shall be required within 12" of inside face of manhole. (except for plastic pipe)
7. Precast base permitted as approved by Agency.
8. Precast sections shall be used within dimension "A" as required, in order of preference listed:
   A. Cone (notched for pipe if dimension "A" is less than 3').
   B. 3" to 18" of 3' diameter grade rings/and/or risers.
   C. 4' diameter shaft variable height.
   D. Top step to be 15"Max. from top of frame and cover.
9. All patching within manhole base shall be epoxy mortar.
10. Prior approval of precast base is required by the Agency.

Revision		Approved	Date
Notes	IRP	M.B.	10/82
Conc.,Step	&	M.B.	5-86
NOTES	&	A.H.	8-88


SAN DIEGO REGIONAL STANDARD DRAWING

MANHOLE - 4' x 3' DIAMETER (FOR 15" MAX. DIA. PIPE)


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Coordinator R.C.E. 25291 Date July 1979

DRAWING NUMBER S-17



SECTION



PLAN

Revision	By	Approved	Date

SAN DIEGO REGIONAL STANDARD DRAWING

METALLIC TAPE LOCATOR FOR NON-METALLIC SEWER PIPE

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


M. Bahmanian 4-25-86
Coordinator R.C.E. C21133 Date

DRAWING NUMBER S-19


WATER SYSTEMS

NOTES

1. Service clamp and gasket required on 4" A.C. pipe.
2. Tap not permitted in milled sections of A.C. pipe.



TOP TAP
(where permitted by Agency)



1. Bronze Corporation Stop (installed with key on side and open tap) and Adaptor as required by Agency.
   Note: On steel mains use clamp or weld on coupling as required by Agency.
   Install insulating bushing as required by Agency.
2. Copper Tubing or Plastic Pipe (no intermediate joints permitted without approval of the Agency).
3. Bronze Angle Service Stop with Locking Device and Meter Coupling attached.
4. Meter Box (see Standard Drawing W-15 for location).
5. 90° Ell

LEGEND ON PLANS

1" —— (W)

Revision	By	Approved	Date
Notes	JC	D.S.	7-79

SAN DIEGO REGIONAL STANDARD DRAWING


1" WATER SERVICE

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A Kenkel — Dec. 1975

Coordinator R.C.E. 19807 — Date

DRAWING NUMBER **W-1**




TOP TAP
(where permitted by Agency)

Top tap where permitted by Agency

NOTE

Silver Soldered Joints may be used where approved by the Agency.



1. Bronze Service Clamp (double strap). On steel mains use clamp or weld on coupling as required by Agency. Install insulating bushing as required by Agency.
2. Bronze Corporation Stop (installed with key on side and open tap).
3. Copper Tubing or Plastic Pipe except where otherwise specified by the Agency.
4. Coupling as required by Agency when service is 20' or longer, except on Polyethylene Pipe.
5. 90° Ell
6. Bronze Angle Service Stop with Locking Device and adaptable to 1 1/2" and 2" Meter Flange.
7. Meter Box (see Standard Drawing W-15 for location).

LEGEND ON PLANS

2" (W)

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A. Kershaw Dec. 1975
Coordinator R.C.E. 19807 Date

DRAWING NUMBER **W-2**

SAN DIEGO REGIONAL STANDARD DRAWING

1½" AND 2" WATER SERVICES

Revision	By	Approved	Date
Notes	SC	D.S.	7-79



1. Bronze Service Clamp (double strap). On steel mains use clamp or weld on coupling as required by Agency. Install insulating bushing as required by Agency.
2. Bronze Corporation Stop
3. 90° Brass Street Ell
4. Pipe to Tubing Adaptor
5. Copper Tubing
6. Ball Valve
7. Brass Plug
8. Meter Box (see Standard Drawing W-15 for location).

LEGEND ON PLANS

Revision	By	Approved	Date
Notes		D.S.	7-77


SAN DIEGO REGIONAL STANDARD DRAWING

1" AND 2" MANUAL AIR RELEASES

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Coordinator R.C.E. 19887 — Dec. 1975 Date

DRAWING NUMBER W-3



1. Double Strap Bronze Service Clamp. On steel mains use clamp or weld on coupling as required by Agency. Install insulating bushing as required by Agency.
2. Corporation Stop
3. Pipe x Tubing 90° Ell
4. 90° Sweat Ell
5. Copper Tubing
6. Female Adaptor
7. Air and Vacuum Valve
8. 2-90° Ells (not required in above metal ground enclosures).

LEGEND ON PLANS

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan O Kashuba Dec. 1975
Coordinator R.C.E. 19807 Date

DRAWING NUMBER W-4

SAN DIEGO REGIONAL STANDARD DRAWING

1" AND 2" AIR AND VACUUM VALVES

Revision	By	Approved	Date
Notes	JC	O.S.	7-79



1. Flanged Outlet, Cement Lined and Coated Steel
2. Flanged, 90° Ell, Cement Lined and Coated Steel
3. Valve
4. Valve Well and Cap (see Standard Drawing W-12)
5. Steel Pipe, Cement Lined and Coated
6. Air and Vacuum Valve
7. 2 90° Ells (not required with above ground metal enclosures)

LEGEND ON PLANS

Revision	By	Approved	Date


SAN DIEGO REGIONAL STANDARD DRAWING

4" AND 6" AIR AND VACUUM VALVES

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A Kenkel — Coordinator R.C.E. 19807 — Dec. 1975 — Date

DRAWING NUMBER **W-5**



END OF MAIN DETAIL

1. Bronze Service Clamp (double strap). On steel mains use clamp or weld on coupling as required by Agency. Install insulating bushing as required by Agency.
2. Bronze Corporation Stop (installed with key on side and open tap) and adaptor as required by Agency.
3. Copper Tubing
4. 90° Ell
5. Pipe to Tubing Adaptor
6. Ball Valve
7. Brass 2" Iron Pipe Thread x 2 1/2" Hose Pipe Thread Adaptor.
8. 2 1/2" Hose Cap with chain, Brass.
9. Meter Box (see Standard Drawing W-15 for location).

LEGEND ON PLANS

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allan A Kershaw — Coordinator R.C.E. 19807 — Dec. 1975 Date


DRAWING NUMBER **W-6**

SAN DIEGO REGIONAL STANDARD DRAWING


2" BLOW-OFF ASSEMBLY - TYPE A

Revision	By	Approved	Date
Detail	[illegible]	D.S.	7-79






TYPE–B



TYPE–C



TYPE–D

1. Bronze Service Clamp (double strap) or Pretapped Coupling. On steel mains use clamp or weld on coupling as required by Agency. Install insulating bushing as requried by Agency.
2. 2" Nipple (2"x 3")
3. 45° Ell
4. 2" Nipple (2"x 6")
5. 2" Valve
6. 2" Pipe
7. 90° Ell
8. 2" Threaded Cap
9. Valve Well Installation, See Standard Drawing W-12

NOTES

1. Type of installation and materials to be specified by Agency.
2. See Standard Drawing W-6 for end of main detail.

LEGEND ON PLANS

Revision	By	Approved	Date
Notes	SC	D.S	7-79


SAN DIEGO REGIONAL STANDARD DRAWING

2" BLOW-OFF ASSEMBLIES TYPES B, C AND D

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A Kenkel — Coordinator R.C.E. 19807 — Dec. 1975 Date

DRAWING NUMBER **W-7**



1. Flanged Tee or Welded Saddle.
2. Short Radius 90° Flanged Bend, Cement Lined and Coated.
3. Steel Pipe, Cement Lined and Coated.
4. Flanged Valve.
5. Steel Pipe (or P. V. C. Schedule 80 Pipe Where Permitted by Agency).
6. Valve Well (See Standard Drawing W-12).
7. 90° Bend (Same Material as Item 5).

LEGEND ON PLANS

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Allen A Kuckenal Dec. 1975
Coordinator R.C.E. 19807 Date

DRAWING NUMBER **W-8**

SAN DIEGO REGIONAL STANDARD DRAWING


4'' AND 6" BLOW-OFF ASSEMBLIES TYPE A

Revision	By	Approved	Date



1. Main Size x Flanged Outlet, cement lined and coated.
2. Flanged Gate Valve (F x RT for A.C. Pipe).
3. Cast Iron Pipe or A.C. Pipe (6 1/2' min for A.C. Pipe).
4. F x F 90° Bend (F x RT for A.C. Pipe).
5. Galvanized Iron Pipe, threaded and flanged.
6. 10" Class 200 A.C. Pipe Gate Well.
7. Galvanized Iron Coupling, threaded.
8. Galvanized Iron Plug.
9. Gate Well Cap with 4" skirt.
10. Valve Well (see Standard Drawing W–12).

LEGEND ON PLANS



Revision	By	Approved	Date

SAN DIEGO REGIONAL STANDARD DRAWING


4" AND 6" BLOW-OFF ASSEMBLIES TYPE B

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A Kenkel — Coordinator R.C.E. 19807


DEC. 1975 — Date

DRAWING NUMBER **W-9**



NOTE

Items ④ and ⑦ may be cement lined and coated steel pipe where permitted.



3 OUTLETS 2 OUTLETS FLANGE DETAILS

① Fire Hydrant

② 6" Extension Spool (Double Machine Grooved)

③ Break-Off Check Valve Body or Extension Spool as required by agency or shown on plans.

④ Extension Spool

⑤ 0.75" x 3" Hex Head Machine Bolts and Nuts (Typical)

⑥ Hydrant Ell


⑦ Polyvinyl Chloride (PVC) or Ductile Iron (DI) Pipe

⑧ Valve with Concrete Support, Std. Dwg. W-19 (Type A)

⑨ Valve Well and Cover, Std. Dwgs. W-12A & W-12B

⑩ See Std. Dwg. W-11 for fire hydrant locations.

LEGEND ON PLANS



RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

2-95


Chairman R.C.E. 25902 Date

DRAWING NUMBER W-10

SAN DIEGO REGIONAL STANDARD DRAWING

FIRE HYDRANT WITH CHECK VALVE

Revision	By	Approved	Date
Title	DM	RLM	2/95
Notes			



NOTES:

1. Apron, where required by Agency, shall be 4" thick (520-C-2500) concrete.
2. When distance from hydrant to the top or toe of slope is less than 2'–0", special hydrant installation will be required by Agency.
3. Where hydrant is not protected by a vertical face of curb protective posts are required. See Standard Drawing W-16 for details.
4. The centerline of the hydrant shall be located 5' minimum from curb return and minimum 3'-6" from driveway, pedestrian ramp or any fixed obstruction.

Revision	By	Approved	Date
Notes	TRP	M.B.	10-82
Note 4		A.H.	9-88


SAN DIEGO REGIONAL STANDARD DRAWING


FIRE HYDRANT LOCATIONS

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen D Kenkel — Dec. 1975
Coordinator R.C.E. 19807 — Date

DRAWING NUMBER W-11





CAST IRON
VALVE WELL COVER
(40 lbs. min.)

VALVE WELL COVER PAINT CHART			
VALVE CONDITION	BUTTERFLY VALVES	GATE VALVES	BLOW-OFF VALVES
PERMANENTLY CLOSED	RED	RED	-
TEMPORARILY CLOSED	YELLOW w/RED DOT	WHITE w/RED DOT	ALUMINUM
PERMANENTLY OPEN	YELLOW	WHITE	-

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Chairman R.C.E. 25902 Date 2-95

DRAWING NUMBER W-12A


SAN DIEGO REGIONAL STANDARD DRAWING

VALVE WELL COVER


Revision	By	Approved	Date
New Dwg	OH	RLM	2/95




TYPE 1 | TYPE 2



CAST IRON
VALVE WELL FRAME



VALVE WELL AND FRAME
For New Installations



CAST IRON RISER RING
For Retrofitting
and
Overlay Projects

NOTES:

1. Provide valve key extension for all butteryfly valves. For gate valves, provide valve key extension where this dimension exceeds 25".
2. The surface of the valve well cover shall match the street cross slope and profile.
3. See Standard Dtawing W-13 for valve stem extension when required by agency.

Revision	By	Approved	Date
New Dwg	DA	RLM	2/95

SAN DIEGO REGIONAL STANDARD DRAWING


VALVE WELL FRAME AND ASSEMBLY

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Chairman R.C.E. 25902 Date 2-9-95

DRAWING NUMBER W-12B

BLANK PAGE



TOP VIEW

ELEVATION

BOTTOM VIEW

NOTES:

1. Extension to be used when top of operating nut is 5 feet or more below finish grade.
2. Paint all finished surfaces with asphalt varnish.

Revision	By	Approved	Date


SAN DIEGO REGIONAL STANDARD DRAWING

VALVE STEM EXTENSION

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE


Chairman RCE 25902 Date 5-11-92

DRAWING NUMBER W-13




PLAN


Valve Size	Dia	H
1" & 2"	14"	24"
4"	14"	30"
6"	16"	36"



TYPE A



TYPE B



TYPE C

(1) Steel enclosure, paint as specified by Agency.

(2) Meter box, see Standard Drawing W-15 for location.

(3) 2' x 2' pad, 470 - C - 2000 Concrete

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A Kershaw Dec. 1975


Coordinator R.C.E. 19807 Date

DRAWING NUMBER **W-14**

SAN DIEGO REGIONAL STANDARD DRAWING

AIR AND VACUUM VALVE ENCLOSURES

Revision	By	Approved	Date



TYPE *A1
WITH OR WITHOUT COMMERCIAL
OR RESIDENTIAL SIDEWALK

TYPE *A2
CONTIGUOUS SIDEWALK

TYPE B
NON-CONTIGUOUS SIDEWALK

TYPE C
NO CURB

TYPE D
NO CURB

* Agency to determine alternate

NOTE:
Meter boxes shall not be located within driveways.

Revision	By	Approved	Date
Note	[illegible]	A.H.	7-88


SAN DIEGO REGIONAL STANDARD DRAWING

METER BOX LOCATIONS


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen A Kenkel — Coordinator R.C.E. 19807 — Dec. 1975 — Date


DRAWING NUMBER **W-15**




RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Coordinator R.C.E. 19807 — Date: Dec. 1975	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
DRAWING NUMBER **W-16**	**PROTECTION POST**				




TEE




HORIZONTAL OR
VERTICAL BEND




WYE






CROSS BLOCKING



STEEL PIPE
PLAN



A.C. PIPE
ELEVATION

DEAD END BLOCKING

NOTES

1. Concrete shall be 470 - C - 2000.
2. See Standard Drawing W-18 for bearing areas.

Revision	By	Approved	Date


SAN DIEGO REGIONAL STANDARD DRAWING

CONCRETE THRUST BLOCKS

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan A Kenkel — Dec. 1975
Coordinator R.C.E. 19807 — Date


DRAWING NUMBER **W-17**




NOTES

1. Based on 225 psi test pressure and bearing values of dry soils.
2. Values from curves are for tees and deadends, i.e.; straight line thrust.
   For 90° bend: 1.4 value from curve.
   For 45° bend: 0.8 value from curve.
   For 22 1/2° bend: 0.4 value from curve.
3. For conditions not covered by curves, special thrust blocks must be computed and approved.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
Allan A Kershaw Dec. 1975 Coordinator R.C.E. 19607 Date					
DRAWING NUMBER W-18	THRUST BLOCK BEARING AREAS				



TYPE–A SUPPORT BLOCK



TYPE–B THRUST BLOCK

NOTE
Concrete shall be 470-C-2000.

Revision	By	Approved	Date


SAN DIEGO REGIONAL STANDARD DRAWING

CONCRETE VALVE BLOCKING

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen J. Kercheval — Dec. 1975
Coordinator R.C.E. 19807 — Date

DRAWING NUMBER **W-19**



Pipe Nominal Dia	Cubic Ft. Of Concrete Required per 100 P.S.I. Pressure *		
	45°	22 1/2°	11 1/4°
4	7	4	2
6	15	8	4
8	27	14	7
10	* *	21	11
12	* *	* *	16

* Increase volumes shown in proportion to pressures existing when pressure testing pipeline.

* * Special design required.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allen A Kershaw Dec. 1975


Coordinator R.C.E. 19807 Date

DRAWING NUMBER **W-20**

SAN DIEGO REGIONAL STANDARD DRAWING

ANCHOR BLOCK (VERTICAL BEND ONLY)

Revision	By	Approved	Date



SECTION

NOTES

1. For trenching on improved streets see standard drawing G-24 or G-25 for resurfacing details.
2. (*) indicates minimum relative compaction.
3. Bedding material shall either be sand, gravel, crushed aggregate or native free draining granular material having a sand equivalent (SE) of not less than (50) and an expansion coefficient, when saturated with water, of not more than 0.5 of one percent (0.5%).

Revision	By	Approved	Date
Section	SC	O.S.	7-77
Reference	MP	M.B.	10-82
Compact.	TC	M.B.	5-86
Note 3	SR	G.L.	5-92


SAN DIEGO REGIONAL STANDARD DRAWING


PIPE BEDDING AND TRENCH BACKFILL FOR WATER MAINS

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Allan D Kenkel — Coordinator R.C.E. 19807 — Dec. 1975 Date


DRAWING NUMBER **W-21**





NOTE:
Bearing area shall be the difference between the bearing areas required for thrust anchorage of mains on each side of reducer as found from Std. Dwg. W-18 plus the area of the trench opening, except that minimum dimensions shown shall be adhered to.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
David J. Solomon Coordinator R.C.E. 25291 July 1979 Date	THRUST ANCHOR FOR WATER MAIN REDUCER - 4 THRU 16 INCH				
DRAWING NUMBER W-22					



SECTION A-A

ELEVATION

1. 1" Water service per Dwg W-1
2. 1" Curb stop
3. Main connection X multiple branch connection
4. Brass coupling or 45° elbow
5. Brass nipple - 4" min. length
6. Brass 45° elbow
7. Cast iron cap
8. Asbestos cement pipe
9. Thrust block per Dwg W-17

NOTE: Nipple lengths to be sufficient to allow service connection to clear thrust block.

Service Connection	Main Connection Item 5
2	1¼"
3	1½"
4	2"
6	2½"
8	3"

Revision		Approved	Date


SAN DIEGO REGIONAL STANDARD DRAWING

MULTIPLE SERVICE ASSEMBLY DEAD END MAIN


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

Coordinator R.C.E. 25291 — July 1979 Date

DRAWING NUMBER W-23




ELEVATION




SECTION A-A

NOTE:
Contractor shall provide handholes as required to complete the work

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE Coordinator R.C.E. 25291 July 1979 Date	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
DRAWING NUMBER W-24	SPLIT BUTT STRAP				



SECTION



PLAN

* 1. Use 2" tape for depths of 30" or less.
2. Use 3" tape for depths greater than 30".
3. Adequately bond service tape to main tape to ensure electrical continuity.
4. Tape shall extend into service box or well casing to allow for mark-out by continuity tester.

Revision	By	Approved	Date
Notes 3,4	JP	G.D.	5/92


SAN DIEGO REGIONAL STANDARD DRAWING

METALLIC TAPE LOCATOR FOR NON-METALLIC WATER PIPE


RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE

M. Behrmann 4-25-86
Coordinator R.C.E C21133 Date

DRAWING NUMBER W-25



ELEVATION



PLAN

NOTES

1. Public water main.
2. 90° ductile iron elbow: flange x flange; flange x ring tight; flange x mechanical joint (uni-flange shall not be used).
3. Flanged ductile iron spool (both ends shall be flanged).
4. 90° flanged ductile iron elbow.
5. Factory assembled Double Checked Detector Assembly/Reduced Pressure Detection Assembly with resilient seat shut off. Valves approved by the Dept. of Health Services, Office of Drinking Water.
6. Backflow preventor assembly shall be tested upon installation by a certified backflow assy. tester. Contractor shall provide the Engineer with written test results completed by a certified tester prior to the acceptance by the Engineer.

RECOMMENDED BY THE SAN DIEGO REGIONAL STANDARDS COMMITTEE	SAN DIEGO REGIONAL STANDARD DRAWING	Revision	By	Approved	Date
Chairman RCE 25902 Date 5-11-92					
DRAWING NUMBER W-26	BACKFLOW PREVENTER REDUCED PRESSURE PRINCIPLE				

APPENDIX "A"

TRAFFIC CONTROL PLANS

TRAFFIC CONTROL PLANS

REVISION	BY	APPROVED	DATE	SAN DIEGO REGIONAL STANDARD - APPENDIX "A"	DWG. NO.
				TRAFFIC CONTROL PLANS	TC

TRAFFIC CONTROL PLANS

GENERAL INFORMATION

The Traffic Control Plans depicted in this Appendix are intended to supplement Chapter 5 of the Caltrans Manual in providing guidance and information on preparing traffic control plans in an urban environment. Other references, such as the "W.A.T.C.H." manual, may also provide useful information on traffic control procedures. It should be understood that implementation of traffic control plans must conform with the latest edition of the Caltrans Traffic Manual (Chapter 5).

Chapter 5 of the Caltrans Traffic Manual, Traffic Controls for Construction and Maintenance Work Zones, is published by the State of California, Department of Transportation (Caltrans). This manual is issued to provide the basic standards for uniform types of warning signs, lights, and devices to be placed upon any public roadway or street by a person engaged in performing work which interferes with or endangers the safe movement of traffic upon such highway or street, in accordance with Section 21400 of the California Vehicle Code.

It is the responsibility of the Contractor or Organization performing work on, or adjacent to, a roadway to install and maintain such devices which are necessary to provide safe passage for the traveling public through the work area and for the safety of the workers. Before work begins, traffic control plans for handling traffic through a construction or maintenance project shall be approved by the engineer of the public agency or authority having jurisdiction over the roadway.

Typical plans for intersections that are controlled by a traffic signal or a multi-way stop are not identified in this Appendix. These intersections require special attention in the preparation of traffic control plans. The approving agency should be notified prior to the preparation of traffic control plans when the work is in or near these intersections.

Special attention is also needed on the traffic control plans when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Notification of the approving agency is desireable prior to the preparation of the plan when bicycles and pedestrian routes are affected by the work.

Nothing contained in this Appendix shall prevent local jurisdictions from modifying, changing, or adopting new specifications deemed necessary. The text and typical drawings in this Appendix are not a legal standard. Criteria for position, location, and use of traffic control devices is furnished solely for the purpose of guidance and information to assist in the preparation of traffic control plans.

Revision	By	Approved	Date
DRAWING	DWV		4-91
ORIG.			10-8-91
			10-4-94

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

TRAFFIC CONTROL PLANS

GENERAL INFORMATION

DRAWING NUMBER TC-1

TRAFFIC CONTROL PLANS

TABLE OF CONTENTS

TC-1 GENERAL INFORMATION
TC-2 TABLE OF CONTENTS
TC-3 TABLE OF CONTENTS
TC-4 DEVICE SPACING TABLES
TC-5 TRAFFIC CONTROL PLAN COVER SHEET
TC-6 SIDE OF ROAD - TWO LANE ROADWAY w/o CENTERLINE
TC-7 SIDE OF ROAD - TWO LANE ROADWAY w/CENTERLINE
TC-8 CENTER OF ROAD - TWO LANE ROADWAY
TC-9 SIDE OF ROAD - TWO LANE ROADWAY WITH FLAGGERS
TC-10 SIDE OF ROAD - MULTILANE w/CENTERLINE - ONE RIGHT LANE
TC-11 SIDE OF ROAD - MULTILANE w/CENTERLINE - TWO RIGHT LANES
TC-12 CENTER OF ROAD - MULTILANE W/CENTERLINE - ONE LEFT LANE
TC-13 CENTER OF ROAD - MULTILANE w/CENTERLINE - TWO LEFT LANES
TC-14 SIDE OF ROAD - MULTILANE w/TWO-WAY LEFT-TURN - ONE RIGHT LANE
TC-15 CENTER OF ROAD - MULTILANE w/TWO-WAY LEFT-TURN - ONE LEFT LANE
TC-16 SIDE OF ROAD - MULTILANE w/TWO-WAY LEFT-TURN - ONE RIGHT LANE
TC-17 SIDE OF ROAD - MULTILANE w/TWO-WAY LEFT-TURN - TWO RIGHT LANES
TC-18 SIDE OF ROAD - MULTILANE w/TWO-WAY LEFT-TURN - THREE RIGHT LANES
TC-19 CENTER OF ROAD - MULTILANE w/TWO-WAY LEFT-TURN - TWO LEFT LANES
TC-20 CENTER OF ROAD - MULTILANE w/TWO-WAY LEFT-TURN - THREE LEFT LANES
TC-21 SIDE OF ROAD - MULTILANE w/RAISED MEDIAN - ONE RIGHT LANE
TC-22 CENTER OF ROAD - MULTILANE w/RAISED MEDIAN - ONE LEFT LANE
TC-23 SIDE OF ROAD - INTERSECTION - WORK ON MAIN STREET - FAR SIDE
TC-24 SIDE OF ROAD - INTERSECTION - WORK ON MAIN STREET - NEAR SIDE
TC-25 CENTER OF ROAD - INTERSECTION - WORK ON MAIN STREET - FAR SIDE
TC-26 CENTER OF ROAD - INTERSECTION - WORK ON MAIN STREET - NEAR SIDE
TC-27 CENTER OF ROAD - INTERSECTION - WORK IN CENTER OF INTERSECTION
TC-28 SIDE OF ROAD - INTERSECTION - WORK ON MINOR STREET - FAR SIDE
TC-29 CENTER OF ROAD - INTERSECTION - WORK ON MINOR STREET - FAR SIDE
TC-30 SIDE/SIDE OF ROAD - INTERSECTION - WORK IN INTERSECTION
TC-31 SIDE/CENTER OF ROAD - INTERSECTION - WORK IN INTERSECTION
TC-32 LEFT TURN INTERSECTION - W/COMBINATION THRU/LEFT LANE.
TC-33 LEFT TURN INTERSECTION -
TC-34 LEFT TURN INTERSECTION -
TC-35 LEFT TURN INTERSECTION -
TC-36 RIGHT TURN INTERSECTION -
TC-37 RIGHT TURN INTERSECTION -

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

TRAFFIC CONTROL PLANS

TABLE OF CONTENTS

DRAWING NUMBER TC-2

Revision	By	Approved	Date
DRAWING	DWV		4-91
DRAWING	FHM		8-91
ORIG.			10-8-91
	WAJ		8-3-94

TRAFFIC CONTROL PLANS

TABLE OF CONTENTS

TC-38 RIGHT TURN INTERSECTION -
TC-39 RIGHT TURN INTERSECTION -
TC-40 BIKE LANE CLOSURE
TC-41 SIDE OF ROAD WORK AREA - TYPICAL PEDESTRIAN CONTROL SIGNS
TC-42 SIDE OF ROAD WORK AREA - MULTILANE ROADWAY W/ RAISED MEDIAN
TC-43 WORK WITHIN INTERSECTION - RIGHT LANE / LEFT LANE
TC-44 TYPICAL SHOULDER CLOSURE - MULTILANE ROADWAY WITH RAISED MEDIAN
TC-90 SPECIAL CONDITIONS - TWO LANE ROADWAY w/o CENTERLINE
TC-91 SPECIAL CONDITIONS - TWO LANE ROADWAY w/CENTERLINE
TC-92 SPECIAL CONDITIONS - MULTILANE ROADWAY w/CENTERLINE
TC-93 SPECIAL CONDITIONS - MULTILANE ROADWAY w/TWO-WAY LEFT-TURN
TC-94 SPECIAL CONDITIONS - MULTILANE ROADWAY w/TWO-WAY LEFT-TURN
TC-95 SPECIAL CONDITIONS - MULTILANE ROADWAY w/RAISED MEDIAN
TC-96 SPECIAL CONDITIONS - INTERSECTION
TC-97 TYPICAL CONSTRUCTION SIGNS
TC-98 TYPICAL CONSTRUCTION SIGNS

Revision	By	Approved	Date
DRAWING	DWV		4-91
ORIG.			10-8-91
			8-3-94

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

TRAFFIC CONTROL PLANS

TABLE OF CONTENTS

DRAWING NUMBER TC-3

TABLE 1

RECOMMENDED SIGN SPACING FOR ADVANCE WARNING SIGN SERIES

APPROACH SPEED (MPH)	MINIMUM DISTANCE IN FEET BETWEEN SIGNS AND FROM LAST SIGN TO TAPER	MAXIMUM DEVICE SPACING IN FEET	MINIMUM TAPER LENGTHS FOR LANE WIDTHS *		
			10 FT	11 FT	12 FT
25	150-200	25	105	115	125
30	200-300	30	150	165	180
35	250-400	35	205	225	245
40	350-500	40	265	295	320
45	500-750	45	450	495	540
50	500-1000	50	500	550	600
55+	500-1500	50	550	605	660

* $L=WS^2/60$ FOR S OF 40 MPH OR LESS; $L=WS$ FOR S OF 45MPH OR MORE. TAPER LENGTHS SHOWN ARE ROUNDED TO NEAREST 5 FEET.

TABLE 2

RECOMMENDED TAPER LENGTH AND DEVICE SPACING FOR CHANNELIZING TAPERS

APPROACH SPEED (MPH)	TAPER LENGTH (L) *	SPACING OF CONES ALONG TAPER (FEET) +_
25	125	25
30	180	30
35	245	35
40	320	40
45	540	45
50	600	50
50+	1000	50

(*) Based on 12-foot wide lane. This column is also appropriate for lane widths less than 12 feet

NOTES:

Taper Formula

$L = S \times W$ for speeds > 40 mph.

$L = \frac{W \times S^2}{60}$ for speeds < 40 mph.

Where:

L = Minimum length of taper

S = Numerical value of APPROACH speed prior to work (mph)

W = Width of offset. (feet)

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

DEVICE SPACING TABLES

SIGN SPACING TABLE
TAPER LENGTH AND CONE SPACING TABLE

DRAWING NUMBER TC-4

Revision	By	Approved	Date
DRAWING	DWV		4-91
DRAWING	FMM		8-91
ORIG.			10-8-91
	WAJ		8-28-94

Revision	By	Approved	Date
ORIG.	VAJ		8-28-94
DRAWING	PMH		10-8-91
DRAWING	F.T.		8-91
			4-91

Agency: _____

Address: _____ Phone: _____ Fax: _____

TRAFFIC CONTROL PLAN / PERMIT EXTENSION

JOB LOCATION	BEGIN CROSS STREET	END CROSS STREET	PERMIT NO.

WORK HOURS continuous FROM A.M. P.M. TO A.M. P.M.	SPEED LIMIT	WORK TO BE DONE

START DATE	END DATE	WORK DATE EXTENSION FROM	TO NEW END DATE	WORK DATE EXTENSION FROM	TO NEW END DATE

WORK DATE EXTENSIONS MUST BE OBTAINED PRIOR TO END DATE

CONTRACTOR	ADDRESS	CITY, STATE, ZIP TELEPHONE

PROJECT CONTACT	24 HOUR TELEPHONE	FAX NUMBER

REQUIREMENTS:*

1. The contractor is responsible for restoring the road back to satisfactory condition which will include, but is not limited to, paving, striping, markings, signing, and loop detection.

2. The Agency reserves the right to observe these traffic control plans in operation and to make changes as field conditions warrant.

3. Trench will be backfilled or steel-plated during non-working hours.
Steel plates shall have asphaltic ramp on all edges.
All dirt, dust, and debris shall be removed from street at end of each day and at the end of the job.
The street shall be in driveable condition at all times.

4. Any work that creates an undue safety risk or creates severe congestion will be shut down by the Agency.

5. A copy of all traffic requirements and traffic control plans issued by the Agency must be kept on the job site.

6. Approval of this plan does not constitute an official Permit. Contact the Agency for information on obtaining a permit.

7. All travel lanes will typically be a minimum of 12 feet wide unless otherwise approved specifically by the local jurisdiction.

8. Flashing arrow boards as required by the local jurisdiction.

9. Warning (W) series signs used in work zones shall be Black on Orange.

10. Cones and pylons shall have yellow reflectorized sleeves along centerline, white reflectorized sleeves along outside shoulder.

11. If parking is allowed in advance warning area, advance warning signs should be mounted on high level devices.

THIS TRAFFIC CONTROL PLAN IS NOT VALID UNLESS AN APPLICABLE PERMIT IS ATTACHED

*SUBJECT TO LOCAL AGENCY REQUIREMENTS.

SEE ATTACHED SHEET(S) FOR TRAFFIC CONTROL PLAN LAYOUT
STANDARD DRAWINGS MAY BE APPLICABLE

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

TRAFFIC CONTROL PLAN
COVER SHEET


DRAWING NUMBER TC-5

DRAWING NUMBER TC-6

SIDE OF ROAD WORK AREA

TWO LANE TRAFFIC CONTROL
WITHOUT CENTERLINE

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD



LEGEND

CONE | BARRICADE | FLAGGER | SIGN | FLASHING ARROW SIGN | WORK AREA | TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

Revision	By	Approved	Date
DRAWING	DWV		4-91
DRAWING	FHW		8-91
ORIG.	WAJ	8-23-94	10-8-9


Revision	By	Approved	Date
DRAWING	DWV		4-91
DRAWING	FHM		8-91
ORIG.			10-8-91
	WAJ		8-3-94

SIDE OF ROAD WORK AREA

TWO LANE TRAFFIC CONTROL WITH CENTERLINE

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

DRAWING NUMBER TC-7



LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.


DRAWING NUMBER TC-8

CENTER OF ROAD WORK AREA

TWO LANE TRAFFIC CONTROL

APPENDIX "A"

SAN DIEGO REGIONAL STANDARD



LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

Revision	By	Approved	Date
DRAWING	DWV	4-91	
DRAWING	FHH	8-91	
ORIG.		10-8-91	
	WAJ	8-3-94	


Revision	By	Approved	Date
DRAWING	DWV		4-91
DRAWING	FHH		8-91
ORIG.			10-8-91
	VAJ		8-30-94

SIDE OF ROAD WORK AREA

TWO LANE TRAFFIC CONTROL WITH FLAGGERS

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

DRAWING NUMBER TC-9



EYE CONTACT MUST BE MAINTAINED BETWEEN FLAGGERS OR USE 2-WAY RADIO COMMUNICATION.

FLAGGER - REFER TO CALTRANS MANUAL 5-07.3

LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.


TC-5 is required for all Traffic Control Plans.
FLAGGER - REFER TO CALTRANS MANUAL 5-07.3

DRAWING NUMBER TC-10

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

SIDE OF ROAD WORK AREA

MULTILANE TRAFFIC CONTROL WITH CENTERLINE
RIGHT TRAFFIC LANE CLOSURE - ONE LANE



LEGEND

CONE | BARRICADE | FLAGGER | SIGN | FLASHING ARROW SIGN | WORK AREA | TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

Revision	By	Approved	Date
DRAWING	DWV		4-91
DRAWING	FMM		8-91
ORIG.	WAJ		10-8-91
			8-30-94


Revision	By	Approved	Date
DRAWING	DWV		4-91
DRAWING	FHH		8-91
ORIG.			10-9-91
			11-18-91
	WAJ		10-4-94

SIDE OF ROAD WORK AREA

MULTILANE TRAFFIC CONTROL WITH CENTERLINE
RIGHT TRAFFIC LANE CLOSURE - TWO LANES

APPENDIX 'A'
SAN DIEGO REGIONAL STANDARD

DRAWING NUMBER TC-11



LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.


TC-5 is required for all Traffic Control Plans.

DRAWING NUMBER TC-12

CENTER OF ROAD WORK AREA

MULTILANE TRAFFIC CONTROL WITH CENTERLINE
LEFT TRAFFIC LANE CLOSURE - ONE LANE

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD



LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

Revision	By	Approved	Date
DRAWING	DWV		4-91
DRAWING	FHM		8-91
ORIG.			10-8-91
	WAJ		8-30-94


Revision	By	Approved	Date
DRAWING	DAV	4-91	
DRAWING	FMM	8-91	
ORIG.			10-8-91
	WAJ		8-3-94

CENTER OF ROAD WORK AREA

MULTILANE TRAFFIC CONTROL WITH CENTERLINE
LEFT TRAFFIC LANE CLOSURE - TWO LANES

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

DRAWING NUMBER TC-13



LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.


TC-5 is required for all Traffic Control Plans.

DRAWING NUMBER TC-14

SIDE OF ROAD WORK AREA

MULTILANE TRAFFIC CONTROL WITH TWO WAY LEFT TURN
RIGHT LANE TRAFFIC CLOSURE - ONE LANE

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD



LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

Revision	By	Approved	Date
ORIG.			
DRAWING	FHM		10-9-91
DRAWING	DWV		8-91
			4-91
			11-18-91
			4-2-92
	WAJ		8-3-94


Revision	By	Approved	Date
DRAWING	DWV		4-91
DRAWING	FHM		8-91
ORIG.			10-8-91
	WAJ		8-30-94

CENTER OF ROAD WORK AREA

MULTILANE TRAFFIC CONTROL WITH CENTERLINE
LEFT LANE CLOSURE - ONE LANE

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

DRAWING NUMBER TC-15



LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.


TC-5 is required for all Traffic Control Plans.

DRAWING NUMBER TC-16

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

SIDE OF ROAD WORK AREA

MULTILANE TRAFFIC CONTROL WITH TWO WAY LEFT TURN
RIGHT TRAFFIC LANE CLOSURE - ONE LANE



LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

Revision	By	Approved	Date
ORIG.			10-8-91
DRAWING	FHN		8-91
DRAWING	DWV		4-91
	WAJ		4-2-92
			9-23-94


Revision	By	Approved	Date
DRAWING	DMV		4-91
DRAWING	FMH		8-91
ORIG.			10-9-91
			11-18-91
	WAJ		9-23-94

SIDE OF ROAD WORK AREA

MULTILANE TRAFFIC CONTROL WITH TWO WAY LEFT TURN
RIGHT TRAFFIC LANE CLOSURE - TWO LANES

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

DRAWING NUMBER TC-17



LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.


TC-5 is required for all Traffic Control Plans.

DRAWING NUMBER TC-18

SIDE OF ROAD WORK AREA

MULTILANE TRAFFIC CONTROL WITH TWO WAY LEFT TURN
RIGHT TRAFFIC LANE CLOSURE - THREE LANES

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD



LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

Revision	By	Approved	Date
DRAWING ORIG.	FHH		8-91
DRAWING	DWV		4-91
	WAJ		11-18-91
			10-9-91


Revision	By	Approved	Date
ORIG.	DRAWING FHH	DRAWING DWV	4-91
			8-91
			10-8-91

CENTER OF ROAD WORK AREA

MULTILANE TRAFFIC CONTROL WITH TWO WAY LEFT TURN LEFT TRAFFIC LANE CLOSURE - TWO LANES

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

DRAWING NUMBER TC-19



LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME _____
AGENCY _____
ADDRESS _____
PHONE _____

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.


TC-5 is required for all Traffic Control Plans.

DRAWING NUMBER TC-20

CENTER OF ROAD WORK AREA

MULTILANE TRAFFIC CONTROL WITH CENTERLINE
LEFT LANE TRAFFIC LANE CLOSURE - THREE LANES

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD



LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME _____
AGENCY _____
ADDRESS _____
PHONE _____

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

Revision	By	Approved	Date
DRAWING	DWV		4-91
DRAWING	FHM		8-91
ORIG.	WAJ		10-8-91
			8-30-94


Revision	By	Approved	Date
ORIG.	WAJ		8-23-94
DRAWING	FHM		10-8-91
DRAWING	DMY		8-91
			4-91

SIDE OF ROAD WORK AREA

MULTILANE TRAFFIC CONTROL WITH RAISED MEDIAN
RIGHT TRAFFIC LANE CLOSURE - ONE LANE

APPENDIX 'A'
SAN DIEGO REGIONAL STANDARD

DRAWING NUMBER TC-21



LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.


TC-5 is required for all Traffic Control Plans.

DRAWING NUMBER TC-22

CENTER OF ROAD WORK AREA

MULTILANE TRAFFIC CONTROL WITH RAISED MEDIAN
LEFT TRAFFIC LANE CLOSURE - ONE LANE

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD



SEE GENERAL NOTES

LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

Revision	By	Approved	Date
DRAWING ORIG.	FHH		10-8-91
DRAWING	DWV		8-91
	WAJ		4-91
			8-23-94


Revision	By	Approved	Date
DRAWING	DWV		4-91
DRAWING	FMM		8-91
ORIG.			10-8-91
			4-2-92
	WAJ		8-30-94

SIDE OF ROAD WORK AREA

INTERSECTION TRAFFIC CONTROL

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

DRAWING NUMBER TC-23



* LEFT OR RIGHT TURN MOVES MAY BE RESTRICTED.

LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.


DRAWING NUMBER TC-24

SIDE OF ROAD WORK AREA

INTERSECTION TRAFFIC CONTROL

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

Revision	By	Approved	Date
ORIG.	VAJ		8-38-94
DRAWING	FHH		10-8-91
DRAWING	DW		8-91
			4-91



* RIGHT TURN MOVES MAY BE RESTRICTED.

LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.


Revision	By	Approved	Date
ORIG.			
DRAWING	DWV		4-91
DRAWING	FHH		8-91
			10-8-91
			4-2-92
	WAJ		8-30-94

CENTER OF ROAD WORK AREA

INTERSECTION TRAFFIC CONTROL

APPENDIX 'A'
SAN DIEGO REGIONAL STANDARD

DRAWING NUMBER TC-25



* LEFT OR RIGHT TURN MOVES MAY BE RESTRICTED.

LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME _____
AGENCY _____
ADDRESS _____
PHONE _____

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.


DRAWING NUMBER TC-26

CENTER OF ROAD WORK AREA

INTERSECTION TRAFFIC CONTROL

APPENDIX "A"

SAN DIEGO REGIONAL STANDARD



• LEFT TURN MOVES MAY BE RESTRICTED.

LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

Revision	By	Approved	Date
ORIG.	DRAWING	FHW	8-91
	DRAWING	DWV	4-91
			10-8-91
			11-18-91
	VAJ		9-30-94


Revision	By	Approved	Date
DRAWING	DWV	4-91	8-91
ORIG.	WAJ	10-8-91	9-23-94

CENTER OF ROAD WORK AREA

INTERSECTION TRAFFIC CONTROL

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

DRAWING NUMBER TC-27



* LEFT OR RIGHT TURN MOVES MAY BE RESTRICTED.

** PARKING PROHIBITED APPROACHING INTERSECTION ON ALL 4 LEGS.

LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.


TC-5 is required for all Traffic Control Plans.

DRAWING NUMBER TC-28

SIDE OF ROAD WORK AREA

INTERSECTION TRAFFIC CONTROL

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD



* RIGHT TURN MOVES MAY BE RESTRICTED.

LEGEND

CONE | BARRICADE | FLAGGER | SIGN | FLASHING ARROW SIGN | WORK AREA | TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

Revision	By	Approved	Date
DRAWING	DWV		4-91
DRAWING	FHH		8-91
ORIG.			10-8-91
	WAJ		8-30-94


Revision	By	Approved	Date
DRAWING	DAV		4-91
DRAWING	FHM		8-91
ORIG.			10-8-91
	VAJ		9-23-94

CENTER OF ROAD WORK AREA

INTERSECTION TRAFFIC CONTROL

APPENDIX 'A'
SAN DIEGO REGIONAL STANDARD

DRAWING NUMBER TC-29



• LEFT OR RIGHT TURN MOVES MAY BE RESTRICTED.

LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.


TC-5 is required for all Traffic Control Plans.

DRAWING NUMBER TC-30

SIDE OF ROAD WORK AREA

INTERSECTION TRAFFIC CONTROL

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD



* LEFT OR RIGHT TURN MOVES MAY BE RESTRICTED.

LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

Revision	By	Approved	Date
ORIG.			4-91
DRAWING	DWV		10-8-91
	WAJ		9-23-94


Revision	By	Approved	Date
DRAWING	DWV		4-91
DRAWING	FHH		8-91
ORIG.	WAJ		10-8-91
	WAJ		9-23-94

CENTER OF ROAD WORK AREA

INTERSECTION TRAFFIC CONTROL

APPENDIX 'A'
SAN DIEGO REGIONAL STANDARD

DRAWING NUMBER TC-31



LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.


TC-5 is required for all Traffic Control Plans.

DRAWING NUMBER TC-32

SIDE OF ROAD WORK AREA

LEFT TURN INTERSECTION TRAFFIC CONTROL

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD



LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

Revision	By	Approved	Date
DRAWING	TRD		5-31-94
	WAJ		8-30-94


Revision	By	Approved	Date
DRAWING	TRD		5-31-94
	MAJ		8-30-94

SIDE OF ROAD WORK AREA

LEFT TURN INTERSECTION TRAFFIC CONTROL

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

DRAWING NUMBER TC-33



LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME _____
AGENCY _____
ADDRESS _____
PHONE _____

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.


TC-5 is required for all Traffic Control Plans.

DRAWING NUMBER TC-34

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

SIDE OF ROAD WORK AREA

LEFT TURN INTERSECTION TRAFFIC CONTROL



* RIGHT TURNS MAY BE RESTRICTED. SEE TC-12

LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

Revision	By	Approved	Date
DRAWING	TRD		5-31-94
	WAJ		9-26-94


Revision	By	Approved	Date
DRAWING	TRD		5-31-94
	WAJ		9-26-94

SIDE OF ROAD WORK AREA

LEFT TURN INTERSECTION TRAFFIC CONTROL

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

DRAWING NUMBER TC-35



• RIGHT TURNS MAY BE RESTRICTED.

LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME _____
AGENCY _____
ADDRESS _____
PHONE _____

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.


DRAWING NUMBER TC-36

SIDE OF ROAD WORK AREA

RIGHT TURN INTERSECTION TRAFFIC CONTROL

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

Revision	By	Approved	Date
DRAWING	TRD		5-31-94
	WAJ		9-26-94



LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.


Revision	By	Approved	Date
DRAWING	TRD		5-31-94
	WAJ		9-26-94

SIDE OF ROAD WORK AREA

RIGHT TURN INTERSECTION TRAFFIC CONTROL

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

DRAWING NUMBER TC-37



LEGEND

CONE | BARRICADE | FLAGGER | SIGN | FLASHING ARROW SIGN | WORK AREA | TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.


DRAWING NUMBER TC-38

SIDE OF ROAD WORK AREA

RIGHT TURN INTERSECTION TRAFFIC CONTROL

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

Revision	By	Approved	Date
DRAWING	TRD		5-31-94
	WAJ		9-26-94



LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.


TC-5 is required for all Traffic Control Plans.

Revision	By	Approved	Date
DRAWING	TRD	WAJ	5-31-94
			9-26-94

SIDE OF ROAD WORK AREA

RIGHT TURN INTERSECTION TRAFFIC CONTROL

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD



LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.


TC-5 is required for all Traffic Control Plans.

DRAWING NUMBER TC-39

DRAWING NUMBER TC-40

BIKE LANE CLOSURE

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD



LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN AND CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

Revision	By	Approved	Date
DRAWING	TRD		5-31-94
	MAJ		9-26-94


Revision	By	Approved	Date
DRAWING	TRD		
	WAJ		5-31-94
			9-26-94

SIDE OF ROAD WORK AREA

TYPICAL PEDESTRIAN CONTROL SIGNS

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

DRAWING NUMBER TC-41



LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

DRAWING NUMBER TC-42

SIDE OF ROAD WORK AREA


MULTILANE ROADWAY W/ RAISED MEDIAN

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

Revision	By	Approved	Date
DRAWING	TRD		
	MAJ		6-94
			9-25

C18 C20 (RT) W11 (RT)

RAISED MEDIAN OR DIVIDING STRIP



C18 C20 (RT) W11 (RT)

HIGH LEVEL WARNING DEVICE WITH C30 SIGN

WORK AREA

C13

SIGN SPACING SEE TC-4 TABLE 1

TAPER SEE TC-4 TABLE 2

• MEDIAN MAY REQUIRE TEMPORARY PAVEMENT TO CONVEY TRAFFIC VOLUME.

LEGEND

CONE BARRICADE FLAGGER SIGN FLASHING ARROW SIGN WORK AREA TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.


Revision	By	Approved	Date
DRAWING	TRD		6-10-94
	WAJ		9-26-94

WORK WITHIN INTERSECTION

RIGHT LANE / LEFT LANE

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

DRAWING NUMBER TC-43



LEGEND

CONE | BARRICADE | FLAGGER | SIGN | FLASHING ARROW SIGN | WORK AREA | TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN, CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

DRAWING NUMBER TC-90

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

SPECIAL CONDITIONS WORK AREA

TWO LANE ROADWAY
WITHOUT CENTERLINE

Revision	By	Approved	Date
DRAWING ORIG.	DMV		4-91
	MAJ		10-8-91
			10-4-94

LEGEND

● CONE ⊢⊣ BARRICADE ⚑ FLAGGER ⚑ SIGN ▯ FLASHING ARROW SIGN ▨ WORK AREA ⇄ TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

← SEE TC-4 FOR SIGN AND CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

Revision	By	Approved	Date
DRAWING ORIG.	DWV		4-91
	WAJ		10-8-91
			10-4-94

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

SPECIAL CONDITIONS WORK AREA
TWO LANE ROADWAY
WITH CENTERLINE

DRAWING NUMBER TC-91

LEGEND

CONE | BARRICADE | FLAGGER | SIGN | FLASHING ARROW SIGN | WORK AREA | TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN AND CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

LEGEND

CONE · BARRICADE · FLAGGER · SIGN · FLASHING ARROW SIGN · WORK AREA · TRAFFIC DIRECTION

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN AND CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying, changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

TRAFFIC ENGINEERS COMMENTS


SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

SPECIAL CONDITIONS WORK AREA
MULTILANE ROADWAY
WITH CENTERLINE

DRAWING NUMBER TC-92

Revision	By	Approved	Date
DRAWING	DWV		4-91
ORIG.			10-8-91
	WAJ		10-4-94



LEGEND

● CONE ⟷ BARRICADE ⚑ FLAGGER ⚑ SIGN ▯ FLASHING ARROW SIGN ▨ WORK AREA ← → TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME _____
AGENCY _____
ADDRESS _____
PHONE _____

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

← SEE TC-4 FOR SIGN AND CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

Revision	By	Approved	Date
DRAWING	DMV		4-91
ORIG.			10-8-91
	WAJ		10-4-94

SPECIAL CONDITIONS WORK AREA

TWO LANE ROADWAY
WITH TWO WAY LEFT TURN LANE

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

DRAWING NUMBER TC-93

LEGEND

● CONE ⊣⊢ BARRICADE ▮ FLAGGER ▬ SIGN ☐ FLASHING ARROW SIGN ▨ WORK AREA ↓↑ TRAFFIC DIRECTION

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

SEE TC-4 FOR SIGN AND CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME
AGENCY
ADDRESS
PHONE

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

SPECIAL CONDITIONS WORK AREA
MULTILANE ROADWAY
WITH TWO WAY LEFT TURN LANE

DRAWING NUMBER TC-94

Revision	By	Approved	Date
DRAWING	DWV		4-91
ORIG.			10-8-91
	WAJ		10-4-94

Revision	By	Approved	Date
DRAWING	DMV		4-91
ORIG.			10-8-91
	WAJ		10-4-94

SPECIAL CONDITIONS WORK AREA

MULTILANE ROADWAY
WITH RAISED MEDIAN

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

DRAWING NUMBER TC-95

RAISED MEDIAN

LEGEND

● CONE ⟷ BARRICADE ⚑ FLAGGER ⚑ SIGN ▯ FLASHING ARROW SIGN ▨ WORK AREA ⟵⟶ TRAFFIC DIRECTION

TRAFFIC ENGINEERS COMMENTS

SUBMITTED BY:
NAME _____
AGENCY _____
ADDRESS _____
PHONE _____

POSTED SPEED LIMIT	APPROACH SPEED	TAPER LENGTH	SPACING OF CONES	SIGN SPACING

← SEE TC-4 FOR SIGN AND CONE SPACING AND TAPER LENGTH

GENERAL NOTES

For hours of darkness, change cones to vertical barricades with steady burn lights.

This plan DOES NOT apply at signalized or multi-way stop intersections. Consult the local jurisdiction when preparing Traffic Control Plans near these intersections.

This plan MAY NOT apply when the work areas affect bike lanes, sidewalks, pedestrian access, and curved or narrow roadways. Consult the approving agency when preparing the Traffic Control Plan for these areas.

Nothing contained on this drawing shall prevent local jurisdictions from modifying changing, or adopting new specifications deemed necessary. Criteria for position, location, and use of Traffic Control Devices is solely for the purpose of guidance to assist in the set up of the Traffic Control Plans.

TC-5 is required for all Traffic Control Plans.

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

SPECIAL CONDITIONS WORK AREA

INTERSECTION

DRAWING NUMBER TC-96


Revision	By	Approved	Date
DRAWING	DWV		4-91
ORIG.			10-8-91
	WAJ		10-4-94




C1



C2



C3



C3A



C5 (RT)



C5 (LT)



C7



C9A



C12



C13



C14



C18



C19



C20 (RT)



C20 (LT)

Revision	By	Approved	Date
DRAWING	TRO		6-94

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

TYPICAL CONSTRUCTION SIGNS

DRAWING NUMBER TC-97



C21



C23



C24



C27



C28A
FLAGGER
PADDLE



C28B
FLAGGER
PADDLE



C30



C30A



C36



R1



R7



R16



R17



R18(RT)



R18 (LT)




R26



R34



R34-2



R41



R42

Revision	By	Approved	Date
DRAWING	TRD		9-94

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

TYPICAL CONSTRUCTION SIGNS

DRAWING NUMBER TC-98



R49M



R96



SR45



W1 (RT)



W1 (LT)



W2 (RT)



W2 (LT)



W11 (LT)



W11 (RT)

Revision	By	Approved	Date
DRAWING	TRD		9-94

APPENDIX "A"
SAN DIEGO REGIONAL STANDARD

TYPICAL CONSTRUCTION SIGNS

DRAWING NUMBER TC-99

INDEX

-A-

AIR AND VACUUM VALVE
- 1" and 2" W-4
- 4" and 6" W-5
- Enclosure W-14

AIR RELEASE VALVE
- Manual. W-3

ALLEY
- Apron, Concrete G-17
- Concrete, Pavement. G-21

ANCHOR, PIPE
- Concrete. S-9
- Thrust. W-22
- Valve W-19
- Vertical Bend W-20

-B-

BACKFILL, PIPE TRENCH
- Irrigation. I-25, I-26
- Sewer S-4
- Storm Drain D-60
- Water Main. W-21

BACKFLOW PREVENTER
- Continuous Pressure I-8, I-9
- Guard Fence I-32
- Reduced Pressure. I-31
- Reduced Pressure. W-26
- Vacuum Breaker. I-7

BARRICADE, STREET. M-9

BARRIER. M-42, M-43, M-39

BENCH MARK, BRASS PLUS M-11

BERM, ASPHALT CONCRETE G-5

BLOCK, CONCRETE
- Anchor. W-20, W-22
- Thrust. W-17, W-22
- Valve W-19

BLOW-OFF WATER
- 2". W-6, W-7
- 4" and 6" W-8, W-9

BROW DITCH D-75

BUTT STRAP, SPLIT. W-24

-C-

CATCH BASIN
- Corrugated Steel Pipe Types A and B D-16
- Grate Top, Type G, I. . . . D-8, D-29
- Side Opening, Type F. . . . D-7

CHANNEL, DRAINAGE
- Cutoff Wall D-72
- Debris Fence. D-82
- Earthen D-74
- Concrete Lined. D-70, D-71
- Pipe Connection D-73

CLEANOUT
- Sewer, Force Main S-16
- Sewer, Gravity. S-3
- Storm Drain, Type A, B. . . D-9, D-10
- Storm Drain, Notes and Details D-11

CONCRETE
- Backfill, Sewer S-8
- Collar, Pipe. D-62
- Cradle, Sewer S-6
- Encasement, Sewer S-7, S-12
- Protection, Sewer S-11
- Lug, Pipe D-63
- Mowing Strip. L-3
- Removal and Replacement . . G-11
- Steps M-26

CORRUGATED STEEL PIPE
- Inlets, Type A, B D-16, D-17
- Slotted Drain D-18, D-19

CULVERT, BOX
- Double. D-77A, D-76B
- Miscellaneous Details . . . D-81A, D-81B

Single. D-76A, D-76B
Triple. D-78A, D-78B
Wingwalls, Type A, B, C . . D-79A, D-79B
Wingwalls, Warped D-80A, D-80B

CURB AND GUTTER
Combined. G-2
Median. G-6
Monolithic With Sidewalk. . G-3
Removal and Replacement . . G-11
Rolled. G-4
Separate. G-1

CURB INLET
Apron, Concrete D-20
Grate D-15
Median, Type J. D-45
Notes and Details D-11
Opening D-12
Side Opening Only D-1, D-2, D-4
Side Opening w/Gate D-3

CURB OUTLET
Concrete, Type A. D-25
Pipe. D-27

CURTAIN WALL D-38

CUTOFF WALL
Alley Pavement. G-23
Channel D-72
Street Pavement G-22
Trench. S-10

-D-

DATUMS M-12

DEBRIS FENCE D-82

DIKE, A.C. G-5

DISSIPATOR, ENERGY
Concrete. D-41, D-42, D-43
Rip Rap D-40

DITCH, BROW, TERRACE D-75

DOWNDRAIN
Asphalt Concrete. D-22
Flume D-23
Pipe. D-24

DRINKING FOUNTAIN. M-18

DRIVEWAY
Concrete. G-14A, G-14B
Location. G-15, G-16
Width G-16

-E-

ELECTRICAL PEDESTAL. E-33

ENCASEMENT
Sewer Pipe S-7
Sewer Pipe, Undercut. . . . S-12

-F-

FENCE
Chain Link. M-6
Debris Fence. D-82
Details M-20
Tennis Court. M-17

FIRE HYDRANT
6" Hydrant. W-10
Locations W-11
Markers M-19

FLUME DOWN DRAIN D-23

FRAME
Grate D-13
Manhole M-1, M-2, M-3

INDEX

-G-

GRATE
- Drainage D-15
- Frame D-13
- Tree Well L-4

GUARD RAIL, METAL BEAM
- Connections M-40, M-41
- Details M-36
- End Anchors M-37, M-38, M-39
- Flares M-34, M-35
- Hardware M-32
- Posts and Blocks M-33
- Railing M-31
- Standard M-30

GUTTER
- Cross G-12
- Cross, Mid-Block G-13
- Separate from Curb G-1

-H-

HANDICAPPED PARKING
- Sign M-28
- Spaces M-27
- Legend M-29

HEADWALL
- Gravity Type D-32, D-33
- L Type D-36, D-37
- Straight, Type A, B D-30, D-31
- Warped D-44
- Wing and U Type D-334, D-35

HYDRANT MARKERS, FIRE M-19

-I-

INLET APRON D-39

INLET, DRAIN
- Corrugated Steel Pipe, Type A & B D-16, D-17
- Slotted, Corrugated Steel Pipe D-18, D-19

INLET, PROTECTION BAR D-12

-J-

JOINT TRENCH M-15

-L-

LATERAL
- Sewer S-13
- Sewer, Deep Cut S-14
- Sewer, Repair S-15

LIGHTING
- Grounding E-2
- Light Pole Pad L-5
- Standard E-1

LUG, COMPLETE D-62

-M-

MANHOLE, FRAME AND COVER
- 24" Heavy Duty M-1
- 24" Light Duty M-2
- 36" Concentric Covers . . . M-3
- Locking Device M-4

MANHOLE, SEWER
- 4' x 3' Diameter S-17
- 5' x 3' Diameter S-2

MEDIAN
- Curb Inlet D-45
- Curbs and Gutter G-6

METER BOX LOCATION W-15

METRIC EQUIVALENTS M-14

MONUMENT
- Bench Mark M-11
- Street Survey M-10
- Survey M-13

MOWING STRIP, CONCRETE L-3

INDEX

-P-

PARKING
Disabled Parking. M-27A, M-27B, M-28A, M-28B, M-29

PAVEMENT, CONCRETE
Alley Section G-21
Joints. G-10
Width 40' or Less G-18
Width 40' to 62'. G-19
Width 53' to 69'. G-20

PEDESTAL, ELECTRICAL E-33

PEDESTRIAN
Protective Railings M-24, M-25,
Ramp. G-27, G-28, G-29, G-30 G-31
Ramp General Notes. G-32

PIPE
Collar. D-62
Lug D-63
Rounded Ends. D-61
Slotted D-18, D-19

PLANTING, TREE AND SHRUB . . . L-1, L-2

POST
Demountable M-16
Guard M-9
Protection. W-16

-R-

RAILING
Pedestrian. M-24, M-25
Temporary M-44

RAMP, PEDESTRIAN G-27, G-28, G-29, G-30 G-31

General Notes G-32

RETAINING WALL
Concrete. C-11, C-12
Details, Concrete C-13, C-14
Details, Gravity. C-10
Details, Masonry. C-7, C-8
Gravity C-9
Masonry C-1, C-2, C-3, C-4 C-5, C-6

-S-

SERVICE, WATER W-1, W-2, W-21
SEWER LATERAL. S-13, S-14

SIDEWALK
Drain Outlet. D-25
Joint Details G-10
Joint Locations G-9
Monolithic Curb G-3
Pipe Underdrain D-27
Removal and Replacement . . G-11
Typical Section G-3, G-7

SPRINKLER
Above Ground Installation . I-21, I-22, I-23
Controller Mounting I-17, I-18
Connection, Main. I-28, I-29
Head, Fixed Spray I-1
Head, Pop Up Rotary I-3
Head, Pop Up Spray. I-2
Head, Impact. I-19, I-30
Head, Shrub Rotor I-34
Pull Box, Electrical. . . . I-15
Trench Detail I-25, I-30

STAKING, TREE. L-2

STEPS CONCRETE M-26

STREET LIGHT
Foundation. E-2
Grounding E-2
Standard. E-1

INDEX

-T-

TAPE LOCATOR, METALLIC
- Sewer Pipe. S-19
- Water Pipe. W-25

TENNIS COURT FENCE M-17

TERRACE DITCH. D-75

THRUST ANCHORS
- Bearing Area. W-18
- Concrete. W-17, W-19, W-20, W-22

TRAFFIC
- Control Plans . . . . . APPENDIX A

TRENCH DETAILS
- Irrigation. I-25, I-26
- Joint Utilities M-15
- Narrow. G-33, G-34, G-35
- Resurfacing G-24, G-25
- Sewer S-4
- Slurry Backfill G-36
- Storm Drain D-60
- Water Main. W-21

-U-

UNDERDRAIN, SIDEWALK
- Pipe. D-27
- Concrete, Reinforced. . . . D-25

UNDERGROUND TYPICAL LOCATION
- Conversion. M-21
- Replacement M-21
- Upgrade M-21

UTILITY LOCATIONS
- Collector Streets M-22
- Expressways M-23
- Joint Trench. M-15
- Local Streets M-22
- Major Streets M-23
- Prime Arterials M-23

-V-

VALVE, SPRINKLER
- Gate. I-12
- Hose Bibb I-6
- Manifold Assembly I-33
- Manual. I-13, I-21
- Remote Control. I-14
- Quick Coupling. I-5, I-22
- Well. I-27

VALVE, WATER
- Air and Vacuum. W-4, W-5
- Blocking, Concrete. W-19
- Enclosure, Air and Vacuum . W-14
- Stem Extension. W-13
- Well Installation W-12

-W-

WATER SERVICE
- 1". W-1
- 1 1/2" and 2" W-2
- Multiple. W-23


COUNTY OF SAN DIEGO
DEPARTMENT OF PUBLIC WORKS

INDEX OF DESIGN STANDARDS

NUMBER	TITLE
DS-1	TYPICAL ROADWAY SECTIONS
DS-2	HILLSIDE RESIDENTIAL STREET, ALTERNATE NO. 1
DS-3	HILLSIDE RESIDENTIAL STREET, ALTERNATE NO. 2
DS-4	HILLSIDE RESIDENTIAL STREET, ALTERNATE NO. 3
DS-5	TEMPORARY TURN-AROUND AT DEAD-END STREET
DS-6	TURNAROUND AND CALCULATIONS
DS-7	ASPHALT CONCRETE DRIVEWAY
DS-8	LOT GRADING
DS-9	FENCING CUT BANKS
DS-10	GRADING OF SLOPES
DS-11	REQUIRED SETBACKS
DS-12	CONSTRUCTION PLAN SYMBOLS
DS-13	STANDARD STREET SIGN
DS-14	DIP SECTION (FOR PRIVATE STREETS)
DS-15	STREET KNUCKLE
DS-16	CLEAR SPACE MARKERS
DS-17	GATED DRIVEWAY ENTRANCE - TYPE I
DS-18	GATED DRIVEWAY ENTRANCE - TYPE II
DS-19	GATED DRIVEWAY ENTRANCE - TYPE III

ROADWAY SECTION

SYMMETRICAL ABOUT CENTERLINE




ROAD CLASSIFICATION	TRAVELED WAY NUMBER OF LANES/WIDTH	R.O.W. WIDTH	ROAD SURFACING WIDTH	PAVED SHOULDERS NO./WIDTH	PARKWAY WIDTH
CIRCULATION ELEMENT					
Expressway	6+34' Median	146'	126'	2–10'	10'
Prime Arterial	6+14' Median	122'	102'	2–8'	10'
Major Road	6+14' Median	98'	78'	2–8'	10'
Collector	4/12'	84'	64'	2–8'	10'
Light Collector	2/12'	60'	40'	2–8'	10'
Rural Collector	2/12'	84'	40'	2–8'	22'
Rural Light Collector	2/12'	60'	40'	2–8'	10'
Recreational Parkway	2/12'	100'	40'	2–8'	30'
Rural Mountain	2/12'	100'	40'	2–8'	30'
NON–CIRCULATION ELEMENT					
Residential Collector	2/12'	60'	40'	2–8'	10'
Residential	2/12'	56'	36'	2–6'	10'
Residential Cul–de–sac	2/12'	52'	32'	2–4'	10'
Residential Loop	2/12'	52'	32'	2–4'	10'
Industrial/Commercial Collector	4/12'	88'	68'	2–10'	10'
Industrial/Commercial	2/16'	72'	52'	2–10'	10'
Industrial/Commertial Cul–de–sac	2/16'	72'	52'	2–10'	10'
Frontage	2/12'	52' min	32' min	1–8'	10'
Alley	2/10'	20'–30'	20'–30'	None	None
Split–Level	See Note 1	---	---	---	---


NOTES:

1. FOR STANDARDS, SEE COUNTY DESIGN STANDARDS DS–2, DS–3, DS–4, AND THE "PUBLIC ROAD STANDARDS".
2. ADDITIONAL PAVEMENT AND R/W MAY BE REQUIRED FOR C.E. COLLECTORS AND LIGHT COLLECTORS IN INDUSTRIAL/COMMERCIAL ZONES, (4 FT. AND 12 FT. RESPECTIVELY).
3. C.E. ROADS NEEDING ADDITIONAL TURN LANES WILL REQUIRE AN ADDITIONAL 12 TO 14 FT. OF PAVEMENT AND R/W FOR EACH LANE.
4. C.E. ROADS DESIGNATED WITH BIKE LANES WILL REQUIRE AN ADDITIONAL 10 FT. OF PAVEMENT AND R/W.
5. INTERIM ROADS SHALL HAVE A MINIMUM WIDTH OF 28 FT. A.C. WITHIN A 40 FT. GRADED ROADBED. WIDTHS WILL BE LARGER IF TRAFFIC VOLUMES REQUIRE MORE TRAVEL LANES.


DRAWN BY S.P. CHECKED BY [illegible]	SAN DIEGO COUNTY DESIGN STANDARD	REVISION	BY	APPROVED / DATE
RECOMMENDED BY [illegible]		NOTES		O. Mahin 3/95
APPROVED BY COUNTY ENGINEER	TYPICAL ROADWAY SECTIONS			
[illegible] R.C.E. 20410				
DATE 3/7/95		DRAWING NUMBER		DS–1



PLAN



TYPICAL ROADWAY SECTION




TYPICAL SECTION OF PARKING BAY


NOTES:

1. SEE SAN DIEGO COUNTY STANDARD DRAWINGS AND SAN DIEGO COUNTY TECHNICAL ROAD POLICY FOR CURB, SIDEWALK & ROADWAY REQUIREMENTS.
2. NATURAL SLOPE EXCEEDS 20% AS DEFINED IN SAN DIEGO COUNTY TECHNICAL ROAD POLICY SECT 4.22
3. REQUIRED: ONE 600 SQUARE FOOT PERPENDICULAR PARKING BAY PER LOT. THE SURVEYOR-ROAD COMMISSIONER MAY ALSO ESTABLISH ALTERNATE STANDARD TYPICAL SECTIONS WHICH WILL PROVIDE A MINIMUM OF TWO PARKING STALLS PER LOT.
4. USE OF THIS STREET SECTION LIMITED TO AREAS IN WHICH AT LEAST 80% OF THE LOTS HAVE A NET AREA NOT LESS THAN 20,000 SQUARE FEET.


DRAWN BY ____ CHECKED BY ____	SAN DIEGO COUNTY DESIGN STANDARD	
RECOMMENDED BY [illegible]		REVISION | BY | APPROVED | DATE
APPROVED BY COUNTY ENGINEER	HILLSIDE RESIDENTIAL STREET	FORMERLY STANDARD DRAWING 311-1
[illegible] R.C.E. 10355	ALTERNATE No. 1	NUMBER DS-2
DATE 2/22/72		



PLAN



TYPICAL ROADWAY SECTION




CONCRETE GUTTER DETAIL


NOTES:

1. SEE SAN DIEGO COUNTY STANDARD DRAWINGS AND SAN DIEGO COUNTY TECHNICAL ROAD POLICY FOR CURB, SIDEWALK & ROADWAY REQUIREMENTS.
2. NATURAL SLOPE EXCEEDS 20% AS DEFINED IN SAN DIEGO COUNTY TECHNICAL ROAD POLICY SECT. 4.22
3. USE OF THIS STREET SECTION LIMITED TO AREAS IN WHICH AT LEAST 80% OF THE LOTS HAVE A NET AREA OF NOT LESS THAN 20,000 SQUARE FEET.
4. USE OF HILLSIDE RESIDENTIAL STREET STANDARDS ARE APPLICABLE ONLY TO STREETS CLASSIFIED AS, RESIDENTIAL, RESIDENTIAL CUL-DE-SAC, OR RESIDENTIAL LOOP STREETS AND ARE NOT APPLICABLE TO STREETS IN AREAS ZONED FOR COMMERCIAL, INDUSTRIAL OR MULTIPLE RESIDENTIAL USE

DRAWN BY ____ CHECKED BY ____	SAN DIEGO COUNTY DESIGN STANDARD	
RECOMMENDED BY [illegible]		
APPROVED BY COUNTY ENGINEER	HILLSIDE RESIDENTIAL STREET	REVISION | BY | APPROVED | DATE
[illegible] R.C.E. 10355	ALTERNATE No. 2	FORMERLY STANDARD DRAWING 312-1
DATE [illegible]		NUMBER DS-3



PLAN




TYPICAL ROADWAY SECTION


NOTES:

1. SEE SAN DIEGO COUNTY STANDARD DRAWINGS AND SAN DIEGO COUNTY TECHNICAL ROAD POLICY FOR CURB, SIDEWALK & ROAD REQUIREMENTS.
2. NATURAL SLOPE EXCEEDS 20% AS DEFINED IN SAN DIEGO COUNTY TECHNICAL ROAD POLICY SECT. 4.22.
3. USE OF THIS STREET SECTION LIMITED TO AREAS IN WHICH AT LEAST 80% OF THE LOTS HAVE A NET AREA OF NOT LESS THAN 20,000 SQUARE FEET.
4. USE OF HILLSIDE RESIDENTIAL STREET STANDARDS ARE APPLICABLE ONLY TO STREETS CLASSIFIED AS RESIDENTIAL, RESIDENTIAL CUL-DE-SAC, OR RESIDENTIAL LOOP STREETS AND ARE NOT APPLICABLE TO STREETS IN AREAS ZONED FOR COMMERCIAL, INDUSTRIAL OR MULTIPLE RESIDENTIAL USE.

DRAWN BY ___ CHECKED BY ___	SAN DIEGO COUNTY DESIGN STANDARD	T. E. K. [illegible]
RECOMMENDED BY [illegible]		
APPROVED BY COUNTY ENGINEER		REVISION | BY | APPROVED | DATE
[illegible] R.C.E. 10358	HILLSIDE RESIDENTIAL STREET	FORMERLY STANDARD DRAWING 313-1
DATE 1/12/76	ALTERNATE No. 3	NUMBER DS-4




SECTION A-A



NOTE:


1. FOR USE ON EITHER 36' OR 40' WIDTH STREETS.

DRAWN BY ____	CHECKED BY ____	SAN DIEGO COUNTY DESIGN STANDARD	TITLE BLK [illegible] 2-24-76
RECOMMENDED BY [signature]			
APPROVED BY COUNTY ENGINEER		TEMPORARY TURN-AROUND AT DEAD-END STREET	REVISION / BY / APPROVED / DATE
[signature] R.C.E. 10358			FORMERLY STANDARD DRAWING 3i4-1
DATE 2/24/76			NUMBER DS-5




DIMENSIONS					CURVE 1.								CURVE 2				
						CURB			PROP.					CURB		PROP.	
R/W	A	B	C	D	△	R	L	T	R	L	T	△	R	L	R	L
52'	26'	16'	10'	50.95'	46°42' 30"	32'	26.09'	13.82'	22'	17.93'	9.50'	273°25' 00"	38'	181.34'	48'	229.06'
56'	28'	18'	10'	50.99'	42°50' 00"	37'	27.66'	14.52'	27'	20.18'	10.59'	265°40' 00"	38'	176.20'	48'	222.56'
60'	30'	20'	10'	68.15'	29°35' 31"	100'	51.65'	26.41'	90'	46.48'	23.77'	239° 11' 02"	38'	158.63'	48'	200.38'
72'	36'	26'	10'	81.39'	32°51' 36"	100'	57.35'	29.49'	90'	51.62'	26.54'	245°43' 12"	50'	214.43'	60'	257.32'


DRAWN BY ____ CHECKED BY ____	SAN DIEGO COUNTY DESIGN STANDARD	T-3.0K	RCV Kimber 2/24/76
RECOMMENDED BY [signature]			
APPROVED BY COUNTY ENGINEER		REVISION	BY APPROVED DATE
[signature] R.C.E. 10358	TURNAROUND AND CALCULATIONS	FORMERLY STANDARD DRAWING 3C4-3	
DATE 2/17/76		NUMBER DS-6	



PROFILE



TYPICAL SECTION



PLAN


NOTES:

1. DRIVEWAYS WITH GRADES GREATER THAN 15% SHALL BE SURFACED WITH ASPHALT CONCRETE OR PORTLAND CEMENT CONCRETE.
2. MAXIMUM GRADE BREAK 14%.
3. SEE STANDARD DRAWING G-14 FOR CONCRETE DRIVEWAYS.
4. SEE STANDARD DRAWING G-15 & G-16 FOR LOCATION & WIDTH REQUIREMENTS.

DRIVEWAY
PAVING SCHEDULE

DEPTH OF A.C.	GRADE
0.17'	0-15%
0.25'	15-20%
0.33'	20-25%

DRAWN BY ____ CHECKED BY ____	SAN DIEGO COUNTY DESIGN STANDARD	TITLE: ROAD STANDARDS
RECOMMENDED BY [signature]		REVISION BY APPROVED DATE
APPROVED BY COUNTY ENGINEER [signature] R.C.E. 10358	ASPHALT CONCRETE DRIVEWAY	FORMERLY STANDARD DRAWING 23.7
DATE 11/22/71		NUMBER DS-7




TYPICAL FINISHED GRADING


NOTES:

1. ELEV. A IS TO BE DETERMINED FOR THE MOST REMOTE CORNER OF THE LOT FROM THE DRAIN POINT. ELEV. A = ELEV. B PLUS 1% TIMES ONE-HALF THE PERIMETER OF THE LOT
2. MIN. 1% SWALE TO STREET OR OTHER DISCHARGE POINT .
3. ALL SLOPE SURFACES TO BE PROTECTED BY APPROVED EROSION CONTROL.

DRAWN BY ____	CHECKED BY ____	SAN DIEGO COUNTY DESIGN STANDARD			
RECOMMENDED BY [signature]					
APPROVED BY COUNTY ENGINEER			REVISION	BY	APPROVED	DATE
[signature] R.C.E. 10358		LOT GRADING	FORMERLY STANDARD DRAWING 231T			
DATE 11/14/75			NUMBER DS-8			



FENCING CUT BANKS




RETAINING WALL & CHAIN LINK FENCE
FOR WALL HEIGHTS GREATER THAN 4 FT.


NOTES:

1. CHAIN LINK FENCE OR ALTERNATE ACCEPTABLE TO THE COUNTY ENGINEER SHALL BE INSTALLED ALONG THE TOP OF SLOPES EXCEEDING 15 FEET VERTICAL HEIGHT AND 3 TO 1 SLOPE RATIO, AND ALONG THE TOP OF WALLS EXCEEDING 6' VERTICAL HEIGHT.
2. RETAINING WALLS AND CHAIN LINK FENCE OR ALTERNATE SHALL BE CONSTRUCTED IN ACCORDANCE WITH COUNTY OF SAN DIEGO STANDARD SPECIFICATIONS.


DRAWN BY ____	CHECKED BY ____	SAN DIEGO COUNTY DESIGN STANDARD	TITLE 3-14 BC [illegible] 2/24/76
RECOMMENDED BY [illegible]			
APPROVED BY COUNTY ENGINEER			REVISION / BY / APPROVED / DATE
[illegible] R.C.E. 10358		FENCING CUT BANKS	FORMERLY STANDARD DRAWING 23CT
DATE 2/24/76			NUMBER DS-9




TYPICAL CUT SLOPE



DETAIL C
TYPICAL BERM AT TOP OF ALL FILL SLOPES



DETAIL D



TYPICAL FILL SLOPE

TABLE 1
REQUIRED SETBACK

H FEET	d
0 - 15'	3'
OVER 15'	5'


TABLE 2
SLOPE ROUNDING

H FEET	L FEET
0' - 5'	-
5' - 20'	2.5'
20' - 40'	5'
OVER 40'	10'


DRAWN BY ____	CHECKED BY ____	SAN DIEGO COUNTY DESIGN STANDARD	
RECOMMENDED BY [signature]			
APPROVED BY COUNTY ENGINEER [signature] R.C.E. 10358		GRADING OF SLOPES	
DATE 12/24/76			

TITLE	BY	O. Butler	12/24/76
REVISION	BY	APPROVED	DATE
FORMERLY STANDARD DRAWING 206-17			
NUMBER DS-10			

PROPERTY LINE SETBACKS



BUILDING SETBACKS



REQUIRED SETBACKS			
H FEET	a	b	d
0 - 15	1' - 6"	5'	3'
15 - 30	3'	5'	5'
OVER 30	5'	5'	5'

a. DISTANCE FROM TOE OF SLOPE TO PROPERTY LINE

b. DISTANCE FROM EDGE OF FOUNDATION TO TOE OR TOP OF SLOPE.

d. DISTANCE FROM TOP OF SLOPE TO PROPERTY LINE.


H. TOTAL SLOPE HEIGHT MEASURED VERTICALLY.

DRAWN BY ____ CHECKED BY ____	SAN DIEGO COUNTY DESIGN STANDARD	TITLE	BY / APPROVED / DATE
RECOMMENDED BY [signature]			
APPROVED BY COUNTY ENGINEER [signature] R.C.E. 10358	REQUIRED SETBACKS	REVISION	BY / APPROVED / DATE
DATE 7/12/16		FORMERLY STANDARD DRAWING 209	
		NUMBER DS-11	

PROPOSED CONSTRUCTION


LINES

- ULTIMATE CENTERLINE (℄)*
- STAGE CONSTRUCTION LINE
- INTERSECTING ROADS & STREETS
- RIGHT OF WAY LINE
- EQUATION OR RADIUS LINE
- OFFSET TIE
- GRADE LINES ON PROFILES
- GROUND LINES ON PROFILES
- SLOPE LIMIT LINES




POINTS

- BC & EC
- PI OR ANGLE PT.
- ℄ MONUMENT
- BENCH MARK




CONSTRUCTION

- PAVEMENT EDGE & SHOULDERS
- A C DIKE (LABEL TYPE)
- CURB & GUTTER (LABEL TYPE)
- CULVERT
- DOWNDRAIN, A C SPILLWAY
- DROP INLET
- BOX CULVERT
- HEADWALL, STANDARD
- HEADWALL "L" TYPE
- HEADWALL & WINGWALL
- GUARD RAIL
- DRIVEWAY APRONS A C
- UTILITY DUCT (LABEL)




- DRIVEWAY APRONS P C C
- CONCRETE CROSS GUTTER
- SIDEWALK
- RETAINING WALL
- FENCE (LABEL TYPE)
- DITCH, LINED
- DITCH, UNLINED
- BRIDGE




UTILITIES

- GAS LINE
- WATER LINE
- ELECTRIC CABLE
- TELEPHONE CABLE
- SEWER LINE
- UTILITY MANHOLE




STRUCTURAL SYMBOLS

- PORTLAND CEMENT CONCRETE
- ASPHALT CONCRETE (EXISTING)
- ROAD OIL MIX OR ASPHALT CONCRETE SURFACING
- BASE MATERIAL
- ORIGINAL GROUND



MISCELLANEOUS SYMBOLS


- CONTRACTED LINE (NOT TO SCALE)
- LIMIT ARROWS
- PROJECT, WORK LIMIT
- CUTTING PLANE




CADASTRAL SYMBOLS


LAND LINES


- TOWNSHIP LINES
- SECTION LINES
- GRANT LINE (RHO BOUNDARY OR INDIAN RESERVATION)
- SUBDIVISION BOUNDARY LINE
- CITY / COUNTY BOUNDARY LINE
- PROPERTY LINE
- LOT LINE
- EASEMENT LINE





DRAWN BY ____ CHECKED BY ____	SAN DIEGO COUNTY DESIGN STANDARD	TITLE [illegible]
RECOMMENDED BY WEB		REVISION | BY | APPROVED | DATE
APPROVED BY COUNTY ENGINEER [signature] R.C.E. 10358	CONSTRUCTION PLAN SYMBOLS	FORMERLY STANDARD DRAWING
DATE 11-24-76		NUMBER DS-12





TYPICAL STREET NAME LAYOUT


Typical layout of legend and border on variable length sign blade of extruded aluminum with reverse screened reflective sheeting engineering grade. White letters and border on green background.

① 5"–U.C., 3 3/4"–L.C.

② 4 11/16" spacing of two 11/32" holes centered on both top and bottom edge of blade to match holes in sign bracket assemblies.


③ 2" x 2 3/4"–Arrow


④ 2"–U.C.



POST CAP DETAIL

Curb and Sidewalk	Sidewalk Width	Setback
Contiguous	6' or less	Sidewalk Width
Contiguous	more than 6'	2'-0"
Separate	———	2'-0"






HALF–SECTION DETAIL


NOTES

1. Ⓐ denotes 4 11/16" spacing shall match the holes in the extruded blades.
2. Bracket to be die cast aluminum.
3. All attaching screws shall be vandal proof type.




STREET NAME SIGN LOCATION
(numbers indicate priority of location selection)

DRAWN BY GR.	CHECKED BY	SAN DIEGO COUNTY DESIGN STANDARD	DAF DIM. L.J. D.S. 12/6/76
RECOMMENDED BY R.F. Walsh			
APPROVED BY COUNTY ENGINEER			REVISION BY APPROVED DATE
K.L. Emerson R.C.E. 10358		STANDARD STREET SIGN	FORMERLY STANDARD DRAWING 301-2
DATE 10/6/76			NUMBER DS–13



SECTION A–A




DIP SECTION PROFILE

NOTES:

1. Dip sections shall conform to Section 5.7–10(d) of the San Diego County Standards.
2. The maximum water depth, based on a 10 year frequency storm, shall be 10". The depth (D) in feet multiplied by the velocity (V) in feet per second shall be equal to six or less. (DxV=6)
3. Vertical curves shall be designed based on road design speed and the percent change in longitudinal road grade.
4. Low Flow pipes may be omitted if the conditions of Note 2 can be met without their use.

DRAWN BY RG CHECKED BY MC RECOMMENDED BY M. Baker	SAN DIEGO COUNTY DESIGN STANDARD				
APPROVED BY COUNTY ENGINEER R F Walsh R.C.E. 10358 DATE 4-29-82	DIP SECTION (FOR PRIVATE STREETS)	REVISION	BY	APPROVED	DATE
		NUMBER DS–14			



PLAN

NOTES:

1. Δ = 110° Max., 70° Min. If Δ is greater than 110°, then 200 Ft. minimum centerline radius required.
2. Centerline curve data: Δ, R, L, T to be shown on plans.

A	B	R_1*	R_2*	C*
72'	52'	80'	40'	10'
60'	40'	68'	30'	10'
56'	36'	64'	30'	10'
52'	32'	60'	30'	10'
48'	28'	56'	30'	10'


* DIMENSIONS SHOWN ARE MINIMUMS

DRAWN BY RH CHECKED BY MB	SAN DIEGO COUNTY DESIGN STANDARD	R+C	RC M. Bahmani	8-19-85
RECOMMENDED BY D. Johnson				
APPROVED BY COUNTY ENGINEER RF Webb for R.C.E. 10358	STREET KNUCKLE	REVISION	BY	APPROVED / DATE
DATE 11-6-84		NUMBER DS-15		




BRONZE MARKER

NOTE A:
Rotate arrow to indicate location of target point



CASE II MARKER




CASE I: BRONZE MARKER TO BE SET IN P.C.C. CURB AT LINE OF SIGHT – CURB INTERSECTION


CASE II: IF NO CURB, SET BRONZE MARKER IN CONCRETE IN 2" X 24" LONG STEEL PIPE AT INTERSECTION OF LINE OF SIGHT AND PROPERTY LINE

CLEAR SPACE EASEMENTS FOR SIGHT DISTANCE, WHERE SPECIFIED IN PLANS, SHALL BE DESIGNATED BY A BRONZE MARKER ACCORDING TO CASE I OR CASE II ABOVE.


DRAWN BY CAD CHECKED BY A.H.	SAN DIEGO COUNTY DESIGN STANDARD	REVISION	BY	APPROVED	DATE
RECOMMENDED BY CMH		Title	WE	CM Hunt	9/89
APPROVED BY: H K Dalie for DIRECTOR OF PUBLIC WORKS, R.C.E. 13681	CLEAR SPACE MARKERS				
DATE 6-23-89		NUMBER DS-16			



DRAWN BY J.P.	CHECKED BY	SAN DIEGO COUNTY DESIGN STANDARD	REVISION	BY	APPROVED	DATE
RECOMMENDED BY						
APPROVED BY COUNTY ENGINEER						
R.C.E. 20410		GATED DRIVEWAY ENTRANCE - TYPE I				
DATE 10/23/92			DRAWING NUMBER		DS-17	



DRAWN BY J.P. CHECKED BY RC	SAN DIEGO COUNTY DESIGN STANDARD	REVISION	BY	APPROVED	DATE
RECOMMENDED BY Linda Kerami					
APPROVED BY COUNTY ENGINEER					
W Abelon R.C.E. 20410	**GATED DRIVEWAY ENTRANCE - TYPE II**	DRAWING NUMBER		**DS-18**	
DATE 10/23/92					



DRAWN BY S.P. CHECKED BY	SAN DIEGO COUNTY DESIGN STANDARD	REVISION	BY	APPROVED	DATE
RECOMMENDED BY					
APPROVED BY COUNTY ENGINEER					
R.C.E. 20410	**GATED DRIVEWAY ENTRANCE - TYPE III**				
DATE 10/23/92		DRAWING NUMBER		**DS-19**	