

TRAFFIC ANALYSIS AND PARKING ASSESSMENT

Casa de Oro Specific Plan

Prepared for:
County of San Diego
Planning & Development Services
5510 Overland Avenue
San Diego, CA 92123

July 28, 2021

TABLE OF CONTENTS

1	INTRODUCTION	1
1.1	Study Area.....	1
1.2	Surrounding Roadway Network.....	2
1.3	Field Work and Data Collection	3
2	EXISTING TRAFFIC CONDITIONS.....	6
2.1	Roadway Segment Evaluation.....	6
2.1.1	Roadway Segment Analysis Methodology	6
2.1.2	Roadway Segment Level of Service.....	7
2.2	Intersection Evaluation	3
2.2.1	Intersection Analysis Methodology	3
2.2.2	Peak Hour Intersection Level of Service	4
2.3	Existing Pedestrian Facilities	8
2.3.1	Sidewalks.....	8
2.3.2	Crosswalks.....	9
2.3.3	ADA Facilities.....	17
2.4	Existing Bicycle Facilities	17
2.5	Existing Transit Facilities	19
3	EXISTING PARKING ASSESSMENT	22
3.1	Data Collection.....	22
3.2	Parking Survey.....	22
3.2.1	Parking Inventory	22
3.2.2	Parking Utilization	25
3.3	Existing Parking Ratios	27
4	HORIZON YEAR 2035 WITH PROJECT TRAFFIC CONDITIONS.....	29
4.1	Casa De Oro Revitalization.....	29
4.1.1	Horizon Year 2035 With Project Study Area	31
4.2	Horizon Year 2035 With Project Traffic Volumes	31
4.3	Horizon Year 2035 With Project Intersection Analysis	34
4.3.1	Preferred Campo Road Corridor Concept Plan	34
4.4	Summary & Recommendations	34
4.4.1	Operational Assessment of Alternative Intersection Controls	36
5	CONCLUSIONS	37
5.1	Existing Conditions Summary.....	37
5.2	Horizon Year 2035 With Project Summary and Recommendations.....	37

Exhibit 1 – Study Area	4
Exhibit 2 – Valle de Oro Community Plan Mobility Element Network	5
Exhibit 3 - Existing Street Segment Classifications.....	2
Exhibit 4 – Existing Intersection Lane Geometry	6
Exhibit 5 – Existing AM/PM Peak Hour Intersection Volumes.....	7
Exhibit 6 – Existing Pedestrian Facilities and Pedestrian Peak Hour Volumes	10
Exhibit 7 – Driveway Locations on Campo Road	16
Exhibit 8 – Existing Bicycle Facilities & Cyclist Peak Hour Volumes	18
Exhibit 9 – MTS Route 855 – Spring Street Trolley to Rancho San Diego	20
Exhibit 10– Existing Transit Facilities & Amenities.....	21
Exhibit 11 – Parking Survey Zones	23
Exhibit 12 - Peak Parking Utilization Heat Map	26
Exhibit 13 - Proposed Campo Road Corridor Concept Plan	30
Exhibit 14 - Horizon Year 2035 With Project Assumed Lane Geometry	32
Exhibit 15 - Horizon Year 2035 With Project AM/PM Peak Hour Volumes	33

LIST OF TABLES

Table 1- LOS Criteria for Roadway Segments	6
Table 2 - Existing Conditions Roadway Segment LOS	7
Table 3 - Level of Service & Delay Range	3
Table 4 - Existing AM/PM Peak Hour Intersection LOS.....	4
Table 5 - ADA Factors.....	17
Table 6 - Existing Bus Stop Amenities along Campo Road	19
Table 7 – Existing Parking Inventory	22
Table 8 – Peak Parking Utilization.....	25
Table 9 – Existing County Parking Requirements	27
Table 10 – Existing Parking Supply & Actual Parking Demand Rates.....	28
Table 11 - Horizon Year 2035 With Project Conditions AM/PM Peak Hour LOS	34
Table 12 Horizon Year 2035 With Project Alternative Intersection Operations.....	36

ATTACHMENTS

- Attachment A: Mobility Element Network & Matrix
- Attachment B: Traffic Volume Count Data
- Attachment C: Parking Survey Data
- Attachment D: Existing Traffic Signal Timing Worksheets
- Attachment E: Existing Conditions Synchro Worksheets
- Attachment F: Parking Utilization Worksheets
- Attachment G: Horizon Year 2035 With Project HCM Worksheets

1 INTRODUCTION

This report summarizes existing transportation conditions within the Casa de Oro community located in the Valle de Oro Community Planning Area of San Diego County. The study area is focused along an approximate ¾-mile section of Campo Road in the commercial corridor between Granada Avenue and Rogers Road and includes five (5) stop-controlled intersections, seven (7) signalized intersections, and ten (10) roadway segments.

The existing conditions assessment considers the physical roadway conditions and intersection operations as well as the current pedestrian, bicycle, and transit facilities within the study area. In addition to the traffic operations analysis, this report also documents the parking conditions for on-street and off-street parking facilities serving the non-residential uses within the study area. A parking survey was conducted which collected existing inventory data as well as parking utilization in 1-hour increments for 7 hours. Existing parking supply rates and actual parking demand rates were calculated and compared to parking ratios per County code requirements.

1.1 STUDY AREA

The study evaluates the following twelve (12) intersections during the AM and PM peak hours within the study area:

1. Kenwood Drive / SR-94 Eastbound Ramps (All-Way Stop)
2. Kenwood Drive / SR-94 Westbound Ramps (All-Way Stop)
3. Kenwood Drive / Kenora Drive (One-Way Stop)
4. Campo Road / Kenwood Drive (Traffic Signal)
5. Campo Road / Conrad Drive (Traffic Signal)
6. Campo Road / Bonita Street (Traffic Signal)
7. Campo Road / Barcelona Street (Traffic Signal)
8. Campo Road / Cordoba Avenue (Two-Way Stop)
9. Campo Road / Granada Avenue / Casa de Oro Boulevard (Traffic Signal)
10. Campo Road / Agua Dulce Boulevard / SR-94 WB On-Ramp (Traffic Signal)
11. Campo Road / SR-94 Eastbound Ramps (Traffic Signal)
12. Agua Dulce Boulevard / SR-94 Westbound Off-Ramp (One-Way Stop)

The study also evaluates the following ten (10) roadway segments for average daily (24-hour) traffic volumes in the vicinity of the project site:

- A. Kenwood Drive – SR-94 Westbound Ramps to Kenora Drive
- B. Campo Road – Kenwood Drive to Conrad Drive
- C. Campo Road – Conrad Drive to Bonita Street
- D. Campo Road – Bonita Street to Barcelona Street
- E. Campo Road – Cordoba Street to Granada Avenue / Casa De Oro Boulevard
- F. Campo Road – Granada Avenue / Casa De Oro Boulevard to Agua Dulce Boulevard
- G. Conrad Drive – Campo Road to San Juan Street
- H. Barcelona Street – Dolores Street to Campo Road
- I. Casa De Oro Boulevard – East of Ramona Drive

J. Ramona Drive – South of Casa De Oro Boulevard

Exhibit 1 shows the study intersections, roadway segments, and extents of the parking survey.

1.2 SURROUNDING ROADWAY NETWORK

The characteristics of the roadway system in the vicinity of the project site are described below:

Campo Road is oriented in the east-west direction and is classified as a 4-lane Boulevard with Intermittent Turn Lanes (4.2B) per the Valle de Oro Mobility Element. A two-way-left-turn-lane is provided approximately 400 feet west of Kenwood Drive to approximately 230 feet east of Granada Avenue / Casa de Oro Boulevard with left-turn turn lanes at signalized intersections. Within the study area, the posted speed limit is 35 MPH between Kenwood Drive and Granada Avenue / Casa de Oro Boulevard; 40 MPH between Granada Avenue / Casa de Oro Boulevard and Agua Dulce Boulevard and 45 MPH south-east of the SR-94. On-street parallel parking is prohibited in both directions within the study area. Class II bike lanes and sidewalks are provided on both sides of the roadway.

Kenwood Drive is oriented in the northeast-southwest direction and is classified as a 4-lane Major Road with Intermittent Turn Lanes (4.1B) between the SR-94 and Campo Road per the Valle de Oro Mobility Element. On-street parallel parking is prohibited in both directions within the study area. Class II bike lanes are provided on both sides of the roadway. Sidewalks are provided on the east side between the SR-94 eastbound ramps and Kenora Drive only.

Conrad Drive is oriented in the north-south direction and is classified as a 2-lane Light Collector (2.2E) per the Valle de Oro Mobility Element. There are two lanes in the northbound direction immediately north of Campo Road, which taper to a single lane north of San Juan Street (approximately 550') Within the study area, the posted speed limit is 35 MPH. On-street parallel parking is allowed intermittently in both directions between Campo Road and Spring Valley Middle School. There are no bike lanes provided within the study area. Sidewalks are provided on both sides of the roadway between Campo Road and Spring Valley Middle School. There are no sidewalks north of the school.

Barcelona Street is oriented in north-south direction and is classified as a 2-lane Light Collector (2.2E) per the Valle de Oro Mobility Element. Barcelona Street provides a connection for residents south of SR-94 to the commercial corridor via a freeway underpass. Within the study area, the posted speed limit is 25 MPH. On-street parallel parking is allowed in both directions between north and south of Campo Road. There are no bike lanes provided within the study area and sidewalks are provided on both sides of the roadway.

Casa de Oro Boulevard is oriented in the east-west direction and is an unclassified Local Public Road. Within the study area, the posted speed limit is 25 MPH. There are no bike lanes provided within the study area and sidewalks are provided on both sides of the roadway between Campo Road and San Juan Street only.

Exhibit 2 shows the Valle de Oro Community Plan Mobility Element Network. **Attachment A** shows the associated Mobility Element Network Map and Matrix.

1.3 FIELD WORK AND DATA COLLECTION

A detailed field review was conducted in November 2019 to establish current traffic conditions and included an examination of the following factors:

- Lane widths and intersection geometries
- Intersection traffic control and signal phasing at signalized locations
- Crosswalk inventory and ADA compliance
- Posted speed limits
- Bike and sidewalk facilities
- Transit facilities

To determine the existing operations of the study intersections and roadway segments, peak hour intersection movement counts and directional roadway segment traffic counts were collected on Tuesday, November 12, 2019.


Morning (AM) peak period counts were generally collected between 7:00 AM to 9:00 AM and evening (PM) peak period counts were generally collected from 4:00 PM to 6:00 PM. The counts used in this analysis represent the highest hour within the peak periods counted for each intersection.

Of the 12 24-hour roadway segments counts, 10 locations were broken down into axle specific classifications (i.e. passenger vehicle, bus, 2/3/4+ axle trucks). For the purposes of this analysis, roadway segment counts were converted to passenger car equivalents (PCE's).

Detailed traffic count data is provided in [Attachment B](#).

A detailed parking inventory and parking utilization survey was conducted for on-street and off-street parking facilities serving non-residential land uses on Friday, December 13, 2019. The parking inventory identified regular parking spaces, ADA spaces, time-restricted spaces, and other posted restricted parking. The parking utilization survey was conducted over a 7-hour period from 10:00 AM to 5:00 PM where parking data was collected at 1-hour intervals.

Detailed parking utilization data is contained in [Attachment C](#).




Not to Scale

Michael Baker
INTERNATIONAL

January 2020
H:\PDATA\175688_Casa De Oro\Traffic\Exhibits

Study Area

Exhibit 1



2 EXISTING TRAFFIC CONDITIONS

2.1 ROADWAY SEGMENT EVALUATION

2.1.1 Roadway Segment Analysis Methodology

The basis for roadway segment analysis is the relationship between the measured daily traffic volume and the Level of Service (LOS) capacity thresholds established according to roadway classifications. The analysis results provide a planning-level assessment of whether a segment is under, approaching, or over capacity. The County of San Diego has adopted level of service “D” or better as acceptable operating conditions for roadway segments; however, the Valle de Oro Mobility indicates LOS “F” is accepted for the segment of Campo Road between Kenwood Drive and Conrad Drive. **Table 1** presents the roadway segment capacity thresholds by LOS contained in the San Diego County Public Road Standards.

TABLE 1- LOS CRITERIA FOR ROADWAY SEGMENTS

Mobility Element Roads		No. of Travel Lanes	Maximum Level of Service Capacity (ADT)				
			LOS A	LOS B	LOS C	LOS D	LOS E
Expressway (6.1)		6	36,000	54,000	70,000	86,000	108,000
Prime Arterial (6.2)		6	22,000	37,000	44,600	50,000	57,000
Major Road	With Raised Medians (4.1A)	4	14,800	24,700	29,600	33,400	37,000
	With Intermittent Turn Lanes (4.1B)		13,700	22,800	27,400	30,800	34,200
Boulevard	With Raised Medians (4.2A)	4	18,000	21,000	24,000	27,000	30,000
	With Intermittent Turn Lanes (4.2B)		16,800	19,600	22,500	25,000	28,000
Community Collector	With Raised Medians (2.1A)	2	10,000	11,700	13,400	15,000	19,000
	With Continuous Turn Lanes (2.1B)		3,000	6,000	9,500	13,500	19,000
	With Intermittent Turn Lanes (2.1C)		3,000	6,000	9,500	13,500	19,000
	With Improvement Options (2.1D)		3,000	6,000	9,500	13,500	19,000
	No Median (2.1E)		1,900	4,100	7,100	10,900	16,200
Light Collector	With Raised Medians (2.2A)	2	3,000	6,000	9,500	13,500	19,000
	With Continuous Turn Lanes (2.2B)		3,000	6,000	9,500	13,500	19,000
	With Intermittent Turn Lanes (2.2C)		3,000	6,000	9,500	13,500	19,000
	With Improvement Options (2.2D)		3,000	6,000	9,500	13,500	19,000
	No Median (2.2E)		1,900	4,100	7,100	10,900	16,200
	With Reduced Shoulders (2.2F)		5,800	6,800	7,800	8,700	9,700
Minor Collector	With Raised Medians (2.3A)	2	3,000	6,000	7,000	8,000	9,000
	With Intermittent Turn Lanes (2.3B)		3,000	6,000	7,000	8,000	9,000
	No Median (2.3C)		1,900	4,100	6,000	7,000	8,000
Non-Mobility Element Roads		No. of Travel Lanes	Maximum Level of Service Capacity (ADT)				
			LOS A	LOS B	LOS C	LOS D	LOS E
Residential Collector		2	-	-	4,500	-	-
Rural Residential Collector		2	-	-	4,500	-	-
Residential Road		2	-	-	1,500	-	-
Rural Residential Road		2	-	-	1,500	-	-
Residential Cul-de-Sac or Loop Road		2	-	-	200	-	-

Source: County of San Diego Public Road Standards (March 2012)

2.1.2 Roadway Segment Level of Service

Exhibit 3 shows the street segment classification within the study area.

Level of Service (LOS) for roadway segments are calculated based on the capacity of the roadway determined by the existing functional classification and existing daily traffic volumes. Existing traffic counts were converted to passenger car equivalents (PCE's) using the following PCE factors from the SANDAG 2050 Regional Travel Demand Model Documentation (2011):

- Passenger Car = 1.0
- 2-Axle Truck = 1.3
- 3-Axle Truck = 1.5
- 4+ Axle Trucks = 2.5

Table 2 summarizes existing conditions average daily traffic level of service for all study roadway segments.

TABLE 2 - EXISTING CONDITIONS ROADWAY SEGMENT LOS

Roadway	Segment	Classification	No. Lanes	LOS E Capacity ⁽¹⁾	Existing		
					ADT	V/C	LOS
Kenwood Dr.	SR-94 WB Ramps to Kenora Dr.	Major Road with Intermittent Turn Lanes (4.1B)	4	34,200	23,207	0.68	C
Campo Rd.	Kenwood Dr. to Conrad Dr.	Boulevard with Intermittent Turn Lanes (4.2B)	4	28,000	24,390	0.87	D
	Conrad Dr. to Bonita St.	Boulevard with Intermittent Turn Lanes (4.2B)	4	28,000	19,890	0.71	C
	Bonita St. to Barcelona St.	Boulevard with Intermittent Turn Lanes (4.2B)	4	28,000	17,708	0.63	B
	Cordoba St. to Granada Ave./Casa de Oro Blvd.	Boulevard with Intermittent Turn Lanes (4.2B)	4	28,000	13,227	0.47	A
	Granada Ave./Casa de Oro Blvd. to Agua Dulce Blvd.	Boulevard with Intermittent Turn Lanes (4.2B)	4	28,000	14,282	0.51	A
Conrad Dr.	Campo Rd. to San Juan St.	Light Collector (2.2E)	2	16,200	6,007	0.37	C
Barcelona St.	Dolores St. to Campo Rd.	Light Collector (2.2E)	2	16,200	6,975	0.43	C
Casa de Oro Blvd.	East of Ramona Dr.	Residential Collector	2	4,500	2,572	Under Capacity	
Ramona Dr.	South of Casa de Oro Blvd.	Residential Collector	2	4,500	1,286	Under Capacity	

Note: Deficient roadway segment operations shown in **bold**

ADT= Average Daily Traffic


LOS= Level of Service

V/C= Volume to Capacity Ratio

⁽¹⁾ Capacity for a Residential Collector reflects LOS C thresholds per Non-Mobility Element Roads shown in Table 1

As shown in **Table 2**, all study roadway segments are currently operating at an acceptable level of service (LOS D or better) for Existing conditions.

Roadway segment level of service standards based on daily traffic are generally used as long-range planning guidelines to determine the roadway capacity and classification and are not always accurate indicators of roadway performance. Typically, the performance and level of service of a roadway segment is heavily influenced by traffic flows during the peak hour and the ability of intersections to accommodate peak hour flows. Therefore, peak hour operating conditions at the signalized and unsignalized intersections within the study area were also evaluated.



Not to Scale

2.2 INTERSECTION EVALUATION

2.2.1 Intersection Analysis Methodology

Level of Service (LOS) is commonly used as a qualitative description of intersection operation and is based on the capacity of the travel lanes approaching the intersection, the volume of traffic using the intersection, and the average vehicle delay. The intersection analysis conforms to the operational analysis methodology outlined in the *Highway Capacity Manual (HCM 6th Edition)* and performed utilizing the *Synchro 10* traffic analysis software.

The *HCM* analysis methodology describes the operation of an intersection using a range of level of service from LOS A (free-flow conditions) to LOS F (severely congested conditions), based on the corresponding stopped delay experienced per vehicle for study intersections as shown in **Table 3**.

For signalized intersections, signal timing data and parameters such as cycle lengths, splits, clearance intervals, etc. were obtained from the current signal timing data sheets provided by City staff and incorporated into the Synchro model (see **Attachment D**). Synchro reports average vehicle delay for a signalized intersection, which correspond to a particular LOS, to describe the overall operation of an intersection.

Unsignalized intersection LOS for all-way stops is based on the average vehicle delay for all approaches. Average vehicle delay for one-way or two-way stop-controlled intersections is influenced by available gaps in traffic flow on the non-controlled approaches and LOS is based on the approach with the worst delay.

The County of San Diego has adopted level of service “D” or better as acceptable operating conditions for intersections.

TABLE 3 - LEVEL OF SERVICE & DELAY RANGE

Level of Service	Control Delay (seconds/vehicle)		Description
	Signalized Intersections	Unsignalized Intersections	
A	≤ 10.0	≤ 10.0	Operates with very low delay and most vehicles do not stop.
B	> 10.0 to 20.0	> 10.0 to 15.0	Operates with good progression with some restricted movements.
C	> 20.0 to 35.0	>15.1 to 25.0	Operates with significant number of vehicles stopping with some backup and light congestion.
D	> 35.0 to 55.0	> 25.0 to 35.0	Operates with noticeable congestion, longer delays occur, and many vehicles stop.
E	> 55.0 to 80.0	> 35.1 to 50.0	Operates with significant delay, extensive queuing and unfavorable progression.
F	> 80.0	> 50.0	Operates at a level that is unacceptable to most drivers. Arrival rates exceed capacity of the intersection. Extensive queuing occurs.

Source: Highway Capacity Manual (HCM) 6th Edition.

2.2.2 Peak Hour Intersection Level of Service

Exhibit 4 shows the Existing study intersection lane geometry. **Exhibit 5** shows the AM and PM peak hour traffic volumes at the study intersections.

Table 2 summarizes existing conditions AM/PM peak hour level of service for all study intersections. Detailed analysis sheets are contained in **Attachment E**.

TABLE 4 - EXISTING AM/PM PEAK HOUR INTERSECTION LOS

Study Intersection	Traffic Control	Existing Conditions					
		AM			PM		
		Delay ¹	-	LOS	Delay ¹	-	LOS
1 - Kenwood Drive / SR-94 EB Ramps	AWSC	28.5	-	D	31.5	-	D
2 - Kenwood Drive / SR-94 WB Ramps	AWSC	79.3	-	F	23.9	-	C
3 - Kenwood Drive / Kenora Drive	OWSC	106.8	-	F	69.1	-	F
4 - Campo Road / Kenwood Drive	Signal	25.8	-	C	26.1	-	C
5 - Campo Road / Conrad Drive	Signal	23.6	-	C	17.7	-	B
6 - Campo Road / Bonita Street	Signal	13.2	-	B	12.0	-	B
7 - Campo Road / Barcelona Street	Signal	18.3	-	B	12.7	-	B
8 - Campo Road / Cordoba Avenue	TWSC	270.4	-	F	21.9	-	C
9 - Campo Road / Granada Avenue / Casa de Oro Blvd	Signal	72.6	-	E	23.5	-	C
10 - Campo Road / Agua Dulce Blvd / SR-94 WB On-Ramp	Signal	68.5	-	E	61.2	-	E
11 - Campo Road / SR-94 EB Ramps	Signal	33.9	-	C	33.7	-	C
12 - Agua Dulce Blvd / SR-94 WB Off-Ramp	OWSC	256.0	-	F	14.3	-	B

Note: Deficient intersection operation indicated in **bold**.

¹ Average seconds of delay per vehicle.

LOS = level of service.

AWSC = All-Way Stop Control

TWSC = Two-Way Stop Control

OWSC = One-Way Stop Control

As shown in **Table 2**, six study intersections are currently operating at an acceptable level of service (LOS D or better) for Existing conditions and the following intersections are currently operating at a deficient level of service (LOS E or F):

2. Kenwood Drive / SR-94 Westbound Ramps (AM Peak Hour Only)
3. Kenwood Drive / Kenora Drive (AM & PM Peak Hours)
8. Campo Road / Cordoba Avenue (AM Peak Hour Only)
9. Campo Road / Granada Avenue / Casa de Oro Boulevard (AM Peak Hour Only)
10. Campo Road / Agua Dulce Boulevard / SR-94 WB On-Ramp (AM & PM Peak Hours)
12. Agua Dulce Boulevard / SR-94 WB Off-Ramp (AM Peak Hour Only)


While not reflected in the level of service analysis, there are other abnormal intersection features that effect the operations of several intersections as described below.

At the intersection of Campo Road and Kenwood Drive, there are two uncontrolled driveways in the middle of the intersection on the north side. There are no signal heads, crosswalks, or pedestrian signal heads for these driveways, and they are signed as “right-turn only” for exiting vehicles. There are also no turn movements designated into the driveways from the eastbound or northbound directions (i.e. no

pavement markings or signal heads). The westbound approach can turn right into these driveways from the through-lane. The existing peak hour counts showed a total 3 vehicles in the AM peak hour and 1 vehicle in the PM peak hour entering the driveways. There were no vehicles exiting the driveways during either peak hour. While these unusual driveway related access features and traffic movements exist, the intersection analysis shows this location operating at acceptable levels of service during the AM and PM peak hours.

Similarly, the intersection of Campo Road at Conrad Drive has an uncontrolled driveway on the south side of the intersection with no signal heads, crosswalks, or pedestrian signal heads. While the driveway is signed as a “right-turn only” for exiting vehicles, existing peak hour counts show 2 vehicles making illegal turn movements (1 through, and 1 left-turn) out of the driveway. There were 562 vehicles in the AM peak hour and 612 vehicles in the PM peak hour turn right out of the driveway. There was a total of 20 vehicles in the AM peak hour and 42 vehicles in the PM peak hour entering the driveway. There are designated turn movements from all approaches to enter the driveway. While these unusual driveway related access features and traffic movements exist, the intersection analysis shows this location operating at acceptable levels of service during the AM and PM peak hours.


Lastly, the intersection of Campo Road at Granada Avenue / Casa de Oro Boulevard is a signalized 5-legged intersection. The through movement is prioritized for Campo Road (north-westbound to westbound and westbound to south-eastbound) movements. Granada Avenue and Casa de Oro Boulevard are considered minor streets and the signal is split-phased for these approaches; that is each individual minor street approach is given a protected green signal indication for all movements at that approach. While traffic flows well through the intersection, the amount of time needed to serve all movements requires a long cycle-length and this causes vehicles at the intersection to experience long average delays and a deficient level of service during the AM peak hour.



Legend

- = Signal Control Intersection
- = Stop Control Intersection
- = Yield Control Movement
- TWLTL = Two-Way-Left-Turn-Lane
- D = Defacto Turn-Lane





Notes: XX / XX = AM / PM Peak Hour Volumes



2.3 EXISTING PEDESTRIAN FACILITIES

Existing peak hour pedestrian activity was recorded on Tuesday, November 12, 2019. Based on the existing counts, pedestrian activity on Campo Road during the AM peak hour peaks at the Conrad Drive westside crosswalk with 84 pedestrians crossing Campo Road. During the PM Peak hour, pedestrian activity peaks at the Kenwood Drive/ SR-94 Eastbound Ramp intersection where 20 pedestrians cross the on-ramp.

Exhibits 6a-6f illustrate the existing activity as well as the current pedestrian facilities within the study area. The types of facilities shown include the following:

- Sidewalks
- Ped Ramps
- Marked Crosswalks
- Pedestrian Push Buttons (at signalized intersections)
- Pedestrian Signal Heads (at signalized intersections)

Within the study area, there are approximately a combined 70 driveways on the north and south sides of Campo Road within a 2/3 mile stretch between Rogers Road and Granada Avenue. On average, this is approximately one driveway every 50 feet. The high frequency of driveways along the corridor creates numerous conflict points between motorists, pedestrians, and bicyclists and the excessive curb cuts prevent landscaping, lighting, and parking. All driveways are paved concrete and appear to meet County standards. **Exhibit 7** shows all of the driveway locations on Campo Road.

In addition to the conflict points caused by the driveways, the existing retaining walls within the shopping centers prevent pedestrian and vehicular connectivity between adjacent properties. These barriers impede access, complicate circulation, and generate additional traffic from the increased turn movements to and from Campo Road.

2.3.1 Sidewalks

Campo Road – Sidewalks are provided on both sides of Campo Road between Kenwood Drive and Casa de Oro Boulevard. On the westerly side of the study area, sidewalks terminate approximately 400' feet west of Kenwood Drive on the north side of Campo Road and approximately 525' west of Kenwood Drive on the south side of Campo Road. To the east, there is a gap in the sidewalk for approximately 0.2 miles between Casa de Oro Boulevard and Agua Dulce Boulevard on the northeast side of Campo Road. On the southwest side of Campo Road, there is a gap in the sidewalk between the SR-94 ramps across the bridge.

Sidewalks are generally 6 feet wide along Campo Road, however they are reduced to as little as 3 feet where transit stops have benches

Kenwood Drive – Within the study area, sidewalks are provided on the southeast side of Kenwood Drive with the exception of approximately 185' between Kenora Drive and Campo Road. There are no sidewalks on the northwest side of Kenwood Drive.

Conrad Drive – Within the study area, sidewalks are provided on both sides of the street between Campo Road and the north boundary of Spring Valley Middle School. There are no sidewalks on Conrad Drive north of the school.

Bonita Street – Within the study area, sidewalks are provided on both sides of the street between Buena Vista Drive and San Juan Street.

Barcelona Street – Within the study area, sidewalks are provided on both sides of the street between Buena Vista Drive and San Juan Street. There are no sidewalks on Barcelona Street south of Buena Vista Drive.

Cordoba Avenue – Within the study area, sidewalks are provided on both sides of the street between Buena Vista Drive and San Juan Street.

Granada Avenue – Within the study area, sidewalks are provided on both sides of the street between Buena Vista Drive and Dolores Street. There are no sidewalks on Granada Avenue on either side of the street between Dolores Street and Buena Vista Drive.

Casa de Oro Boulevard – Within the study area, sidewalks are provided on both sides of the street between Campo Road and San Juan Street. East of San Juan Street sidewalks are intermittent within the residential neighborhoods with many gaps.

2.3.2 Crosswalks

Standard marked crosswalks are provided at all signalized intersections with the exception of the intersection of Campo Road and Barcelona Street. At the intersections of Campo Road at Conrad Drive and Bonita Street, marked crosswalks are only provided across Campo Road and do not exist across the minor streets. Throughout the corridor, many of the crosswalk pavement markings are beginning to fade and need to be restriped.

Near Spring Valley Middle School, there are two mid-block, controlled crossings with flashing beacon warnings on Conrad Drive at the north and south limits of the school. These locations are striped as continental crosswalks with pedestrian push buttons that control the overhead flashing beacons as well as ADA compliant ramps with truncated domes.

At the easterly end of the study area, there are continental crosswalks across Casa de Oro at San Juan Street as well as across Ramona Drive at Casa de Oro. These locations, however, do not have any ramps and pedestrians must step off of the curb into the street.



Legend

- = Existing Sidewalk
- = Ped. Ramp
- = Ped. Ramp with Truncated Domes
- = Marked Crosswalk
- = Signal Controlled Intersection
- = Stop Controlled Intersection
- = Ped. Push Button (non-ADA)
- = Ped. Push Button (ADA)
- = Ped. Signal Head
- = Ped. Signal Head with Countdown
- = AM / PM Peak Hour Ped. Volumes
- = Bus Stop



Not to Scale

Michael Baker
INTERNATIONAL

January 2020
H:\PDATA\175688_Casa De Oro\Traffic\Exhibits

Existing Pedestrian Facilities & AM/PM Peak Hour Pedestrian Volumes

Exhibit 6a



Legend

- = Existing Sidewalk
- = Ped. Ramp
- = Ped. Ramp with Truncated Domes
- = Marked Crosswalk
- = Signal Controlled Intersection
- = Stop Controlled Intersection

- = Ped. Push Button (non-ADA)
- = Ped. Push Button (ADA)
- = Ped. Signal Head
- = Ped. Signal Head with Countdown
- = AM / PM Peak Hour Ped. Volumes
- = Bus Stop



Not to Scale

Michael Baker
INTERNATIONAL

January 2020
H:\PDATA\175688_Casa De Oro\Traffic\Exhibits

Existing Pedestrian Facilities & AM/PM Peak Hour Pedestrian Volumes

Exhibit 6b

Matchline Exhibit 6c



Legend

- = Existing Sidewalk
- = Ped. Ramp
- = Ped. Ramp with Truncated Domes
- = Marked Crosswalk
- = Signal Controlled Intersection
- = Stop Controlled Intersection

- = Ped. Push Button (non-ADA)
- = Ped. Push Button (ADA)
- = Ped. Signal Head
- = Ped. Signal Head with Countdown
- = AM / PM Peak Hour Ped. Volumes
- = Bus Stop



Not to Scale

Michael Baker
INTERNATIONAL

January 2020
H:\PDATA\175688_Casa De Oro\Traffic\Exhibits

Existing Pedestrian Facilities & AM/PM Peak Hour Pedestrian Volumes

Exhibit 6c



Legend

- = Existing Sidewalk
- ▲ = Ped. Ramp
- = Ped. Ramp with Truncated Domes
- = Marked Crosswalk
- = Signal Controlled Intersection
- = Stop Controlled Intersection
- = Ped. Push Button (non-ADA)
- = Ped. Push Button (ADA)
- = Ped. Signal Head
- = Ped. Signal Head with Countdown
- #/# = AM / PM Peak Hour Ped. Volumes
- = Bus Stop



Not to Scale

Michael Baker
INTERNATIONAL

January 2020
H:\PDATA\175688_Casa De Oro\Traffic\Exhibits

Existing Pedestrian Facilities & AM/PM Peak Hour Pedestrian Volumes

Exhibit 6d



Legend

- = Existing Sidewalk
- = Ped. Ramp
- = Ped. Ramp with Truncated Domes
- = Marked Crosswalk
- = Signal Controlled Intersection
- = Stop Controlled Intersection
- = Ped. Push Button (non-ADA)
- = Ped. Push Button (ADA)
- = Ped. Signal Head
- = Ped. Signal Head with Countdown
- = AM / PM Peak Hour Ped. Volumes
- = Bus Stop




Not to Scale

Michael Baker
INTERNATIONAL

January 2020
H:\PDATA\175688_Casa De Oro\Traffic\Exhibits

Existing Pedestrian Facilities & AM/PM Peak Hour Pedestrian Volumes

Exhibit 6e



Legend

- = Existing Sidewalk
- = Ped. Ramp
- = Ped. Ramp with Truncated Domes
- = Marked Crosswalk
- = Signal Controlled Intersection
- = Stop Controlled Intersection

- = Ped. Push Button (non-ADA)
- = Ped. Push Button (ADA)
- = Ped. Signal Head
- = Ped. Signal Head with Countdown
- = AM / PM Peak Hour Ped. Volumes
- = Bus Stop




Not to Scale

Michael Baker
INTERNATIONAL

January 2020
H:\PDATA\175688_Casa De Oro\Traffic\Exhibits

Existing Pedestrian Facilities & AM/PM Peak Hour Pedestrian Volumes

Exhibit 6f



Legend

- = Existing Sidewalk
- = No Sidewalk
- ▲ = Existing Driveways



Not to Scale

Michael Baker
INTERNATIONAL

January 2020
H:\PDATA\175688_Casa De Oro\Traffic\Exhibits

Driveway Locations on Campo Road

Exhibit 7

2.3.3 ADA Facilities

The majority of the signalized intersections within the study area have controlled crossings as discussed above; however, these crossings are only partially ADA compliant. It should be noted that none of these crossings have audible cues or any other non-visual indicators.

Exhibits 6a-6f show the existing pedestrian facilities and include the following factors that have been considered in evaluating whether a crossing is considered ADA compliant:

TABLE 5 - ADA FACTORS

ADA Facility	Evaluation Factor
Pedestrian Ramp	Presence of Truncated Domes
Pedestrian Push Button	2" Diameter
Pedestrian Signal Head	Presence of Countdown Timer

Along Campo Road, the following intersections have truncated domes:

- Campo Road / Kenwood Drive – Pedestrian Refuge (southwest corner) only
- Campo Road / Barcelona Street – Northwest and Southwest corners only
- Campo Road / Granada Avenue / Casa de Oro Boulevard – Southwest and Southeast corners only

It should be noted that the northeast and southeast corners of intersection of Campo Road and Barcelona Street do not have any pedestrian ramps for the north/south crossing of Campo Road. There are pushbuttons and pedestrian signal heads, but no ramps.

The presence of ADA compliant pedestrian push buttons that are considered “accessible” (2 inches in diameter) are intermittent within the study area. Of the 36 pedestrian push buttons on Campo Road between Kenwood Drive and Granada Avenue / Casa de Oro Boulevard, only 13 buttons are “accessible”.


The presence of countdown timers on pedestrian signal heads are prevalent within the study area. Of the 36 pedestrian signal heads on Campo Road between Kenwood Drive and Granada Avenue / Casa de Oro Boulevard, 27 signal heads have a countdown timer. The only location without countdown timers in the study area is at Campo Road and Barcelona Street.

2.4 EXISTING BICYCLE FACILITIES

Existing peak hour bicycle activity was recorded on Tuesday, November 12, 2019. Based on existing counts during the AM peak hour, bicycle activity peaks near the southern extents of study area on Kenwood Drive (5 bicycles northbound). In the PM Peak hour, bicycle activity peaks near Kenora Drive (4 bicycles on westbound Kenora).

Within the study area, Class II bike lanes are provided on Kenwood Drive and on Campo Road on both sides of the street. These bike lanes are consistently 5 feet in width with the exception of a portion of Kenwood Drive between Kenora Drive and Campo Road where the bike lane is reduced to 4 feet on the east side. There are no buffers separating bicyclists from vehicles on Kenwood Drive or Campo Road.

Exhibit 8 shows the existing bicycle facilities as well as the peak hour bicyclist volumes.



Not to Scale

Michael Baker
INTERNATIONAL

Existing Bicycle Facilities & Cyclist Peak Hour Volumes

January 2020
H:\PDATA\175688_Casa De Oro\Traffic\Exhibits

Exhibit 8

2.5 EXISTING TRANSIT FACILITIES

The Metropolitan Transit System (MTS) operates the local bus service within the Valle de Oro Community. MTS Route 855 travels along Campo Road as shown in [Exhibit 9](#) connecting La Mesa, Casa de Oro, Spring Valley, and Rancho San Diego. Destinations on Route 855 include Campo Road, Casa de Oro Plaza, Monte Vista High School, and Sweetwater Springs Boulevard. The bus route travels between the Spring Street Trolley Station (with connections to Route 851 and the Orange Line Trolley), and Rancho San Diego (with connections to Route 856 at Jamacha Boulevard and Lamplighter Village Drive).

Full service is provided Monday through Friday with reduced service on weekends and holidays. According to the MTS website, the average headways on a weekday is approximately 30 minutes between 6:04 AM and 10:51 PM in the eastbound direction. In the westbound direction, the bus operates between 5:02 AM and 9:19 PM with approximately 30 minute headways.

Within the study area, there are 14 bus stops along Campo Road (7 eastbound & 7 westbound). None of the bus stop locations have shelters or maps/wayfinding information. The following amenities are provided:


- Trash Receptacle (7 of 14 locations)
- Bench Seating (11 of 14 locations)
- Lighting (6 of 14 locations)


None of the bus stop locations have dedicated lighting, however 6 of the 14 locations have adjacent street lights or traffic signal poles with a luminaire mast arm.

The available amenities at each bus stop are summarized in [Table 6](#) and [Exhibit 10](#).

TABLE 6 - EXISTING BUS STOP AMENITIES ALONG CAMPO ROAD

ID	Bus Stop	Direction	Available Amenities			
			Sign	Trash Receptacle	Bench	Lighting
1	Kenwood Drive	EB	✓	✓		
2	Kenwood Drive	WB	✓	✓		
3	Conrad Drive	EB	✓		✓	✓
4	Conrad Drive	WB	✓		✓	
5	Bonita Street	EB	✓		✓	✓
6	Bonita Street	WB	✓	✓	✓	✓
7	Barcelona Street	EB	✓			✓
8	Barcelona Street	WB	✓		✓	
9	Granada Avenue	EB	✓	✓	✓	✓
10	Granada Avenue	WB	✓	✓	✓	
11	Agua Dulce Boulevard	SB	✓		✓	
12	Agua Dulce Boulevard	NB	✓		✓	✓
13	Sweetwater Springs @ Campo Road	SB	✓	✓	✓	
14	Sweetwater Springs @ Del Rio	NB	✓	✓	✓	





Not to Scale

3 EXISTING PARKING ASSESSMENT

3.1 DATA COLLECTION

A detailed parking utilization survey was conducted in and around the Casa de Oro community on Friday, December 13, 2019. The counts were conducted in December to document the peak season parking demand. The parking survey was conducted for 7 hours from 10:00 AM to 5:00 PM with utilization data collected every hour.

Exhibits 11a and **11b** show the parking survey zones included in the survey. For the purposes of this study, the study area was broken up into a total of 72 parking survey zones. The general extents of the survey included 60 off-street parking lots on non-residential parcels along Campo Road between Rodgers Road and Granada Avenue / Casa de Oro Boulevard. In addition, 12 road segments with on-street parking block faces were included along both sides of the following minor streets:

- Conrad Avenue (Campo Road to San Juan Street)
- Bonita Street (Dolores Street to San Juan Street)
- Barcelona Street (Dolores Street to San Juan Street)
- Cordoba Avenue (Dolores Street to San Juan Street)
- Granada Avenue (Dolores Street to San Juan Street)

Appendix C contains detailed parking inventory and survey data.

3.2 PARKING SURVEY

3.2.1 Parking Inventory

The survey included an inventory of the existing non-residential parking facilities within the study area. The parking inventory was broken down into different types of parking including regular parking spaces, ADA spaces (including van), and restricted spaces (i.e. temporary parking, customer only, etc.). **Table 7** summarizes the parking inventory. As shown, The parking survey determined there is a total parking supply of 175 on-street public parking spaces and 1,794 off-street parking spaces within the study area.

Occupied spaces were recorded each hour within each off-street parking lot as well as the identified on-street block faces.

TABLE 7 – EXISTING PARKING INVENTORY

Parking Type		Total Inventory
On-Street		175
Off-Street	Regular	1,607
	ADA	62
	ADA - Van	25
	Customer Only	16
	Time Restricted	55
	Other ⁽¹⁾	29
Sub-Total Off-Street		1,794
Total Parking Supply		1,969



Legend

- = On-Street Parking
- = Off-Street Parking
- ##** = Parking Zone ID




Not to Scale

Michael Baker
INTERNATIONAL

January 2020
H:\PDATA\175688_Casa De Oro\Traffic\Exhibits

Parking Survey Zones Area 1

Exhibit 11a



Legend

- = On-Street Parking
- = Off-Street Parking
- ##** = Parking Zone ID



Not to Scale

Michael Baker
INTERNATIONAL

January 2020
H:\PDATA\175688_Casa De Oro\Traffic\Exhibits

Parking Survey Zones Area 2

Exhibit 11b

3.2.2 Parking Utilization

As part of the survey, occupied spaces were recorded every hour for 7 hours from 10:00 to 5:00 PM for all 72 of the parking survey zones. This data was used to document the parking utilization (percent of available spaces occupied) for each parking survey zone.

Detailed Parking Utilization data is contained in [Appendix F](#).

Based on the parking survey, the lowest combined parking demand for the study area is during the 10:00 AM hour when 35.2% of the total available spaces were utilized. The peak parking demand for the study area occurred at 2:00 PM when 102 on-street parking spaces and 798 off-street parking spaces were occupied for a total of 900 occupied spaces. This represents a combined parking utilization of 45.7%. This shows that during the peak period, less than half of the available parking spaces are occupied within the study area. The survey found that on-street parking utilization (58.3%) was higher than off-street parking utilization (44.5%)

Exhibit 12 and **Table 8** summarizes the peak parking utilization at 2:00 PM on Friday December 13, 2019.


TABLE 8 – PEAK PARKING UTILIZATION

Parking	Inventory	Peak Occupancy ⁽¹⁾	Peak Utilization
On-Street	175	102	58.3%
Off-Street	1794	798	44.5%
Total	1,969	900	45.7%


⁽¹⁾ Peak Parking Demand based on parking survey data from Friday, December 13 at 2:00 PM

It should be noted that the land uses which experience the highest level of occupancy are automotive repair related. That is, a high number of vehicles are temporarily stored on-site while being worked on or awaiting pick-up. In many of these areas, the utilization exceeds 100% because the vehicles are being parked in unmarked spaces.

Additionally, other parking survey zones had vehicles parked in unmarked spaces, including two car-washes. These unmarked spaces were not included in the inventory, but they were counted towards the utilization. Even so, only 7 of the 72 survey zones experienced parking utilization rate greater than 85%.



Source: National Data & Surveying Services



Not to Scale

Michael Baker
INTERNATIONAL

January 2020
H:\PDATA\175688_Casa De Oro\Traffic\Exhibits

Peak Parking Utilization Friday December 13, 2019 - 2:00 PM to 3:00 PM

Exhibit 12

3.3 EXISTING PARKING RATIOS

The Casa de Oro community along the Campo Road corridor is primarily a commercial area with a mix of retail, fast-food, restaurants, and offices. **Table 9** shows the County of San Diego required parking rates per Zoning Ordinance Part 6.

As shown, the parking rates range from 1.0 spaces per 1,000 square feet (KSF) for light manufacturing to 12.0 spaces per KSF for a fast-food restaurant without a drive-thru and averages at 5.2 spaces per KSF.

TABLE 9 – EXISTING COUNTY PARKING REQUIREMENTS

Land Use		Parking Rate
Commercial Office		4.0 / KSF
Bank		4.0 / KSF
Restaurant	Up to 3 KSF	6.0 / KSF
	More than 3 KSF	10.0 / KSF
Fast-Food Restaurant	With Drive-Thru	9.5 / KSF
	Without Drive-Thru	12.0 / KSF
Retail		4.5 / KSF
Liquor Store		3.3 / KSF
Drugstore		3.5 / KSF
Library		3.0 / KSF
General Manufacturing		1.5 / KSF
Light Manufacturing		1.0 / KSF

Source:

San Diego County Zoning Ordinance (Part 6: General Provisions, Section 6762-6764)

KSF = 1,000 square feet

Based on available land parcel information within the study area, existing parking supply rates were calculated for non-residential properties included in the parking inventory. It should be noted that this parcel information did not include specific land use type categories. **Table 10** summarizes the existing parking supply rate per the parking inventory. **Table 10** also compares these supply rates to the actual parking demand that was recorded during the parking utilization survey for the properties included in the analysis.

As shown, the existing parking supply provided by individual parcels ranges from 0.9 spaces per KSF to 10.3 spaces per KSF. When the entire study area is considered as a whole, parking is provided at a rate of 3.3 spaces per KSF (1,786 spaces / 548.43 KSF = 3.3 spaces per KSF). This range of parking supply rates for the study area parcels and the average supply rate is consistent with the County code parking requirements.

The actual parking demand rate according to the parking utilization survey ranges from 0.2 spaces per KSF to 6.7 spaces per KSF. When the entire study area is considered as a whole, parking is utilized at a demand rate of 1.4 spaces per KSF (793 spaces / 548.43 KSF = 1.4 spaces per KSF). Therefore, the actual parking demand is less than half of the parking supply within the study area.

TABLE 10 – EXISTING PARKING SUPPLY & ACTUAL PARKING DEMAND RATES

Parking Zone ID	Floor Area (SF)	Parking Inventory	Existing Parking Supply Rate ⁽¹⁾	Peak Parking Demand ⁽²⁾	Actual Parking Demand Rate ⁽³⁾
13	7,730	11	1.4	4	0.5
14	5,780	11	1.9	4	0.7
15	25,130	109	4.3	27	1.1
16	3,440	25	7.3	4	1.2
17	10,980	25	2.3	15	1.4
18	7,360	29	3.9	11	1.5
19	11,180	36	3.2	19	1.7
20	5,230	16	3.1	7	1.3
21	4,150	35	8.4	7	1.7
22	4,970	11	2.2	1	0.2
23	3,290	3	0.9	1	0.3
24-26	37,090	201	5.4	65	1.8
28-29	27,200	67	2.5	38	1.4
30-33	59,630	308	5.2	135	2.3
34-36	69,010	196	2.8	112	1.6
37	2,920	5	1.7	2	0.7
38	1,040	2	1.9	7	6.7
39	8,790	37	4.2	14	1.6
40-41	38,960	220	5.6	79	2.0
42	2,420	8	3.3	5	2.1
43	17,250	32	1.9	7	0.4
44	5,730	25	4.4	7	1.2
45	18,120	28	1.5	22	1.2
46	5,150	9	1.7	4	0.8
47	3,900	14	3.6	7	1.8
48	15,240	26	1.7	20	1.3
49	13,310	11	0.8	16	1.2
50	6,140	14	2.3	5	0.8
51	2,150	4	1.9	2	0.9
52	20,740	20	1.0	13	0.6
53-54	4,190	17	4.1	7	1.7
55	3,380	15	4.4	5	1.5
56	1,640	9	5.5	9	5.5
58	17,640	18	1.0	10	0.6
59	10,770	18	1.7	17	1.6
61	3,120	5	1.6	2	0.6
62*	4,100	1	0.2	5	1.2
64	2,530	26	10.3	7	2.8
65	2,500	6	2.4	3	1.2
66	18,550	18	1.0	13	0.7
67-68	10,940	31	2.8	3	0.3
69	6,360	9	1.4	7	1.1
70	10,710	26	2.4	23	2.1
71	8,870	22	2.5	15	1.7
72	3,200	28	8.8	12	3.8
Totals	548,430	1,786	3.3	793	1.4

⁽¹⁾ Existing parking rate calculated using total parking inventory per 1,000 SF of floor area (spaces/1,000 SF)

⁽²⁾ Peak Parking Demand based on parking survey data from Friday, December 13 at 2:00 PM

⁽³⁾ Actual parking rate calculated using peak parking utilization per 1,000 SF of floor area (spaces/1,000 SF)

* Not included in total calculations

4 HORIZON YEAR 2035 WITH PROJECT TRAFFIC CONDITIONS


4.1 CASA DE ORO REVITALIZATION

The Campo Road Revitalization Specific Plan covers a 63-acre area (42 acres excluding roads and rights-of-way) centered on Campo Road between Rogers Road and Granada Avenue and serves as the commercial and civic center of the Casa de Oro community. The Specific Plan area primarily encompasses the commercial area extending one block north and south of Campo Road. The Specific Plan intends to transform Campo Road from “drive-through” to a walkable “main street” that is pedestrian-friendly, attractive, and efficient for all modes and becomes the center of the Casa de Oro community and a catalyst for future investment and development.

The proposed Casa De Oro Revitalization proposes to reduce Campo Road between Conrad Drive and Casa De Oro Boulevard / Granada Avenue from 4-lanes to 2-lanes, construct raised medians, provide buffered bike lanes, and construct on-street angled-parking. Additional improvements throughout the corridor include the following intersection modifications:

- Campo Road / Kenwood Drive – Provide improved pedestrian crossings and raised medians to channelize turning vehicles and improve safety
- Campo Road / Conrad Drive – Construct southern roadway extension (New Street A) between Campo Road and existing alley (Kenora Drive extension).
- Campo Road / New Road B – Construct new roadway (New Street B) between San Juan Street and existing alley (Kenora Drive extension). Construct new single-lane roundabout at the intersection with Campo Road.
- Campo Road / New Road C - Construct new roadway (New Street C) between San Juan Street and existing alley (Kenora Drive extension). Construct pedestrian crossing (HAWK or Pedestrian Signal) at the intersection to Campo Road. Northbound and southbound approaches will have restricted left-turn-movements and will be left/right-in and right-out only operations with stop controls on the minor street. Campo Road will have free movements through this intersection.
- Campo Road / Bonita Street – Remove existing signal and construct new single-lane roundabout. Provide improved pedestrian facilities.
- Campo Road / Barcelona Street – Remove existing signal and construct new single-lane roundabout. Provide improved pedestrian facilities.
- Campo Road / Cordoba Avenue – Construct a raised median through this intersection. Northbound and southbound approaches will have restricted left-turn-movements and will be left/right-in and right-out only operations with stop controls on the minor street. Campo Road will have free movements through this intersection.
- Campo Road / Casa De Oro Boulevard / Granada Avenue – Remove existing traffic signal and construct new modified single-lane roundabout with slip-lanes. Provide improved pedestrian facilities.

Exhibit 13 shows the proposed Campo Road Corridor Concept Plan.



Not to Scale

Michael Baker
INTERNATIONAL

Proposed Campo Road Corridor Concept Plan

July 2021
H:\PDATA\175688_Casa De Oro\Traffic\Exhibits\HY 2035+P Exhibits

Exhibit 13

4.1.1 Horizon Year 2035 With Project Study Area

For the purposes of the Horizon Year 2035 With Project traffic conditions assessment, the study area was reduced to include the following intersection locations along the Campo Road study corridor:

- | | |
|---|--|
| 4. Campo Road / Kenwood Drive | 6. Campo Road / Bonita Street |
| 5. Campo Road / Conrad Drive | 7. Campo Road / Barcelona Street |
| A. Campo Road / New Road A | 8. Campo Road / Cordoba Avenue |
| B. Campo Road / New Road B (intersection alternative) | 9. Campo Road / Casa De Oro Boulevard / Granada Avenue |

Exhibit 14 shows the intersection lane geometry shown in the proposed Campo Road corridor plan and assumed in this analysis.

Roadway segment level of service standards based on daily traffic volumes are generally used as long-range planning guidelines to determine the functional classification of roadways and are not always accurate indicators of roadway operations during the more critical peak periods. Typically, the performance and level of service of a roadway segment is heavily influenced by the ability of intersections to accommodate peak hour volumes. Therefore, peak hour signalized and un-signalized intersections within the study area are the focus of Horizon Year 2035 With Project traffic conditions assessment since intersections are most influential in controlling the movement of vehicles along road segments.

4.2 HORIZON YEAR 2035 WITH PROJECT TRAFFIC VOLUMES


In order to derive baseline Horizon Year 2035 traffic volumes, the SANDAG Series 13 model daily traffic volumes available online at the Transportation Forecast Information Center (TFIC) were used to establish a forecast growth trend that was applied to existing traffic volumes. From the Series 13 model, a growth rate of 1.11% was calculated from the model baseline year 2016 to year 2025 and 0.77% from 2025 to 2035. These growth rates were applied to existing traffic volumes for 6 years (2019-2025) and 10 years (2025-2035) respectively to develop Horizon Year 2035 without project AM and PM peak hour volumes.

This traffic forecast methodology represents a conservative estimate of conditions with the currently proposed land use scenarios for the following reasons:

1. The SANDAG Series 13 model includes land use projections that are consistent with the previous Casa de Oro community plan and the previously approved land use plan proposed a significantly higher development density than the currently proposed land use concepts.
2. The year 2035 forecast likely reflects a development level that is less than build-out of the previously approved land use plan. Due to the higher development density reflected in the previous area land use plan, even a partial build out of that land use plan would likely represent development levels that are consistent with full build out of the currently proposed land use concepts.

Based on the proposed roadway network, traffic volumes were applied to New Street A, New Street B, and New Street C utilizing SANDAG trip generation rates, area travel patterns, and engineering judgement. In addition, the restricted left-turns at New Street C and Cordoba Avenue require vehicles to make a U-turn at the adjacent streets. This shift in traffic volumes were accounted for under Horizon Year 2035 With Project Conditions.

Exhibit 15 shows the AM and PM peak hour traffic volumes at the study intersections for Horizon Year 2035 With Project Conditions.




Legend

- = Signal Control Intersection
- = Stop Control Intersection
- TWLTL = Two-Way-Left-Turn-Lane
- = Roundabout
- = Yield Control Movement
- D = Defacto Turn-Lane



Horizon Year 2035 With Project Assumed Lane Geometry



Notes:



4.3 HORIZON YEAR 2035 WITH PROJECT INTERSECTION ANALYSIS

4.3.1 Preferred Campo Road Corridor Concept Plan

The Horizon Year 2035 With Project intersection analysis utilizes the same methodology as the Existing Conditions assessment which conforms to the operational analysis methodology outlined the *Highway Capacity Manual (HCM 6th Edition)* and performed utilizing *Synchro 10* and *Sidra 9* traffic analysis software.

Table 11 summarizes the Horizon Year 2035 With Project Conditions AM/PM peak hour level of service for all study intersections. Detailed analysis worksheets are contained in **Attachment G**.

TABLE 11 - HORIZON YEAR 2035 WITH PROJECT CONDITIONS AM/PM PEAK HOUR LOS

Study Intersection	Traffic Control	Horizon Year 2035 With Project	
		AM	PM
		Delay ¹ - LOS	Delay ¹ - LOS
4 - Campo Road / Kenwood Drive	Signal	17.5 - B	19.9 - B
5 - Campo Road / Conrad Drive	Signal	32.3 - C	20.8 - C
A - Campo Road / New Road A	ROBO	56.8 - F	59.2 - F
B - Campo Road / New Road B	TWSC	22.2 - C	12.3 - B
6 - Campo Road / Bonita Street	ROBO	136.9 - F	15.6 - C
7 - Campo Road / Barcelona Street	ROBO	148.8 - F	13.5 - B
8 - Campo Road / Cordoba Avenue	TWSC	28.8 - D	20.6 - C
9 - Campo Road / Granada Avenue / Casa de Oro Blvd	ROBO	32.6 - D	11.5 - B

Note: Deficient intersection operation indicated in **bold**.

¹ Average seconds of delay per vehicle.

LOS = level of service.

ROBO = Roundabout

TWSC = Two-Way Stop Control

4.4 SUMMARY & RECOMMENDATIONS

With the proposed corridor concept plan and the reduction to one travel lane in each direction, reduced crossing distance, lower vehicular speeds, and additional crosswalks, pedestrian safety and connectivity will be greatly improved. Reallocation of space dedicated to vehicular travel will create a more friendly bicycle community with the addition of buffered bike lanes and will also improve parking access by providing of on-street angled parking.

The results of the Horizon Year 2035 With Project peak hour intersection analysis shows all the study intersections will operate at acceptable levels of service (LOS D or better) with the exception of the following locations:

- Campo Road / New Road A (Roundabout) – LOS F during AM and PM peak hours
- Campo Road / Bonita Street (Roundabout) – LOS F during AM peak hour only
- Campo Road / Barcelona Street (Roundabout) – LOS F during AM peak hour only

The loss of a travel lane on Campo Road will have minimal operational affects in terms of vehicular delay except at some of the westerly located roundabouts where the traffic volumes are higher. While

roundabouts provide numerous benefits for all modes, the reported delay and slower vehicular speeds at the single lane entry roundabouts will also cause longer queues that may extend multiple blocks during peak periods. It should be noted that queueing at roundabouts tends to be dynamic vehicle queueing rather than stopped vehicle queueing. This means that the vehicles in the queue are moving at slow speeds and this type of delay is more tolerable to motorists than stopped delay.

Since the AM traffic patterns consist of a very short peak from 7:00 AM – 8:30 AM and most traffic at that time is comprised of commuters, we do not consider the peak period delays to be significant enough to offset the benefits to all modes offered by the roundabouts during non-peak periods. The PM peak period eastbound traffic peak is less pronounced and extends from 2:30 PM – 6:00 PM. It should be noted that the analysis does not consider the likely diversion of some peak hour commuter traffic shown on Campo Road to San Juan Street and the new east-west street south of Campo Road. This would reduce the peak westbound traffic flows and delay at the affected roundabouts. Additionally, there is an unknown impact of COVID-19 on “work from home” (telecommuting) trends in the future. It is evident that post-COVID-19 conditions will likely include an increase in telecommuting and a reduction in auto travel during the commuter peak hours.

The greatest concern shown in the analysis results is the forecast eastbound queueing on Campo Road at the approach to the proposed roundabout at New Street A during the PM peak hour. The analysis shows these queues will likely extend back into the Campo Road intersections and Conrad Drive and Kenwood Drive. The Kenwood Drive and Conrad Drive intersections serve the highest volumes of traffic along the Campo Road corridor and it is important to maintain adequate traffic flow at these intersections during peak periods.

Based on the operations analysis findings, it is recommended that the type of intersection traffic control at Street A include a non-roundabout alternative and the final intersection control selection be deferred to a later phase of corridor implementation. The alternative intersection configuration and control at Street A could be a Two-Way Stop intersection that only allows left turns from Campo Road onto New Street A (similar to that at New Street B). Once telecommuting trends have stabilized, forecast traffic during the PM peak can be re-visited and the preferred intersection control for Street A can be made.

The poor Level of Service during the AM peak hour at the Bonita Street and Barcelona Street roundabouts primarily affect westbound traffic flow and alternative travel routes are available. Our recommendation at this time is to maintain the roundabouts. If signals are considered by the County as the preferred traffic control for the plan in lieu of the roundabouts, the highest priority for a signal from an operational viewpoint, would be the Bonita Street intersection. This would still maintain two roundabouts at the east end of the corridor and would not mix roundabout and signal-controlled intersections east of Bonita Street. It is generally not desirable to place signals between closely spaced roundabouts due to vehicle queueing concerns.

4.4.1 Operational Assessment of Alternative Intersection Controls

The following proposed intersections that were found to operate at LOS F during one or both of the peak periods were analyzed with an alternative traffic control for comparison and consideration and the results are summarized in **Table 12**. The alternative traffic controls include the following:

- New Road A – Two-Way Stop Control with raised medians to restrict left-turns on the northbound and southbound approach. Similar to assumed controls at New Road B and Cordoba Avenue.
- Bonita Street – Signal control with dedicated left turn lanes on Campo Road and shared left/through/right-lanes on Bonita Street.
- Barcelona Street – Signal control with dedicated left turn lanes on Campo Road and shared left/through/right-lanes on Barcelona Street.

TABLE 12 HORIZON YEAR 2035 WITH PROJECT ALTERNATIVE INTERSECTION OPERATIONS

Study Intersection	Horizon Year 2035 With Project			Horizon Year 2035 With Project Intersection Control Alternatives		
	Traffic Control	AM	PM	Traffic Control	AM	PM
		Delay ¹ - LOS	Delay ¹ - LOS		Delay ¹ - LOS	Delay ¹ - LOS
A - Campo Road / New Road A	ROBO	56.8 - F	59.2 - F	TWSC	25.1 - D	34.6 - D
6 - Campo Road / Bonita Street	ROBO	136.9 - F	15.6 - C	Signal	54.0 - D	18.8 - B
7 - Campo Road / Barcelona Street	ROBO	148.8 - F	13.5 - B	Signal	28.9 - C	21.3 - C

Note: Deficient intersection operation indicated in **bold**.

ROBO = Roundabout

TWSC = Two-Way Stop Control

¹ Average seconds of delay per vehicle.

LOS = level of service.

As shown, the alternative traffic controls are shown to be operating at improved levels of service (LOS D or better).

5 CONCLUSIONS

5.1 EXISTING CONDITIONS SUMMARY

This report summarizes existing transportation conditions within the Casa de Oro community located in the Valle de Oro Community Planning Area of San Diego County. The study area is focused along approximately $\frac{3}{4}$ mile of Campo Road in the commercial corridor between Granada Avenue and Rogers Road and includes five (5) stop-controlled intersections, seven (7) signalized intersections, and ten (10) roadway segments.

Based on existing daily traffic counts, all roadway segments are shown to operate at an acceptable level of service.

The intersection analysis shows that half of the study intersections (6 out of 12) are currently operating at a deficient level of service (LOS E or F) and half are operating at LOS D or better during one or both peak hours.

The existing conditions assessment considers the physical roadway conditions and intersection operations as well as the current pedestrian, bicycle, and transit facilities within the study area.

In addition to the traffic operations analysis, this report also documents the existing parking conditions for on-street and off-street parking facilities serving the non-residential uses within the study area. A parking survey was conducted which collected existing inventory data as well as parking utilization in 1-hour increments for 7 hours. Existing parking supply rates and actual parking demand rates were calculated and compared to parking ratios per County code requirements.

The parking utilization survey shows that the peak parking demand occurs during the 2 o'clock hour where 900 spaces are occupied out of the total 1,969 spaces available. This represents a parking utilization of 45.7%.

5.2 HORIZON YEAR 2035 WITH PROJECT SUMMARY AND RECOMMENDATIONS

With the proposed corridor concept plan and the reduction to one travel lane in each direction, reduced crossing distance, lower vehicular speeds, and additional crosswalks, pedestrian safety and connectivity will be greatly improved. Reallocation of space dedicated to vehicular travel will create a more friendly bicycle community with the addition of buffered bike lanes and will also improve parking access by providing of on-street angled parking.


The results of the Horizon Year 2035 With Project peak hour intersection analysis shows all the study intersections will operate at acceptable levels of service (LOS D or better) with the exception of the following locations:

- Campo Road / New Road A (Roundabout) – LOS F during AM and PM peak hours
- Campo Road / Bonita Street (Roundabout) – LOS F during AM peak hour only
- Campo Road / Barcelona Street (Roundabout) – LOS F during AM peak hour only

These intersections were analyzed with an alternative traffic control for comparison and consideration and are shown to operate at improved levels of service (LOS D or better). The alternative traffic controls include the following:

- New Road A – Two-Way Stop Control with raised medians to restrict left-turns on the northbound and southbound approach. Similar to assumed controls at New Road B and Cordoba Avenue.
- Bonita Street – Signal control with dedicated left turn lanes on Campo Road and shared left/through/right-lanes on Bonita Street.
- Barcelona Street – Signal control with dedicated left turn lanes on Campo Road and shared left/through/right-lanes on Barcelona Street.

Attachment A: Mobility Element Network & Matrix





Mobility Element Network—Valle de Oro Community Planning Area Matrix			
ID ^a	Road Segment	Designation/Improvement #.X = [# of lanes].[roadway classification][improvement]	Special Circumstances
1	Fuerte Drive (SC 2111/SA 920/SC 2060) <u>Segment</u> : La Mesa city limits to Chase Avenue	2.2E Light Collector	Accepted at LOS E <u>Segment</u> : Bancroft Drive to Avocado Boulevard
2	Lemon Avenue (SA 930) <u>Segment</u> : SR-125 to Fuerte Drive	2.1E Community Collector	None
3	Edgewood Drive / Grandview Drive (SC 2115) <u>Segment</u> : Bancroft Drive to Fuerte Drive	2.3B Minor Collector Road Intermittent Turn Lanes—Bancroft Drive to Resmar Road 2.1E Community Collector Resmar Road to Fuerte Drive	None
4	Bancroft Drive <u>Segment</u> : SR-94 to Edgewood Drive	2.1C Community Collector Intermittent Turn Lanes	None
5	Conrad Drive /Resmar Road (SC 2125) <u>Segment</u> : Campo Road to Grandview Drive	2.2E Community Collector	None
6	Campo Road (SC 2118) <u>Segment</u> : La Mesa city limits to SR-94	4.1B Major Road Intermittent Turn Lanes—La Mesa city limits to Camino Paz 2.1C Community Collector Intermittent Turn Lanes—Camino Paz to Rodgers Road 4.2B Boulevard Intermittent Turn Lanes—Rodgers Road to SR-94	Accepted at LOS F <u>Segment</u> : Kenwood Drive to Conrad Drive
7	State Route 94/Campo Road <u>Segment</u> : La Mesa city limits to Jamul/Dulzura Subregion boundary	Freeway/6.1 Expressway La Mesa city limits to Jamacha Road 4.1A Major Road and Interchange with Jamacha Road Raised Median—Jamacha Road / SR-54 to Jamul CPA boundary	Caltrans Facilities Programming Improvements to a four-lane conventional highway programmed in the 2030 RTP (Unconstrained Revenue scenario) Recommended Improvement Ramps to Jamacha Road interchange
8	Kenwood Drive (SC 2122) <u>Segment</u> : SR- 94 to Campo Road	4.1B Major Road Intermittent Turn Lanes	None

Mobility Element Network—Valle de Oro Community Planning Area Matrix			
ID ^a	Road Segment	Designation/Improvement #.X = [# of lanes].[roadway classification][improvement]	Special Circumstances
9	Barcelona Street (SC 2110) <u>Segment</u> : Campo Road to SR- 94	2.2E Light Collector Intersection Improvements	None
10	Avocado Boulevard (SF 1398) <u>Segment</u> : Spring Valley community boundary to El Cajon city limits	4.1B Major Road Intermittent Turn Lanes	None
11	Chase Avenue (SA 910.1) <u>Segment</u> : El Cajon city limits to Hillsdale Road	4.1B Major Road Intermittent Turn Lanes	None
12	Fury Lane (SC 2070/SA 921) <u>Segment</u> : Avocado Boulevard to Jamacha Road	4.1B Major Road Intermittent Turn Lanes—Avocado Boulevard to Wieghorst Way 4.1A Major Road Raised Median—Wieghorst Way to Jamacha Road	None
13	Jamacha Road (SF 1399) <u>Segment</u> : -SR-94 / Campo Road to El Cajon city limits	6.2 Prime Arterial SR 94/Campo Road to Chase Avenue 4.1A Major Road Raised Median—Chase Avenue to El Cajon city limits	Accepted at LOS F <u>Segment</u> : SR-94 / Campo Road to Fury Lane
14	Steele Canyon Road (SC 2050) <u>Segment</u> : Willow Glen Drive to Jamul/Dulzura Subregion boundary	4.1B Major Road Intermittent Turn Lanes	None
15	Jamul Drive (SC 2055) <u>Segment</u> : Steele Canyon Road to Jamul/Dulzura Subregion boundary	2.1C Light Collector Intermittent Turn Lanes	None
16	Hillsdale Road (SC 2030) <u>Segment</u> : Jamacha Road to Willow Glen Drive	2.1C Community Collector Intermittent Turn Lanes	None

**Mobility Element Network—Valle de Oro Community Planning Area Matrix**

ID ^a	Road Segment	Designation/Improvement #. #X = [# of lanes].[roadway classification][improvement]	Special Circumstances
17	Willow Glen Drive (SF 1397) <u>Segment:</u> Jamacha Road to Camino de las Piedras	4.1B Major Road Intermittent Turn Lanes—Jamacha Road to Hillsdale Road 2.1D Community Collector Improvement Options [Unspecified Improvements]—Hillsdale Road to Camino de las Piedras	None
18	Vista Grande Road (SC 2030) <u>Segment:</u> Hillsdale Road to Dehesa Road	2.2E Light Collector	None
19	Jamacha Boulevard SF 1397) <u>Segment:</u> Spring Valley CPA boundary to SR-94 / Campo Road	4.1A Major Road Raised Median	Recommended Improvement Grade-separated interchange with SR-94/Campo Road

a. ID = Roadway segment on Figure M-A-22

Attachment B: Traffic Volume Count Data

CLASSIFICATION

Kenwood Dr Bet. SR-94 WB Ramps & Kenora Dr

Day: Tuesday

Date: 11/12/2019

City: Spring Valley

Project #: CA19_4443_001

Summary

Time	# 1	# 2	# 3	# 4	# 5	# 6	# 7	# 8	# 9	# 10	# 11	# 12	# 13	Total
00:00 AM	0	123	22	0	1	0	0	0	0	0	0	0	0	146
01:00	0	60	6	0	0	0	0	0	0	0	0	0	0	66
02:00	0	46	6	0	0	1	0	0	0	0	0	0	0	53
03:00	0	38	11	0	0	0	0	0	0	0	0	0	0	49
04:00	0	130	26	0	4	0	0	0	0	0	0	0	0	160
05:00	0	385	78	1	11	0	0	0	0	0	0	0	0	475
06:00	0	720	136	1	22	1	0	0	0	0	0	0	0	880
07:00	0	1254	227	3	32	1	0	2	0	0	0	0	0	1519
08:00	0	1256	250	4	36	1	0	1	0	0	0	0	0	1548
09:00	0	898	200	2	27	1	0	0	0	0	0	0	0	1128
10:00	0	929	195	2	33	0	0	0	0	0	0	0	0	1159
11:00	1	945	200	1	32	0	0	0	0	0	0	0	0	1179
12:00 PM	2	1128	224	1	32	3	0	0	0	0	0	0	0	1390
13:00	1	1299	259	2	31	0	0	0	0	0	0	0	0	1592
14:00	0	1426	282	2	43	0	0	2	0	0	0	0	0	1755
15:00	1	1354	287	2	46	1	0	1	0	0	0	0	0	1692
16:00	0	1241	248	0	35	0	0	0	0	0	0	0	0	1524
17:00	0	1261	233	2	28	0	0	2	0	0	0	0	0	1526
18:00	0	1063	178	1	23	1	0	1	0	0	0	0	0	1267
19:00	0	778	134	0	15	0	0	0	0	0	0	0	0	927
20:00	0	629	110	0	14	0	0	0	0	0	0	0	0	753
21:00	0	500	85	0	8	0	0	0	0	0	0	0	0	593
22:00	0	325	53	0	9	0	0	0	0	0	0	0	0	387
23:00	0	190	29	0	4	0	0	0	0	0	0	0	0	223
Totals	5	17978	3479	24	486	10		9						21991
% of Totals	0%	82%	16%	0%	2%	0%		0%						100%

AM Volumes	1	6784	1357	14	198	5	0	3	0	0	0	0	0	8362
% AM	0%	31%	6%	0%	1%	0%		0%						38%
AM Peak Hour	11:00	08:00	08:00	08:00	08:00	02:00		07:00						08:00
Volume	1	1256	250	4	36	1		2						1548
PM Volumes	4	11194	2122	10	288	5	0	6	0	0	0	0	0	13629
% PM	0%	51%	10%	0%	1%	0%		0%						62%
PM Peak Hour	12:00	14:00	15:00	13:00	15:00	12:00		14:00						14:00
Volume	2	1426	287	2	46	3		2						1755
Directional Peak Periods			AM 7-9			NOON 12-2			PM 4-6			Off Peak Volumes		
All Classes			Volume		%	Volume		%	Volume		%	Volume		%
			3067	↔	14%	2982	↔	14%	3050	↔	14%	12892	↔	59%

Classification Definitions

1 Motorcycles	4 Buses	7 >=4-Axle Single Units	10 >=6-Axle Single Trailers	13 >=7-Axle Multi-Trailers
2 Passenger Cars	5 2-Axle, 6-Tire Single Units	8 <=4-Axle Single Trailers	11 <=5-Axle Multi-Trailers	
3 2-Axle, 4-Tire Single Units	6 3-Axle Single Units	9 5-Axle Single Trailers	12 6-Axle Multi-Trailers	

DAILY TOTALS					NB	SB						EB	WB						To
					10,423	11,568						0	0						21,
AM Period	NB	SB	EB	WB	TOTAL		PM Period	NB	SB	EB	WB	TOTAL		TO					
00:00	26	19	0	0	45		12:00	158	173	0	0	331							
00:15	27	11	0	0	38		12:15	165	173	0	0	338							
00:30	23	23	0	0	46		12:30	162	183	0	0	345							
00:45	10	86	7	60	0	0	12:45	203	688	173	702	0	0	376					
01:00	10	13	0	0	23		13:00	161	262	0	0	423							
01:15	10	8	0	0	18		13:15	143	239	0	0	382							
01:30	8	3	0	0	11		13:30	177	209	0	0	386							
01:45	10	38	4	28	0	0	13:45	200	681	201	911	0	0	401					
02:00	6	4	0	0	10		14:00	204	222	0	0	426							
02:15	4	4	0	0	8		14:15	215	239	0	0	454							
02:30	11	16	0	0	27		14:30	215	248	0	0	463							
02:45	5	26	3	27	0	0	14:45	193	827	219	928	0	0	412					
03:00	6	7	0	0	13		15:00	188	233	0	0	421							
03:15	5	5	0	0	10		15:15	205	247	0	0	452							
03:30	5	11	0	0	16		15:30	204	212	0	0	416							
03:45	5	21	5	28	0	0	15:45	187	784	216	908	0	0	403					
04:00	8	14	0	0	22		16:00	197	164	0	0	361							
04:15	11	25	0	0	36		16:15	195	194	0	0	389							
04:30	12	36	0	0	48		16:30	196	197	0	0	393							
04:45	19	50	35	110	0	0	16:45	187	775	194	749	0	0	381					
05:00	22	51	0	0	73		17:00	196	203	0	0	399							
05:15	29	70	0	0	99		17:15	192	192	0	0	384							
05:30	43	85	0	0	128		17:30	191	184	0	0	375							
05:45	56	150	119	325	0	0	17:45	194	773	174	753	0	0	368					
06:00	78	128	0	0	206		18:00	174	154	0	0	328							
06:15	74	133	0	0	207		18:15	173	164	0	0	337							
06:30	90	128	0	0	218		18:30	162	151	0	0	313							
06:45	119	361	130	519	0	0	18:45	133	642	156	625	0	0	289					
07:00	124	194	0	0	318		19:00	132	118	0	0	250							
07:15	154	167	0	0	321		19:15	130	129	0	0	259							
07:30	227	195	0	0	422		19:30	113	102	0	0	215							
07:45	225	730	233	789	0	0	19:45	98	473	105	454	0	0	203					
08:00	183	250	0	0	433		20:00	99	85	0	0	184							
08:15	174	209	0	0	383		20:15	94	107	0	0	201							
08:30	169	247	0	0	416		20:30	113	94	0	0	207							
08:45	126	652	190	896	0	0	20:45	80	386	81	367	0	0	161					
09:00	134	151	0	0	285		21:00	88	77	0	0	165							
09:15	135	127	0	0	262		21:15	82	63	0	0	145							
09:30	107	173	0	0	280		21:30	94	65	0	0	159							
09:45	146	522	155	606	0	0	21:45	74	338	50	255	0	0	124					
10:00	114	159	0	0	273		22:00	59	63	0	0	122							
10:15	144	155	0	0	299		22:15	54	55	0	0	109							
10:30	136	154	0	0	290		22:30	40	39	0	0	79							
10:45	126	520	171	639	0	0	22:45	38	191	39	196	0	0	77					
11:00	135	160	0	0	295		23:00	41	37	0	0	78							
11:15	137	146	0	0	283		23:15	30	21	0	0	51							
11:30	153	137	0	0	290		23:30	27	22	0	0	49							
11:45	154	579	157	600	0	0	23:45	32	130	13	93	0	0	45					
TOTALS	3735	4627			8362		TOTALS	6688	6941										
SPLIT %	44.7%	55.3%			38.0%		SPLIT %	49.1%	50.9%										


DAILY TOTALS					NB	SB						EB	WB						To
					10,423	11,568						0	0						21,
AM Peak Hour	07:30	07:45			07:30		PM Peak Hour	13:45	14:30										
AM Pk Volume	809	939			1696		PM Pk Volume	834	947										
Pk Hr Factor	0.891	0.939			0.926		Pk Hr Factor	0.970	0.955										
7 - 9 Volume	1382	1685	0	0	3067		4 - 6 Volume	1548	1502	0	0								
7 - 9 Peak Hour	07:30	07:45			07:30		4 - 6 Peak Hour	16:00	16:15										
7 - 9 Pk Volume	809	939	0	0	1696		4 - 6 Pk Volume	775	788	0	0								
Pk Hr Factor	0.891	0.939	0.000	0.000	0.926		Pk Hr Factor	0.984	0.970	0.000	0.000								

Project #: CA19_4443_001

City: Spring Valley

Location: Kenwood Dr Bet. SR-94 WB Ramps & Kenora

Date: 11/12/2019



CLASSIFICATION

Campo Rd Bet. Kenwood Dr & Conrad Dr

Day: Tuesday

Date: 11/12/2019

City: Spring Valley

Project #: CA19_4443_002

Summary

Time	# 1	# 2	# 3	# 4	# 5	# 6	# 7	# 8	# 9	# 10	# 11	# 12	# 13	Total
00:00 AM	0	112	17	0	2	0	0	0	0	0	0	0	0	131
01:00	0	53	13	0	1	0	0	0	0	0	0	0	0	67
02:00	0	45	12	0	1	0	0	0	1	0	0	0	0	59
03:00	0	36	9	0	0	0	0	0	0	0	0	0	0	45
04:00	0	110	27	0	3	0	0	0	0	0	0	0	0	140
05:00	0	352	88	4	12	0	0	1	0	0	0	0	0	457
06:00	0	688	158	6	39	0	1	0	2	0	0	0	0	894
07:00	0	1370	278	9	52	4	0	0	0	0	0	0	0	1713
08:00	0	1419	293	6	57	0	0	1	2	0	0	0	0	1778
09:00	0	895	170	5	29	1	0	0	0	0	0	0	0	1100
10:00	0	976	186	6	35	1	0	1	2	0	0	0	0	1207
11:00	0	1017	198	6	39	1	0	1	0	0	0	0	0	1262
12:00 PM	0	1190	217	5	43	2	0	0	0	0	0	0	0	1457
13:00	0	1278	251	8	47	0	1	0	2	0	0	0	0	1587
14:00	0	1407	320	7	57	0	0	0	1	0	0	0	0	1792
15:00	0	1393	284	6	43	2	0	2	0	0	0	0	0	1730
16:00	0	1386	254	6	42	2	0	0	0	0	0	0	0	1690
17:00	0	1425	230	4	34	0	1	1	0	0	0	0	0	1695
18:00	0	1127	207	3	26	1	0	0	0	0	0	0	0	1364
19:00	0	805	141	2	20	0	0	1	2	0	0	0	0	971
20:00	0	621	105	2	13	1	0	0	0	0	0	0	0	742
21:00	0	496	65	2	13	0	0	0	0	0	0	0	0	576
22:00	0	307	48	2	5	0	0	0	0	0	0	0	0	362
23:00	0	200	30	0	5	0	0	0	0	0	0	0	0	235
Totals		18708	3601	89	618	15	3	8	12					23054
% of Totals		81%	16%	0%	3%	0%	0%	0%	0%					100%

AM Volumes	0	7073	1449	42	270	7	1	4	7	0	0	0	0	8853
% AM		31%	6%	0%	1%	0%	0%	0%	0%					38%
AM Peak Hour		08:00	08:00	07:00	08:00	07:00	06:00	05:00	06:00					08:00
Volume		1419	293	9	57	4	1	1	2					1778
PM Volumes	0	11635	2152	47	348	8	2	4	5	0	0	0	0	14201
% PM		50%	9%	0%	2%	0%	0%	0%	0%					62%
PM Peak Hour		17:00	14:00	13:00	14:00	12:00	13:00	15:00	13:00					14:00
Volume		1425	320	8	57	2	1	2	2					1792
Directional Peak Periods			AM 7-9			NOON 12-2			PM 4-6			Off Peak Volumes		
All Classes			Volume		%	Volume		%	Volume		%	Volume		%
			3491	↔	15%	3044	↔	13%	3385	↔	15%	13134	↔	57%

Classification Definitions

1 Motorcycles	4 Buses	7 >=4-Axle Single Units	10 >=6-Axle Single Trailers	13 >=7-Axle Multi-Trailers
2 Passenger Cars	5 2-Axle, 6-Tire Single Units	8 <=4-Axle Single Trailers	11 <=5-Axle Multi-Trailers	
3 2-Axle, 4-Tire Single Units	6 3-Axle Single Units	9 5-Axle Single Trailers	12 6-Axle Multi-Trailers	

DAILY TOTALS					NB	SB	EB					WB						To
					0	0	11,746					11,308						23,
AM Period	NB	SB	EB	WB	TOTAL		PM Period	NB	SB	EB	WB	TOTAL						TO
00:00	0	0	26	17	43		12:00	0	0	199	156	355						355
00:15	0	0	22	8	30		12:15	0	0	207	146	353						353
00:30	0	0	23	19	42		12:30	0	0	194	148	342						342
00:45	0	0	10	81	6	50	12:45	0	0	241	841	166	616	407				407
01:00	0	0	14	12	26		13:00	0	0	182	243	425						425
01:15	0	0	12	7	19		13:15	0	0	145	231	376						376
01:30	0	0	8	5	13		13:30	0	0	209	168	377						377
01:45	0	0	7	41	2	26	13:45	0	0	224	760	185	827	409				409
02:00	0	0	11	5	16		14:00	0	0	229	185	414						414
02:15	0	0	9	4	13		14:15	0	0	240	231	471						471
02:30	0	0	9	11	20		14:30	0	0	263	216	479						479
02:45	0	0	5	34	5	25	14:45	0	0	250	982	178	810	428				428
03:00	0	0	9	6	15		15:00	0	0	228	193	421						421
03:15	0	0	2	3	5		15:15	0	0	254	196	450						450
03:30	0	0	8	7	15		15:30	0	0	239	178	417						417
03:45	0	0	6	25	4	20	15:45	0	0	251	972	191	758	442				442
04:00	0	0	8	15	23		16:00	0	0	254	177	431						431
04:15	0	0	13	21	34		16:15	0	0	250	186	436						436
04:30	0	0	12	29	41		16:30	0	0	230	195	425						425
04:45	0	0	16	49	26	91	16:45	0	0	224	958	174	732	398				398
05:00	0	0	23	51	74		17:00	0	0	261	182	443						443
05:15	0	0	32	64	96		17:15	0	0	242	171	413						413
05:30	0	0	42	77	119		17:30	0	0	229	190	419						419
05:45	0	0	59	156	109	301	17:45	0	0	259	991	161	704	420				420
06:00	0	0	75	131	206		18:00	0	0	217	146	363						363
06:15	0	0	66	128	194		18:15	0	0	229	159	388						388
06:30	0	0	76	150	226		18:30	0	0	194	121	315						315
06:45	0	0	110	327	158	567	18:45	0	0	163	803	135	561	298				298
07:00	0	0	97	237	334		19:00	0	0	165	115	280						280
07:15	0	0	129	255	384		19:15	0	0	150	115	265						265
07:30	0	0	204	270	474		19:30	0	0	130	96	226						226
07:45	0	0	211	641	310	1072	19:45	0	0	117	562	83	409	200				200
08:00	0	0	174	326	500		20:00	0	0	104	83	187						187
08:15	0	0	156	331	487		20:15	0	0	109	73	182						182
08:30	0	0	157	305	462		20:30	0	0	119	82	201						201
08:45	0	0	118	605	211	1173	20:45	0	0	101	433	71	309	172				172
09:00	0	0	116	156	272		21:00	0	0	93	76	169						169
09:15	0	0	143	121	264		21:15	0	0	93	56	149						149
09:30	0	0	122	157	279		21:30	0	0	90	59	149						149
09:45	0	0	146	527	139	573	21:45	0	0	70	346	39	230	109				109
10:00	0	0	128	146	274		22:00	0	0	67	45	112						112
10:15	0	0	172	148	320		22:15	0	0	55	45	100						100
10:30	0	0	146	164	310		22:30	0	0	49	35	84						84
10:45	0	0	147	593	156	614	22:45	0	0	38	209	28	153	66				66
11:00	0	0	143	154	297		23:00	0	0	45	29	74						74
11:15	0	0	169	148	317		23:15	0	0	37	19	56						56
11:30	0	0	158	132	290		23:30	0	0	30	30	60						60
11:45	0	0	198	668	160	594	23:45	0	0	30	142	15	93	45				45
TOTALS			3747	5106	8853		TOTALS			7999	6202							
SPLIT %			42.3%	57.7%	38.4%		SPLIT %			56.3%	43.7%							


DAILY TOTALS					NB	SB	EB					WB						To
					0	0	11,746					11,308						23,
AM Peak Hour			11:45	07:45	07:30		PM Peak Hour			15:15	13:00							
AM Pk Volume			798	1272	1982		PM Pk Volume			998	827							
Pk Hr Factor			0.964	0.961	0.951		Pk Hr Factor			0.982	0.851							
7 - 9 Volume	0	0	1246	2245	3491		4 - 6 Volume	0	0	1949	1436							
7 - 9 Peak Hour			07:30	07:45	07:30		4 - 6 Peak Hour			17:00	16:15							
7 - 9 Pk Volume	0	0	745	1272	1982		4 - 6 Pk Volume	0	0	991	737							
Pk Hr Factor	0.000	0.000	0.883	0.961	0.951		Pk Hr Factor	0.000	0.000	0.949	0.945							

Project #: CA19_4443_002

City: Spring Valley

Location: Campo Rd Bet. Kenwood Dr & Conrad Dr

Date: 11/12/2019



CLASSIFICATION

Campo Rd 250' E/O Conrad Dr

Day: Tuesday
Date: 11/12/2019

City: Spring Valley
Project #: CA19_4443_003

Summary

Time	# 1	# 2	# 3	# 4	# 5	# 6	# 7	# 8	# 9	# 10	# 11	# 12	# 13	Total
00:00 AM	0	106	11	0	0	0	0	0	0	0	0	0	0	117
01:00	0	59	9	0	1	0	0	0	0	0	0	0	0	69
02:00	0	46	10	0	1	0	0	0	0	0	0	0	0	57
03:00	0	37	7	0	0	0	0	0	0	0	0	0	0	44
04:00	0	80	17	0	1	0	0	0	0	0	0	0	0	98
05:00	0	274	53	4	3	0	0	0	0	0	0	0	0	334
06:00	2	594	95	10	21	1	0	1	0	0	0	0	0	724
07:00	1	1154	182	9	24	4	0	0	0	0	0	0	0	1374
08:00	6	1138	166	8	29	2	0	0	4	0	0	0	0	1353
09:00	0	765	109	4	18	2	0	0	0	0	0	0	0	898
10:00	0	831	122	6	22	2	0	1	1	0	0	0	0	985
11:00	0	883	126	6	21	0	0	0	0	0	0	0	0	1036
12:00 PM	3	1014	135	10	23	2	0	0	0	0	0	0	0	1187
13:00	1	1045	146	7	31	1	0	0	1	0	0	0	0	1232
14:00	0	1221	206	10	36	1	0	2	1	0	0	0	0	1477
15:00	1	1206	176	4	22	3	0	0	0	0	0	0	0	1412
16:00	0	1229	179	6	25	4	0	0	0	0	0	0	0	1443
17:00	0	1277	151	4	23	0	0	0	0	0	0	0	0	1455
18:00	2	1014	134	3	15	1	0	0	0	0	0	0	0	1169
19:00	0	730	106	2	10	0	0	0	0	0	0	0	0	848
20:00	0	573	74	2	6	1	0	0	0	0	0	0	0	656
21:00	0	462	46	2	11	0	0	0	0	0	0	0	0	521
22:00	0	300	32	2	3	0	0	0	0	0	0	0	0	337
23:00	0	187	17	0	3	0	0	0	0	0	0	0	0	207
Totals	16	16225	2309	99	349	24		4	7					19033
% of Totals	0%	85%	12%	1%	2%	0%		0%	0%					100%

AM Volumes	9	5967	907	47	141	11	0	2	5	0	0	0	0	7089
% AM	0%	31%	5%	0%	1%	0%		0%	0%					37%
AM Peak Hour	08:00	07:00	07:00	06:00	08:00	07:00		06:00	08:00					07:00
Volume	6	1154	182	10	29	4		1	4					1374
PM Volumes	7	10258	1402	52	208	13	0	2	2	0	0	0	0	11944
% PM	0%	54%	7%	0%	1%	0%		0%	0%					63%
PM Peak Hour	12:00	17:00	14:00	12:00	14:00	16:00		14:00	13:00					14:00
Volume	3	1277	206	10	36	4		2	1					1477
Directional Peak Periods		AM 7-9				NOON 12-2				PM 4-6				Off Peak Volumes
All Classes		Volume		%		Volume		%		Volume		%		Volume
		2727		14%		2419		13%		2898		15%		10989
		↔				↔				↔				↔

Classification Definitions

1 Motorcycles	4 Buses	7 >=4-Axle Single Units	10 >=6-Axle Single Trailers	13 >=7-Axle Multi-Trailers
2 Passenger Cars	5 2-Axle, 6-Tire Single Units	8 <=4-Axle Single Trailers	11 <=5-Axle Multi-Trailers	
3 2-Axle, 4-Tire Single Units	6 3-Axle Single Units	9 5-Axle Single Trailers	12 6-Axle Multi-Trailers	

DAILY TOTALS					NB	SB	EB					WB	To	
					0	0						9,944	9,089	19,
AM Period	NB	SB	EB	WB	TOTAL		PM Period	NB	SB	EB	WB	TO		
00:00	0	0	25	16	41		12:00	0	0	167	136	303		
00:15	0	0	19	9	28		12:15	0	0	173	121	294		
00:30	0	0	17	17	34		12:30	0	0	150	123	273		
00:45	0	0	7	68	7	49	12:45	0	0	190	680	127	507	317
01:00	0	0	12	12	24		13:00	0	0	160	193	353		
01:15	0	0	9	7	16		13:15	0	0	121	169	290		
01:30	0	0	10	4	14		13:30	0	0	164	139	303		
01:45	0	0	11	42	4	27	13:45	0	0	154	599	132	633	286
02:00	0	0	8	6	14		14:00	0	0	176	155	331		
02:15	0	0	5	3	8		14:15	0	0	213	164	377		
02:30	0	0	10	13	23		14:30	0	0	237	160	397		
02:45	0	0	8	31	4	26	14:45	0	0	226	852	146	625	372
03:00	0	0	9	3	12		15:00	0	0	181	155	336		
03:15	0	0	2	3	5		15:15	0	0	209	152	361		
03:30	0	0	9	6	15		15:30	0	0	223	125	348		
03:45	0	0	8	28	4	16	15:45	0	0	209	822	158	590	367
04:00	0	0	4	9	13		16:00	0	0	216	152	368		
04:15	0	0	10	13	23		16:15	0	0	229	153	382		
04:30	0	0	9	22	31		16:30	0	0	195	150	345		
04:45	0	0	13	36	18	62	16:45	0	0	208	848	140	595	348
05:00	0	0	18	35	53		17:00	0	0	232	140	372		
05:15	0	0	25	46	71		17:15	0	0	201	135	336		
05:30	0	0	28	53	81		17:30	0	0	223	155	378		
05:45	0	0	43	114	86	220	17:45	0	0	236	892	133	563	369
06:00	0	0	49	103	152		18:00	0	0	184	117	301		
06:15	0	0	43	108	151		18:15	0	0	190	138	328		
06:30	0	0	72	128	200		18:30	0	0	155	108	263		
06:45	0	0	82	246	139	478	18:45	0	0	160	689	117	480	277
07:00	0	0	75	202	277		19:00	0	0	149	99	248		
07:15	0	0	100	211	311		19:15	0	0	135	108	243		
07:30	0	0	143	236	379		19:30	0	0	112	81	193		
07:45	0	0	170	488	237	886	19:45	0	0	98	494	66	354	164
08:00	0	0	134	258	392		20:00	0	0	97	78	175		
08:15	0	0	137	211	348		20:15	0	0	98	64	162		
08:30	0	0	150	196	346		20:30	0	0	103	63	166		
08:45	0	0	111	532	156	821	20:45	0	0	97	395	56	261	153
09:00	0	0	95	120	215		21:00	0	0	85	68	153		
09:15	0	0	113	110	223		21:15	0	0	80	47	127		
09:30	0	0	89	132	221		21:30	0	0	95	48	143		
09:45	0	0	121	418	118	480	21:45	0	0	65	325	33	196	98
10:00	0	0	100	128	228		22:00	0	0	62	38	100		
10:15	0	0	147	132	279		22:15	0	0	49	44	93		
10:30	0	0	116	126	242		22:30	0	0	47	35	82		
10:45	0	0	126	489	110	496	22:45	0	0	41	199	21	138	62
11:00	0	0	103	133	236		23:00	0	0	42	27	69		
11:15	0	0	137	129	266		23:15	0	0	28	21	49		
11:30	0	0	141	114	255		23:30	0	0	30	21	51		
11:45	0	0	152	533	127	503	23:45	0	0	24	124	14	83	38
TOTALS			3025	4064	7089		TOTALS			6919	5025			
SPLIT %			42.7%	57.3%	37.2%		SPLIT %			57.9%	42.1%			


DAILY TOTALS			NB	SB	EB			WB			To
			0	0							9,944
AM Peak Hour			11:45	07:15	07:30	PM Peak Hour			17:00	13:00	
AM Pk Volume			642	942	1526	PM Pk Volume			892	633	
Pk Hr Factor			0.928	0.913	0.937	Pk Hr Factor			0.945	0.820	
7 - 9 Volume	0	0	1020	1707	2727	4 - 6 Volume	0	0	1740	1158	
7 - 9 Peak Hour			07:45	07:15	07:30	4 - 6 Peak Hour			17:00	16:00	
7 - 9 Pk Volume	0	0	591	942	1526	4 - 6 Pk Volume	0	0	892	595	
Pk Hr Factor	0.000	0.000	0.869	0.913	0.937	Pk Hr Factor	0.000	0.000	0.945	0.972	

Project #: CA19_4443_003

City: Spring Valley

Location: Campo Rd 250' E/O Conrad Dr

Date: 11/12/2019



CLASSIFICATION

Campo Rd Bet. Bonita St & Barcelona St

Day: Tuesday

Date: 11/12/2019

City: Spring Valley

Project #: CA19_4443_004

Summary

Time	# 1	# 2	# 3	# 4	# 5	# 6	# 7	# 8	# 9	# 10	# 11	# 12	# 13	Total
00:00 AM	0	98	10	0	1	0	0	0	0	0	0	0	0	109
01:00	0	55	4	0	0	0	0	0	0	0	0	0	0	59
02:00	0	40	5	0	1	0	0	0	0	0	0	0	0	46
03:00	0	36	7	0	0	0	0	0	0	0	0	0	0	43
04:00	0	57	7	0	1	0	0	0	0	0	0	0	0	65
05:00	0	212	33	2	3	0	0	0	0	0	0	0	0	250
06:00	1	470	60	9	14	2	0	0	2	0	0	0	0	558
07:00	1	1103	134	6	20	4	0	0	0	0	0	0	0	1268
08:00	1	1233	151	5	25	0	0	2	3	0	0	0	0	1420
09:00	1	733	99	5	11	0	0	1	0	0	0	0	0	850
10:00	0	763	109	4	17	1	0	0	2	0	0	0	0	896
11:00	1	857	94	4	22	1	0	1	0	0	0	0	0	980
12:00 PM	3	907	126	6	20	1	0	0	0	0	0	0	0	1063
13:00	1	1020	125	7	21	2	0	0	2	0	0	0	0	1178
14:00	0	1117	161	8	20	2	0	0	0	0	0	0	0	1308
15:00	0	1118	130	4	13	1	0	0	0	0	0	0	0	1266
16:00	2	1119	142	6	15	2	0	0	1	0	0	0	0	1287
17:00	0	1118	112	4	13	0	0	0	0	0	0	0	0	1247
18:00	2	926	95	3	9	1	0	0	0	0	0	0	0	1036
19:00	0	636	65	2	9	0	0	0	0	0	0	0	0	712
20:00	0	496	44	2	5	0	0	0	0	0	0	0	0	547
21:00	0	382	32	2	0	0	0	0	0	0	0	0	0	416
22:00	0	245	20	2	0	0	0	0	0	0	0	0	0	267
23:00	0	161	13	0	2	0	0	0	0	0	0	0	0	176
Totals	13	14902	1778	81	242	17		4	10					17047
% of Totals	0%	87%	10%	0%	1%	0%		0%	0%					100%

AM Volumes	5	5657	713	35	115	8	0	4	7	0	0	0	0	6544
% AM	0%	33%	4%	0%	1%	0%		0%	0%					38%
AM Peak Hour	06:00	08:00	08:00	06:00	08:00	07:00		08:00	08:00					08:00
Volume	1	1233	151	9	25	4		2	3					1420
PM Volumes	8	9245	1065	46	127	9	0	0	3	0	0	0	0	10503
% PM	0%	54%	6%	0%	1%	0%			0%					62%
PM Peak Hour	12:00	16:00	14:00	14:00	13:00	13:00			13:00					14:00
Volume	3	1119	161	8	21	2			2					1308
Directional Peak Periods			AM 7-9			NOON 12-2			PM 4-6			Off Peak Volumes		
All Classes			Volume	%		Volume	%		Volume	%		Volume	%	
			2688	↔	16%	2241	↔	13%	2534	↔	15%	9584	↔	56%

Classification Definitions

1 Motorcycles	4 Buses	7 >=4-Axle Single Units	10 >=6-Axle Single Trailers	13 >=7-Axle Multi-Trailers
2 Passenger Cars	5 2-Axle, 6-Tire Single Units	8 <=4-Axle Single Trailers	11 <=5-Axle Multi-Trailers	
3 2-Axle, 4-Tire Single Units	6 3-Axle Single Units	9 5-Axle Single Trailers	12 6-Axle Multi-Trailers	

DAILY TOTALS					NB	SB	EB					WB						To
					0	0	8,649					8,398						17,
AM Period	NB	SB	EB	WB	TOTAL		PM Period	NB	SB	EB	WB	TOTAL						TO
00:00	0	0	20	18	38		12:00	0	0	148	120	268						268
00:15	0	0	17	9	26		12:15	0	0	149	122	271						271
00:30	0	0	16	11	27		12:30	0	0	131	112	243						243
00:45	0	0	9	62	9	47	12:45	0	0	170	598	111	465	281				
01:00	0	0	11	9	20		13:00	0	0	153	199	352						352
01:15	0	0	7	5	12		13:15	0	0	126	157	283						283
01:30	0	0	9	4	13		13:30	0	0	153	138	291						291
01:45	0	0	9	36	5	23	13:45	0	0	119	551	133	627	252				
02:00	0	0	7	7	14		14:00	0	0	152	159	311						311
02:15	0	0	5	3	8		14:15	0	0	187	162	349						349
02:30	0	0	7	10	17		14:30	0	0	187	133	320						320
02:45	0	0	4	23	3	23	14:45	0	0	203	729	125	579	328				
03:00	0	0	6	0	6		15:00	0	0	184	149	333						333
03:15	0	0	6	4	10		15:15	0	0	198	138	336						336
03:30	0	0	9	5	14		15:30	0	0	191	112	303						303
03:45	0	0	6	27	7	16	15:45	0	0	170	743	124	523	294				
04:00	0	0	4	4	8		16:00	0	0	190	137	327						327
04:15	0	0	8	10	18		16:15	0	0	200	142	342						342
04:30	0	0	5	14	19		16:30	0	0	176	126	302						302
04:45	0	0	7	24	13	41	16:45	0	0	188	754	128	533	316				
05:00	0	0	12	27	39		17:00	0	0	198	130	328						328
05:15	0	0	13	39	52		17:15	0	0	180	109	289						289
05:30	0	0	16	44	60		17:30	0	0	199	141	340						340
05:45	0	0	25	66	74	184	17:45	0	0	177	754	113	493	290				
06:00	0	0	30	77	107		18:00	0	0	152	107	259						259
06:15	0	0	27	93	120		18:15	0	0	165	112	277						277
06:30	0	0	59	87	146		18:30	0	0	152	99	251						251
06:45	0	0	64	180	121	378	18:45	0	0	146	615	103	421	249				
07:00	0	0	67	176	243		19:00	0	0	117	81	198						198
07:15	0	0	85	200	285		19:15	0	0	120	85	205						205
07:30	0	0	107	226	333		19:30	0	0	107	66	173						173
07:45	0	0	159	418	248	850	19:45	0	0	86	430	50	282	136				
08:00	0	0	129	344	473		20:00	0	0	81	61	142						142
08:15	0	0	120	273	393		20:15	0	0	91	54	145						145
08:30	0	0	130	188	318		20:30	0	0	93	46	139						139
08:45	0	0	93	472	143	948	20:45	0	0	77	342	44	205	121				
09:00	0	0	85	119	204		21:00	0	0	73	49	122						122
09:15	0	0	101	107	208		21:15	0	0	66	36	102						102
09:30	0	0	82	117	199		21:30	0	0	72	34	106						106
09:45	0	0	106	374	133	476	21:45	0	0	53	264	33	152	86				
10:00	0	0	101	105	206		22:00	0	0	56	29	85						85
10:15	0	0	125	116	241		22:15	0	0	39	32	71						71
10:30	0	0	98	140	238		22:30	0	0	35	22	57						57
10:45	0	0	109	433	102	463	22:45	0	0	40	170	14	97	54				
11:00	0	0	100	124	224		23:00	0	0	33	17	50						50
11:15	0	0	117	127	244		23:15	0	0	28	18	46						46
11:30	0	0	126	121	247		23:30	0	0	22	22	44						44
11:45	0	0	137	480	128	500	23:45	0	0	21	104	15	72	36				
TOTALS			2595	3949	6544		TOTALS			6054	4449							
SPLIT %			39.7%	60.3%	38.4%		SPLIT %			57.6%	42.4%							


DAILY TOTALS					NB	SB	EB					WB						To
					0	0	8,649					8,398						17,
AM Peak Hour			11:45	07:30	07:30		PM Peak Hour			14:45	13:00							
AM Pk Volume			565	1091	1606		PM Pk Volume			776	627							
Pk Hr Factor			0.948	0.793	0.849		Pk Hr Factor			0.956	0.788							
7 - 9 Volume	0	0	890	1798	2688		4 - 6 Volume	0	0	1508	1026							
7 - 9 Peak Hour			07:45	07:30	07:30		4 - 6 Peak Hour			16:45	16:00							
7 - 9 Pk Volume	0	0	538	1091	1606		4 - 6 Pk Volume	0	0	765	533							
Pk Hr Factor	0.000	0.000	0.846	0.793	0.849		Pk Hr Factor	0.000	0.000	0.961	0.938							

Project #: CA19_4443_004

City: Spring Valley

Location: Campo Rd Bet. Bonita St & Barcelona St

Date: 11/12/2019



CLASSIFICATION

Campo Rd Bet. Cordoba Ave & Granada Ave & Casa De Oro Blvd

Day: Tuesday

Date: 11/12/2019

City: Spring Valley

Project #: CA19_4443_005e

East Bound

Time	# 1	# 2	# 3	# 4	# 5	# 6	# 7	# 8	# 9	# 10	# 11	# 12	# 13	Total
00:00 AM	0	48	2	0	0	0	0	0	0	0	0	0	0	50
01:00	0	14	1	0	0	0	0	0	0	0	0	0	0	15
02:00	0	8	3	0	1	0	0	0	0	0	0	0	0	12
03:00	0	14	5	0	0	0	0	0	0	0	0	0	0	19
04:00	0	33	3	0	1	0	0	0	0	0	0	0	0	37
05:00	0	63	15	0	0	0	0	0	0	0	0	0	0	78
06:00	0	173	26	4	2	1	0	0	0	0	0	0	0	206
07:00	1	293	39	3	7	2	0	0	0	0	0	0	0	345
08:00	0	350	45	2	3	0	0	3	0	0	0	0	0	403
09:00	2	241	37	3	1	0	0	1	0	0	0	0	0	285
10:00	0	291	45	2	6	3	0	0	0	0	0	0	0	347
11:00	0	332	43	2	6	0	0	0	0	0	0	0	0	383
12:00 PM	0	377	47	4	6	0	0	0	0	0	0	0	0	434
13:00	0	377	59	3	8	1	0	0	0	0	0	0	0	448
14:00	0	473	59	2	7	0	0	0	0	0	0	0	0	541
15:00	0	496	56	2	8	0	0	0	0	0	0	0	0	562
16:00	0	464	52	4	5	0	0	0	0	0	0	0	0	525
17:00	0	463	43	2	6	0	0	0	0	0	0	0	0	514
18:00	1	364	40	2	2	0	0	0	0	0	0	0	0	409
19:00	0	247	20	1	0	0	0	0	0	0	0	0	0	268
20:00	0	212	19	1	0	0	0	0	0	0	0	0	0	232
21:00	0	137	11	1	0	0	0	0	0	0	0	0	0	149
22:00	0	103	8	1	0	0	0	0	0	0	0	0	0	112
23:00	0	75	6	0	1	0	0	0	0	0	0	0	0	82
Totals	4	5648	684	39	70	7		4						6456
% of Totals	0%	87%	11%	1%	1%	0%		0%						100%

AM Volumes	3	1860	264	16	27	6	0	4	0	0	0	0	0	2180
% AM	0%	29%	4%	0%	0%	0%		0%						34%
AM Peak Hour	09:00	08:00	08:00	06:00	07:00	10:00		08:00						08:00
Volume	2	350	45	4	7	3		3						403
PM Volumes	1	3788	420	23	43	1	0	0	0	0	0	0	0	4276
% PM	0%	59%	7%	0%	1%	0%								66%
PM Peak Hour	18:00	15:00	13:00	12:00	13:00	13:00								15:00
Volume	1	496	59	4	8	1								562
Directional Peak Periods		AM 7-9		NOON 12-2		PM 4-6		Off Peak Volumes						
All Classes		Volume	%	Volume	%	Volume	%	Volume	%					
		748	↔ 12%	882	↔ 14%	1039	↔ 16%	3787	↔ 59%					

Classification Definitions

1 Motorcycles	4 Buses	7 >=4-Axle Single Units	10 >=6-Axle Single Trailers	13 >=7-Axle Multi-Trailers
2 Passenger Cars	5 2-Axle, 6-Tire Single Units	8 <=4-Axle Single Trailers	11 <=5-Axle Multi-Trailers	
3 2-Axle, 4-Tire Single Units	6 3-Axle Single Units	9 5-Axle Single Trailers	12 6-Axle Multi-Trailers	

CLASSIFICATION

Campo Rd Bet. Granada Ave & Case De Oro Blvd & SR-94 WB Ramps

Day: Tuesday

Date: 11/12/2019

City: Spring Valley

Project #: CA19_4443_006

Summary

Time	# 1	# 2	# 3	# 4	# 5	# 6	# 7	# 8	# 9	# 10	# 11	# 12	# 13	Total
00:00 AM	0	84	12	0	0	0	0	0	0	0	0	0	0	96
01:00	0	33	6	0	0	0	0	0	0	0	0	0	0	39
02:00	0	22	6	0	2	0	0	0	0	0	0	0	0	30
03:00	0	37	7	0	2	0	0	0	0	0	0	0	0	46
04:00	0	68	20	0	3	0	0	0	0	0	0	0	0	91
05:00	1	177	48	2	7	0	0	0	0	0	0	0	0	235
06:00	1	436	100	9	17	1	0	1	0	0	0	0	0	565
07:00	1	881	140	6	25	6	0	0	1	0	0	0	0	1060
08:00	1	907	162	4	18	2	0	0	3	0	0	0	0	1097
09:00	0	528	112	6	9	1	0	0	0	0	0	0	0	656
10:00	2	564	99	4	12	2	0	0	0	0	0	0	0	683
11:00	1	671	117	4	19	1	0	0	0	0	0	0	0	813
12:00 PM	3	697	110	7	16	0	0	0	0	0	0	0	0	833
13:00	0	715	131	6	19	2	0	1	0	0	0	0	0	874
14:00	4	914	151	8	18	1	0	0	0	0	0	0	0	1096
15:00	3	907	148	5	18	0	0	1	0	0	0	0	0	1082
16:00	2	806	115	8	14	1	0	0	0	0	0	0	0	946
17:00	2	813	108	4	13	0	0	0	0	0	0	0	0	940
18:00	1	661	93	3	13	0	0	0	0	0	0	0	0	771
19:00	0	481	60	2	7	0	0	0	0	0	0	0	0	550
20:00	0	372	53	2	5	0	0	0	0	0	0	0	0	432
21:00	0	264	38	2	2	0	0	0	0	0	0	0	0	306
22:00	0	180	21	2	0	0	0	0	0	0	0	0	0	203
23:00	0	131	19	0	2	0	0	0	2	0	0	0	0	154
Totals	22	11349	1876	84	241	17		3	6					13598
% of Totals	0%	83%	14%	1%	2%	0%		0%	0%					100%

AM Volumes	7	4408	829	35	114	13	0	1	4	0	0	0	0	5411
% AM	0%	32%	6%	0%	1%	0%		0%	0%					40%
AM Peak Hour	10:00	08:00	08:00	06:00	07:00	07:00		06:00	08:00					08:00
Volume	2	907	162	9	25	6		1	3					1097
PM Volumes	15	6941	1047	49	127	4	0	2	2	0	0	0	0	8187
% PM	0%	51%	8%	0%	1%	0%		0%	0%					60%
PM Peak Hour	14:00	14:00	14:00	14:00	13:00	13:00		13:00	23:00					14:00
Volume	4	914	151	8	19	2		1	2					1096
Directional Peak Periods		AM 7-9		NOON 12-2		PM 4-6		Off Peak Volumes						
All Classes		Volume	%	Volume	%	Volume	%	Volume	%					
		2157	↔ 16%	1707	↔ 13%	1886	↔ 14%	7848	↔ 58%					

Classification Definitions

1 Motorcycles	4 Buses	7 >=4-Axle Single Units	10 >=6-Axle Single Trailers	13 >=7-Axle Multi-Trailers
2 Passenger Cars	5 2-Axle, 6-Tire Single Units	8 <=4-Axle Single Trailers	11 <=5-Axle Multi-Trailers	
3 2-Axle, 4-Tire Single Units	6 3-Axle Single Units	9 5-Axle Single Trailers	12 6-Axle Multi-Trailers	

DAILY TOTALS					NB	SB	EB					WB						To
					0	0	7,464					6,134						13,
AM Period	NB	SB	EB	WB	TOTAL		PM Period	NB	SB	EB	WB	TOTAL						TO
00:00	0	0	11	13	24		12:00	0	0	111	100	211						211
00:15	0	0	14	13	27		12:15	0	0	121	91	212						212
00:30	0	0	10	17	27		12:30	0	0	108	93	201						201
00:45	0	0	11	46	7	50	18	96	12:45	0	0	117	457	92	376	209		209
01:00	0	0	6	11	17		13:00	0	0	140	99	239						239
01:15	0	0	0	3	3		13:15	0	0	129	103	232						232
01:30	0	0	7	2	9		13:30	0	0	123	84	207						207
01:45	0	0	4	17	6	22	10	39	13:45	0	0	104	496	92	378	196		196
02:00	0	0	6	4	10		14:00	0	0	147	81	228						228
02:15	0	0	5	6	11		14:15	0	0	166	121	287						287
02:30	0	0	2	2	4		14:30	0	0	170	120	290						290
02:45	0	0	4	17	1	13	5	30	14:45	0	0	164	647	127	449	291		291
03:00	0	0	3	2	5		15:00	0	0	143	113	256						256
03:15	0	0	5	1	6		15:15	0	0	161	155	316						316
03:30	0	0	13	1	14		15:30	0	0	147	117	264						264
03:45	0	0	10	31	11	15	21	46	15:45	0	0	132	583	114	499	246		246
04:00	0	0	9	4	13		16:00	0	0	140	105	245						245
04:15	0	0	13	3	16		16:15	0	0	134	85	219						219
04:30	0	0	21	5	26		16:30	0	0	132	109	241						241
04:45	0	0	21	64	15	27	36	91	16:45	0	0	163	569	78	377	241		241
05:00	0	0	36	12	48		17:00	0	0	166	122	288						288
05:15	0	0	27	12	39		17:15	0	0	123	99	222						222
05:30	0	0	50	24	74		17:30	0	0	139	89	228						228
05:45	0	0	45	158	29	77	74	235	17:45	0	0	118	546	84	394	202		202
06:00	0	0	60	37	97		18:00	0	0	127	95	222						222
06:15	0	0	77	55	132		18:15	0	0	115	72	187						187
06:30	0	0	86	64	150		18:30	0	0	105	83	188						188
06:45	0	0	108	331	78	234	186	565	18:45	0	0	88	435	86	336	174		174
07:00	0	0	103	115	218		19:00	0	0	97	60	157						157
07:15	0	0	99	139	238		19:15	0	0	86	69	155						155
07:30	0	0	100	163	263		19:30	0	0	73	50	123						123
07:45	0	0	170	472	171	588	341	1060	19:45	0	0	69	325	46	225	115		115
08:00	0	0	134	199	333		20:00	0	0	67	55	122						122
08:15	0	0	141	143	284		20:15	0	0	49	62	111						111
08:30	0	0	137	120	257		20:30	0	0	66	46	112						112
08:45	0	0	118	530	105	567	223	1097	20:45	0	0	46	228	41	204	87		87
09:00	0	0	93	90	183		21:00	0	0	48	35	83						83
09:15	0	0	81	71	152		21:15	0	0	47	40	87						87
09:30	0	0	77	68	145		21:30	0	0	35	35	70						70
09:45	0	0	97	348	79	308	176	656	21:45	0	0	32	162	34	144	66		66
10:00	0	0	83	74	157		22:00	0	0	30	29	59						59
10:15	0	0	95	70	165		22:15	0	0	25	23	48						48
10:30	0	0	107	85	192		22:30	0	0	22	27	49						49
10:45	0	0	84	369	85	314	169	683	22:45	0	0	28	105	19	98	47		47
11:00	0	0	110	85	195		23:00	0	0	22	20	42						42
11:15	0	0	115	96	211		23:15	0	0	26	16	42						42
11:30	0	0	108	93	201		23:30	0	0	18	12	30						30
11:45	0	0	108	441	98	372	206	813	23:45	0	0	21	87	19	67	40		40
TOTALS			2824	2587	5411		TOTALS			4640	3547							
SPLIT %			52.2%	47.8%	39.8%		SPLIT %			56.7%	43.3%							


DAILY TOTALS					NB	SB	EB					WB						To
					0	0	7,464					6,134						13,
AM Peak Hour			07:45	07:30	07:30		PM Peak Hour			14:00	14:30							
AM Pk Volume			582	676	1221		PM Pk Volume			647	515							
Pk Hr Factor			0.856	0.849	0.895		Pk Hr Factor			0.951	0.831							
7 - 9 Volume	0	0	1002	1155	2157		4 - 6 Volume	0	0	1115	771							
7 - 9 Peak Hour			07:45	07:30	07:30		4 - 6 Peak Hour			16:15	16:30							
7 - 9 Pk Volume	0	0	582	676	1221		4 - 6 Pk Volume	0	0	595	408							
Pk Hr Factor	0.000	0.000	0.856	0.849	0.895		Pk Hr Factor	0.000	0.000	0.896	0.836							

Project #: CA19_4443_006

City: Spring Valley

Location: Campo Rd Bet. Granada Ave & Case De Oro

Date: 11/12/2019



CLASSIFICATION

Conrad Dr N/O Campo Rd

Day: Tuesday
Date: 11/12/2019

City: Spring Valley
Project #: CA19_4443_007

Summary

Time	# 1	# 2	# 3	# 4	# 5	# 6	# 7	# 8	# 9	# 10	# 11	# 12	# 13	Total
00:00 AM	0	25	0	0	0	0	0	0	0	0	0	0	0	25
01:00	0	10	0	0	0	0	0	0	0	0	0	0	0	10
02:00	0	6	1	0	0	0	0	0	0	0	0	0	0	7
03:00	0	7	0	0	0	0	0	0	0	0	0	0	0	7
04:00	0	24	2	0	0	0	0	0	0	0	0	0	0	26
05:00	0	134	10	0	0	0	0	0	0	0	0	0	0	144
06:00	0	223	11	0	0	1	0	0	0	0	0	0	0	235
07:00	0	506	44	1	3	0	0	0	0	0	0	0	0	554
08:00	0	703	61	1	5	0	0	0	0	0	0	0	0	770
09:00	0	236	30	0	1	0	0	0	0	0	0	0	0	267
10:00	0	227	22	2	6	0	0	0	0	0	0	0	0	257
11:00	0	269	8	0	2	1	0	0	0	0	0	0	0	280
12:00 PM	0	322	33	2	6	2	0	0	0	0	0	0	0	365
13:00	0	455	40	0	3	0	0	0	0	0	0	0	0	498
14:00	1	527	54	2	3	0	0	0	0	0	0	0	0	587
15:00	0	338	27	1	0	0	0	0	0	0	0	0	0	366
16:00	0	351	36	0	2	0	0	0	0	0	0	0	0	389
17:00	0	328	30	1	0	0	0	0	0	0	0	0	0	359
18:00	0	202	22	0	0	0	0	0	0	0	0	0	0	224
19:00	1	137	8	0	0	0	0	0	0	0	0	0	0	146
20:00	0	132	12	0	0	0	0	0	0	0	0	0	0	144
21:00	0	85	5	0	0	0	0	0	0	0	0	0	0	90
22:00	0	68	5	0	0	0	0	0	0	0	0	0	0	73
23:00	0	26	3	0	1	0	0	0	0	0	0	0	0	30
Totals	2	5341	464	10	32	4								5853
% of Totals	0%	91%	8%	0%	1%	0%								100%

AM Volumes	0	2370	189	4	17	2	0	0	0	0	0	0	0	2582
% AM		40%	3%	0%	0%	0%								44%
AM Peak Hour		08:00	08:00	10:00	10:00	06:00								08:00
Volume		703	61	2	6	1								770
PM Volumes	2	2971	275	6	15	2	0	0	0	0	0	0	0	3271
% PM	0%	51%	5%	0%	0%	0%								56%
PM Peak Hour	14:00	14:00	14:00	12:00	12:00	12:00								14:00
Volume	1	527	54	2	6	2								587
Directional Peak Periods		AM 7-9		NOON 12-2		PM 4-6		Off Peak Volumes						
All Classes		Volume	%	Volume	%	Volume	%	Volume	%					
		1324	↔ 23%	863	↔ 15%	748	↔ 13%	2918	↔ 50%					

Classification Definitions

1 Motorcycles	4 Buses	7 >=4-Axle Single Units	10 >=6-Axle Single Trailers	13 >=7-Axle Multi-Trailers
2 Passenger Cars	5 2-Axle, 6-Tire Single Units	8 <=4-Axle Single Trailers	11 <=5-Axle Multi-Trailers	
3 2-Axle, 4-Tire Single Units	6 3-Axle Single Units	9 5-Axle Single Trailers	12 6-Axle Multi-Trailers	

DAILY TOTALS					NB	SB	EB				WB	To	
					2,758	3,095	0				0	5,8	
AM Period	NB	SB	EB	WB	TOTAL	PM Period	NB	SB	EB	WB	TOTAL		
00:00	3	3	0	0	6	12:00	43	40	0	0	83		
00:15	6	1	0	0	7	12:15	45	48	0	0	93		
00:30	6	2	0	0	8	12:30	58	40	0	0	98		
00:45	3	18	1	7	4	12:45	58	204	33	161	91		
01:00	2	1	0	0	3	13:00	53	88	0	0	141		
01:15	4	1	0	0	5	13:15	47	78	0	0	125		
01:30	0	1	0	0	1	13:30	51	43	0	0	94		
01:45	1	7	0	3	1	13:45	72	223	66	275	138		
02:00	2	0	0	0	2	14:00	75	60	0	0	135		
02:15	1	1	0	0	2	14:15	79	129	0	0	208		
02:30	2	0	0	0	2	14:30	58	69	0	0	127		
02:45	0	5	1	2	1	14:45	58	270	59	317	117		
03:00	1	2	0	0	3	15:00	50	53	0	0	103		
03:15	0	2	0	0	2	15:15	41	58	0	0	99		
03:30	0	1	0	0	1	15:30	23	49	0	0	72		
03:45	0	1	1	6	1	15:45	43	157	49	209	92		
04:00	0	2	0	0	2	16:00	43	30	0	0	73		
04:15	1	5	0	0	6	16:15	44	49	0	0	93		
04:30	1	7	0	0	8	16:30	54	65	0	0	119		
04:45	3	5	7	21	10	16:45	49	190	55	199	104		
05:00	2	19	0	0	21	17:00	38	62	0	0	100		
05:15	9	13	0	0	22	17:15	36	48	0	0	84		
05:30	8	33	0	0	41	17:30	34	53	0	0	87		
05:45	28	47	32	97	60	17:45	42	150	46	209	88		
06:00	20	39	0	0	59	18:00	27	38	0	0	65		
06:15	29	26	0	0	55	18:15	29	24	0	0	53		
06:30	17	35	0	0	52	18:30	32	21	0	0	53		
06:45	35	101	34	134	69	18:45	26	114	27	110	53		
07:00	37	49	0	0	86	19:00	22	22	0	0	44		
07:15	50	49	0	0	99	19:15	23	17	0	0	40		
07:30	87	79	0	0	166	19:30	21	14	0	0	35		
07:45	84	258	119	296	203	19:45	15	81	12	65	27		
08:00	97	96	0	0	193	20:00	17	13	0	0	30		
08:15	100	113	0	0	213	20:15	18	15	0	0	33		
08:30	122	140	0	0	262	20:30	23	22	0	0	45		
08:45	43	362	59	408	102	20:45	21	79	15	65	36		
09:00	26	35	0	0	61	21:00	18	11	0	0	29		
09:15	29	31	0	0	60	21:15	16	9	0	0	25		
09:30	36	41	0	0	77	21:30	10	9	0	0	19		
09:45	28	119	41	148	69	21:45	9	53	8	37	17		
10:00	28	30	0	0	58	22:00	12	8	0	0	20		
10:15	26	31	0	0	57	22:15	16	6	0	0	22		
10:30	27	48	0	0	75	22:30	10	11	0	0	21		
10:45	27	108	40	149	67	22:45	7	45	3	28	10		
11:00	33	33	0	0	66	23:00	3	1	0	0	4		
11:15	34	37	0	0	71	23:15	9	3	0	0	12		
11:30	30	27	0	0	57	23:30	5	3	0	0	8		
11:45	42	139	44	141	86	23:45	5	22	1	8	6		
TOTALS	1170	1412			2582	TOTALS	1588	1683					
SPLIT %	45.3%	54.7%			44.1%	SPLIT %	48.5%	51.5%					


DAILY TOTALS					NB	SB	EB				WB	To	
					2,758	3,095	0				0	5,8	
AM Peak Hour	07:45	07:45			07:45	PM Peak Hour	13:45	13:45					
AM Pk Volume	403	468			871	PM Pk Volume	284	324					
Pk Hr Factor	0.826	0.836			0.831	Pk Hr Factor	0.899	0.628					
7 - 9 Volume	620	704	0	0	1324	4 - 6 Volume	340	408	0	0			
7 - 9 Peak Hour	07:45	07:45			07:45	4 - 6 Peak Hour	16:00	16:15					
7 - 9 Pk Volume	403	468	0	0	871	4 - 6 Pk Volume	190	231	0	0			
Pk Hr Factor	0.826	0.836	0.000	0.000	0.831	Pk Hr Factor	0.880	0.888	0.000	0.000			

Project #: CA19_4443_007

City: Spring Valley

Location: Conrad Dr N/O Campo Rd

Date: 11/12/2019



CLASSIFICATION

Barcelona St S/O Campo Rd

Day: Tuesday
Date: 11/12/2019

City: Spring Valley
Project #: CA19_4443_008

Summary

Time	# 1	# 2	# 3	# 4	# 5	# 6	# 7	# 8	# 9	# 10	# 11	# 12	# 13	Total
00:00 AM	0	55	1	0	0	0	0	0	0	0	0	0	0	56
01:00	0	34	3	0	0	0	0	0	0	0	0	0	0	37
02:00	0	19	1	0	1	0	0	0	0	0	0	0	0	21
03:00	0	13	3	0	0	0	0	0	0	0	0	0	0	16
04:00	0	30	13	0	2	0	0	0	0	0	0	0	0	45
05:00	0	101	37	0	4	0	0	0	0	0	0	0	0	142
06:00	0	211	23	0	2	0	0	0	0	0	0	0	0	236
07:00	4	477	51	2	6	2	0	1	0	0	0	0	0	543
08:00	1	368	36	0	6	1	0	2	0	0	0	0	0	414
09:00	2	261	31	0	3	0	0	2	1	0	0	0	0	300
10:00	0	247	35	0	11	0	0	0	0	0	0	0	0	293
11:00	3	340	40	4	8	2	0	1	0	0	0	0	0	398
12:00 PM	3	335	45	2	5	2	0	1	1	0	0	0	0	394
13:00	1	362	44	5	2	1	0	1	1	0	0	0	0	417
14:00	1	373	56	2	7	3	0	1	0	0	0	0	0	443
15:00	3	403	61	0	4	0	0	1	1	0	0	0	0	473
16:00	5	435	44	0	2	1	0	1	1	0	0	0	0	489
17:00	2	510	32	1	2	0	0	1	0	0	0	0	0	548
18:00	0	380	30	0	7	3	0	0	0	0	0	0	0	420
19:00	0	291	27	2	1	2	0	0	0	0	0	0	0	323
20:00	0	232	18	0	0	0	0	0	0	0	0	0	0	250
21:00	0	200	18	0	0	0	0	0	0	0	0	0	0	218
22:00	0	122	10	0	1	0	0	0	0	0	0	0	0	133
23:00	0	96	7	0	0	0	0	0	0	0	0	0	0	103
Totals	25	5895	666	18	74	17		12	5					6712
% of Totals	0%	88%	10%	0%	1%	0%		0%	0%					100%

AM Volumes	10	2156	274	6	43	5	0	6	1	0	0	0	0	2501
% AM	0%	32%	4%	0%	1%	0%		0%	0%					37%
AM Peak Hour	07:00	07:00	07:00	11:00	10:00	07:00		08:00	09:00					07:00
Volume	4	477	51	4	11	2		2	1					543
PM Volumes	15	3739	392	12	31	12	0	6	4	0	0	0	0	4211
% PM	0%	56%	6%	0%	0%	0%		0%	0%					63%
PM Peak Hour	16:00	17:00	15:00	13:00	14:00	14:00		12:00	12:00					17:00
Volume	5	510	61	5	7	3		1	1					548
Directional Peak Periods		AM 7-9		NOON 12-2		PM 4-6		Off Peak Volumes						
All Classes		Volume	%	Volume	%	Volume	%	Volume	%					
		957	↔ 14%	811	↔ 12%	1037	↔ 15%	3907	↔ 58%					

Classification Definitions

1 Motorcycles	4 Buses	7 >=4-Axle Single Units	10 >=6-Axle Single Trailers	13 >=7-Axle Multi-Trailers
2 Passenger Cars	5 2-Axle, 6-Tire Single Units	8 <=4-Axle Single Trailers	11 <=5-Axle Multi-Trailers	
3 2-Axle, 4-Tire Single Units	6 3-Axle Single Units	9 5-Axle Single Trailers	12 6-Axle Multi-Trailers	

DAILY TOTALS					NB	SB	EB				WB	To	
					3,459	3,253	0				0	6,7	
AM Period	NB	SB	EB	WB	TOTAL	PM Period	NB	SB	EB	WB	TOTAL		
00:00	5	10	0	0	15	12:00	59	49	0	0	108		
00:15	13	7	0	0	20	12:15	57	44	0	0	101		
00:30	5	9	0	0	14	12:30	43	46	0	0	89		
00:45	4	27	3	29	0	0	57	216	39	178	0	0	96
01:00	3	5	0	0	8	13:00	51	69	0	0	120		
01:15	8	8	0	0	16	13:15	55	58	0	0	113		
01:30	5	2	0	0	7	13:30	49	46	0	0	95		
01:45	1	17	5	20	0	0	43	198	46	219	0	0	89
02:00	3	6	0	0	9	14:00	44	56	0	0	100		
02:15	2	3	0	0	5	14:15	59	54	0	0	113		
02:30	4	0	0	0	4	14:30	60	51	0	0	111		
02:45	2	11	1	10	0	0	56	219	63	224	0	0	119
03:00	3	0	0	0	3	15:00	59	71	0	0	130		
03:15	2	3	0	0	5	15:15	50	71	0	0	121		
03:30	1	1	0	0	2	15:30	52	61	0	0	113		
03:45	5	11	1	5	0	0	40	201	69	272	0	0	109
04:00	5	2	0	0	7	16:00	57	68	0	0	125		
04:15	7	0	0	0	7	16:15	45	77	0	0	122		
04:30	8	2	0	0	10	16:30	54	61	0	0	115		
04:45	16	36	5	9	0	0	51	207	76	282	0	0	127
05:00	21	6	0	0	27	17:00	49	76	0	0	125		
05:15	25	9	0	0	34	17:15	43	95	0	0	138		
05:30	29	5	0	0	34	17:30	66	79	0	0	145		
05:45	38	113	9	29	0	0	61	219	79	329	0	0	140
06:00	44	14	0	0	58	18:00	38	88	0	0	126		
06:15	42	11	0	0	53	18:15	45	56	0	0	101		
06:30	44	16	0	0	60	18:30	46	55	0	0	101		
06:45	42	172	23	64	0	0	42	171	50	249	0	0	92
07:00	80	26	0	0	106	19:00	39	52	0	0	91		
07:15	76	38	0	0	114	19:15	35	39	0	0	74		
07:30	98	50	0	0	148	19:30	41	52	0	0	93		
07:45	109	363	66	180	0	0	32	147	33	176	0	0	65
08:00	79	50	0	0	129	20:00	23	35	0	0	58		
08:15	63	35	0	0	98	20:15	30	46	0	0	76		
08:30	64	34	0	0	98	20:30	21	41	0	0	62		
08:45	60	266	29	148	0	0	23	97	31	153	0	0	54
09:00	50	35	0	0	85	21:00	25	47	0	0	72		
09:15	61	23	0	0	84	21:15	25	30	0	0	55		
09:30	33	30	0	0	63	21:30	13	27	0	0	40		
09:45	44	188	24	112	0	0	20	83	31	135	0	0	51
10:00	53	31	0	0	84	22:00	17	28	0	0	45		
10:15	41	29	0	0	70	22:15	13	23	0	0	36		
10:30	46	29	0	0	75	22:30	11	15	0	0	26		
10:45	41	181	23	112	0	0	15	56	11	77	0	0	26
11:00	41	27	0	0	68	23:00	16	16	0	0	32		
11:15	33	59	0	0	92	23:15	11	11	0	0	22		
11:30	50	49	0	0	99	23:30	10	16	0	0	26		
11:45	85	209	54	189	0	0	14	51	9	52	0	0	23
TOTALS	1594	907			2501	TOTALS	1865	2346					
SPLIT %	63.7%	36.3%			37.3%	SPLIT %	44.3%	55.7%					


DAILY TOTALS					NB	SB	EB				WB	To	
					3,459	3,253	0				0	6,7	
AM Peak Hour	07:00	11:15			07:15	PM Peak Hour	14:15	17:15					
AM Pk Volume	363	211			566	PM Pk Volume	234	341					
Pk Hr Factor	0.833	0.894			0.809	Pk Hr Factor	0.975	0.897					
7 - 9 Volume	629	328	0	0	957	4 - 6 Volume	426	611	0	0			
7 - 9 Peak Hour	07:00	07:15			07:15	4 - 6 Peak Hour	17:00	17:00					
7 - 9 Pk Volume	363	204	0	0	566	4 - 6 Pk Volume	219	329	0	0			
Pk Hr Factor	0.833	0.773	0.000	0.000	0.809	Pk Hr Factor	0.830	0.866	0.000	0.000			

Project #: CA19_4443_008

City: Spring Valley

Location: Barcelona St S/O Campo Rd

Date: 11/12/2019



VOLUME

Casa De Oro Blvd E/O Campo Rd & Granada Ave

Day: Tuesday
Date: 11/12/2019City: Spring Valley
Project #: CA19_4443_009

DAILY TOTALS					NB	SB						EB	WB						Total
					1,176	1,286						0	0						2,462
AM Period	NB	SB	EB	WB	TOTAL		PM Period	NB	SB	EB	WB	TOTAL							
00:00	4	0			4		12:00	26	18			44							
00:15	0	0			0		12:15	31	13			44							
00:30	2	2			4		12:30	24	19			43							
00:45	0	6	0	2	0	8	12:45	23	104	22	72	45	176						
01:00	1	0			1		13:00	25	35			60							
01:15	0	0			0		13:15	22	16			38							
01:30	0	1			1		13:30	23	23			46							
01:45	0	1	0	1	0	2	13:45	26	96	14	88	40	184						
02:00	0	0			0		14:00	22	23			45							
02:15	2	0			2		14:15	32	19			51							
02:30	1	1			2		14:30	16	28			44							
02:45	0	3	0	1	0	4	14:45	26	96	25	95	51	191						
03:00	1	0			1		15:00	19	16			35							
03:15	1	2			3		15:15	33	23			56							
03:30	0	3			3		15:30	25	32			57							
03:45	0	2	1	6	1	8	15:45	29	106	25	96	54	202						
04:00	0	1			1		16:00	33	10			43							
04:15	2	0			2		16:15	26	13			39							
04:30	1	3			4		16:30	26	30			56							
04:45	0	3	2	6	2	9	16:45	32	117	17	70	49	187						
05:00	0	5			5		17:00	29	17			46							
05:15	2	7			9		17:15	18	27			45							
05:30	2	10			12		17:30	30	22			52							
05:45	4	8	9	31	13	39	17:45	25	102	25	91	50	193						
06:00	3	13			16		18:00	20	19			39							
06:15	3	17			20		18:15	14	12			26							
06:30	4	13			17		18:30	20	19			39							
06:45	6	16	21	64	27	80	18:45	19	73	14	64	33	137						
07:00	9	16			25		19:00	10	15			25							
07:15	13	28			41		19:15	9	12			21							
07:30	13	39			52		19:30	14	9			23							
07:45	20	55	46	129	66	184	19:45	17	50	12	48	29	98						
08:00	25	41			66		20:00	11	9			20							
08:15	10	34			44		20:15	11	6			17							
08:30	19	14			33		20:30	18	9			27							
08:45	9	63	13	102	22	165	20:45	9	49	7	31	16	80						
09:00	16	28			44		21:00	8	6			14							
09:15	11	23			34		21:15	9	6			15							
09:30	9	26			35		21:30	9	5			14							
09:45	12	48	21	98	33	146	21:45	6	32	3	20	9	52						
10:00	11	25			36		22:00	6	3			9							
10:15	15	14			29		22:15	3	3			6							
10:30	10	23			33		22:30	4	1			5							
10:45	13	49	21	83	34	132	22:45	8	21	3	10	11	31						
11:00	15	11			26		23:00	2	0			2							
11:15	14	21			35		23:15	1	1			2							
11:30	11	18			29		23:30	0	2			2							
11:45	28	68	20	70	48	138	23:45	5	8	5	8	10	16						
TOTALS	322	593			915		TOTALS	854	693			1547							
SPLIT %	35.2%	64.8%			37.2%		SPLIT %	55.2%	44.8%			62.8%							

DAILY TOTALS					NB	SB						EB	WB						Total
					1,176	1,286						0	0						2,462
AM Peak Hour	11:45	07:30			07:30		PM Peak Hour	15:15	12:45			15:15							
AM Pk Volume	109	160			228		PM Pk Volume	120	96			210							
Pk Hr Factor	0.879	0.870			0.864		Pk Hr Factor	0.909	0.686			0.921							
7 - 9 Volume	118	231	0	0	349		4 - 6 Volume	219	161	0	0	380							
7 - 9 Peak Hour	07:45	07:30			07:30		4 - 6 Peak Hour	16:00	16:30			16:30							
7 - 9 Pk Volume	74	160	0	0	228		4 - 6 Pk Volume	117	91	0	0	196							
Pk Hr Factor	0.740	0.870	0.000	0.000	0.864		Pk Hr Factor	0.886	0.758	0.000	0.000	0.875							

Project #: CA19_4443_009

City: Spring Valley

Location: Casa De Oro Blvd E/O Campo Rd & Granada

Date: 11/12/2019



VOLUME

Ramona Dr Bet. Madrid Way & Casa De Oro Blvd

Date: Tuesday
Date: 11/12/2019

City: Spring Valley
Project #: CA19_4443_010

DAILY TOTALS					NB	SB	EB					WB	Total				
					0	0	599					632	1,231				
AM Period	NB	SB	EB	WB	TOTAL		PM Period	NB	SB	EB	WB	TOTAL					
00:00			0	0	0		12:00			6	8		14				
00:15			2	1	3		12:15			7	9		16				
00:30			0	0	0		12:30			9	4		13				
00:45			1	3	0	1	12:45			24	46	10	31	34	77		
01:00			0	0	0		13:00			34		33		67			
01:15			0	0	0		13:15			9		15		24			
01:30			0	0	0		13:30			12		9		21			
01:45			0	0	0		13:45			11	66	3	60	14	126		
02:00			0	0	0		14:00			7		21		28			
02:15			0	0	0		14:15			7		14		21			
02:30			0	0	0		14:30			12		10		22			
02:45			1	1	0	1	14:45			11	37	13	58	24	95		
03:00			0	0	0		15:00			9		8		17			
03:15			0	0	0		15:15			11		7		18			
03:30			0	0	0		15:30			12		10		22			
03:45			0	0	0		15:45			19	51	18	43	37	94		
04:00			0	0	0		16:00			11		11		22			
04:15			0	1	1		16:15			10		15		25			
04:30			0	0	0		16:30			8		3		11			
04:45			0	1	2	1	16:45			17	46	13	42	30	88		
05:00			0	1	1		17:00			14		15		29			
05:15			1	4	5		17:15			16		6		22			
05:30			0	7	7		17:30			8		13		21			
05:45			2	3	4	16	17:45			10	48	6	40	16	88		
06:00			3	7	10		18:00			8		9		17			
06:15			1	5	6		18:15			11		2		13			
06:30			2	3	5		18:30			5		5		10			
06:45			1	7	4	19	18:45			2	26	6	22	8	48		
07:00			6	12	18		19:00			5		3		8			
07:15			19	11	30		19:15			5		3		8			
07:30			32	27	59		19:30			1		3		4			
07:45			58	115	40	90	19:45			1	12	1	10	2	22		
08:00			18	69	87		20:00			4		0		4			
08:15			6	21	27		20:15			3		0		3			
08:30			6	10	16		20:30			4		3		7			
08:45			7	37	5	105	20:45			2	13	1	4	3	17		
09:00			7	9	16		21:00			3		1		4			
09:15			4	12	16		21:15			3		3		6			
09:30			6	6	12		21:30			1		2		3			
09:45			4	21	6	33	21:45			4	11	1	7	5	18		
10:00			5	3	8		22:00			3		0		3			
10:15			5	5	10		22:15			0		3		3			
10:30			8	3	11		22:30			2		0		2			
10:45			3	21	6	17	22:45			1	6	0	3	1	9		
11:00			5	6	11		23:00			0		0		0			
11:15			5	8	13		23:15			2		0		2			
11:30			8	6	14		23:30			0		1		1			
11:45			6	24	8	28	23:45			3	5	0	1	3	6		
TOTALS	232				311	543	TOTALS	367				321	688				
SPLIT %	42.7%				57.3%	44.1%	SPLIT %	53.3%				46.7%	55.9%				


DAILY TOTALS					NB	SB						EB	WB						Total
					0	0						599	632						1,231
AM Peak Hour			07:15	07:30	07:15		PM Peak Hour			12:45	12:45	12:45							
AM Pk Volume			127	157	274		PM Pk Volume			79	67	146							
Pk Hr Factor			0.547	0.569	0.699		Pk Hr Factor			0.581	0.508	0.545							
7 - 9 Volume	0	0	152	195	347		4 - 6 Volume	0	0	94	82	176							
7 - 9 Peak Hour			07:15	07:30	07:15		4 - 6 Peak Hour			16:30	16:45	16:45							
7 - 9 Pk Volume	0	0	127	157	274		4 - 6 Pk Volume	0	0	55	47	102							
Pk Hr Factor	0.000	0.000	0.547	0.569	0.699		Pk Hr Factor	0.000	0.000	0.809	0.783	0.850							

Project #: CA19_4443_010

City: Spring Valley

Location: Ramona Dr Bet. Madrid Way & Casa De Oro

Date: 11/12/2019




Kenwood Dr & SR-94 EB Ramps


Peak Hour Turning Movement Count

ID: 19-04442-001
City: Spring Valley


Day: Tuesday
Date: 11/12/2019




Total Vehicles (AM)




Total Vehicles (Noon)




Total Vehicles (PM)




Bikes (AM)



Bikes (Noon)




Bikes (PM)



NORTHBOUND

Kenwood Dr




Kenwood Dr & SR-94 WB Ramps


Peak Hour Turning Movement Count

ID: 19-04442-002
City: Spring Valley


Day: Tuesday
Date: 11/12/2019




Total Vehicles (AM)




Total Vehicles (Noon)




Total Vehicles (PM)





Bikes (AM)



Bikes (Noon)



Bikes (PM)




Kenwood Dr & Kenora Dr


Peak Hour Turning Movement Count

ID: 19-04442-003
City: Spring Valley


Day: Tuesday
Date: 11/12/2019




Total Vehicles (AM)




Bikes (AM)




Total Vehicles (Noon)





Bikes (NOON)



Total Vehicles (PM)



Bikes (PM)




Kenwood Dr & Campo Rd


Peak Hour Turning Movement Count

ID: 19-04442-004
City: Spring Valley


Day: Tuesday
Date: 11/12/2019




Total Vehicles (AM)




Bikes (AM)




Total Vehicles (Noon)





Bikes (NOON)



Total Vehicles (PM)



Bikes (PM)




Bonita St & Campo Rd

Peak Hour Turning Movement Count

ID: 19-04442-006
City: Spring Valley

Day: Tuesday
Date: 11/12/2019




Cordoba Ave & Campo Rd


Peak Hour Turning Movement Count

ID: 19-04442-008
City: Spring Valley


Day: Tuesday
Date: 11/12/2019




Total Vehicles (AM)




Total Vehicles (Noon)




Total Vehicles (PM)




Bikes (AM)




Bikes (Noon)



Bikes (PM)



Pedestrians (Crosswalks)



National Data & Surveying Services

Intersection Turning Movement Count

Location: Granada Ave/Casa De Oro Blvd & Campo Rd
City: Spring Valley
Control: Signalized

Project ID: 19-04442-009
Date: 11/12/2019

		Total																										
NS/EW Streets:		Granada Ave/Casa De Oro Blvd					Granada Ave/Casa De Oro Blvd					Campo Rd					Campo Rd											
AM		NORTHBOUND					SOUTHBOUND					EASTBOUND					WESTBOUND					SOUTHBOUND2					TOTAL	
		0 NL	0.5 NT	0.5 NR	0 NU	0 NT2	0 SL	1 ST	0 SR	0 SU	0 SU2	1 EL	2 ET	0 ER	0 EU	0 EL2	1 WL	1.5 WT	0.5 WR	0 WU	0 WR2	0 S2U	0 S2L2	0 S2T2	0 S2R2	0 S2U2		
	7:00 AM	8	0	19	0	0	6	0	1	0	0	1	52	3	0	5	1	109	7	0	9	0	15	0	10	1	247	
	7:15 AM	5	0	16	0	2	7	0	2	0	0	2	62	1	0	15	1	136	3	0	10	0	8	0	21	0	291	
	7:30 AM	7	0	28	0	8	9	0	2	0	0	4	53	5	0	19	2	116	5	0	8	0	9	2	29	5	311	
	7:45 AM	3	1	30	0	10	5	1	2	0	0	3	110	3	0	28	2	143	4	0	21	0	16	6	32	3	423	
	8:00 AM	10	0	13	0	5	15	1	6	0	0	7	84	1	0	14	2	230	10	0	17	0	13	7	56	2	493	
	8:15 AM	3	0	16	0	2	11	1	5	0	0	3	98	0	0	5	3	215	7	0	5	0	11	2	23	4	414	
	8:30 AM	4	0	12	0	2	12	0	3	0	1	0	104	1	0	8	1	114	2	0	7	0	8	1	12	1	293	
	8:45 AM	8	0	15	0	0	4	0	2	0	0	0	73	2	0	7	1	51	2	0	9	0	6	0	11	0	191	
TOTAL VOLUMES:		NL 48	NT 1	NR 149	NU 0	NT2 29	SL 69	ST 3	SR 23	SU 0	SU2 1	EL 20	ET 636	ER 16	EU 0	EL2 101	WL 13	WT 1114	WR 40	WU 0	WR2 86	S2U 0	S2L2 86	S2T2 18	S2R2 194	S2U2 16	TOTAL 2663	
APPROACH %'s:		21.15%	0.44%	65.64%	0.00%	12.78%	71.88%	3.13%	23.96%	0.00%	1.04%	2.59%	82.28%	2.07%	0.00%	13.07%	1.04%	88.91%	3.19%	0.00%	6.86%	0.00%	27.39%	5.73%	61.78%	5.10%		
PEAK HR:		07:30 AM - 08:30 AM																										TOTAL
PEAK HR VOL:		23	1	87	0	25	40	3	15	0	0	17	345	9	0	66	9	704	26	0	51	0	49	17	140	14	1641	
PEAK HR FACTOR:		0.575	0.250	0.725 0.773	0.000	0.625	0.667	0.750	0.625 0.659	0.000	0.000	0.607	0.784	0.450 0.759	0.000	0.589	0.750	0.765	0.650 0.763	0.000	0.607	0.000	0.766	0.607 0.705	0.625	0.700	0.832	


PM		NORTHBOUND					SOUTHBOUND					EASTBOUND					WESTBOUND					SOUTHBOUND2					TOTAL	
		0 NL	0.5 NT	0.5 NR	0 NU	0 NT2	0 SL	1 ST	0 SR	0 SU	0 SU2	1 EL	2 ET	0 ER	0 EU	0 EL2	1 WL	1.5 WT	0.5 WR	0 WU	0 WR2	0 S2U	0 S2L2	0 S2T2	0 S2R2	0 S2U2		
	4:00 PM	1	1	13	0	4	13	0	1	0	0	2	97	7	0	19	3	95	10	0	10	0	8	2	10	1	297	
	4:15 PM	3	2	17	0	2	4	0	2	0	1	1	106	2	0	19	1	77	2	0	14	0	6	2	15	5	281	
	4:30 PM	5	1	9	0	0	8	0	7	0	1	2	111	7	0	21	4	75	1	0	6	0	8	3	12	1	282	
	4:45 PM	5	0	13	0	3	12	2	3	0	0	0	128	2	0	21	5	84	1	0	15	0	8	0	17	1	320	
	5:00 PM	3	0	16	0	3	8	1	1	0	1	0	124	2	0	22	8	73	1	0	7	0	11	1	20	1	303	
	5:15 PM	3	0	7	0	0	8	0	2	0	0	2	100	2	0	21	4	73	8	0	9	0	6	3	16	1	265	
	5:30 PM	2	1	13	0	1	0	0	3	0	0	1	122	3	0	19	2	82	1	0	13	0	14	1	25	1	304	
	5:45 PM	5	1	9	0	5	1	1	1	0	0	0	101	4	0	13	2	54	1	0	12	0	9	0	22	1	242	
TOTAL VOLUMES:		NL 27	NT 6	NR 97	NU 0	NT2 18	SL 54	ST 4	SR 20	SU 0	SU2 3	EL 8	ET 889	ER 29	EU 0	EL2 155	WL 29	WT 613	WR 25	WU 0	WR2 86	S2U 0	S2L2 70	S2T2 12	S2R2 137	S2U2 12	TOTAL 2294	
APPROACH %'s:		18.24%	4.05%	65.54%	0.00%	12.16%	66.67%	4.94%	24.69%	0.00%	3.70%	0.74%	82.24%	2.68%	0.00%	14.34%	3.85%	81.41%	3.32%	0.00%	11.42%	0.00%	30.30%	5.19%	59.31%	5.19%		
PEAK HR:		04:45 PM - 05:45 PM																										TOTAL
PEAK HR VOL:		13	1	49	0	7	28	3	9	0	1	3	474	9	0	83	19	312	11	0	44	0	39	5	78	4	1192	
PEAK HR FACTOR:		0.650	0.250	0.766 0.795	0.000	0.583	0.583	0.375	0.750 0.603	0.000	0.250	0.375	0.926	0.750 0.942	0.000	0.943	0.594	0.929	0.344 0.919	0.000	0.733	0.000	0.696	0.417 0.768	0.780	1.000	0.931	

Campo Rd & SR-94 WB On-Ramps/Agua Dulce Blvd


Peak Hour Turning Movement Count

ID: 19-04442-010
City: Spring Valley


Day: Tuesday
Date: 11/12/2019




Total Vehicles (AM)




Total Vehicles (Noon)




Total Vehicles (PM)




Bikes (AM)




Bikes (Noon)



Bikes (PM)



Pedestrians (Crosswalks)




Campo Rd & SR-94 EB Ramps


Peak Hour Turning Movement Count

ID: 19-04442-011
City: Spring Valley


Day: Tuesday
Date: 11/12/2019




Total Vehicles (AM)




Total Vehicles (Noon)




Total Vehicles (PM)




Bikes (AM)



Bikes (NOON)





Bikes (PM)



NORTHBOUND

Campo Rd





Attachment C: Parking Survey Data

Parking Study**Location:** Spring Valley Parking- On Street**Date:** 12/13/2019**City:** Spring Valley**Day:** Friday

Segment	Street	From	To	Curb	Space	Restrictions	10:00 AM	11:00 AM	12:00 PM	1:00 PM	2:00 PM	3:00 PM	4:00 PM	Note
001 S	San Juan St	Lot 40	Conrad St	Regular	9	Unrestricted	6	8	8	7	8	8	7	
001N	San Juan St	School DWY	Bonita St	Regular	7	Unrestricted	3	5	5	4	4	4	3	
002N	Dolores St	Cordoba Ave	Barcelona St	Regular	10	Unrestricted	9	9	10	10	10	9	9	
002S	Dolores St	Barcelona St	Cordoba Ave	Regular	10	Unrestricted	3	3	7	8	9	7	8	
003N	Dolores St	Granda Ave	Cordoba Ave	Regular	8	Unrestricted	4	4	4	4	5	5	6	
003S	Dolores St	Cordoba Ave	Granda Ave	Regular	8	Unrestricted	4	4	4	4	4	4	4	
004E	Conrad Dr	Campo Rd	San Juan Rd	Regular	7	Unrestricted	4	5	5	4	5	5	5	
004W	Conrad Dr	San Juan St	Campo Rd	Regular	6	Unrestricted	2	4	4	4	4	3	2	
005E	Bonita St	Campo Rd	Bonita St	Regular	7	Unrestricted	3	3	3	4	5	5	4	
005W	Bonita St	San Juan St	Campo Rd	Regular	10	Unrestricted	3	5	5	4	3	3	4	
006E	Bonita St	Dolores St	Campo Rd	Regular	5	Unrestricted	4	5*	5	5*	5*	5*	4	*One vehicle parked illegally in front of driveway (Vehicle not included in occupancy)
006W	Bonita St	Campo Rd	Dolores St	Regular	8	Unrestricted	6	6	6	5	5	5	5	
007E	Barcelona St	Campo Rd	San Juan St	Regular	7	Unrestricted	6	7	6	4	4	4	3	
007W	Barcelona St	San Juan St	Campo Rd	Regular	7	Unrestricted	3	4	4	3	3	3	4	
008 E	Barcelona St	Dolores St	Campo Rd	Regular	5	Unrestricted	5	5	4	3	3	4	4	
008 W	Barcelona St	Campo Rd	Dolores St	Regular	6	Unrestricted	6	6	5	5	5	5	5	
009E	Cordoba Ave	Campo Rd	San Juan St	Regular	8	Unrestricted	1	1	2	2	2	2	1	
009W	Cordoba Ave	San Juan St	Campo Rd	Regular	5	Unrestricted	0	0	0	0	1	1	0	
010E	Cordoba Ave	Dolores St	Campo Rd	Regular	6	Unrestricted	6	6	5	4	4	5	3	
010W	Cordoba Ave	Campo Rd	Dolores St	Regular	8	Unrestricted	4	4	3	4	3	4	2	
011E	Granda Ave	Campo Rd	San Juan St	Regular	8	Unrestricted	6	6	7	8	8	7	6	
011W	Granda Ave	San Juan St	Campo Rd	Regular	5	Unrestricted	3	3	4	4	2	2	2	
012E	Granda Ave	Dolores St	Campo Rd	Regular	8	Unrestricted	1	1	1	0	0	1	0	
012W	Granda Ave	Campo Rd	Dolores St	Regular	7	Unrestricted	0	0	1	0	0	0	0	

Parking Study

Location: Spring Valley Parking- Off Street
City: Spring Valley

Date: 12/13/2019
Day: Friday

Lot	Restriction	Space	10:00 AM	11:00 AM	12:00 PM	1:00 PM	2:00 PM	3:00 PM	4:00 PM	Notes
13	Regular	11	3	2	2	4	4	3	5	
14	Regular	11	3	4	2	4	4	4	5	
15	Regular	103	20	25	35	26	27	17	21	
	HC	4	0	0	1	1	0	0	0	
	HC Van	2	0	0	1	1	0	0	0	
16	Regular	24	3	3	1	2	4	4	6	
	HC Van	1	0	0	0	0	0	0	0	
17	Regular	9	4	6	8	8	5	9	6	
	HC	1	0	1	1	0	0	0	0	
	Round Table	8	2	3	6	6	3	4	4	
	Customer Only	2	1	1	2	2	2	1	1	
	Patient/Customer	5	5	3	3	5	5	5	5	
18	Regular	27	14	14	14	13	11	6	5	
	HC	1	0	0	0	0	0	0	0	
	Reserved for Pastor	1	0	0	1	1	0	0	0	
19	Regular	34	19	22	19	21	19	25	23	
	HC	1	0	0	0	0	0	0	0	
	HC Van	1	0	0	0	0	0	0	0	
20	Regular	15	10	10	8	5	7	9	4	
	HC Van	1	1	0	0	0	0	0	0	
21	Regular	33	9	7	16	6	7	7	8	
	HC	1	0	0	0	0	0	0	0	
	HC Van	1	0	1	0	0	0	0	1	
22	Regular	10	1	1	2	1	1	1	0	
	HC Van	1	0	0	0	0	0	0	0	
23	Regular	2	1	2	1	0	1	2	1	
	HC Van	1	0	0	0	0	0	0	0	
24	Regular	69	15	19	22	22	28	30	28	
	HC	2	0	1	0	0	1	0	0	
	HC Van	2	0	1	0	0	0	1	1	
25	Regular	117	32	36	31	45	36	43	43	
	HC	3	0	0	1	1	0	1	0	
	HC Van	3	0	1	0	0	0	0	1	
26	Regular	5	0	0	0	0	0	0	0	
27	Unmarked Spaces		0	0	0	1	1	1	1	Unmarked inventory (Vehicles using vaccums)
28	Regular	49	23	24	24	24	24	22	21	
	HC	1	0	0	0	0	0	0	0	
	HC Van	1	0	0	0	0	0	0	0	
29	Regular	16	14	15	15	16	14	15	13	
30	Regular	54	5	6	6	6	6	5	5	
31	Regular	89	40	48	45	38	26	23	27	
	HC	8	1	2	3	4	3	3	2	
	Veteran Parking	1	0	1	0	0	1	1	0	
	Family Parking	1	1	0	0	1	1	1	1	
	15 Min (Green)	10	2	1	3	2	4	3	3	
32	Regular	10	2	3	4	4	5	5	4	
	HC Van	1	0	0	0	0	0	0	0	
33	Regular	130	43	55	68	71	85	75	61	
	HC	3	0	0	0	2	3	2	1	
	HC Van	1	0	0	0	1	1	0	0	
34	Regular	20	10	11	11	10	10	10	8	
35	Regular	59	21	27	31	33	35	32	24	
	HC	5	1	2	2	3	3	2	2	
	HC Van	1	0	1	1	0	0	0	0	
36	Regular	109	47	58	59	62	64	61	53	
	HC	1	0	0	1	0	0	0	0	
	HC Van	1	0	0	0	0	0	0	0	
37	Regular	4	1	2	2	1	2	2	1	
	HC Van	1	0	0	0	0	0	0	0	
38	Regular	2	2	1	1	2	2	2	1	
	Unmarked Spaces		3	4	4	4	5	4	4	
39	Regular	35	6	8	10	12	14	15	13	
	HC	1	0	0	1	0	0	0	0	
	HC Van	1	0	0	0	0	0	0	0	
40	Regular	50	7	7	7	6	7	7	6	
41	Regular	118	36	45	49	51	42	38	39	
	HC	7	0	0	0	1	1	2	1	
	20 Min (Green)	45	16	23	25	28	29	29	26	
42	Regular	8	3	4	4	4	5	5	4	

43	Regular	31	8	10	9	7	6	6	7	
	HC	1	0	0	0	1	1	0	0	
44	Regular	22	7	10	9	6	5	7	6	
	HC	2	0	0	0	1	2	1	1	
	HC Van	1	0	0	0	1	0	0	0	
45	Regular	15	3	4	9	12	15	14	11	
	HC	2	0	0	0	1	0	0	0	
	HC Van	1	0	0	0	1	1	1	0	
	La Postas	6	3	4	4	5	6	6	5	
	Pawn Shop (Green)	4	0	0	0	0	0	0	0	
46	Regular	8	0	0	2	4	4	4	3	
	HC Van	1	0	0	0	0	0	0	0	
47	Regular	13	1	2	4	5	7	6	6	
	HC	1	0	0	1	0	0	0	0	
048	Regular	16	5	6	8	10	11	13	10	
	HC	1	0	0	0	1	1	1	0	
	Customer Only	9	1	2	3	5	7	5	4	
	Unmarked Spaces		1	1	1	1	1	0	0	
49	Regular	11	11	11	10	11	11	10	9	
	Unmarked Spaces		2	3	2	2	5	4	3	
50	Regular	14	3	3	4	3	5	4	4	
51	Regular	4	1	1	1	1	2	2	1	
52	Regular	13	10	10	11	9	11	10	9	
	HC	1	0	0	0	0	0	0	0	
	Dental	6	2	2	3	1	2	2	1	
53	Regular	10	4	5	5	3	4	3	3	
54	Regular	6	4	4	3	2	3	2	2	
	HC	1	0	0	0	0	0	0	0	
55	Regular	14	3	5	5	5	5	3	4	
	HC	1	0	0	0	0	0	0	0	
56	Regular	8	6	8	8	8	8	8	8	
	HC	1	1	1	1	1	1	1	1	
57	Regular	6	0	0	0	0	0	0	0	
	HC	1	0	0	0	0	0	0	0	
58	Regular	17	8	10	15	10	10	7	5	
	HC	1	0	0	0	0	0	0	0	
59	Regular	17	13	13	15	17	17	15	15	
	HC	1	0	1	1	1	0	0	0	
060 Dirt	Unmarked Spaces		0	0	0	0	0	0	0	
61	Regular	4	2	2	2	2	2	2	1	
	HC	1	0	0	0	0	0	0	0	
62	HC	1	0	0	0	0	0	0	0	
	Unmarked Spaces		5	5	4	4	5	4	4	
063 Carwash	Unmarked Spaces		3	4	3	3	3	4	2	
64	Regular	25	1	1	5	6	7	5	5	
	HC	1	0	0	1	1	0	0	0	
65	Regular	6	3	3	3	3	3	3	3	
66	Regular	17	11	13	14	14	13	15	11	
	HC	1	0	0	0	0	0	0	0	
67	Regular	16	1	2	2	2	3	2	3	
68	Regular	8	8	8	8	7	7	8	6	
	HC	1	1	1	1	0	0	0	0	
69	Regular	13	2	4	0	2	0	0	0	
	HC	1	0	0	0	0	0	0	0	
	HC Van	1	0	0	0	0	0	0	0	
	Regular	23	23	23	21	23	20	21	19	
70	HC	1	1	1	1	1	0	0	0	
	Reserved	2	1	1	0	1	1	1	0	
	Unmarked Spaces		2	2	1	1	2	0	0	
71	Regular	21	8	10	13	13	15	15	16	
	HC	1	0	0	0	0	0	0	0	
72	Regular	26	7	10	13	11	12	13	11	
	HC	1	1	1	0	0	0	0	0	
	HC Van	1	1	1	0	0	0	0	0	

Attachment D: Existing Traffic Signal Timing Worksheets

	INTERVAL	PHASE TIMING								9	PRE-EMPTION		F																	
		1	2	3	4	5	6	7	8		E		FLAGS	1	2	3	4	5	6	7	8									
0	WALK	1	8	1	9	1	1	1	1	CLK RST	EV SEL	0	PERMIT	1	2		4	5	6									0		
1	DONT WALK	1	17	1	32	1	1	1	1		RR1 CLR	15	RED LOCK	1			4	5										1		
2	MIN GREEN	5	6	1	5	5	5	1	1		EVA DLY	0	YEL LOCK															2		
3	TYPE 3 DET	0	0	0	0	0	0	0	0		EVA CLR	5	V RECALL		2				6									3		
4	ADD/VEH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		EVB DLY	0	P RECALL															4		
5	PASSAGE	2.0	3.0	0.9	3.0	2.0	3.0	0.9	0.9		EVB CLR	5	PED PHASES		2		4											5		
6	MAX GAP	2.0	3.0	0.9	3.0	2.0	3.0	0.9	0.9		EVC DLY	0	RT OLA															6		
7	MIN GAP	2.0	3.0	0.9	3.0	2.0	3.0	0.9	0.9		EVC CLR	5	RT OLB															7		
8	MAX EXT	20	30	9	25	25	30	9	9		EVD DLY	0	DBL ENTRY															8		
9	MAX 2									YR	EVD CLR	5	MAX 2 PHASES															9		
A	MAX 3									MO	MAX EV	255	LAG PHASES	READ ONLY																A
B										DAY	RR2 CLR	15	RED REST															B		
C	REDUCE BY	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	DOW			REST-IN-WALK															C		
D	EVERY	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	HR			MAX 3 PHASES															D		
E	YELLOW	3.6	4.8	3.0	4.3	4.1	4.8	3.0	3.0	MIN			YEL START UP		2				6									E		
F	RED	2.0	1.5	0.0	2.0	1.0	1.5	0.0	0.0	SEC			FIRST PHASE				4											F		
3.5'	PED XING FT		57		112									1	2	3	4	5	6	7	8									
	BIKE XING FT	-	80		-	-	55																							

FOC LONG FAILURE	
FOD SHORT FAILURE	
FOE	30
FOF	5

FCO	3
FC1	3
FC2	10
FCA	0.0
FCB	0.0
FCC	0.0
FCD	0.0

FDO TB SELECT	1
FD3 PED SELECT	0
FD4 7 WIRE	0
FD5 PERMISSIVE	0
FD8 OS SEEKING	1

CO5 FLASH TYPE	1
CC2 DOWNLOAD	1

ENTRIES IN THESE LOCATIONS CAN BE CHANGED IN CC1 FLASH ONLY



C PAGE

		CONTROL PLANS									Y-COORD			LAG PHASE	FLAGS													
		1	2	3	4	5	6	7	8	9		C	D	E	F	1	2	3	4	5	6	7	8					
0	CYCLE LENGTH														LAG FZ FREE		2		4		6		8	0				
1	FZ1 GRN FCTR													GAPOUT CP1	LAG FZ CP 1									1				
2														GAPOUT CP2	LAG FZ CP 2									2				
3	FZ3 GRN FCTR													GAPOUT CP3	LAG FZ CP 3									3				
4	FZ4 GRN FCTR										PERM TIME			GAPOUT CP4	LAG FZ CP 4									4				
5	FZ5 GRN FCTR										LAG OFFSET			GAPOUT CP5	LAG FZ CP 5									5				
6											FORCE OFF			GAPOUT CP6	LAG FZ CP 6									6				
7	FZ7 GRN FCTR										LONG GRN			GAPOUT CP7	LAG FZ CP 7									7				
8	FZ8 GRN FCTR										NO GREEN			GAPOUT CP8	LAG FZ CP 8									8				
9	MULTI CYCLE													GAPOUT CP9	LAG FZ CP 9									9				
A	OFFSET A										OFFSET				LAG C COORD									A				
B	OFFSET B														LAG D COORD									B				
C	OFFSET C														COORD FAZES		2				6			C				
D	FZ 3 EXT																							D				
E	FZ 7 EXT																							E				
F	OFFSET INTRPT																							F				
																1	2	3	4	5	6	7	8					

CO1 MANUAL CP

CO2 MASTER CP

CO3 CURRENT CP

CO4 LAST CP

CO7 TRNSMT CP

COD MANUAL OFFSET

CAO LOCAL CYCLE TIMER

CBO MASTER CYCLE TIMER

CAA LOCAL OFFSET

CBA MASTER OFFSET

FEATURE

	OFF	ON
1		
2		
3		
4		
5		
6		
7		
8	1c1	

LOCATION

	OFF	ON
1	1	1
2	2	
3	4	
4	8	
5	16	
6	32	
7		
8		

COO = 1

CCB/CDB OFFSET TIMER

CCC/CDC LAG GREEN TIMER

CCD/CDD FORCE OFF TIMER

CCE/CDE LONG GREEN TIMER

CCF/CDF NO GREEN TIMER

D PAGE

E PAGE

	D	FLAGS								E	FLAGS								F	FLAGS							
	MAX	1	2	3	4	5	6	7	8	MIN	1	2	3	4	5	6	7	8	PED	1	2	3	4	5	6	7	8
0	RCL									RCL									RCL								
1	CP 1									CP 1									CP 1								
2	CP 2									CP 2									CP 2								
3	CP 3									CP 3									CP 3								
4	CP 4									CP 4									CP 4								
5	CP 5									CP 5									CP 5								
6	CP 6									CP 6									CP 6								
7	CP 7									CP 7									CP 7								
8	CP 8									CP 8									CP 8								
9	CP 9									CP 9									CP 9								
A																			RCL 1								
B																			RCL 2								
C																											
D																											
E																											
F																											
		1	2	3	4	5	6	7	8		1	2	3	4	5	6	7	8		1	2	3	4	5	6	7	8

LAST POWER FAILURE REGISTER

HOUR = D-A-E

MINUTE = D-B-E

DAY = D-C-E

RCL 1 = TIME OF DAY MAX RECALL (1ST SELECT) PHASES

(CALL ACTIVE LIGHTS)

RCL 2 = TIME OF DAY MAX RECALL (2ND SELECT) PHASES

(CALL ACTIVE LIGHTS)

LAST FLASH TIME REGISTER

HOUR = D-A-F

MINUTE = D-B-F

DAY = D-C-F

D-E-E = C8 VERSION NUMBER

D-E-F = LITHIUM BATTERY CONDITION

84 = BAD

85 = GOOD


	E	FLAGS							F	FLAGS								
	FUNCTION	1	2	3	4	5	6	7	8	FUNCTION	1	2	3	4	5	6	7	8
0										CODE 4								0
1										CODE 5								1
2										C-RECALL								2
3										D-RECALL								3
4										EXCLUSIVE								4
5										2 PED		2						5
6										6 PED						6		6
7										4 PED				4				7
8										8 PED								8
9																		9
A	OLA NOT									OLA ON								A
B	OLB NOT									OLB ON								B
C	OLC NOT									OLC ON								C
D	OLD NOT									OLD ON								D
E																		E
F																		F
		1	2	3	4	5	6	7	8		1	2	3	4	5	6	7	8

[illegible]

- 9 TIME OF DAY MAX RECALL (1ST SELECT)
A TRAFFIC ACT. MAX 2 OPERATION
B TIME OF DAY MAX RECALL (2ND SELECT)
C YELLOW YIELD COORDINATION
D YELLOW YIELD COORDINATION
E TIME OF DAY FREE OPERATION
F FLASHING OPERATION

LOCATION: RTE 94 EB @ SWEETWATER SPRINGS BLVD

CONFLICT MONITOR PROGRAM



	INTERVAL	PHASE TIMING								9	PRE-EMPTION		F															
		1	2	3	4	5	6	7	8		E		FLAGS	1	2	3	4	5	6	7	8							
0	WALK	1	7	1	1	1	1	1	8	CLK RST	EV SEL	0	PERMIT	1	2			5	6		8	0						
1	DONT WALK	1	29	1	1	1	1	1	36		RR1 CLR	15	RED LOCK	1				5			8	1						
2	MIN GREEN	10	7	1	1	5	5	1	5		EVA DLY	0	YEL LOCK									2						
3	TYPE 3 DET	0	0	0	0	0	0	0	0		EVA CLR	5	V RECALL		2				6			3						
4	ADD/VEH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0		EVB DLY	0	P RECALL									4						
5	PASSAGE	2.0	3.0	0.9	0.9	3.0	3.0	0.9	3.0		EVB CLR	5	PED PHASES		2						8	5						
6	MAX GAP	2.0	3.0	0.9	0.9	3.0	3.0	0.9	3.0		EVC DLY	0	RT OLA									6						
7	MIN GAP	2.0	3.0	0.9	0.9	3.0	3.0	0.9	3.0		EVC CLR	5	RT OLB									7						
8	MAX EXT	20	30	9	9	35	30	9	35		EVD DLY	0	DBL ENTRY									8						
9	MAX 2									YR	EVD CLR	5	MAX 2 PHASES									9						
A	MAX 3									MO	MAX EV	255	LAG PHASES	READ ONLY								A						
B										DAY	RR2 CLR	15	RED REST									B						
C	REDUCE BY	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	DOW			REST-IN-WALK									C						
D	EVERY	1.0	1.0	1.0	1.0	1.0	1.0	1.0	1.0	HR			MAX 3 PHASES									D						
E	YELLOW	3.6	4.8	3.0	3.0	4.3	4.8	3.0	4.3	MIN			YEL START UP		2				6			E						
F	RED	2.0	2.0	0.0	0.0	2.0	1.5	0.0	2.0	SEC			FIRST PHASE								8	F						
3.5'	PED XING FT		100						124					1	2	3	4	5	6	7	8							
	BIKE XING FT	125	105			-	65		70																			

FOC LONG FAILURE	
FOD SHORT FAILURE	
FOE	30
FOF	5

FCO	3
FC1	3
FC2	10
FCA	0.0
FCB	0.0
FCC	0.0
FCD	0.0

FDO TB SELECT	1
FD3 PED SELECT	0
FD4 7 WIRE	0
FD5 PERMISSIVE	0
FD8 OS SEEKING	1

CO5 FLASH TYPE	1
CC2 DOWNLOAD	1

ENTRIES IN THESE LOCATIONS CAN BE CHANGED IN CC1 FLASH ONLY



C PAGE

		CONTROL PLANS									Y-COORD			LAG PHASE	FLAGS													
		1	2	3	4	5	6	7	8	9		C	D	E	F	1	2	3	4	5	6	7	8					
0	CYCLE LENGTH														LAG FZ FREE		2		4		6		8	0				
1	FZ1 GRN FCTR													GAPOUT CP1	LAG FZ CP 1									1				
2														GAPOUT CP2	LAG FZ CP 2									2				
3	FZ3 GRN FCTR													GAPOUT CP3	LAG FZ CP 3									3				
4	FZ4 GRN FCTR										PERM TIME			GAPOUT CP4	LAG FZ CP 4									4				
5	FZ5 GRN FCTR										LAG OFFSET			GAPOUT CP5	LAG FZ CP 5									5				
6											FORCE OFF			GAPOUT CP6	LAG FZ CP 6									6				
7	FZ7 GRN FCTR										LONG GRN			GAPOUT CP7	LAG FZ CP 7									7				
8	FZ8 GRN FCTR										NO GREEN			GAPOUT CP8	LAG FZ CP 8									8				
9	MULTI CYCLE													GAPOUT CP9	LAG FZ CP 9									9				
A	OFFSET A										OFFSET				LAG C COORD									A				
B	OFFSET B														LAG D COORD									B				
C	OFFSET C														COORD FAZES		2				6			C				
D	FZ 3 EXT																							D				
E	FZ 7 EXT																							E				
F	OFFSET INTRPT																							F				
																1	2	3	4	5	6	7	8					

CO1 MANUAL CP

CO2 MASTER CP

CO3 CURRENT CP

CO4 LAST CP

CO7 TRNSMT CP

COD MANUAL OFFSET

CAO LOCAL CYCLE TIMER

CBO MASTER CYCLE TIMER

CAA LOCAL OFFSET

CBA MASTER OFFSET

FEATURE

	OFF	ON
1		
2		
3		
4		
5		
6		
7		
8	1c1	

LOCATION

	OFF	ON
1	1	
2	2	2
3	4	
4	8	
5	16	
6	32	
7		
8		

COO = 2

CCB/CDB OFFSET TIMER

CCC/CDC LAG GREEN TIMER

CCD/CDD FORCE OFF TIMER

CCE/CDE LONG GREEN TIMER

CCF/CDF NO GREEN TIMER

D PAGE

E PAGE

	D	FLAGS								E	FLAGS								F	FLAGS							
	MAX	1	2	3	4	5	6	7	8	MIN	1	2	3	4	5	6	7	8	PED	1	2	3	4	5	6	7	8
0	RCL									RCL									RCL								
1	CP 1									CP 1									CP 1								
2	CP 2									CP 2									CP 2								
3	CP 3									CP 3									CP 3								
4	CP 4									CP 4									CP 4								
5	CP 5									CP 5									CP 5								
6	CP 6									CP 6									CP 6								
7	CP 7									CP 7									CP 7								
8	CP 8									CP 8									CP 8								
9	CP 9									CP 9									CP 9								
A																			RCL 1								
B																			RCL 2								
C																											
D																											
E																											
F																											
		1	2	3	4	5	6	7	8		1	2	3	4	5	6	7	8		1	2	3	4	5	6	7	8

LAST POWER FAILURE REGISTER

HOUR = D-A-E

MINUTE = D-B-E

DAY = D-C-E

RCL 1 = TIME OF DAY MAX RECALL (1ST SELECT) PHASES
(CALL ACTIVE LIGHTS)RCL 2 = TIME OF DAY MAX RECALL (2ND SELECT) PHASES
(CALL ACTIVE LIGHTS)**LAST FLASH TIME REGISTER**

HOUR = D-A-F

MINUTE = D-B-F

DAY = D-C-F

D-E-E = C8 VERSION NUMBER

D-E-F = LITHIUM BATTERY CONDITION

84 = BAD

85 = GOOD


	E	FLAGS							F	FLAGS								
	FUNCTION	1	2	3	4	5	6	7	8	FUNCTION	1	2	3	4	5	6	7	8
0										CODE 4								
1										CODE 5								
2										C-RECALL								
3										D-RECALL								
4										EXCLUSIVE								
5										2 PED		2						
6										6 PED						6		
7										4 PED				4				
8										8 PED								8
9																		
A	OLA NOT									OLA ON								
B	OLB NOT									OLB ON								
C	OLC NOT									OLC ON								
D	OLD NOT									OLD ON								
E																		
F																		
		1	2	3	4	5	6	7	8		1	2	3	4	5	6	7	8

[illegible]

F FLASHING OPERATION

LOCATION: RTE 94 WB @ SWEETWATER SPRINGS BLVD

CONFLICT MONITOR PROGRAM



Do not reproduce

INTERSECTION: CampoRd @ CasadeOro @ Granad 750

Page 1 (of 10)

QuicNet
System
Parameters

Group Assignment: **#NAME?**
 Field Master Assignment: **#NAME?**
 System Reference Number: **18**
 Communications Channel: **#NAME?**
 Drop Address: **8**
 Area Number: **6**
 Area Address: **8**

N/S Street Name: **#####**
 E/W Street Name: **#####**

Last QuicNet Database Change: 4/3/2014 12:10

Notes:

Field Change Record					
Change	By	Date	Change	By	Date

Excl Ped Assignment	#NAME?	Note: Set the Exclusive Ped Outputs on the "Outputs / General" page	
Exclusive Walk	0		
Exclusive FDW	0		
All Red Clear	0.0		
Exclusive Ped Phase			
		Walk Output	0
		Don't Walk Output	0

	Phase							
	1	2	3	4	5	6	7	8
Basic Phase Timing	Min Green	4	6	4	4	8	6	0 4
	Extension	1.0	4.0	1.0	1.0	4.0	2.0	0.0 1.0
	Max	20	45	30	28	24	45	0 25
	Max 2	0	0	0	0	0	0	0 0
Clear	Cond Serve Check	0	0	0	0	0	0	0 0
Pedestrian Timing	Yellow Change	3.9	4.3	3.2	3.2	3.9	4.3	0.0 3.2
	Red Clear	0.5	1.0	1.0	1.0	0.5	1.0	0.0 1.0
Volume Density	Walk	0	7	7	7	0	7	0 0
	Ped Clear - FDW	0	11	11	19	0	11	0 0
	Adv / Delay Walk	0	0	0	0	0	0	0 0
	PE Min Ped FDW	0	0	0	0	0	0	0 0
Volume Density	Type 3 Disconnect	0	0	0	0	0	0	0 0
	Added per Vehicle	0.0	0.0	0.0	0.0	0.0	0.0	0.0 0.0
	Max Added Initial	0	0	0	0	0	0	0 0
	Min Gap	2.0	4.0	1.0	1.0	5.0	2.0	0.0 1.0
	Max Gap	2.0	3.0	0.5	0.5	5.0	1.0	0.0 0.5
	Reduce Every	24.0	6.0	10.0	10.0	24.0	6.0	0.0 10.0
Phase Timing - Bank 1								

	Phase							
	1	2	3	4	5	6	7	8
Alternate Walk	0	0	0	0	0	0	0	0
Alternate Ped Clear	0	0	0	0	0	0	0	0
Alternate Minimum	0	0	0	0	0	0	0	0
Alternate Extension	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Alternate Timing - Bank 1								

Red Lock	#NAME?
Yellow Lock	#NAME?
Simultaneous Gap	#NAME?
Rest In Walk	#NAME?
Advance Walk	#NAME?
Flashing Walk	#NAME?
Max Extension	#NAME?

Red Rest	#NAME?
Dual Entry	#NAME?
Sequential Timing	#NAME?
Inhibit Ped Reservice	#NAME?
Semi-Actuated	#NAME?
Guaranteed Passage	#NAME?
Conditional Service	#NAME?

Phase Functions - Page 1	
--------------------------	--

		Phase							
		1	2	3	4	5	6	7	8
Basic Phase Timing	Min Green	0	0	0	0	0	0	0	0
	Extension	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Max	0	0	0	0	0	0	0	0
	Max 2	0	0	0	0	0	0	0	0
	Cond Serve Check	0	0	0	0	0	0	0	0
Clear	Yellow Change	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Red Clear	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Pedestrian Timing	Walk	0	0	0	0	0	0	0	0
	Ped Clear - FDW	0	0	0	0	0	0	0	0
	Adv / Delay Walk	0	0	0	0	0	0	0	0
	PE Min Ped FDW	0	0	0	0	0	0	0	0
Volume Density	Type 3 Disconnect	0	0	0	0	0	0	0	0
	Added per Vehicle	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Max Added Initial	0	0	0	0	0	0	0	0
	Min Gap	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Max Gap	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Reduce Every	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Phase Timing - Bank 2									

		Phase							
		1	2	3	4	5	6	7	8
Alternate Walk		0	0	0	0	0	0	0	0
Alternate Ped Clear		0	0	0	0	0	0	0	0
Alternate Minimum		0	0	0	0	0	0	0	0
Alternate Extension		0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Alternate Timing - Bank 2									

		Phase							
		1	2	3	4	5	6	7	8
Basic Phase Timing	Min Green	0	0	0	0	0	0	0	0
	Extension	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Max	0	0	0	0	0	0	0	0
	Max 2	0	0	0	0	0	0	0	0
	Cond Serve Check	0	0	0	0	0	0	0	0
Clear	Yellow Change	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Red Clear	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Pedestrian Timing	Walk	0	0	0	0	0	0	0	0
	Ped Clear - FDW	0	0	0	0	0	0	0	0
	Adv / Delay Walk	0	0	0	0	0	0	0	0
	PE Min Ped FDW	0	0	0	0	0	0	0	0
Volume Density	Type 3 Disconnect	0	0	0	0	0	0	0	0
	Added per Vehicle	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Max Added Initial	0	0	0	0	0	0	0	0
	Min Gap	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Max Gap	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Reduce Every	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Phase Timing - Bank 3									

		Phase							
		1	2	3	4	5	6	7	8
Alternate Walk		0	0	0	0	0	0	0	0
Alternate Ped Clear		0	0	0	0	0	0	0	0
Alternate Minimum		0	0	0	0	0	0	0	0
Alternate Extension		0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Alternate Timing - Bank 3									

INTERSECTION: Barcelona St @ Campo Rd 750

Page 1 (of 10)

QuicNet
System
Parameters

Group Assignment: #####
Field Master Assignment: #####
System Reference Number: 17
Communications Channel: #####
Drop Address: 7
Area Number: 6
Area Address: 7

N/S Street Name: #####
E/W Street Name: #####

Last QuicNet Database Change: 5/6/2014 13:22

Notes:

Field Change Record					
Change	By	Date	Change	By	Date

Excl Ped Assignment	#NAME?
Exclusive Walk	0
Exclusive FDW	0
All Red Clear	0.0

Note: Set the Exclusive Ped Outputs on the "Outputs / General" page

Walk Output	0
Don't Walk Output	0

Exclusive Ped Phase

	Phase							
	1	2	3	4	5	6	7	8
Min Green	4	6	0	4	4	6	0	0
Extension	2.0	2.0	0.0	3.0	2.0	2.0	0.0	0.0
Max	30	45	0	36	30	45	0	0
Max 2	0	0	0	0	0	0	0	0
Cond Serve Check	0	0	0	0	0	0	0	0

Basic Phase
Timing

	Phase							
	1	2	3	4	5	6	7	8
Alternate Walk	0	0	0	0	0	0	0	0
Alternate Ped Clear	0	0	0	0	0	0	0	0
Alternate Minimum	0	0	0	0	0	0	0	0
Alternate Extension	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

Alternate Timing - Bank 1

Yellow Change	3.2	3.6	0.0	3.2	3.2	3.6	0.0	0.0
Red Clear	0.5	1.0	0.0	1.0	0.5	1.0	0.0	0.0

Clear

Walk	0	7	0	7	0	7	0	0
Ped Clear - FDW	0	12	0	19	0	13	0	0
Adv / Delay Walk	0	0	0	0	0	0	0	0
PE Min Ped FDW	0	0	0	0	0	0	0	0

Pedestrian
Timing

Red Lock	#NAME?
Yellow Lock	#NAME?
Simultaneous Gap	#NAME?
Rest In Walk	#NAME?
Advance Walk	#NAME?
Flashing Walk	#NAME?
Max Extension	#NAME?

Red Rest	#NAME?
Dual Entry	#NAME?
Sequential Timing	#NAME?
Inhibit Ped Reservice	#NAME?
Semi-Actuated	#NAME?
Guaranteed Passage	#NAME?
Conditional Service	#NAME?

Phase Functions - Page 1

Type 3 Disconnect	0	0	0	0	0	0	0	0
Added per Vehicle	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Max Added Initial	0	0	0	0	0	0	0	0
Min Gap	2.0	1.5	0.0	3.0	2.0	1.5	0.0	0.0
Max Gap	2.0	2.1	0.0	3.0	2.0	2.1	0.0	0.0
Reduce Every	0.0	7.0	0.0	0.0	0.0	7.0	0.0	0.0

Phase Timing - Bank 1

Minimum Recall	#NAME?
Ped Recall	#NAME?
Maximum Recall	#NAME?
Green Flash	#NAME?
Overlap Green Flash	#NAME?

Soft Recall	#NAME?
External Recall	#NAME?
Manual Control Calls	#NAME?
Fast Green Flash	#NAME?
Fast Overlap G. Flash	#NAME?

Phase Functions - Page 2

		Phase							
		1	2	3	4	5	6	7	8
Basic Phase Timing	Min Green	0	0	0	0	0	0	0	0
	Extension	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Max	0	0	0	0	0	0	0	0
	Max 2	0	0	0	0	0	0	0	0
	Cond Serve Check	0	0	0	0	0	0	0	0
Clear	Yellow Change	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Red Clear	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Pedestrian Timing	Walk	0	0	0	0	0	0	0	0
	Ped Clear - FDW	0	0	0	0	0	0	0	0
	Adv / Delay Walk	0	0	0	0	0	0	0	0
	PE Min Ped FDW	0	0	0	0	0	0	0	0
Volume Density	Type 3 Disconnect	0	0	0	0	0	0	0	0
	Added per Vehicle	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Max Added Initial	0	0	0	0	0	0	0	0
	Min Gap	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Max Gap	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Reduce Every	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Phase Timing - Bank 2									

		Phase							
		1	2	3	4	5	6	7	8
	Alternate Walk	0	0	0	0	0	0	0	0
	Alternate Ped Clear	0	0	0	0	0	0	0	0
	Alternate Minimum	0	0	0	0	0	0	0	0
	Alternate Extension	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Alternate Timing - Bank 2									

		Phase							
		1	2	3	4	5	6	7	8
Basic Phase Timing	Min Green	0	0	0	0	0	0	0	0
	Extension	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Max	0	0	0	0	0	0	0	0
	Max 2	0	0	0	0	0	0	0	0
	Cond Serve Check	0	0	0	0	0	0	0	0
Clear	Yellow Change	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Red Clear	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Pedestrian Timing	Walk	0	0	0	0	0	0	0	0
	Ped Clear - FDW	0	0	0	0	0	0	0	0
	Adv / Delay Walk	0	0	0	0	0	0	0	0
	PE Min Ped FDW	0	0	0	0	0	0	0	0
Volume Density	Type 3 Disconnect	0	0	0	0	0	0	0	0
	Added per Vehicle	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Max Added Initial	0	0	0	0	0	0	0	0
	Min Gap	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Max Gap	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Reduce Every	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Phase Timing - Bank 3									

		Phase							
		1	2	3	4	5	6	7	8
	Alternate Walk	0	0	0	0	0	0	0	0
	Alternate Ped Clear	0	0	0	0	0	0	0	0
	Alternate Minimum	0	0	0	0	0	0	0	0
	Alternate Extension	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Alternate Timing - Bank 3									

INTERSECTION: Bonita St @ Campo Rd 750

Page 1 (of 10)

 QuicNet
System
Parameters

 Group Assignment: **NONE**
 Field Master Assignment: **NONE**
 System Reference Number: **16**
 Communications Channel: **Not Assigned**
 Drop Address: **6**
 Area Number: **6**
 Area Address: **6**

 N/S Street Name: **Bonita St**
 E/W Street Name: **Campo Rd**

 Last QuicNet Database Change: **8/1/2016 11:51**

Notes:

Field Change Record					
Change	By	Date	Change	By	Date

Excl Ped Assignment	_____
Exclusive Walk	0
Exclusive FDW	0
All Red Clear	0.0

Note: Set the Exclusive Ped Outputs on the "Outputs / General" page

Walk Output	0
Don't Walk Output	0

Exclusive Ped Phase

	Phase							
	1	2	3	4	5	6	7	8
Min Green	4	6	0	4	4	6	0	4
Extension	1.5	2.0	0.0	2.0	1.5	2.0	0.0	2.0
Max	20	50	0	27	20	50	0	27
Max 2	0	0	0	0	0	0	0	0
Cond Serve Check	0	0	0	0	0	0	0	0

 Basic Phase
Timing

	Phase							
	1	2	3	4	5	6	7	8
Alternate Walk	0	0	0	0	0	0	0	0
Alternate Ped Clear	0	0	0	0	0	0	0	0
Alternate Minimum	0	0	0	0	0	0	0	0
Alternate Extension	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

Alternate Timing - Bank 1

Yellow Change	3.6	4.1	0.0	3.6	3.6	4.1	0.0	3.6
Red Clear	0.5	1.0	0.0	1.0	0.5	1.0	0.0	1.0

Clear

Walk	0	7	0	7	0	7	0	7
Ped Clear - FDW	0	12	0	19	0	12	0	19
Adv / Delay Walk	0	0	0	0	0	0	0	0
PE Min Ped FDW	0	0	0	0	0	0	0	0

 Pedestrian
Timing

Red Lock	_____
Yellow Lock	_____
Simultaneous Gap	_____
Rest In Walk	_____
Advance Walk	_____
Flashing Walk	_____
Max Extension	_____

Red Rest	_____
Dual Entry	<u>2_4_6_8</u>
Sequential Timing	_____
Inhibit Ped Reservice	_____
Semi-Actuated	_____
Guaranteed Passage	_____
Conditional Service	_____

Phase Functions - Page 1

Type 3 Disconnect	0	0	0	0	0	0	0	0
Added per Vehicle	0.0	0.0	0.0	0.0	0.0	2.0	0.0	0.0
Max Added Initial	0	0	0	0	0	10	0	0
Min Gap	1.0	1.0	0.0	5.0	1.0	1.0	0.0	5.0
Max Gap	1.5	2.0	0.0	5.0	1.5	2.0	0.0	5.0
Reduce Every	10.0	10.0	0.0	24.0	10.0	10.0	0.0	24.0

Phase Timing - Bank 1

Minimum Recall	<u>2_6</u>
Ped Recall	_____
Maximum Recall	_____
Green Flash	_____
Overlap Green Flash	_____

Soft Recall	_____
External Recall	_____
Manual Control Calls	_____
Fast Green Flash	_____
Fast Overlap G. Flash	_____

Phase Functions - Page 2

		Phase							
		1	2	3	4	5	6	7	8
Basic Phase Timing	Min Green	0	0	0	0	0	0	0	0
	Extension	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Max	0	0	0	0	0	0	0	0
	Max 2	0	0	0	0	0	0	0	0
	Cond Serve Check	0	0	0	0	0	0	0	0
Clear	Yellow Change	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Red Clear	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Pedestrian Timing	Walk	0	0	0	0	0	0	0	0
	Ped Clear - FDW	0	0	0	0	0	0	0	0
	Adv / Delay Walk	0	0	0	0	0	0	0	0
	PE Min Ped FDW	0	0	0	0	0	0	0	0
Volume Density	Type 3 Disconnect	0	0	0	0	0	0	0	0
	Added per Vehicle	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Max Added Initial	0	0	0	0	0	0	0	0
	Min Gap	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Max Gap	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Reduce Every	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Phase Timing - Bank 2									

		Phase							
		1	2	3	4	5	6	7	8
	Alternate Walk	0	0	0	0	0	0	0	0
	Alternate Ped Clear	0	0	0	0	0	0	0	0
	Alternate Minimum	0	0	0	0	0	0	0	0
	Alternate Extension	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Alternate Timing - Bank 2									

		Phase							
		1	2	3	4	5	6	7	8
Basic Phase Timing	Min Green	0	0	0	0	0	0	0	0
	Extension	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Max	0	0	0	0	0	0	0	0
	Max 2	0	0	0	0	0	0	0	0
	Cond Serve Check	0	0	0	0	0	0	0	0
Clear	Yellow Change	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Red Clear	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Pedestrian Timing	Walk	0	0	0	0	0	0	0	0
	Ped Clear - FDW	0	0	0	0	0	0	0	0
	Adv / Delay Walk	0	0	0	0	0	0	0	0
	PE Min Ped FDW	0	0	0	0	0	0	0	0
Volume Density	Type 3 Disconnect	0	0	0	0	0	0	0	0
	Added per Vehicle	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Max Added Initial	0	0	0	0	0	0	0	0
	Min Gap	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Max Gap	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	Reduce Every	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Phase Timing - Bank 3									

		Phase							
		1	2	3	4	5	6	7	8
	Alternate Walk	0	0	0	0	0	0	0	0
	Alternate Ped Clear	0	0	0	0	0	0	0	0
	Alternate Minimum	0	0	0	0	0	0	0	0
	Alternate Extension	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Alternate Timing - Bank 3									

QuicNet® System	
System ID	15
Group	NONE
Field Master	NONE
N-S Street	Conrad
E-W Street	Campo
Communications	
Channel	UDP:8002:10.197.1.11
Address	5
Area Number	6
Area Address	5
Database	
Last Changed	3/19/2019 9:24

QuicNet Timing Notes

Phase Timing - Bank 1								
	Phase 1	Phase 2	Phase 3	Phase 4	Phase 5	Phase 6	Phase 7	Phase 8
Min Green	4	6	4	0	6	4	4	0
Extension	2.0	2.0	2.0	0.0	2.0	2.0	2.0	0.0
Max	25	40	30	0	40	30	30	0
Max 2	0	0	0	0	0	0	0	0
Cond Serve Check	0	0	0	0	0	0	0	0
Clearance Timing								
Yellow Change	3.6	4.1	3.4	0.0	3.6	4.1	4.8	0.0
Red Clear	0.5	1.0	1.0	0.0	0.5	1.0	1.0	0.0
Pedestrian Timing								
Walk	0	7	0	0	0	7	0	0
Pedestrian Change	0	22	15	0	0	29	12	0
Advance/Delay Walk	0	0	7	0	0	0	7	0
PE Min. Ped. Change	0	0	0	0	0	0	0	0
Volume-Density								
Type 3 Disconnect	0	0	0	0	0	0	0	0
Add per Vehicle	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Max Added Initial	0	0	0	0	0	0	0	0
Min Gap	2.0	2.0	2.0	0.0	2.0	2.0	2.0	0.0
Max Gap	2.0	2.0	2.0	0.0	2.0	2.0	2.0	0.0
Reduce Every	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Alternate Timing								
Alternate Walk	0	0	0	0	0	0	0	0
Alternate Ped. Change	0	0	0	0	0	0	0	0
Alternate Minimum	0	0	0	0	0	0	0	0
Alternate Extension	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

Phase Timing - Exclusive Pedestrian	
Exclusive Ped Assignment	_____
Exclusive Walk	0
Exclusive Pedestrian Change	0
Red Clear	0.0
Walk Output	0
Don't Walk Output	0

Phase Functions - Page 1	
Red Lock	_____
Yellow Lock	__3__7__
Simultaneous Gap	_____
Rest In Walk	_____
Advance Walk	__3__7__
Flashing Walk	_____
Max Extension	_____
Red Rest	_____
Dual Entry	_____
Sequential Timing	_____
Inhibit Ped Reservice	_____
Delay Walk	_____
Guaranteed Passage	_____
Conditional Service	_____

Phase Functions - Page 2	
Minimum Recall	__2__5__
Ped Recall	_____
Maximum Recall	_____
Green Flash	_____
Overlap Green Flash	_____
Flashing Yellow Arrow for PPLT	_____
Max2	_____
Soft Recall	_____
External Recall	_____
Manual Control Calls	_____
Fast Green Flash	_____
Fast Overlap Green Flash	_____
Semi-Actuated	_____

Attachment E: Existing Conditions Synchro Worksheets

Casa De Oro
1: Kenwood Dr & SR-94 EB Ramps

Existing AM

Intersection

Intersection Delay, s/veh	28.5
Intersection LOS	D

Movement	WBL	WBR	SEL	SER	NEL	NET	NER	SWL	SWT	SWR
Lane Configurations										
Traffic Vol, veh/h	0	0	1	102	0	552	259	55	460	0
Future Vol, veh/h	0	0	1	102	0	552	259	55	460	0
Peak Hour Factor	0.92	0.92	0.88	0.88	0.85	0.85	0.85	0.88	0.88	0.88
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	0	0	1	116	0	649	305	63	523	0
Number of Lanes	0	0	1	1	0	2	1	0	2	0

Approach	NE	SW
Opposing Approach	SW	NE
Opposing Lanes	2	3
Conflicting Approach Left	SE	
Conflicting Lanes Left	3	0
Conflicting Approach Right		SE
Conflicting Lanes Right	0	3
HCM Control Delay	27.4	39.2
HCM LOS	D	E

Lane	NELn1	NELn2	NELn3	SELn1	SELn2	SELn3	SWLn1	SWLn2
Vol Left, %	0%	0%	0%	100%	100%	0%	26%	0%
Vol Thru, %	100%	100%	0%	0%	0%	0%	74%	100%
Vol Right, %	0%	0%	100%	0%	0%	100%	0%	0%
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop
Traffic Vol by Lane	276	276	259	170	171	102	208	307
LT Vol	0	0	0	170	171	0	55	0
Through Vol	276	276	0	0	0	0	153	307
RT Vol	0	0	259	0	0	102	0	0
Lane Flow Rate	325	325	305	193	194	116	237	348
Geometry Grp	8	8	8	7	7	7	8	8
Degree of Util (X)	0.762	0.762	0.495	0.475	0.478	0.246	0.601	0.872
Departure Headway (Hd)	8.444	8.444	5.844	8.986	8.986	7.755	9.141	9.005
Convergence, Y/N	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Cap	432	432	609	403	403	466	395	404
Service Time	6.144	6.144	3.642	6.686	6.686	5.455	6.861	6.725
HCM Lane V/C Ratio	0.752	0.752	0.501	0.479	0.481	0.249	0.6	0.861
HCM Control Delay	33.5	33.5	14.3	19.6	19.6	13	24.7	49
HCM Lane LOS	D	D	B	C	C	B	C	E
HCM 95th-tile Q	6.4	6.4	2.7	2.5	2.5	1	3.8	8.7

HCM 6th AWSC

2: Kenwood Dr & SR-94 WB Ramps

01/29/2020

Intersection	
Intersection Delay, s/veh	79.3
Intersection LOS	F

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NEL	NET	NER	SWL	SWT	SWR
Lane Configurations					↰	↰	↰	↰			↰	↰
Traffic Vol, veh/h	0	0	0	178	47	143	223	666	0	0	337	562
Future Vol, veh/h	0	0	0	178	47	143	223	666	0	0	337	562
Peak Hour Factor	0.96	0.96	0.96	0.79	0.79	0.79	0.86	0.86	0.86	0.90	0.90	0.90
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	0	0	0	225	59	181	259	774	0	0	374	624
Number of Lanes	0	0	0	0	1	1	1	2	0	0	2	1


Approach	WB	NE	SW
Opposing Approach		SW	NE
Opposing Lanes	0	3	3
Conflicting Approach Left	NE		WB
Conflicting Lanes Left	3	0	2
Conflicting Approach Right	SW	WB	
Conflicting Lanes Right	3	2	0
HCM Control Delay	48.6	52.1	121.7
HCM LOS	E	F	F

Lane	NELn1	NELn2	NELn3	WBLn1	WBLn2	SWLn1	SWLn2	SWLn3
Vol Left, %	100%	0%	0%	79%	0%	0%	0%	0%
Vol Thru, %	0%	100%	100%	21%	0%	100%	100%	0%
Vol Right, %	0%	0%	0%	0%	100%	0%	0%	100%
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop
Traffic Vol by Lane	223	333	333	225	143	169	169	562
LT Vol	223	0	0	178	0	0	0	0
Through Vol	0	333	333	47	0	169	169	0
RT Vol	0	0	0	0	143	0	0	562
Lane Flow Rate	259	387	387	285	181	187	187	624
Geometry Grp	8	8	8	8	8	8	8	8
Degree of Util (X)	0.704	0.997	0.809	0.893	0.513	0.527	0.527	1.319
Departure Headway (Hd)	10.45	9.929	8.121	11.931	10.811	10.137	10.137	7.604
Convergence, Y/N	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Cap	347	368	449	305	335	358	358	481
Service Time	8.15	7.629	5.821	9.631	8.511	7.868	7.868	5.334
HCM Lane V/C Ratio	0.746	1.052	0.862	0.934	0.54	0.522	0.522	1.297
HCM Control Delay	34.6	78.7	37.2	63.9	24.4	23.7	23.7	180.5
HCM Lane LOS	D	F	E	F	C	C	C	F
HCM 95th-tile Q	5.1	11.6	7.5	8.2	2.8	2.9	2.9	27.3

Intersection						
Int Delay, s/veh	8.9					
Movement	WBL	WBR	NET	NER	SWL	SWT
Lane Configurations						
Traffic Vol, veh/h	119	33	731	66	6	797
Future Vol, veh/h	119	33	731	66	6	797
Conflicting Peds, #/hr	0	0	0	6	6	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	95	95	89	89	90	90
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	125	35	821	74	7	886
Major/Minor	Minor1	Major1	Major2			
Conflicting Flow All	1321	454	0	0	901	0
Stage 1	864	-	-	-	-	-
Stage 2	457	-	-	-	-	-
Critical Hdwy	6.84	6.94	-	-	4.14	-
Critical Hdwy Stg 1	5.84	-	-	-	-	-
Critical Hdwy Stg 2	5.84	-	-	-	-	-
Follow-up Hdwy	3.52	3.32	-	-	2.22	-
Pot Cap-1 Maneuver	148	553	-	-	750	-
Stage 1	373	-	-	-	-	-
Stage 2	604	-	-	-	-	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	144	550	-	-	746	-
Mov Cap-2 Maneuver	144	-	-	-	-	-
Stage 1	371	-	-	-	-	-
Stage 2	593	-	-	-	-	-
Approach	WB	NE		SW		
HCM Control Delay, s	106.8	0		0.2		
HCM LOS	F					
Minor Lane/Major Mvmt	NET	NERWBLn1	SWL	SWT		
Capacity (veh/h)	-	-	171	746	-	
HCM Lane V/C Ratio	-	-	0.936	0.009	-	
HCM Control Delay (s)	-	-	106.8	9.9	0.1	
HCM Lane LOS	-	-	F	A	A	
HCM 95th %tile Q(veh)	-	-	7.1	0	-	

Casa De Oro
4: Kenwood Dr & Campo Rd

Existing AM



Movement	EBT	EBR	WBL	WBT	NEL	NER
Lane Configurations	↑↑	↑	↑↑	↑	↑	↑↑
Traffic Volume (vph)	182	74	736	517	205	562
Future Volume (vph)	182	74	736	517	205	562
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	5.1	4.0	4.1	5.1	4.4	4.1
Lane Util. Factor	0.95	1.00	0.97	1.00	1.00	0.88
Frt	1.00	0.85	1.00	1.00	1.00	0.85
Flt Protected	1.00	1.00	0.95	1.00	0.95	1.00
Satd. Flow (prot)	3539	1583	3433	1863	1770	2787
Flt Permitted	1.00	1.00	0.95	1.00	0.95	1.00
Satd. Flow (perm)	3539	1583	3433	1863	1770	2787
Peak-hour factor, PHF	0.83	0.83	0.91	0.91	0.89	0.89
Adj. Flow (vph)	219	89	809	568	230	631
RTOR Reduction (vph)	0	0	0	0	0	311
Lane Group Flow (vph)	219	89	809	568	230	320
Turn Type	NA	Free	Prot	NA	Prot	pm+ov
Protected Phases	6		5	2	3	5
Permitted Phases		Free				3
Actuated Green, G (s)	35.7	100.0	33.3	45.9	17.4	50.7
Effective Green, g (s)	35.7	100.0	33.3	45.9	17.4	50.7
Actuated g/C Ratio	0.36	1.00	0.33	0.46	0.17	0.51
Clearance Time (s)	5.1		4.1	5.1	4.4	4.1
Vehicle Extension (s)	2.0		2.0	2.0	2.0	2.0
Lane Grp Cap (vph)	1263	1583	1143	855	307	1413
v/s Ratio Prot	0.06		c0.24	c0.30	c0.13	0.08
v/s Ratio Perm		0.06				0.04
v/c Ratio	0.17	0.06	0.71	0.66	0.75	0.23
Uniform Delay, d1	22.0	0.0	29.1	21.1	39.2	13.7
Progression Factor	1.00	1.00	1.29	0.67	1.00	1.00
Incremental Delay, d2	0.3	0.1	1.3	3.1	8.5	0.0
Delay (s)	22.3	0.1	38.8	17.3	47.7	13.8
Level of Service	C	A	D	B	D	B
Approach Delay (s)	15.9			29.9	22.8	
Approach LOS	B			C	C	

Intersection Summary

HCM 2000 Control Delay	25.8	HCM 2000 Level of Service	C
HCM 2000 Volume to Capacity ratio	0.73		
Actuated Cycle Length (s)	100.0	Sum of lost time (s)	15.0
Intersection Capacity Utilization	48.7%	ICU Level of Service	A
Analysis Period (min)	15		

c Critical Lane Group

Casa De Oro
5: Campo Rd & Conrad Dr

Existing AM

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	225	457	10	10	898	111	0	0	2	146	10	378
Future Volume (vph)	225	457	10	10	898	111	0	0	2	146	10	378
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	4.1	5.1		5.1	5.1				5.1		5.8	4.1
Lane Util. Factor	1.00	0.95		1.00	0.95				1.00		1.00	1.00
Frpb, ped/bikes	1.00	1.00		1.00	1.00				1.00		1.00	1.00
Flpb, ped/bikes	1.00	1.00		1.00	1.00				1.00		1.00	1.00
Frt	1.00	1.00		1.00	0.98				0.86		1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00				1.00		0.96	1.00
Satd. Flow (prot)	1770	3526		1770	3476				1611		1780	1583
Flt Permitted	0.95	1.00		0.27	1.00				1.00		0.96	1.00
Satd. Flow (perm)	1770	3526		497	3476				1611		1780	1583
Peak-hour factor, PHF	0.82	0.82	0.82	0.92	0.92	0.92	0.50	0.50	0.50	0.86	0.86	0.86
Adj. Flow (vph)	274	557	12	11	976	121	0	0	4	170	12	440
RTOR Reduction (vph)	0	2	0	0	10	0	0	0	2	0	0	38
Lane Group Flow (vph)	274	567	0	11	1087	0	0	0	2	0	182	402
Confl. Bikes (#/hr)			1			1						
Turn Type	Prot	NA		Perm	NA				Perm	Split	NA	pm+ov
Protected Phases	1	6			2					7	7	1
Permitted Phases				2					2			7
Actuated Green, G (s)	23.1	35.7		45.9	45.9				45.9		16.0	39.1
Effective Green, g (s)	23.1	35.7		45.9	45.9				45.9		16.0	39.1
Actuated g/C Ratio	0.23	0.36		0.46	0.46				0.46		0.16	0.39
Clearance Time (s)	4.1	5.1		5.1	5.1				5.1		5.8	4.1
Vehicle Extension (s)	2.0	2.0		2.0	2.0				2.0		2.0	2.0
Lane Grp Cap (vph)	408	1258		228	1595				739		284	618
v/s Ratio Prot	c0.15	0.16			c0.31						0.10	c0.15
v/s Ratio Perm				0.02					0.00			0.10
v/c Ratio	0.67	0.45		0.05	0.68				0.00		0.64	0.65
Uniform Delay, d1	35.0	24.6		15.0	21.3				14.7		39.3	24.9
Progression Factor	1.14	0.83		0.80	0.63				1.00		1.00	1.00
Incremental Delay, d2	3.3	1.1		0.3	2.0				0.0		3.7	1.9
Delay (s)	43.1	21.6		12.4	15.4				14.7		43.0	26.8
Level of Service	D	C		B	B				B		D	C
Approach Delay (s)		28.6			15.4			14.7			31.5	
Approach LOS		C			B			B			C	
Intersection Summary												
HCM 2000 Control Delay			23.6			HCM 2000 Level of Service			C			
HCM 2000 Volume to Capacity ratio			0.67									
Actuated Cycle Length (s)			100.0			Sum of lost time (s)			15.0			
Intersection Capacity Utilization			61.9%			ICU Level of Service			B			
Analysis Period (min)			15									
c Critical Lane Group												

Casa De Oro
6: Bonita St & Campo Rd

Existing AM

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	44	450	35	29	978	92	68	20	30	45	12	60
Future Volume (veh/h)	44	450	35	29	978	92	68	20	30	45	12	60
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		0.98	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	51	517	40	36	1222	115	89	26	39	60	16	80
Peak Hour Factor	0.87	0.87	0.87	0.80	0.80	0.80	0.76	0.76	0.76	0.75	0.75	0.75
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	2	2	2
Cap, veh/h	65	2341	181	45	2258	212	155	42	48	118	36	110
Arrive On Green	0.07	1.00	1.00	0.03	0.69	0.69	0.14	0.14	0.14	0.14	0.14	0.14
Sat Flow, veh/h	1781	3343	258	1781	3277	308	722	307	349	500	266	806
Grp Volume(v), veh/h	51	274	283	36	661	676	154	0	0	156	0	0
Grp Sat Flow(s),veh/h/ln	1781	1777	1824	1781	1777	1807	1378	0	0	1571	0	0
Q Serve(g_s), s	2.8	0.0	0.0	2.0	18.4	18.6	1.6	0.0	0.0	0.0	0.0	0.0
Cycle Q Clear(g_c), s	2.8	0.0	0.0	2.0	18.4	18.6	11.0	0.0	0.0	9.4	0.0	0.0
Prop In Lane	1.00		0.14	1.00		0.17	0.58		0.25	0.38		0.51
Lane Grp Cap(c), veh/h	65	1245	1277	45	1225	1246	244	0	0	264	0	0
V/C Ratio(X)	0.78	0.22	0.22	0.80	0.54	0.54	0.63	0.00	0.00	0.59	0.00	0.00
Avail Cap(c_a), veh/h	287	1245	1277	287	1225	1246	595	0	0	630	0	0
HCM Platoon Ratio	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	0.89	0.89	0.89	0.77	0.77	0.77	1.00	0.00	0.00	1.00	0.00	0.00
Uniform Delay (d), s/veh	45.9	0.0	0.0	48.5	7.7	7.7	42.0	0.0	0.0	41.3	0.0	0.0
Incr Delay (d2), s/veh	6.6	0.4	0.4	8.7	1.3	1.3	1.0	0.0	0.0	0.8	0.0	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	1.3	0.1	0.1	1.0	6.3	6.4	3.8	0.0	0.0	3.7	0.0	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	52.6	0.4	0.4	57.2	9.0	9.0	43.0	0.0	0.0	42.1	0.0	0.0
LnGrp LOS	D	A	A	E	A	A	D	A	A	D	A	A
Approach Vol, veh/h		608			1373			154			156	
Approach Delay, s/veh		4.7			10.3			43.0			42.1	
Approach LOS		A			B			D			D	
Timer - Assigned Phs	1	2		4	5	6		8				
Phs Duration (G+Y+Rc), s	6.6	75.1		18.2	7.8	74.0		18.2				
Change Period (Y+Rc), s	4.1	5.1		4.6	4.1	5.1		4.6				
Max Green Setting (Gmax), s	16.1	32.1		38.0	16.1	32.1		38.0				
Max Q Clear Time (g_c+I1), s	4.0	2.0		11.4	4.8	20.6		13.0				
Green Ext Time (p_c), s	0.0	2.1		0.6	0.0	4.8		0.6				
Intersection Summary												
HCM 6th Ctrl Delay				13.2								
HCM 6th LOS				B								

Casa De Oro
7: Barcelona St & Campo Rd

Existing AM

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	13	340	158	30	793	35	289	33	56	20	12	18
Future Volume (veh/h)	13	340	158	30	793	35	289	33	56	20	12	18
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	16	420	195	38	1017	45	352	40	68	26	15	23
Peak Hour Factor	0.81	0.81	0.81	0.78	0.78	0.78	0.82	0.82	0.82	0.78	0.78	0.78
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	2	2	2
Cap, veh/h	26	1205	554	48	1810	80	442	43	73	257	152	201
Arrive On Green	0.03	1.00	1.00	0.03	0.52	0.52	0.34	0.34	0.34	0.34	0.34	0.34
Sat Flow, veh/h	1781	2365	1086	1781	3466	153	1117	127	216	610	449	594
Grp Volume(v), veh/h	16	314	301	38	521	541	460	0	0	64	0	0
Grp Sat Flow(s),veh/h/ln	1781	1777	1675	1781	1777	1843	1459	0	0	1654	0	0
Q Serve(g_s), s	0.9	0.0	0.0	2.1	19.8	19.8	27.9	0.0	0.0	0.0	0.0	0.0
Cycle Q Clear(g_c), s	0.9	0.0	0.0	2.1	19.8	19.8	30.4	0.0	0.0	2.5	0.0	0.0
Prop In Lane	1.00		0.65	1.00		0.08	0.77		0.15	0.41		0.36
Lane Grp Cap(c), veh/h	26	905	853	48	928	962	558	0	0	611	0	0
V/C Ratio(X)	0.63	0.35	0.35	0.79	0.56	0.56	0.83	0.00	0.00	0.10	0.00	0.00
Avail Cap(c_a), veh/h	287	905	853	287	928	962	617	0	0	673	0	0
HCM Platoon Ratio	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	0.98	0.98	0.98	1.00	1.00	1.00	1.00	0.00	0.00	1.00	0.00	0.00
Uniform Delay (d), s/veh	48.3	0.0	0.0	48.4	16.2	16.2	31.6	0.0	0.0	22.7	0.0	0.0
Incr Delay (d2), s/veh	8.8	1.0	1.1	10.2	0.5	0.5	8.3	0.0	0.0	0.1	0.0	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.4	0.3	0.3	1.1	7.6	7.9	11.8	0.0	0.0	1.1	0.0	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	57.1	1.0	1.1	58.6	16.6	16.6	39.9	0.0	0.0	22.8	0.0	0.0
LnGrp LOS	E	A	A	E	B	B	D	A	A	C	A	A
Approach Vol, veh/h		631			1100			460			64	
Approach Delay, s/veh		2.5			18.1			39.9			22.8	
Approach LOS		A			B			D			C	
Timer - Assigned Phs	1	2		4	5	6		8				
Phs Duration (G+Y+Rc), s	6.4	55.5		38.1	5.1	56.8		38.1				
Change Period (Y+Rc), s	3.7	4.6		* 4.2	3.7	4.6		* 4.2				
Max Green Setting (Gmax), s	16.1	33.4		* 38	16.1	33.4		* 38				
Max Q Clear Time (g_c+I1), s	4.1	2.0		4.5	2.9	21.8		32.4				
Green Ext Time (p_c), s	0.0	2.5		0.3	0.0	3.6		1.5				
Intersection Summary												
HCM 6th Ctrl Delay				18.3								
HCM 6th LOS				B								
Notes												
* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.												

Casa De Oro
8: Cordoba Ave & Campo Rd

Existing AM

Intersection												
Int Delay, s/veh	17.6											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Vol, veh/h	32	400	17	33	798	45	5	11	15	44	5	35
Future Vol, veh/h	32	400	17	33	798	45	5	11	15	44	5	35
Conflicting Peds, #/hr	3	0	13	13	0	3	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	50	-	-	50	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	84	84	84	75	75	75	41	41	41	81	81	81
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	38	476	20	44	1064	60	12	27	37	54	6	43
Major/Minor	Major1			Major2			Minor1			Minor2		
Conflicting Flow All	1127	0	0	509	0	0	1198	1790	261	1513	1770	565
Stage 1	-	-	-	-	-	-	575	575	-	1185	1185	-
Stage 2	-	-	-	-	-	-	623	1215	-	328	585	-
Critical Hdwy	4.14	-	-	4.14	-	-	7.54	6.54	6.94	7.54	6.54	6.94
Critical Hdwy Stg 1	-	-	-	-	-	-	6.54	5.54	-	6.54	5.54	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.54	5.54	-	6.54	5.54	-
Follow-up Hdwy	2.22	-	-	2.22	-	-	3.52	4.02	3.32	3.52	4.02	3.32
Pot Cap-1 Maneuver	616	-	-	1052	-	-	141	80	738	82	82	468
Stage 1	-	-	-	-	-	-	470	501	-	201	261	-
Stage 2	-	-	-	-	-	-	440	252	-	659	496	-
Platoon blocked, %		-	-		-	-						
Mov Cap-1 Maneuver	614	-	-	1039	-	-	109	71	729	~ 51	73	467
Mov Cap-2 Maneuver	-	-	-	-	-	-	109	71	-	~ 51	73	-
Stage 1	-	-	-	-	-	-	435	464	-	188	249	-
Stage 2	-	-	-	-	-	-	373	241	-	553	460	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	0.8			0.3			57.5			270.4		
HCM LOS							F			F		
Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1				
Capacity (veh/h)	140	614	-	-	1039	-	-	83				
HCM Lane V/C Ratio	0.54	0.062	-	-	0.042	-	-	1.249				
HCM Control Delay (s)	57.5	11.3	-	-	8.6	-	-	270.4				
HCM Lane LOS	F	B	-	-	A	-	-	F				
HCM 95th %tile Q(veh)	2.6	0.2	-	-	0.1	-	-	7.7				
Notes												
~: Volume exceeds capacity		\$: Delay exceeds 300s		+: Computation Not Defined				*: All major volume in platoon				

Casa De Oro
9: Granada Ave & Campo Rd & Casa De Oro Blvd

Existing AM

												
Movement	EBL2	EBL	EBR	EBR2	NBL	NBT	NBR	NBR2	SBL	SBT	SBR	NWL2
Lane Configurations												
Traffic Volume (vph)	17	66	345	9	23	1	25	87	40	3	15	9
Future Volume (vph)	17	66	345	9	23	1	25	87	40	3	15	9
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		4.4	5.3			4.2				4.2		4.4
Lane Util. Factor		1.00	0.88			1.00				1.00		1.00
Frpb, ped/bikes		1.00	1.00			1.00				1.00		1.00
Flpb, ped/bikes		1.00	1.00			1.00				1.00		1.00
Frt		1.00	0.85			0.89				0.97		1.00
Flt Protected		0.95	1.00			0.99				0.97		0.95
Satd. Flow (prot)		1770	2787			1641				1738		1770
Flt Permitted		0.95	1.00			0.93				0.33		0.95
Satd. Flow (perm)		1770	2787			1537				586		1770
Peak-hour factor, PHF	0.76	0.76	0.76	0.76	0.78	0.78	0.78	0.78	0.66	0.66	0.66	0.76
Adj. Flow (vph)	22	87	454	12	29	1	32	112	61	5	23	12
RTOR Reduction (vph)	0	0	83	0	0	55	0	0	0	11	0	0
Lane Group Flow (vph)	0	109	383	0	0	119	0	0	0	78	0	12
Confl. Bikes (#/hr)				3								
Turn Type	Prot	Prot	Prot		Perm	NA			Perm	NA		Prot
Protected Phases	5	5	2			8				4		1
Permitted Phases					8				4			
Actuated Green, G (s)		9.7	29.9			10.6				14.1		0.9
Effective Green, g (s)		9.7	29.9			10.6				14.1		0.9
Actuated g/C Ratio		0.11	0.33			0.12				0.16		0.01
Clearance Time (s)		4.4	5.3			4.2				4.2		4.4
Vehicle Extension (s)		4.0	4.0			1.0				1.0		1.0
Lane Grp Cap (vph)		189	920			180				91		17
v/s Ratio Prot		c0.06	0.14									0.01
v/s Ratio Perm						c0.08				c0.13		
v/c Ratio		0.58	0.42			0.66				0.86		0.71
Uniform Delay, d1		38.4	23.5			38.2				37.2		44.7
Progression Factor		1.00	1.00			1.00				1.00		1.00
Incremental Delay, d2		5.0	0.4			6.9				49.2		72.3
Delay (s)		43.5	23.9			45.1				86.4		117.0
Level of Service		D	C			D				F		F
Approach Delay (s)		27.6				45.1				86.4		
Approach LOS		C				D				F		
Intersection Summary												
HCM 2000 Control Delay			72.6			HCM 2000 Level of Service				E		
HCM 2000 Volume to Capacity ratio			0.84									
Actuated Cycle Length (s)			90.5			Sum of lost time (s)			22.3			
Intersection Capacity Utilization			61.0%			ICU Level of Service			B			
Analysis Period (min)			15									
c Critical Lane Group												


Casa De Oro
9: Granada Ave & Campo Rd & Casa De Oro Blvd

Existing AM



Movement	NWL	NWR	NWR2	SWL2	SWL	SWR	SWR2
Lane Configurations							
Traffic Volume (vph)	704	26	51	49	17	140	14
Future Volume (vph)	704	26	51	49	17	140	14
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	5.3				4.2	4.2	
Lane Util. Factor	0.97				1.00	0.95	
Frpb, ped/bikes	1.00				1.00	1.00	
Flpb, ped/bikes	1.00				1.00	1.00	
Frt	0.99				0.94	0.85	
Flt Protected	0.96				0.97	1.00	
Satd. Flow (prot)	3407				1696	1504	
Flt Permitted	0.96				0.97	1.00	
Satd. Flow (perm)	3407				1696	1504	
Peak-hour factor, PHF	0.76	0.76	0.76	0.71	0.71	0.71	0.71
Adj. Flow (vph)	926	34	67	69	24	197	20
RTOR Reduction (vph)	125	0	0	0	0	129	0
Lane Group Flow (vph)	902	0	0	0	160	21	0
Confl. Bikes (#/hr)							
Turn Type	Prot			Perm	Prot	Prot	
Protected Phases	6				3	3	
Permitted Phases				3			
Actuated Green, G (s)	21.1				12.7	12.7	
Effective Green, g (s)	21.1				12.7	12.7	
Actuated g/C Ratio	0.23				0.14	0.14	
Clearance Time (s)	5.3				4.2	4.2	
Vehicle Extension (s)	2.0				1.0	1.0	
Lane Grp Cap (vph)	794				238	211	
v/s Ratio Prot	c0.26					0.01	
v/s Ratio Perm					0.09		
v/c Ratio	1.14				0.67	0.10	
Uniform Delay, d1	34.7				36.9	33.9	
Progression Factor	1.00				1.00	1.00	
Incremental Delay, d2	76.4				5.8	0.1	
Delay (s)	111.1				42.7	34.0	
Level of Service	F				D	C	
Approach Delay (s)	111.2				38.5		
Approach LOS	F				D		
Intersection Summary							

10: Campo Rd/Campo Rd & SR-94 WB Ramps/Agua Dulce Blvd

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	SEL	SET	SER	NWL	NWT	NWR
Lane Configurations					↔		↔	↔		↔	↔	
Traffic Volume (veh/h)	0	0	0	194	162	289	18	322	189	496	526	183
Future Volume (veh/h)	0	0	0	194	162	289	18	322	189	496	526	183
Initial Q (Qb), veh				0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)				1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj				1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach				No			No			No		
Adj Sat Flow, veh/h/ln				1900	1870	1900	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h				234	195	348	22	393	230	557	591	206
Peak Hour Factor				0.83	0.83	0.83	0.82	0.82	0.82	0.89	0.89	0.89
Percent Heavy Veh, %				0	2	0	2	2	2	2	2	2
Cap, veh/h				203	169	302	75	629	363	528	1421	494
Arrive On Green				0.40	0.40	0.40	0.04	0.29	0.29	0.30	0.55	0.55
Sat Flow, veh/h				514	428	765	1781	2169	1253	1781	2586	900
Grp Volume(v), veh/h				777	0	0	22	321	302	557	406	391
Grp Sat Flow(s),veh/h/ln				1707	0	0	1781	1777	1645	1781	1777	1708
Q Serve(g_s), s				51.4	0.0	0.0	1.6	20.4	20.8	38.5	17.3	17.4
Cycle Q Clear(g_c), s				51.4	0.0	0.0	1.6	20.4	20.8	38.5	17.3	17.4
Prop In Lane				0.30		0.45	1.00		0.76	1.00		0.53
Lane Grp Cap(c), veh/h				675	0	0	75	515	477	528	976	939
V/C Ratio(X)				1.15	0.00	0.00	0.29	0.62	0.63	1.06	0.42	0.42
Avail Cap(c_a), veh/h				675	0	0	137	515	477	528	976	939
HCM Platoon Ratio				1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)				1.00	0.00	0.00	1.00	1.00	1.00	0.50	0.50	0.50
Uniform Delay (d), s/veh				39.3	0.0	0.0	60.4	40.0	40.1	45.8	17.1	17.1
Incr Delay (d2), s/veh				84.4	0.0	0.0	0.8	5.6	6.3	43.7	0.7	0.7
Initial Q Delay(d3),s/veh				0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln				37.0	0.0	0.0	0.7	9.5	9.1	22.9	7.0	6.7
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh				123.7	0.0	0.0	61.2	45.6	46.4	89.4	17.8	17.8
LnGrp LOS				F	A	A	E	D	D	F	B	B
Approach Vol, veh/h					777			645			1354	
Approach Delay, s/veh					123.7			46.5			47.3	
Approach LOS					F			D			D	
Timer - Assigned Phs	1	2			5	6		8				
Phs Duration (G+Y+Rc), s	11.1	78.7			44.8	45.0		57.7				
Change Period (Y+Rc), s	5.6	6.8			6.3	* 6.8		6.3				
Max Green Setting (Gmax), s	10.0	49.9			38.5	* 21		51.4				
Max Q Clear Time (g_c+I1), s	3.6	19.4			40.5	22.8		53.4				
Green Ext Time (p_c), s	0.0	5.3			0.0	0.0		0.0				
Intersection Summary												
HCM 6th Ctrl Delay				68.5								
HCM 6th LOS				E								
Notes												
User approved ignoring U-Turning movement.												
* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.												

Casa De Oro
11: Campo Rd & SR-94 EB Ramps

Existing AM

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	SEL	SET	SER	NWL	NWT	NWR
Lane Configurations												
Traffic Volume (vph)	196	5	571	0	0	0	180	282	0	0	1124	240
Future Volume (vph)	196	5	571	0	0	0	180	282	0	0	1124	240
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		6.3	4.5				5.6	6.3			6.3	6.3
Lane Util. Factor		1.00	1.00				1.00	0.95			0.95	1.00
Frt		1.00	0.85				1.00	1.00			1.00	0.85
Flt Protected		0.95	1.00				0.95	1.00			1.00	1.00
Satd. Flow (prot)		1776	1583				1770	3539			3539	1583
Flt Permitted		0.95	1.00				0.95	1.00			1.00	1.00
Satd. Flow (perm)		1776	1583				1770	3539			3539	1583
Peak-hour factor, PHF	0.81	0.81	0.81	0.92	0.92	0.92	0.75	0.75	0.75	0.92	0.92	0.92
Adj. Flow (vph)	242	6	705	0	0	0	240	376	0	0	1222	261
RTOR Reduction (vph)	0	0	49	0	0	0	0	0	0	0	0	124
Lane Group Flow (vph)	0	248	656	0	0	0	240	376	0	0	1222	137
Turn Type	Perm	NA	custom				Prot	NA			NA	Perm
Protected Phases		4	5				1	6			2	
Permitted Phases	4		4									2
Actuated Green, G (s)		23.5	51.1				20.8	41.8			47.5	47.5
Effective Green, g (s)		23.5	51.1				20.8	41.8			47.5	47.5
Actuated g/C Ratio		0.21	0.46				0.19	0.38			0.43	0.43
Clearance Time (s)		6.3	4.5				5.6	6.3			6.3	6.3
Vehicle Extension (s)		3.0	3.0				2.0	3.0			3.0	3.0
Lane Grp Cap (vph)		379	735				334	1344			1528	683
v/s Ratio Prot			c0.22				0.14	0.11			c0.35	
v/s Ratio Perm		0.14	0.19									0.09
v/c Ratio		0.65	0.89				0.72	0.28			0.80	0.20
Uniform Delay, d1		39.5	26.9				41.9	23.7			27.1	19.4
Progression Factor		1.00	1.00				1.00	1.00			1.00	1.00
Incremental Delay, d2		4.0	13.1				6.0	0.5			4.5	0.7
Delay (s)		43.6	40.1				47.9	24.2			31.6	20.1
Level of Service		D	D				D	C			C	C
Approach Delay (s)		41.0			0.0			33.4			29.6	
Approach LOS		D			A			C			C	
Intersection Summary												
HCM 2000 Control Delay		33.9			HCM 2000 Level of Service			C				
HCM 2000 Volume to Capacity ratio		0.88										
Actuated Cycle Length (s)		110.0			Sum of lost time (s)			18.2				
Intersection Capacity Utilization		67.3%			ICU Level of Service			C				
Analysis Period (min)		15										
c Critical Lane Group												

Casa De Oro
12: SR-94 WB Ramps & Agua Dulce Blvd

Existing AM

Intersection						
Int Delay, s/veh	110.5					
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	↑			↑	↖	↗
Traffic Vol, veh/h	202	0	0	334	314	60
Future Vol, veh/h	202	0	0	334	314	60
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	0
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	60	60	67	67	59	59
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	337	0	0	499	532	102
Major/Minor	Major1	Major2		Minor1		
Conflicting Flow All	0	-	-	-	836	337
Stage 1	-	-	-	-	337	-
Stage 2	-	-	-	-	499	-
Critical Hdwy	-	-	-	-	6.42	6.22
Critical Hdwy Stg 1	-	-	-	-	5.42	-
Critical Hdwy Stg 2	-	-	-	-	5.42	-
Follow-up Hdwy	-	-	-	-	3.518	3.318
Pot Cap-1 Maneuver	-	0	0	- ~	337	705
Stage 1	-	0	0	-	723	-
Stage 2	-	0	0	-	610	-
Platoon blocked, %	-			-		
Mov Cap-1 Maneuver	-	-	-	- ~	337	705
Mov Cap-2 Maneuver	-	-	-	- ~	337	-
Stage 1	-	-	-	-	723	-
Stage 2	-	-	-	-	610	-
Approach	EB	WB		NB		
HCM Control Delay, s	0	0		256		
HCM LOS				F		
Minor Lane/Major Mvmt	NBLn1	NBLn2	EBT	WBT		
Capacity (veh/h)	337	705	-	-		
HCM Lane V/C Ratio	1.579	0.144	-	-		
HCM Control Delay (s)	\$ 302.8	11	-	-		
HCM Lane LOS	F	B	-	-		
HCM 95th %tile Q(veh)	30.9	0.5	-	-		
Notes						
~: Volume exceeds capacity		\$: Delay exceeds 300s		+: Computation Not Defined		*: All major volume in platoon

Casa De Oro
1: Kenwood Dr & SR-94 EB Ramps

Existing PM

Intersection

Intersection Delay, s/veh 31.5
Intersection LOS D

Movement	WBL	WBR	SEL	SER	NEL	NET	NER	SWL	SWT	SWR
Lane Configurations										
Traffic Vol, veh/h	0	0	4	204	0	427	210	81	462	0
Future Vol, veh/h	0	0	4	204	0	427	210	81	462	0
Peak Hour Factor	0.92	0.92	0.96	0.96	0.84	0.84	0.84	0.88	0.88	0.88
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	0	0	4	213	0	508	250	92	525	0
Number of Lanes	0	0	1	1	0	2	1	0	2	0

Approach	NE	SW
Opposing Approach	SW	NE
Opposing Lanes	2	3
Conflicting Approach Left	SE	
Conflicting Lanes Left	3	0
Conflicting Approach Right		SE
Conflicting Lanes Right	0	3
HCM Control Delay	24.3	49.4
HCM LOS	C	E

Lane	NELn1	NELn2	NELn3	SELn1	SELn2	SELn3	SWLn1	SWLn2
Vol Left, %	0%	0%	0%	100%	100%	0%	34%	0%
Vol Thru, %	100%	100%	0%	0%	0%	0%	66%	100%
Vol Right, %	0%	0%	100%	0%	0%	100%	0%	0%
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop
Traffic Vol by Lane	214	214	210	248	252	204	235	308
LT Vol	0	0	0	248	252	0	81	0
Through Vol	214	214	0	0	0	0	154	308
RT Vol	0	0	210	0	0	204	0	0
Lane Flow Rate	254	254	250	258	263	212	267	350
Geometry Grp	8	8	8	7	7	7	8	8
Degree of Util (X)	0.659	0.659	0.474	0.643	0.653	0.456	0.72	0.926
Departure Headway (Hd)	9.341	9.341	6.828	8.954	8.954	7.722	9.702	9.524
Convergence, Y/N	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Cap	386	386	525	406	407	470	371	382
Service Time	7.112	7.112	4.599	6.654	6.654	5.422	7.478	7.301
HCM Lane V/C Ratio	0.658	0.658	0.476	0.635	0.646	0.451	0.72	0.916
HCM Control Delay	28.5	28.5	15.7	26.4	27	16.7	34	61.1
HCM Lane LOS	D	D	C	D	D	C	D	F
HCM 95th-tile Q	4.5	4.5	2.5	4.3	4.5	2.3	5.4	9.8

HCM 6th AWSC

2: Kenwood Dr & SR-94 WB Ramps

01/29/2020

Intersection	
Intersection Delay, s/veh	23.9
Intersection LOS	C

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NEL	NET	NER	SWL	SWT	SWR
Lane Configurations					↶	↶	↶	↶↶			↶↶	↶
Traffic Vol, veh/h	0	0	0	176	0	63	198	725	0	0	370	421
Future Vol, veh/h	0	0	0	176	0	63	198	725	0	0	370	421
Peak Hour Factor	0.96	0.96	0.96	0.89	0.89	0.89	0.92	0.92	0.92	0.98	0.98	0.98
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	0	0	0	198	0	71	215	788	0	0	378	430
Number of Lanes	0	0	0	0	1	1	1	2	0	0	2	1


Approach	WB	NE	SW
Opposing Approach		SW	NE
Opposing Lanes	0	3	3
Conflicting Approach Left	NE		WB
Conflicting Lanes Left	3	0	2
Conflicting Approach Right	SW	WB	
Conflicting Lanes Right	3	2	0
HCM Control Delay	21.5	28.6	18.8
HCM LOS	C	D	C

Lane	NELn1	NELn2	NELn3	WBLn1	WBLn2	SWLn1	SWLn2	SWLn3
Vol Left, %	100%	0%	0%	100%	0%	0%	0%	0%
Vol Thru, %	0%	100%	100%	0%	0%	100%	100%	0%
Vol Right, %	0%	0%	0%	0%	100%	0%	0%	100%
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop	Stop	Stop
Traffic Vol by Lane	198	363	363	176	63	185	185	421
LT Vol	198	0	0	176	0	0	0	0
Through Vol	0	363	363	0	0	185	185	0
RT Vol	0	0	0	0	63	0	0	421
Lane Flow Rate	215	394	394	198	71	189	189	430
Geometry Grp	8	8	8	8	8	8	8	8
Degree of Util (X)	0.5	0.858	0.664	0.549	0.172	0.434	0.434	0.689
Departure Headway (Hd)	8.356	7.843	6.064	9.991	8.772	8.271	8.271	5.771
Convergence, Y/N	Yes	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Cap	433	465	599	360	408	436	436	627
Service Time	6.082	5.569	3.79	7.768	6.548	5.999	5.999	3.499
HCM Lane V/C Ratio	0.497	0.847	0.658	0.55	0.174	0.433	0.433	0.686
HCM Control Delay	19.2	42.3	20	24.4	13.4	17.2	17.2	20.3
HCM Lane LOS	C	E	C	C	B	C	C	C
HCM 95th-tile Q	2.7	8.7	4.9	3.2	0.6	2.1	2.1	5.4

Intersection						
Int Delay, s/veh	7.2					
Movement	WBL	WBR	NET	NER	SWL	SWT
Lane Configurations						
Traffic Vol, veh/h	129	36	673	113	18	660
Future Vol, veh/h	129	36	673	113	18	660
Conflicting Peds, #/hr	0	0	0	6	6	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	0	-	-	0
Grade, %	0	-	0	-	-	0
Peak Hour Factor	94	94	98	98	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	137	38	687	115	20	717
Major/Minor	Minor1	Major1	Major2			
Conflicting Flow All	1150	407	0	0	808	0
Stage 1	751	-	-	-	-	-
Stage 2	399	-	-	-	-	-
Critical Hdwy	6.84	6.94	-	-	4.14	-
Critical Hdwy Stg 1	5.84	-	-	-	-	-
Critical Hdwy Stg 2	5.84	-	-	-	-	-
Follow-up Hdwy	3.52	3.32	-	-	2.22	-
Pot Cap-1 Maneuver	192	593	-	-	813	-
Stage 1	427	-	-	-	-	-
Stage 2	647	-	-	-	-	-
Platoon blocked, %			-	-		-
Mov Cap-1 Maneuver	183	590	-	-	808	-
Mov Cap-2 Maneuver	183	-	-	-	-	-
Stage 1	424	-	-	-	-	-
Stage 2	620	-	-	-	-	-
Approach	WB	NE		SW		
HCM Control Delay, s	69.1	0		0.4		
HCM LOS	F					
Minor Lane/Major Mvmt	NET	NERWBLn1	SWL	SWT		
Capacity (veh/h)	-	-	215	808	-	
HCM Lane V/C Ratio	-	-	0.816	0.024	-	
HCM Control Delay (s)	-	-	69.1	9.6	0.2	
HCM Lane LOS	-	-	F	A	A	
HCM 95th %tile Q(veh)	-	-	6	0.1	-	

Casa De Oro
4: Kenwood Dr & Campo Rd

Existing PM



Movement	EBT	EBR	WBL	WBT	NEL	NER
Lane Configurations	↑↑	↑	↑↑	↑	↑	↑↑
Traffic Volume (vph)	349	108	553	191	103	612
Future Volume (vph)	349	108	553	191	103	612
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	5.1	4.0	4.1	5.1	4.4	4.1
Lane Util. Factor	0.95	1.00	0.97	1.00	1.00	0.88
Frt	1.00	0.85	1.00	1.00	1.00	0.85
Flt Protected	1.00	1.00	0.95	1.00	0.95	1.00
Satd. Flow (prot)	3539	1583	3433	1863	1770	2787
Flt Permitted	1.00	1.00	0.95	1.00	0.95	1.00
Satd. Flow (perm)	3539	1583	3433	1863	1770	2787
Peak-hour factor, PHF	0.95	0.95	0.97	0.97	0.96	0.96
Adj. Flow (vph)	367	114	570	197	107	638
RTOR Reduction (vph)	0	0	0	0	0	385
Lane Group Flow (vph)	367	114	570	197	107	253
Turn Type	NA	Free	Prot	NA	Prot	pm+ov
Protected Phases	6		5	2	3	5
Permitted Phases		Free				3
Actuated Green, G (s)	46.8	100.0	26.4	60.7	13.2	39.6
Effective Green, g (s)	46.8	100.0	26.4	60.7	13.2	39.6
Actuated g/C Ratio	0.47	1.00	0.26	0.61	0.13	0.40
Clearance Time (s)	5.1		4.1	5.1	4.4	4.1
Vehicle Extension (s)	2.0		2.0	2.0	2.0	2.0
Lane Grp Cap (vph)	1656	1583	906	1130	233	1103
v/s Ratio Prot	c0.10		c0.17	0.11	c0.06	0.06
v/s Ratio Perm		0.07				0.03
v/c Ratio	0.22	0.07	0.63	0.17	0.46	0.23
Uniform Delay, d1	15.8	0.0	32.5	8.6	40.1	20.1
Progression Factor	1.00	1.00	1.50	0.38	1.00	1.00
Incremental Delay, d2	0.3	0.1	1.0	0.3	0.5	0.0
Delay (s)	16.1	0.1	49.6	3.6	40.6	20.1
Level of Service	B	A	D	A	D	C
Approach Delay (s)	12.3			37.8	23.0	
Approach LOS	B			D	C	
Intersection Summary						
HCM 2000 Control Delay			26.1		HCM 2000 Level of Service	C
HCM 2000 Volume to Capacity ratio			0.39			
Actuated Cycle Length (s)			100.0		Sum of lost time (s)	15.0
Intersection Capacity Utilization			42.5%		ICU Level of Service	A
Analysis Period (min)			15			

c Critical Lane Group

Casa De Oro
5: Campo Rd & Conrad Dr

Existing PM

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	135	819	15	14	584	52	0	0	12	79	13	157
Future Volume (vph)	135	819	15	14	584	52	0	0	12	79	13	157
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	4.1	5.1		5.1	5.1				5.1		5.8	4.1
Lane Util. Factor	1.00	0.95		1.00	0.95				1.00		1.00	1.00
Frpb, ped/bikes	1.00	1.00		1.00	1.00				1.00		1.00	1.00
Flpb, ped/bikes	1.00	1.00		1.00	1.00				1.00		1.00	1.00
Frt	1.00	1.00		1.00	0.99				0.86		1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00				1.00		0.96	1.00
Satd. Flow (prot)	1770	3528		1770	3492				1611		1786	1583
Flt Permitted	0.95	1.00		0.17	1.00				1.00		0.96	1.00
Satd. Flow (perm)	1770	3528		321	3492				1611		1786	1583
Peak-hour factor, PHF	0.93	0.93	0.93	0.96	0.96	0.96	0.75	0.75	0.75	0.93	0.93	0.93
Adj. Flow (vph)	145	881	16	15	608	54	0	0	16	85	14	169
RTOR Reduction (vph)	0	1	0	0	5	0	0	0	6	0	0	128
Lane Group Flow (vph)	145	896	0	15	657	0	0	0	10	0	99	41
Confl. Bikes (#/hr)			1			1						
Turn Type	Prot	NA		Perm	NA				Perm	Split	NA	pm+ov
Protected Phases	1	6			2					7	7	1
Permitted Phases				2					2			7
Actuated Green, G (s)	12.5	46.8		60.7	60.7				60.7		11.8	24.3
Effective Green, g (s)	12.5	46.8		60.7	60.7				60.7		11.8	24.3
Actuated g/C Ratio	0.12	0.47		0.61	0.61				0.61		0.12	0.24
Clearance Time (s)	4.1	5.1		5.1	5.1				5.1		5.8	4.1
Vehicle Extension (s)	2.0	2.0		2.0	2.0				2.0		2.0	2.0
Lane Grp Cap (vph)	221	1651		194	2119				977		210	384
v/s Ratio Prot	c0.08	c0.25			c0.19						c0.06	0.01
v/s Ratio Perm				0.05					0.01			0.01
v/c Ratio	0.66	0.54		0.08	0.31				0.01		0.47	0.11
Uniform Delay, d1	41.7	19.0		8.1	9.5				7.8		41.2	29.4
Progression Factor	1.11	0.77		0.65	0.67				1.00		1.00	1.00
Incremental Delay, d2	5.1	1.2		0.8	0.4				0.0		0.6	0.0
Delay (s)	51.3	15.9		6.0	6.7				7.8		41.8	29.5
Level of Service	D	B		A	A				A		D	C
Approach Delay (s)		20.9			6.7			7.8			34.0	
Approach LOS		C			A			A			C	
Intersection Summary												
HCM 2000 Control Delay			17.7			HCM 2000 Level of Service			B			
HCM 2000 Volume to Capacity ratio			0.50									
Actuated Cycle Length (s)			100.0			Sum of lost time (s)			15.0			
Intersection Capacity Utilization			46.5%			ICU Level of Service			A			
Analysis Period (min)			15									
c Critical Lane Group												

Casa De Oro
6: Bonita St & Campo Rd

Existing PM

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	41	675	55	23	493	19	74	15	54	33	18	40
Future Volume (veh/h)	41	675	55	23	493	19	74	15	54	33	18	40
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		0.98	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	45	734	60	24	514	20	85	17	62	52	29	63
Peak Hour Factor	0.92	0.92	0.92	0.96	0.96	0.96	0.87	0.87	0.87	0.63	0.63	0.63
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	2	2	2
Cap, veh/h	57	2346	192	35	2413	94	147	31	75	111	60	95
Arrive On Green	0.06	1.00	1.00	0.02	0.69	0.69	0.14	0.14	0.14	0.14	0.14	0.14
Sat Flow, veh/h	1781	3326	272	1781	3484	135	673	225	545	449	438	690
Grp Volume(v), veh/h	45	392	402	24	262	272	164	0	0	144	0	0
Grp Sat Flow(s),veh/h/ln	1781	1777	1821	1781	1777	1843	1443	0	0	1578	0	0
Q Serve(g_s), s	2.5	0.0	0.0	1.3	5.3	5.3	2.6	0.0	0.0	0.0	0.0	0.0
Cycle Q Clear(g_c), s	2.5	0.0	0.0	1.3	5.3	5.3	11.1	0.0	0.0	8.5	0.0	0.0
Prop In Lane	1.00		0.15	1.00		0.07	0.52		0.38	0.36		0.44
Lane Grp Cap(c), veh/h	57	1253	1284	35	1230	1276	253	0	0	266	0	0
V/C Ratio(X)	0.79	0.31	0.31	0.69	0.21	0.21	0.65	0.00	0.00	0.54	0.00	0.00
Avail Cap(c_a), veh/h	287	1253	1284	287	1230	1276	604	0	0	635	0	0
HCM Platoon Ratio	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	0.83	0.83	0.83	0.99	0.99	0.99	1.00	0.00	0.00	1.00	0.00	0.00
Uniform Delay (d), s/veh	46.4	0.0	0.0	48.7	5.5	5.5	41.9	0.0	0.0	40.8	0.0	0.0
Incr Delay (d2), s/veh	7.1	0.5	0.5	8.7	0.4	0.4	1.0	0.0	0.0	0.6	0.0	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	1.2	0.2	0.2	0.7	1.8	1.9	4.0	0.0	0.0	3.4	0.0	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	53.6	0.5	0.5	57.4	5.9	5.9	42.9	0.0	0.0	41.4	0.0	0.0
LnGrp LOS	D	A	A	E	A	A	D	A	A	D	A	A
Approach Vol, veh/h		839			558			164			144	
Approach Delay, s/veh		3.4			8.1			42.9			41.4	
Approach LOS		A			A			D			D	
Timer - Assigned Phs	1	2		4	5	6		8				
Phs Duration (G+Y+Rc), s	6.0	75.6		18.3	7.3	74.3		18.3				
Change Period (Y+Rc), s	4.1	5.1		4.6	4.1	5.1		4.6				
Max Green Setting (Gmax), s	16.1	32.1		38.0	16.1	32.1		38.0				
Max Q Clear Time (g_c+I1), s	3.3	2.0		10.5	4.5	7.3		13.1				
Green Ext Time (p_c), s	0.0	3.2		0.6	0.0	2.0		0.7				
Intersection Summary												
HCM 6th Ctrl Delay			12.0									
HCM 6th LOS			B									

Casa De Oro
7: Barcelona St & Campo Rd

Existing PM

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	10	494	236	57	363	20	147	9	63	22	26	22
Future Volume (veh/h)	10	494	236	57	363	20	147	9	63	22	26	22
Initial Q (Qb), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00		1.00	1.00		1.00	1.00		1.00	1.00		1.00
Parking Bus, Adj	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Work Zone On Approach		No			No			No			No	
Adj Sat Flow, veh/h/ln	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870	1870
Adj Flow Rate, veh/h	10	509	243	59	374	21	156	10	67	29	34	29
Peak Hour Factor	0.97	0.97	0.97	0.97	0.97	0.97	0.94	0.94	0.94	0.76	0.76	0.76
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	2	2	2
Cap, veh/h	17	1513	720	76	2329	130	242	13	79	120	137	96
Arrive On Green	0.02	1.00	1.00	0.04	0.68	0.68	0.18	0.18	0.18	0.18	0.18	0.18
Sat Flow, veh/h	1781	2336	1111	1781	3421	191	986	71	427	396	741	523
Grp Volume(v), veh/h	10	387	365	59	194	201	233	0	0	92	0	0
Grp Sat Flow(s),veh/h/ln	1781	1777	1670	1781	1777	1836	1484	0	0	1659	0	0
Q Serve(g_s), s	0.6	0.0	0.0	3.3	3.9	3.9	10.5	0.0	0.0	0.0	0.0	0.0
Cycle Q Clear(g_c), s	0.6	0.0	0.0	3.3	3.9	3.9	15.0	0.0	0.0	4.5	0.0	0.0
Prop In Lane	1.00		0.66	1.00		0.10	0.67		0.29	0.32		0.32
Lane Grp Cap(c), veh/h	17	1151	1082	76	1210	1250	334	0	0	353	0	0
V/C Ratio(X)	0.58	0.34	0.34	0.77	0.16	0.16	0.70	0.00	0.00	0.26	0.00	0.00
Avail Cap(c_a), veh/h	287	1151	1082	287	1210	1250	611	0	0	661	0	0
HCM Platoon Ratio	2.00	2.00	2.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	0.96	0.96	0.96	1.00	1.00	1.00	1.00	0.00	0.00	1.00	0.00	0.00
Uniform Delay (d), s/veh	48.8	0.0	0.0	47.4	5.7	5.7	39.1	0.0	0.0	35.1	0.0	0.0
Incr Delay (d2), s/veh	10.4	0.8	0.8	6.1	0.0	0.0	2.6	0.0	0.0	0.4	0.0	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.3	0.2	0.2	1.6	1.3	1.3	5.8	0.0	0.0	2.0	0.0	0.0
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh	59.3	0.8	0.8	53.5	5.7	5.7	41.8	0.0	0.0	35.5	0.0	0.0
LnGrp LOS	E	A	A	D	A	A	D	A	A	D	A	A
Approach Vol, veh/h		762			454			233			92	
Approach Delay, s/veh		1.6			11.9			41.8			35.5	
Approach LOS		A			B			D			D	
Timer - Assigned Phs	1	2		4	5	6		8				
Phs Duration (G+Y+Rc), s	8.0	69.4		22.6	4.7	72.7		22.6				
Change Period (Y+Rc), s	3.7	4.6		* 4.2	3.7	4.6		* 4.2				
Max Green Setting (Gmax), s	16.1	33.4		* 38	16.1	33.4		* 38				
Max Q Clear Time (g_c+I1), s	5.3	2.0		6.5	2.6	5.9		17.0				
Green Ext Time (p_c), s	0.0	3.2		0.5	0.0	1.4		1.4				
Intersection Summary												
HCM 6th Ctrl Delay				12.7								
HCM 6th LOS				B								
Notes												
* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.												

Intersection												
Int Delay, s/veh	3.4											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Vol, veh/h	60	527	17	27	365	28	10	4	20	33	11	49
Future Vol, veh/h	60	527	17	27	365	28	10	4	20	33	11	49
Conflicting Peds, #/hr	3	0	13	13	0	3	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	50	-	-	50	-	-	-	-	-	-	-	-
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	92	92	92	96	96	96	77	77	77	78	78	78
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	65	573	18	28	380	29	13	5	26	42	14	63

Major/Minor	Major1			Major2			Minor1			Minor2		
Conflicting Flow All	412	0	0	604	0	0	978	1193	309	873	1188	208
Stage 1	-	-	-	-	-	-	725	725	-	454	454	-
Stage 2	-	-	-	-	-	-	253	468	-	419	734	-
Critical Hdwy	4.14	-	-	4.14	-	-	7.54	6.54	6.94	7.54	6.54	6.94
Critical Hdwy Stg 1	-	-	-	-	-	-	6.54	5.54	-	6.54	5.54	-
Critical Hdwy Stg 2	-	-	-	-	-	-	6.54	5.54	-	6.54	5.54	-
Follow-up Hdwy	2.22	-	-	2.22	-	-	3.52	4.02	3.32	3.52	4.02	3.32
Pot Cap-1 Maneuver	1143	-	-	970	-	-	205	186	687	244	187	798
Stage 1	-	-	-	-	-	-	383	428	-	555	568	-
Stage 2	-	-	-	-	-	-	729	560	-	582	424	-
Platoon blocked, %	-	-	-	-	-	-	-	-	-	-	-	-
Mov Cap-1 Maneuver	1140	-	-	958	-	-	163	168	678	214	169	796
Mov Cap-2 Maneuver	-	-	-	-	-	-	163	168	-	214	169	-
Stage 1	-	-	-	-	-	-	357	399	-	522	550	-
Stage 2	-	-	-	-	-	-	635	542	-	521	395	-

Approach	EB			WB			NB			SB		
HCM Control Delay, s	0.8			0.6			19.2			21.9		
HCM LOS							C			C		

Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1
Capacity (veh/h)	297	1140	-	-	958	-	-	331
HCM Lane V/C Ratio	0.149	0.057	-	-	0.029	-	-	0.36
HCM Control Delay (s)	19.2	8.3	-	-	8.9	-	-	21.9
HCM Lane LOS	C	A	-	-	A	-	-	C
HCM 95th %tile Q(veh)	0.5	0.2	-	-	0.1	-	-	1.6

Casa De Oro
9: Granada Ave & Campo Rd & Casa De Oro Blvd

Existing PM

												
Movement	EBL2	EBL	EBR	EBR2	NBL	NBT	NBR	NBR2	SBL	SBT	SBR	NWL2
Lane Configurations												
Traffic Volume (vph)	3	83	474	9	13	1	7	49	29	3	9	19
Future Volume (vph)	3	83	474	9	13	1	7	49	29	3	9	19
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		4.4	5.3			4.2				4.2		4.4
Lane Util. Factor		1.00	0.88			1.00				1.00		1.00
Frpb, ped/bikes		1.00	1.00			1.00				1.00		1.00
Flpb, ped/bikes		1.00	1.00			1.00				1.00		1.00
Frt		1.00	0.85			0.89				0.97		1.00
Flt Protected		0.95	1.00			0.99				0.97		0.95
Satd. Flow (prot)		1770	2787			1645				1746		1770
Flt Permitted		0.95	1.00			0.92				0.38		0.95
Satd. Flow (perm)		1770	2787			1526				686		1770
Peak-hour factor, PHF	0.94	0.94	0.94	0.94	0.80	0.80	0.80	0.80	0.60	0.60	0.60	0.92
Adj. Flow (vph)	3	88	504	10	16	1	9	61	48	5	15	21
RTOR Reduction (vph)	0	0	78	0	0	57	0	0	0	9	0	0
Lane Group Flow (vph)	0	91	436	0	0	30	0	0	0	59	0	21
Confl. Bikes (#/hr)				3								
Turn Type	Prot	Prot	Prot		Perm	NA			Perm	NA		Prot
Protected Phases	5	5	2			8				4		1
Permitted Phases					8				4			
Actuated Green, G (s)		8.4	29.1			4.4				10.9		1.7
Effective Green, g (s)		8.4	29.1			4.4				10.9		1.7
Actuated g/C Ratio		0.11	0.39			0.06				0.14		0.02
Clearance Time (s)		4.4	5.3			4.2				4.2		4.4
Vehicle Extension (s)		4.0	4.0			1.0				1.0		1.0
Lane Grp Cap (vph)		197	1078			89				99		40
v/s Ratio Prot		c0.05	c0.16									0.01
v/s Ratio Perm						c0.02				c0.09		
v/c Ratio		0.46	0.40			0.33				0.59		0.53
Uniform Delay, d1		31.3	16.8			34.0				30.1		36.4
Progression Factor		1.00	1.00			1.00				1.00		1.00
Incremental Delay, d2		2.3	0.3			0.8				6.2		5.6
Delay (s)		33.6	17.1			34.8				36.2		42.0
Level of Service		C	B			C				D		D
Approach Delay (s)		19.6				34.8				36.2		
Approach LOS		B				C				D		
Intersection Summary												
HCM 2000 Control Delay			23.6			HCM 2000 Level of Service				C		
HCM 2000 Volume to Capacity ratio			0.48									
Actuated Cycle Length (s)			75.2			Sum of lost time (s)			22.3			
Intersection Capacity Utilization			43.3%			ICU Level of Service			A			
Analysis Period (min)			15									
c Critical Lane Group												

Casa De Oro
9: Granada Ave & Campo Rd & Casa De Oro Blvd

Existing PM



Movement	NWL	NWR	NWR2	SWL2	SWL	SWR	SWR2
Lane Configurations							
Traffic Volume (vph)	312	11	44	39	5	78	4
Future Volume (vph)	312	11	44	39	5	78	4
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	5.3				4.2	4.2	
Lane Util. Factor	0.97				1.00	0.95	
Frpb, ped/bikes	1.00				1.00	1.00	
Flpb, ped/bikes	1.00				1.00	1.00	
Frt	0.98				0.95	0.85	
Flt Protected	0.96				0.97	1.00	
Satd. Flow (prot)	3388				1715	1504	
Flt Permitted	0.96				0.97	1.00	
Satd. Flow (perm)	3388				1715	1504	
Peak-hour factor, PHF	0.92	0.92	0.92	0.77	0.77	0.77	0.77
Adj. Flow (vph)	339	12	48	51	6	101	5
RTOR Reduction (vph)	117	0	0	0	0	72	0
Lane Group Flow (vph)	282	0	0	0	84	7	0
Confl. Bikes (#/hr)							
Turn Type	Prot			Perm	Prot	Prot	
Protected Phases	6				3	3	
Permitted Phases				3			
Actuated Green, G (s)	22.4				6.8	6.8	
Effective Green, g (s)	22.4				6.8	6.8	
Actuated g/C Ratio	0.30				0.09	0.09	
Clearance Time (s)	5.3				4.2	4.2	
Vehicle Extension (s)	2.0				1.0	1.0	
Lane Grp Cap (vph)	1009				155	136	
v/s Ratio Prot	0.08					0.00	
v/s Ratio Perm					0.05		
v/c Ratio	0.28				0.54	0.05	
Uniform Delay, d1	20.2				32.7	31.3	
Progression Factor	1.00				1.00	1.00	
Incremental Delay, d2	0.1				2.1	0.1	
Delay (s)	20.3				34.8	31.3	
Level of Service	C				C	C	
Approach Delay (s)	21.4				33.1		
Approach LOS	C				C		
Intersection Summary							

10: Campo Rd/Campo Rd & SR-94 WB Ramps/Agua Dulce Blvd

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	SEU	SEL	SET	SER	NWL	NWT
Lane Configurations												
Traffic Volume (veh/h)	0	0	0	201	63	155	2	8	443	126	519	273
Future Volume (veh/h)	0	0	0	201	63	155	2	8	443	126	519	273
Initial Q (Qb), veh				0	0	0		0	0	0	0	0
Ped-Bike Adj(A_pbT)				1.00		1.00		1.00		1.00	1.00	
Parking Bus, Adj				1.00	1.00	1.00		1.00	1.00	1.00	1.00	1.00
Work Zone On Approach				No				No				No
Adj Sat Flow, veh/h/ln				1900	1870	1900		1870	1870	1870	1870	1870
Adj Flow Rate, veh/h				242	76	187		9	509	145	558	294
Peak Hour Factor				0.83	0.83	0.83		0.87	0.87	0.87	0.93	0.93
Percent Heavy Veh, %				0	2	0		2	2	2	2	2
Cap, veh/h				262	82	202		38	608	172	530	1398
Arrive On Green				0.32	0.32	0.32		0.02	0.22	0.22	0.30	0.50
Sat Flow, veh/h				822	258	635		1781	2733	775	1781	2772
Grp Volume(v), veh/h				505	0	0		9	330	324	558	187
Grp Sat Flow(s),veh/h/ln				1715	0	0		1781	1777	1731	1781	1777
Q Serve(g_s), s				34.1	0.0	0.0		0.6	21.3	21.5	35.7	7.0
Cycle Q Clear(g_c), s				34.1	0.0	0.0		0.6	21.3	21.5	35.7	7.0
Prop In Lane				0.48		0.37		1.00		0.45	1.00	
Lane Grp Cap(c), veh/h				546	0	0		38	395	385	530	896
V/C Ratio(X)				0.92	0.00	0.00		0.23	0.84	0.84	1.05	0.21
Avail Cap(c_a), veh/h				629	0	0		148	395	385	530	896
HCM Platoon Ratio				1.00	1.00	1.00		1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)				1.00	0.00	0.00		1.00	1.00	1.00	0.77	0.77
Uniform Delay (d), s/veh				39.5	0.0	0.0		57.7	44.6	44.6	42.2	16.5
Incr Delay (d2), s/veh				18.2	0.0	0.0		1.1	18.5	19.5	49.1	0.4
Initial Q Delay(d3),s/veh				0.0	0.0	0.0		0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln				17.0	0.0	0.0		0.3	11.2	11.1	22.4	2.8
Unsig. Movement Delay, s/veh												
LnGrp Delay(d),s/veh				57.7	0.0	0.0		58.9	63.0	64.2	91.2	16.9
LnGrp LOS				E	A	A		E	E	E	F	B
Approach Vol, veh/h					505				663			932
Approach Delay, s/veh					57.7				63.5			61.4
Approach LOS					E				E			E
Timer - Assigned Phs	1	2			5	6		8				
Phs Duration (G+Y+Rc), s	8.2	67.3			42.0	33.5		44.5				
Change Period (Y+Rc), s	5.6	6.8			6.3	* 6.8		6.3				
Max Green Setting (Gmax), s	10.0	47.3			35.7	* 21		44.0				
Max Q Clear Time (g_c+I1), s	2.6	9.2			37.7	23.5		36.1				
Green Ext Time (p_c), s	0.0	2.2			0.0	0.0		2.1				
Intersection Summary												
HCM 6th Ctrl Delay				61.2								
HCM 6th LOS				E								
Notes												
User approved ignoring U-Turning movement.												
* HCM 6th computational engine requires equal clearance times for the phases crossing the barrier.												



Movement	NWR
Lane Configurations	
Traffic Volume (veh/h)	74
Future Volume (veh/h)	74
Initial Q (Qb), veh	0
Ped-Bike Adj(A_pbT)	1.00
Parking Bus, Adj	1.00
Work Zone On Approach	
Adj Sat Flow, veh/h/ln	1870
Adj Flow Rate, veh/h	80
Peak Hour Factor	0.93
Percent Heavy Veh, %	2
Cap, veh/h	374
Arrive On Green	0.50
Sat Flow, veh/h	741
Grp Volume(v), veh/h	187
Grp Sat Flow(s),veh/h/ln	1737
Q Serve(g_s), s	7.2
Cycle Q Clear(g_c), s	7.2
Prop In Lane	0.43
Lane Grp Cap(c), veh/h	876
V/C Ratio(X)	0.21
Avail Cap(c_a), veh/h	876
HCM Platoon Ratio	1.00
Upstream Filter(I)	0.77
Uniform Delay (d), s/veh	16.5
Incr Delay (d2), s/veh	0.4
Initial Q Delay(d3),s/veh	0.0
%ile BackOfQ(50%),veh/ln	2.9
Unsig. Movement Delay, s/veh	
LnGrp Delay(d),s/veh	17.0
LnGrp LOS	B
Approach Vol, veh/h	
Approach Delay, s/veh	
Approach LOS	
Timer - Assigned Phs	

Casa De Oro
11: Campo Rd & SR-94 EB Ramps

Existing PM

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	SEL	SET	SER	NWL	NWT	NWR
Lane Configurations								 			 	
Traffic Volume (vph)	139	1	800	0	0	0	189	456	0	0	722	208
Future Volume (vph)	139	1	800	0	0	0	189	456	0	0	722	208
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		6.3	5.1				5.6	6.3			6.3	6.3
Lane Util. Factor		1.00	1.00				1.00	0.95			0.95	1.00
Frt		1.00	0.85				1.00	1.00			1.00	0.85
Flt Protected		0.95	1.00				0.95	1.00			1.00	1.00
Satd. Flow (prot)		1775	1583				1770	3539			3539	1583
Flt Permitted		0.95	1.00				0.95	1.00			1.00	1.00
Satd. Flow (perm)		1775	1583				1770	3539			3539	1583
Peak-hour factor, PHF	0.97	0.97	0.97	0.92	0.92	0.92	0.96	0.96	0.96	0.89	0.89	0.89
Adj. Flow (vph)	143	1	825	0	0	0	197	475	0	0	811	234
RTOR Reduction (vph)	0	0	35	0	0	0	0	0	0	0	0	144
Lane Group Flow (vph)	0	144	790	0	0	0	197	475	0	0	811	90
Turn Type	Perm	NA	custom				Prot	NA			NA	Perm
Protected Phases		4	5				1	6			2	
Permitted Phases	4		4									2
Actuated Green, G (s)		17.4	45.3				19.9	27.0			34.5	34.5
Effective Green, g (s)		17.4	45.3				19.9	27.0			34.5	34.5
Actuated g/C Ratio		0.19	0.50				0.22	0.30			0.38	0.38
Clearance Time (s)		6.3	5.1				5.6	6.3			6.3	6.3
Vehicle Extension (s)		3.0	2.0				2.0	3.0			3.0	3.0
Lane Grp Cap (vph)		343	796				391	1061			1356	606
v/s Ratio Prot			c0.31				0.11	0.13			c0.23	
v/s Ratio Perm		0.08	0.19									0.06
v/c Ratio		0.42	0.99				0.50	0.45			0.60	0.15
Uniform Delay, d1		31.9	22.2				30.7	25.5			22.2	18.1
Progression Factor		1.00	1.00				1.00	1.00			1.00	1.00
Incremental Delay, d2		0.8	29.8				0.4	1.4			2.0	0.5
Delay (s)		32.7	51.9				31.1	26.8			24.2	18.7
Level of Service		C	D				C	C			C	B
Approach Delay (s)		49.1			0.0			28.1			22.9	
Approach LOS		D			A			C			C	
Intersection Summary												
HCM 2000 Control Delay			33.7				HCM 2000 Level of Service				C	
HCM 2000 Volume to Capacity ratio			0.87									
Actuated Cycle Length (s)			90.0				Sum of lost time (s)			18.2		
Intersection Capacity Utilization			71.6%				ICU Level of Service			C		
Analysis Period (min)			15									
c Critical Lane Group												

Intersection

Int Delay, s/veh 8.1

Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations	↑			↑	↘	↘
Traffic Vol, veh/h	81	0	0	107	316	14
Future Vol, veh/h	81	0	0	107	316	14
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Stop	Stop
RT Channelized	-	None	-	None	-	None
Storage Length	-	-	-	-	0	0
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	72	72	67	67	93	93
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	113	0	0	160	340	15

Major/Minor	Major1	Major2	Minor1		
Conflicting Flow All	0	-	-	-	273 113
Stage 1	-	-	-	-	113 -
Stage 2	-	-	-	-	160 -
Critical Hdwy	-	-	-	-	6.42 6.22
Critical Hdwy Stg 1	-	-	-	-	5.42 -
Critical Hdwy Stg 2	-	-	-	-	5.42 -
Follow-up Hdwy	-	-	-	-	3.518 3.318
Pot Cap-1 Maneuver	-	0	0	-	716 940
Stage 1	-	0	0	-	912 -
Stage 2	-	0	0	-	869 -
Platoon blocked, %	-			-	
Mov Cap-1 Maneuver	-	-	-	-	716 940
Mov Cap-2 Maneuver	-	-	-	-	716 -
Stage 1	-	-	-	-	912 -
Stage 2	-	-	-	-	869 -

Approach	EB	WB	NB
HCM Control Delay, s	0	0	14.3
HCM LOS			B

Minor Lane/Major Mvmt	NBLn1	NBLn2	EBT	WBT
Capacity (veh/h)	716	940	-	-
HCM Lane V/C Ratio	0.475	0.016	-	-
HCM Control Delay (s)	14.5	8.9	-	-
HCM Lane LOS	B	A	-	-
HCM 95th %tile Q(veh)	2.6	0	-	-

Attachment F: Parking Utilization Worksheets

On-Street Parking Utilization

Parking Zone	Street	Segment	Side-of-Street	Inventory		10:00 AM	11:00 AM	12:00 PM	1:00 PM	2:00 PM	3:00 PM	4:00 PM
01	San Juan St	School Driveway to Bonita St.	North	7	Occupancy	3	5	5	4	4	4	3
		Conrad Dr. to 180' East of Conrad Dr.	South	9	Percent	42.9%	71.4%	71.4%	57.1%	57.1%	57.1%	42.9%
					Occupancy	6	8	8	7	8	8	7
02	Dolores St	Barcelona St. to Cordoba Ave.	North	10	Percent	66.7%	88.9%	88.9%	77.8%	88.9%	88.9%	77.8%
			South	10	Occupancy	9	9	10	10	10	9	9
		Cordoba Ave. to Granada Ave.	North	8	Percent	90.0%	90.0%	100.0%	100.0%	100.0%	90.0%	90.0%
South	8		Occupancy	3	3	7	8	9	7	8		
03	Dolores St	Cordoba Ave. to Granada Ave.	North	8	Percent	30.0%	30.0%	70.0%	80.0%	90.0%	70.0%	80.0%
			South	8	Occupancy	4	4	4	4	5	5	6
		San Juan St. to Campo Rd.	East	7	Percent	50.0%	50.0%	50.0%	50.0%	62.5%	62.5%	75.0%
West	6		Occupancy	4	4	4	4	4	4	4		
04	Conrad Dr	San Juan St. to Campo Rd.	East	7	Percent	50.0%	50.0%	50.0%	50.0%	50.0%	50.0%	50.0%
			West	6	Occupancy	4	5	5	4	5	5	5
		San Juan St. to Campo Rd.	East	7	Percent	57.1%	71.4%	71.4%	57.1%	71.4%	71.4%	71.4%
West	6		Occupancy	2	4	4	4	4	3	2		
05	Bonita St	San Juan St. to Campo Rd.	East	7	Percent	33.3%	66.7%	66.7%	66.7%	66.7%	50.0%	33.3%
			West	10	Occupancy	3	3	3	4	5	5	4
		Campo Rd. to Dolores St.	East	5	Percent	42.9%	42.9%	42.9%	57.1%	71.4%	71.4%	57.1%
West	8		Occupancy	3	5	5	4	3	3	4		
06	Bonita St	Campo Rd. to Dolores St.	East	5	Percent	30.0%	50.0%	50.0%	40.0%	30.0%	30.0%	40.0%
			West	8	Occupancy	4	5	5	5	5	5	4
		San Juan St. to Campo Rd.	East	7	Percent	80.0%	100.0%	100.0%	100.0%	100.0%	100.0%	80.0%
West	7		Occupancy	6	6	6	5	5	5	5		
07	Barcelona St	San Juan St. to Campo Rd.	East	7	Percent	75.0%	75.0%	75.0%	62.5%	62.5%	62.5%	62.5%
			West	7	Occupancy	6	7	6	4	4	4	3
		Campo Rd. to Dolores St.	East	5	Percent	85.7%	100.0%	85.7%	57.1%	57.1%	57.1%	42.9%
West	6		Occupancy	3	4	4	3	3	3	4		
08	Barcelona St	Campo Rd. to Dolores St.	East	5	Percent	42.9%	57.1%	57.1%	42.9%	42.9%	42.9%	57.1%
			West	6	Occupancy	5	5	4	3	3	4	4
		San Juan St. to Campo Rd.	East	8	Percent	100.0%	100.0%	83.3%	83.3%	83.3%	83.3%	83.3%
West	5		Occupancy	6	6	5	5	5	5	5		
09	Cordoba Ave	San Juan St. to Campo Rd.	East	8	Percent	100.0%	100.0%	83.3%	83.3%	83.3%	83.3%	83.3%
			West	5	Occupancy	1	1	2	2	2	2	1
		Campo Rd. to Dolores St.	East	6	Percent	12.5%	12.5%	25.0%	25.0%	25.0%	25.0%	12.5%
West	8		Occupancy	0	0	0	0	1	1	0		
10	Cordoba Ave	Campo Rd. to Dolores St.	East	6	Percent	0.0%	0.0%	0.0%	0.0%	20.0%	20.0%	0.0%
			West	8	Occupancy	6	6	5	4	4	5	3
		San Juan St. to Campo Rd.	East	8	Percent	100.0%	100.0%	83.3%	66.7%	66.7%	83.3%	50.0%
West	5		Occupancy	4	4	3	4	3	4	2		
11	Granda Ave	San Juan St. to Campo Rd.	East	8	Percent	50.0%	50.0%	37.5%	50.0%	37.5%	50.0%	25.0%
			West	5	Occupancy	6	6	7	8	8	7	6
		Campo Rd. to Dolores St.	East	8	Percent	75.0%	75.0%	87.5%	100.0%	100.0%	87.5%	75.0%
West	7		Occupancy	3	3	4	4	2	2	2		
12	Granda Ave	Campo Rd. to Dolores St.	East	8	Percent	60.0%	60.0%	80.0%	80.0%	40.0%	40.0%	40.0%
			West	7	Occupancy	1	1	1	0	0	1	0
		San Juan St. to Campo Rd.	East	8	Percent	12.5%	12.5%	12.5%	0.0%	0.0%	12.5%	0.0%
West	7		Occupancy	0	0	1	0	0	0	0		
Total On-Street Inventory				175	Total Occupancy	92	104	108	100	102	101	91
					Total Utilization	52.6%	59.4%	61.7%	57.1%	58.3%	57.7%	52.0%

	> 85%
	70% - 85%
	55% - 70%
	< 55%

Off-Street Parking Utilization

Parking Zone	Type	Inventory		10:00 AM	11:00 AM	12:00 PM	1:00 PM	2:00 PM	3:00 PM	4:00 PM
13	Regular	11	Total Occupancy	3	2	2	4	4	3	5
			Percent	27.3%	18.2%	18.2%	36.4%	36.4%	27.3%	45.5%
14	Regular	11	Total Occupancy	3	4	2	4	4	4	5
			Percent	27.3%	36.4%	18.2%	36.4%	36.4%	36.4%	45.5%
15	Regular	103		20	25	35	26	27	17	21
	Handicap	4		0	0	1	1	0	0	0
	Handicap Van	2		0	0	1	1	0	0	0
	Total Inventory	109	Total Occupancy	20	25	37	28	27	17	21
			Percent	18.3%	22.9%	33.9%	25.7%	24.8%	15.6%	19.3%
16	Regular	24		3	3	1	2	4	4	6
	Handicap Van	1		0	0	0	0	0	0	0
	Total Inventory	25	Total Occupancy	3	3	1	2	4	4	6
			Percent	12.0%	12.0%	4.0%	8.0%	16.0%	16.0%	24.0%
17	Regular	9		4	6	8	8	5	9	6
	Handicap	1		0	1	1	0	0	0	0
	Round Table	8		2	3	6	6	3	4	4
	Customer Only	2		1	1	2	2	2	1	1
	Patient/Customer	5		5	3	3	5	5	5	5
	Total Inventory	25	Total Occupancy	12	14	20	21	15	19	16
			Percent	48.0%	56.0%	80.0%	84.0%	60.0%	76.0%	64.0%
18	Regular	27		14	14	14	13	11	6	5
	Handicap	1		0	0	0	0	0	0	0
	Reserved for Pastor	1		0	0	1	1	0	0	0
	Total Inventory	29	Total Occupancy	14	14	15	14	11	6	5
			Percent	48.3%	48.3%	51.7%	48.3%	37.9%	20.7%	17.2%
19	Regular	34		19	22	19	21	19	25	23
	Handicap	1		0	0	0	0	0	0	0
	Handicap Van	1		0	0	0	0	0	0	0
	Total Inventory	36	Total Occupancy	19	22	19	21	19	25	23
			Percent	52.8%	61.1%	52.8%	58.3%	52.8%	69.4%	63.9%
20	Regular	15		10	10	8	5	7	9	4
	Handicap									
	Van	1		1	0	0	0	0	0	0
	Total Inventory	16	Total Occupancy	11	10	8	5	7	9	4
			Percent	68.8%	62.5%	50.0%	31.3%	43.8%	56.3%	25.0%
21	Regular	33		9	7	16	6	7	7	8
	Handicap	1		0	0	0	0	0	0	0
	Handicap Van	1		0	1	0	0	0	0	1
	Total Inventory	35	Total Occupancy	9	8	16	6	7	7	9
			Percent	25.7%	22.9%	45.7%	17.1%	20.0%	20.0%	25.7%
22	Regular	10		1	1	2	1	1	1	0
	Handicap Van	1		0	0	0	0	0	0	0
	Total Inventory	11	Total Occupancy	1	1	2	1	1	1	0
			Percent	9.1%	9.1%	18.2%	9.1%	9.1%	9.1%	0.0%
23	Regular	2		1	2	1	0	1	2	1
	Handicap Van	1		0	0	0	0	0	0	0
	Total Inventory	3	Total Occupancy	1	2	1	0	1	2	1
			Percent	33.3%	66.7%	33.3%	0.0%	33.3%	66.7%	33.3%
24	Regular	69		15	19	22	22	28	30	28
	Handicap	2		0	1	0	0	1	0	0
	Handicap Van	2		0	1	0	0	0	1	1
	Total Inventory	73	Total Occupancy	15	21	22	22	29	31	29
			Percent	20.5%	28.8%	30.1%	30.1%	39.7%	42.5%	39.7%
25	Regular	117		32	36	31	45	36	43	43
	Handicap	3		0	0	1	1	0	1	0
	Handicap Van	3		0	1	0	0	0	0	1
	Total Inventory	123	Total Occupancy	32	37	32	46	36	44	44
			Percent	26.0%	30.1%	26.0%	37.4%	29.3%	35.8%	35.8%
26	Regular	5	Total Occupancy	0	0	0	0	0	0	0
			Percent	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
27	Unmarked Spaces	(1)		0	0	0	1	1	1	1

Off-Street Parking Utilization

Parking Zone	Type	Inventory		10:00 AM	11:00 AM	12:00 PM	1:00 PM	2:00 PM	3:00 PM	4:00 PM
28	Regular	49		23	24	24	24	24	22	21
	Handicap	1		0	0	0	0	0	0	0
	Handicap Van	1		0	0	0	0	0	0	0
	Total Inventory	51	Total Occupancy	23	24	24	24	24	22	21
			Percent	45.1%	47.1%	47.1%	47.1%	47.1%	43.1%	41.2%
29	Regular	16	Total Occupancy	14	15	15	16	14	15	13
			Percent	87.5%	93.8%	93.8%	100.0%	87.5%	93.8%	81.3%
30	Regular	54	Total Occupancy	5	6	6	6	6	5	5
			Percent	9.3%	11.1%	11.1%	11.1%	11.1%	9.3%	9.3%
31	Regular	89		40	48	45	38	26	23	27
	Handicap	8		1	2	3	4	3	3	2
	Veteran Parking	1		0	1	0	0	1	1	0
	Family Parking	1		1	0	0	1	1	1	1
	15 Min (Green)	10		2	1	3	2	4	3	3
	Total Inventory	109	Total Occupancy	44	52	51	45	35	31	33
			Percent	40.4%	47.7%	46.8%	41.3%	32.1%	28.4%	30.3%
32	Regular	10		2	3	4	4	5	5	4
	Handicap Van	1		0	0	0	0	0	0	0
	Total Inventory	11	Total Occupancy	2	3	4	4	5	5	4
			Percent	18.2%	27.3%	36.4%	36.4%	45.5%	45.5%	36.4%
33	Regular	130		43	55	68	71	85	75	61
	Handicap	3		0	0	0	2	3	2	1
	Handicap Van	1		0	0	0	1	1	0	0
	Total Inventory	134	Total Occupancy	43	55	68	74	89	77	62
			Percent	32.1%	41.0%	50.7%	55.2%	66.4%	57.5%	46.3%
34	Regular	20	Total Occupancy	10	11	11	10	10	10	8
			Percent	50.0%	55.0%	55.0%	50.0%	50.0%	50.0%	40.0%
35	Regular	59		21	27	31	33	35	32	24
	Handicap	5		1	2	2	3	3	2	2
	Handicap Van	1		0	1	1	0	0	0	0
	Total Inventory	65	Total Occupancy	22	30	34	36	38	34	26
			Percent	33.8%	46.2%	52.3%	55.4%	58.5%	52.3%	40.0%
36	Regular	109		47	58	59	62	64	61	53
	Handicap	1		0	0	1	0	0	0	0
	Handicap Van	1		0	0	0	0	0	0	0
	Total Inventory	111	Total Occupancy	47	58	60	62	64	61	53
			Percent	42.3%	52.3%	54.1%	55.9%	57.7%	55.0%	47.7%
37	Regular	4		1	2	2	1	2	2	1
	Handicap Van	1		0	0	0	0	0	0	0
	Total Inventory	5	Total Occupancy	1	2	2	1	2	2	1
			Percent	20.0%	40.0%	40.0%	20.0%	40.0%	40.0%	20.0%
38	Regular	2		2	1	1	2	2	2	1
	Unmarked Spaces	(2)		3	4	4	4	5	4	4
	Total Inventory	2	Total Occupancy	5	5	5	6	7	6	5
			Percent	250.0%	250.0%	250.0%	300.0%	350.0%	300.0%	250.0%
39	Regular	35		6	8	10	12	14	15	13
	Handicap	1		0	0	1	0	0	0	0
	Handicap Van	1		0	0	0	0	0	0	0
	Total Inventory	37	Total Occupancy	6	8	11	12	14	15	13
			Percent	16.2%	21.6%	29.7%	32.4%	37.8%	40.5%	35.1%
40	Regular	50	Total Occupancy	7	7	7	6	7	7	6
			Percent	14.0%	14.0%	14.0%	12.0%	14.0%	14.0%	12.0%
41	Regular	118		36	45	49	51	42	38	39
	Handicap	7		0	0	0	1	1	2	1
	20 Min (Green)	45		16	23	25	28	29	29	26
	Total Inventory	170	Total Occupancy	52	68	74	80	72	69	66
			Percent	30.6%	40.0%	43.5%	47.1%	42.4%	40.6%	38.8%
42	Regular	8	Total Occupancy	3	4	4	4	5	5	4
			Percent	37.5%	50.0%	50.0%	50.0%	62.5%	62.5%	50.0%
43	Regular	31		8	10	9	7	6	6	7
	Handicap	1		0	0	0	1	1	0	0
	Total Inventory	32	Total Occupancy	8	10	9	8	7	6	7
			Percent	25.0%	31.3%	28.1%	25.0%	21.9%	18.8%	21.9%

Off-Street Parking Utilization

Parking Zone	Type	Inventory		10:00 AM	11:00 AM	12:00 PM	1:00 PM	2:00 PM	3:00 PM	4:00 PM
44	Regular	22		7	10	9	6	5	7	6
	Handicap	2		0	0	0	1	2	1	1
	Handicap Van	1		0	0	0	1	0	0	0
	Total Inventory	25		7	10	9	8	7	8	7
			Percent	28.0%	40.0%	36.0%	32.0%	28.0%	32.0%	28.0%
45	Regular	15		3	4	9	12	15	14	11
	Handicap	2		0	0	0	1	0	0	0
	Handicap Van	1		0	0	0	1	1	1	0
	La Posas	6		3	4	4	5	6	6	5
	Pawn Shop (Green)	4		0	0	0	0	0	0	0
	Total Inventory	28	Total Occupancy	6	8	13	19	22	21	16
			Percent	21.4%	28.6%	46.4%	67.9%	78.6%	75.0%	57.1%
46	Regular	8		0	0	2	4	4	4	3
	Handicap Van	1		0	0	0	0	0	0	0
	Total Inventory	9		0	0	2	4	4	4	3
			Percent	0.0%	0.0%	22.2%	44.4%	44.4%	44.4%	33.3%
47	Regular	13		1	2	4	5	7	6	6
	Handicap	1		0	0	1	0	0	0	0
	Total Inventory	14		1	2	5	5	7	6	6
			Percent	7.1%	14.3%	35.7%	35.7%	50.0%	42.9%	42.9%
048	Regular	16		5	6	8	10	11	13	10
	Handicap	1		0	0	0	1	1	1	0
	Customer Only	9		1	2	3	5	7	5	4
	Unmarked Spaces			1	1	1	1	1	0	0
	Total Inventory	26	Total Occupancy	7	9	12	17	20	19	14
49	Regular	11		11	11	10	11	11	10	9
	Unmarked Spaces			2	3	2	2	5	4	3
	Total Inventory	11		13	14	12	13	16	14	12
			Percent	118.2%	127.3%	109.1%	118.2%	145.5%	127.3%	109.1%
50	Regular	14	Total Occupancy	3	3	4	3	5	4	4
51			Percent	21.4%	21.4%	28.6%	21.4%	35.7%	28.6%	28.6%
	Regular	4	Total Occupancy	1	1	1	1	2	2	1
			Percent	25.0%	25.0%	25.0%	25.0%	50.0%	50.0%	25.0%
52	Regular	13		10	10	11	9	11	10	9
	Handicap	1		0	0	0	0	0	0	0
	Dental	6		2	2	3	1	2	2	1
	Total Inventory	20	Total Occupancy	12	12	14	10	13	12	10
53			Percent	60.0%	60.0%	70.0%	50.0%	65.0%	60.0%	50.0%
	Regular	10	Total Occupancy	4	5	5	3	4	3	3
			Percent	40.0%	50.0%	50.0%	30.0%	40.0%	30.0%	30.0%
54	Regular	6		4	4	3	2	3	2	2
	Handicap	1		0	0	0	0	0	0	0
	Total Inventory	7		4	4	3	2	3	2	2
			Percent	57.1%	57.1%	42.9%	28.6%	42.9%	28.6%	28.6%
55	Regular	14		3	5	5	5	5	3	4
	Handicap	1		0	0	0	0	0	0	0
	Total Inventory	15		3	5	5	5	5	3	4
			Percent	20.0%	33.3%	33.3%	33.3%	33.3%	20.0%	26.7%
56	Regular	8		6	8	8	8	8	8	8
	Handicap	1		1	1	1	1	1	1	1
	Total Inventory	9		7	9	9	9	9	9	9
			Percent	77.8%	100.0%	100.0%	100.0%	100.0%	100.0%	100.0%
57	Regular	6		0	0	0	0	0	0	0
	Handicap	1		0	0	0	0	0	0	0
	Total Inventory	7		0	0	0	0	0	0	0
			Percent	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
58	Regular	17		8	10	15	10	10	7	5
	Handicap	1		0	0	0	0	0	0	0
	Total Inventory	18		8	10	15	10	10	7	5
			Percent	44.4%	55.6%	83.3%	55.6%	55.6%	38.9%	27.8%

Off-Street Parking Utilization

Parking Zone	Type	Inventory		10:00 AM	11:00 AM	12:00 PM	1:00 PM	2:00 PM	3:00 PM	4:00 PM
59	Regular	17		13	13	15	17	17	15	15
	Handicap	1		0	1	1	1	0	0	0
	Total Inventory	18	Total Occupancy	13	14	16	18	17	15	15
			Percent	72.2%	77.8%	88.9%	100.0%	94.4%	83.3%	83.3%
060 Dirt	Unmarked Spaces	(3)	Total Occupancy	0	0	0	0	0	0	0
			Percent	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%	0.0%
61	Regular	4		2	2	2	2	2	2	1
	Handicap	1		0	0	0	0	0	0	0
	Total Inventory	5	Total Occupancy	2	2	2	2	2	2	1
			Percent	40.0%	40.0%	40.0%	40.0%	40.0%	40.0%	20.0%
62	Handicap	1		0	0	0	0	0	0	0
	Unmarked Spaces	(2)		5	5	4	4	5	4	4
	Total Inventory	1	Total Occupancy	5	5	4	4	5	4	4
			Percent	500.0%	500.0%	400.0%	400.0%	500.0%	400.0%	400.0%
063 Carwash	Unmarked Spaces	(4)	Total Occupancy	3	4	3	3	3	4	2
64	Regular	25		1	1	5	6	7	5	5
	Handicap	1		0	0	1	1	0	0	0
	Total Inventory	26	Total Occupancy	1	1	6	7	7	5	5
			Percent	3.8%	3.8%	23.1%	26.9%	26.9%	19.2%	19.2%
65	Regular	6	Total Occupancy	3	3	3	3	3	3	3
66	Regular	17		11	13	14	14	13	15	11
	Handicap	1		0	0	0	0	0	0	0
	Total Inventory	18	Total Occupancy	11	13	14	14	13	15	11
			Percent	61.1%	72.2%	77.8%	77.8%	72.2%	83.3%	61.1%
67	Regular	16	Total Occupancy	1	2	2	2	3	2	3
68	Regular	13		2	4	0	2	0	0	0
	Handicap	1		0	0	0	0	0	0	0
	Handicap Van	1		0	0	0	0	0	0	0
	Total Inventory	15	Total Occupancy	2	4	0	2	0	0	0
			Percent	13.3%	26.7%	0.0%	13.3%	0.0%	0.0%	0.0%
69	Regular	8		8	8	8	7	7	8	6
	Handicap	1		1	1	1	0	0	0	0
	Total Inventory	9	Total Occupancy	9	9	9	7	7	8	6
			Percent	100.0%	100.0%	100.0%	77.8%	77.8%	88.9%	66.7%
70	Regular	23		23	23	21	23	20	21	19
	Handicap	1		1	1	1	1	0	0	0
	Reserved	2		1	1	0	1	1	1	0
	Unmarked Spaces	(2)		2	2	1	1	2	0	0
	Total Inventory	26	Total Occupancy	27	27	23	26	23	22	19
71	Regular	21		8	10	13	13	15	15	16
	Handicap	1		0	0	0	0	0	0	0
	Total Inventory	22	Total Occupancy	8	10	13	13	15	15	16
			Percent	36.4%	45.5%	59.1%	59.1%	68.2%	68.2%	72.7%
72	Regular	26		7	10	13	11	12	13	11
	Handicap	1		1	1	0	0	0	0	0
	Handicap Van	1		1	1	0	0	0	0	0
	Total Inventory	28	Total Occupancy	9	12	13	11	12	13	11
			Percent	32.1%	42.9%	46.4%	39.3%	42.9%	46.4%	39.3%
Total Off-Street Inventory		1794	Total Occupancy	602	715	776	786	798	760	685
			Total Utilization	33.6%	39.9%	43.3%	43.8%	44.5%	42.4%	38.2%

NOTES:

(1) Car Self-Wash Vacuum Stations - Not included in parking analysis

(2) Auto Repair. Vehicles temporarily stored in unmarked spaces



(3) Spring Valley Veterinary Clinic overflow parking

(4) Car Wash - Not included in parking analysis

	> 85%
	70% - 85%
	55% - 70%
	< 55%



19-4471 Casa Del Oro

Date: 13-Dec
Time: 10:00 AM



19-4471 Casa Del Oro



Date: 13-Dec
Time: 11:00 AM



19-4471 Casa Del Oro

Date: 13-Dec



Time: 12:00 PM



19-4471 Casa Del Oro

Date: 13-Dec



Time: 1:00 PM



19-4471 Casa Del Oro

Date: 13-Dec



Time: 2:00 PM



19-4471 Casa Del Oro

Date: 13-Dec



Time: 3:00 PM



19-4471 Casa Del Oro

Date: 13-Dec

Time: 4:00 PM




**Attachment G:
Horizon Year 2035
With Project
HCM Worksheets**

HCM Signalized Intersection Capacity Analysis

4: Kenwood Dr & Campo Rd

HY 2035+P AM
07/13/2021



Movement	EBT	EBR	WBL	WBT	NEL	NER
Lane Configurations	↑↑	↑	↑↑	↑	↑	↑↑
Traffic Volume (vph)	209	85	848	596	236	648
Future Volume (vph)	209	85	848	596	236	648
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	5.1	4.0	4.1	4.1	4.4	4.1
Lane Util. Factor	0.95	1.00	0.97	1.00	1.00	0.88
Frt	1.00	0.85	1.00	1.00	1.00	0.85
Flt Protected	1.00	1.00	0.95	1.00	0.95	1.00
Satd. Flow (prot)	3539	1583	3433	1863	1770	2787
Flt Permitted	1.00	1.00	0.95	1.00	0.95	1.00
Satd. Flow (perm)	3539	1583	3433	1863	1770	2787
Peak-hour factor, PHF	0.83	0.83	0.91	0.91	0.89	0.89
Adj. Flow (vph)	252	102	932	655	265	728
RTOR Reduction (vph)	0	0	0	0	0	235
Lane Group Flow (vph)	252	102	932	655	265	493
Turn Type	NA	Free	Split	NA	Prot	pm+ov
Protected Phases	6		5	5	3	5
Permitted Phases		Free				3
Actuated Green, G (s)	18.7	100.0	50.6	50.6	17.1	67.7
Effective Green, g (s)	18.7	100.0	50.6	50.6	17.1	67.7
Actuated g/C Ratio	0.19	1.00	0.51	0.51	0.17	0.68
Clearance Time (s)	5.1		4.1	4.1	4.4	4.1
Vehicle Extension (s)	2.0		2.0	2.0	2.0	2.0
Lane Grp Cap (vph)	661	1583	1737	942	302	2001
v/s Ratio Prot	c0.07		0.27	c0.35	c0.15	0.12
v/s Ratio Perm		0.06				0.05
v/c Ratio	0.38	0.06	0.54	0.70	0.88	0.25
Uniform Delay, d1	35.6	0.0	16.7	18.8	40.4	6.3
Progression Factor	1.00	1.00	0.69	0.71	1.00	1.00
Incremental Delay, d2	1.7	0.1	0.1	1.2	23.1	0.0
Delay (s)	37.3	0.1	11.7	14.5	63.5	6.3
Level of Service	D	A	B	B	E	A
Approach Delay (s)	26.5			12.9	21.5	
Approach LOS	C			B	C	

Intersection Summary

HCM 2000 Control Delay	17.5	HCM 2000 Level of Service	B
HCM 2000 Volume to Capacity ratio	0.67		
Actuated Cycle Length (s)	100.0	Sum of lost time (s)	15.0
Intersection Capacity Utilization	54.4%	ICU Level of Service	A
Analysis Period (min)	15		

c Critical Lane Group

HCM Signalized Intersection Capacity Analysis

5: New Street A/Conrad Dr & Campo Rd

HY 2035+P AM

07/13/2021

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	259	527	49	28	1035	128	26	7	12	168	21	436
Future Volume (vph)	259	527	49	28	1035	128	26	7	12	168	21	436
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	4.1	5.1		5.1	5.1		5.1	5.1			5.8	4.1
Lane Util. Factor	1.00	1.00		1.00	0.95		1.00	1.00			1.00	1.00
Frpb, ped/bikes	1.00	1.00		1.00	1.00		1.00	1.00			1.00	1.00
Flpb, ped/bikes	1.00	1.00		1.00	1.00		1.00	1.00			1.00	1.00
Frt	1.00	0.99		1.00	0.98		1.00	0.91			1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00		0.95	1.00			0.96	1.00
Satd. Flow (prot)	1770	1836		1770	3476		1770	1690			1783	1583
Flt Permitted	0.95	1.00		0.36	1.00		0.24	1.00			0.73	1.00
Satd. Flow (perm)	1770	1836		664	3476		443	1690			1368	1583
Peak-hour factor, PHF	0.82	0.82	0.82	0.92	0.92	0.92	0.92	0.92	0.92	0.86	0.86	0.86
Adj. Flow (vph)	316	643	60	30	1125	139	28	8	13	195	24	507
RTOR Reduction (vph)	0	4	0	0	9	0	0	7	0	0	0	78
Lane Group Flow (vph)	316	699	0	30	1255	0	28	14	0	0	219	429
Confl. Bikes (#/hr)			1			1						
Turn Type	Prot	NA		Perm	NA		Perm	NA		Perm	NA	pm+ov
Protected Phases	1!	8!			2!			4!			7!	1
Permitted Phases				2!			4!			7!		7
Actuated Green, G (s)	20.6	46.5		43.4	43.4		43.3	43.3			21.0	41.6
Effective Green, g (s)	20.6	46.5		43.4	43.4		43.3	43.3			21.0	41.6
Actuated g/C Ratio	0.21	0.46		0.43	0.43		0.43	0.43			0.21	0.42
Clearance Time (s)	4.1	5.1		5.1	5.1		5.1	5.1			5.8	4.1
Vehicle Extension (s)	2.0	2.0		2.0	2.0		2.0	2.0			2.0	2.0
Lane Grp Cap (vph)	364	853		288	1508		191	731			287	658
v/s Ratio Prot	c0.18	c0.38			c0.36			0.01				0.13
v/s Ratio Perm				0.05			0.06				c0.16	0.14
v/c Ratio	0.87	0.82		0.10	0.83		0.15	0.02			0.76	0.65
Uniform Delay, d1	38.4	23.1		16.8	25.1		17.2	16.2			37.2	23.4
Progression Factor	1.24	0.73		1.00	1.00		1.00	1.00			1.00	1.00
Incremental Delay, d2	18.2	5.7		0.7	5.5		0.1	0.0			10.3	1.8
Delay (s)	65.7	22.7		17.5	30.6		17.3	16.2			47.5	25.2
Level of Service	E	C		B	C		B	B			D	C
Approach Delay (s)		36.0			30.3			16.8			31.9	
Approach LOS		D			C			B			C	

Intersection Summary

HCM 2000 Control Delay	32.3	HCM 2000 Level of Service	C
HCM 2000 Volume to Capacity ratio	0.86		
Actuated Cycle Length (s)	100.0	Sum of lost time (s)	15.0
Intersection Capacity Utilization	76.6%	ICU Level of Service	D
Analysis Period (min)	15		

! Phase conflict between lane groups.

c Critical Lane Group

SITE LAYOUT


 **Site: A [Int. A (Site Folder: General)]**

Campo Road / Street B

Site Category: HY 2035+P AM

Roundabout

Layout pictures are schematic functional drawings reflecting input data. They are not design drawings.



SIDRA INTERSECTION 9.0 | Copyright © 2000-2020 Akcelik and Associates Pty Ltd | sidrasolutions.com

Organisation: MICHAEL BAKER INTERNATIONAL | Licence: NETWORK / 1PC | Created: Tuesday, July 13, 2021 2:24:27 PM

Project: H:\PDATA\175688_Casa De Oro\Traffic\Analysis\Synchro\3_HY 2035 With Project\HY AM.sip9

MOVEMENT SUMMARY

 **Site: A [Int. A (Site Folder: General)]**

Campo Road / Street B

Site Category: HY 2035+P AM

Roundabout

Vehicle Movement Performance														
Mov ID	Turn	INPUT VOLUMES [Total HV] veh/h %		DEMAND FLOWS [Total HV] veh/h %		Deg. Satn v/c	Aver. Delay sec	Level of Service	95% BACK OF QUEUE [Veh. Dist] veh ft		Prop. Que	Effective Stop Rate	Aver. No. Cycles	Aver. Speed mph
South: Street B														
3	L2	41	2.0	48	2.0	0.111	7.9	LOS A	0.4	10.5	0.64	0.64	0.64	31.4
8	T1	1	2.0	1	2.0	0.111	7.9	LOS A	0.4	10.5	0.64	0.64	0.64	31.4
18	R2	10	2.0	12	2.0	0.111	7.9	LOS A	0.4	10.5	0.64	0.64	0.64	30.7
Approach		52	2.0	61	2.0	0.111	7.9	LOS A	0.4	10.5	0.64	0.64	0.64	31.2
East: Campo Road														
1	L2	16	2.0	19	2.0	1.138	88.6	LOS F	157.0	3988.4	1.00	1.53	2.58	15.2
6	T1	1176	2.0	1384	2.0	1.138	88.6	LOS F	157.0	3988.4	1.00	1.53	2.58	15.2
16	R2	8	2.0	9	2.0	1.138	88.6	LOS F	157.0	3988.4	1.00	1.53	2.58	15.0
Approach		1200	2.0	1412	2.0	1.138	88.6	LOS F	157.0	3988.4	1.00	1.53	2.58	15.2
North: Street B														
7	L2	5	2.0	6	2.0	0.073	11.2	LOS B	0.2	6.3	0.75	0.75	0.75	31.0
4	T1	1	2.0	1	2.0	0.073	11.2	LOS B	0.2	6.3	0.75	0.75	0.75	31.1
14	R2	16	2.0	19	2.0	0.073	11.2	LOS B	0.2	6.3	0.75	0.75	0.75	30.4
Approach		22	2.0	26	2.0	0.073	11.2	LOS B	0.2	6.3	0.75	0.75	0.75	30.6
West: Campo Road														
5	L2	23	2.0	27	2.0	0.702	12.5	LOS B	8.6	217.8	0.29	0.09	0.29	31.0
2	T1	697	2.0	820	2.0	0.702	12.5	LOS B	8.6	217.8	0.29	0.09	0.29	31.1
12	R2	62	2.0	73	2.0	0.702	12.5	LOS B	8.6	217.8	0.29	0.09	0.29	30.3
Approach		782	2.0	920	2.0	0.702	12.5	LOS B	8.6	217.8	0.29	0.09	0.29	31.0
All Vehicles		2056	2.0	2419	2.0	1.138	56.8	LOS F	157.0	3988.4	0.72	0.96	1.64	19.3

Site Level of Service (LOS) Method: Delay & v/c (HCM 6). Site LOS Method is specified in the Parameter Settings dialog (Site tab).
Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement.

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 6).

Roundabout Capacity Model: US HCM 6.

Delay Model: HCM Delay Formula (Geometric Delay is not included).

Queue Model: HCM Queue Formula.

Gap-Acceptance Capacity: Traditional M1.

HV (%) values are calculated for All Movement Classes of All Heavy Vehicle Model Designation.

SIDRA INTERSECTION 9.0 | Copyright © 2000-2020 Akcelik and Associates Pty Ltd | sidrasolutions.com

Organisation: MICHAEL BAKER INTERNATIONAL | Licence: NETWORK / 1PC | Processed: Tuesday, July 13, 2021 2:17:17 PM

Project: H:\PDATA\175688_Casa De Oro\Traffic\Analysis\Synchro\3_HY 2035 With Project\HY AM.sip9


Intersection												
Int Delay, s/veh	0.6											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Vol, veh/h	23	610	47	16	1276	8	0	0	17	0	0	21
Future Vol, veh/h	23	610	47	16	1276	8	0	0	17	0	0	21
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	50	-	-	50	-	-	-	-	0	-	-	0
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	92	92	92	92	92	92	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	25	663	51	17	1387	9	0	0	18	0	0	23
Major/Minor	Major1			Major2			Minor1			Minor2		
Conflicting Flow All	1396	0	0	714	0	0	-	-	689	-	-	1392
Stage 1	-	-	-	-	-	-	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-	-	-	-	-	-	-
Critical Hdwy	4.12	-	-	4.12	-	-	-	-	6.22	-	-	6.22
Critical Hdwy Stg 1	-	-	-	-	-	-	-	-	-	-	-	-
Critical Hdwy Stg 2	-	-	-	-	-	-	-	-	-	-	-	-
Follow-up Hdwy	2.218	-	-	2.218	-	-	-	-	3.318	-	-	3.318
Pot Cap-1 Maneuver	490	-	-	886	-	-	0	0	446	0	0	174
Stage 1	-	-	-	-	-	-	0	0	-	0	0	-
Stage 2	-	-	-	-	-	-	0	0	-	0	0	-
Platoon blocked, %		-	-		-	-						
Mov Cap-1 Maneuver	490	-	-	886	-	-	-	-	446	-	-	174
Mov Cap-2 Maneuver	-	-	-	-	-	-	-	-	-	-	-	-
Stage 1	-	-	-	-	-	-	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-	-	-	-	-	-	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	0.4			0.1			13.4			28.8		
HCM LOS							B			D		
Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1				
Capacity (veh/h)	446	490	-	-	886	-	-	174				
HCM Lane V/C Ratio	0.041	0.051	-	-	0.02	-	-	0.131				
HCM Control Delay (s)	13.4	12.7	-	-	9.1	-	-	28.8				
HCM Lane LOS	B	B	-	-	A	-	-	D				
HCM 95th %tile Q(veh)	0.1	0.2	-	-	0.1	-	-	0.4				

SITE LAYOUT

 **Site: 6 [Int. 6 (Site Folder: General)]**

Campo Road / Bonita Street
Site Category: HY 2035+P AM
Roundabout

Layout pictures are schematic functional drawings reflecting input data. They are not design drawings.



SIDRA INTERSECTION 9.0 | Copyright © 2000-2020 Akcelik and Associates Pty Ltd | sidrasolutions.com

Organisation: MICHAEL BAKER INTERNATIONAL | Licence: NETWORK / 1PC | Created: Tuesday, July 13, 2021 2:24:22 PM

Project: H:\PDATA\175688_Casa De Oro\Traffic\Analysis\Synchro\3_HY 2035 With Project\HY AM.sip9

MOVEMENT SUMMARY

 **Site: 6 [Int. 6 (Site Folder: General)]**

Campo Road / Bonita Street
Site Category: HY 2035+P AM
Roundabout

Vehicle Movement Performance														
Mov ID	Turn	INPUT VOLUMES [Total HV] veh/h %		DEMAND FLOWS [Total HV] veh/h %		Deg. Satn v/c	Aver. Delay sec	Level of Service	95% BACK OF QUEUE [Veh. Dist] veh ft		Prop. Que	Effective Stop Rate	Aver. No. Cycles	Aver. Speed mph
South: Bonita Street														
3	L2	79	2.0	104	2.0	0.287	9.5	LOS A	1.2	30.5	0.67	0.67	0.67	31.1
8	T1	23	2.0	30	2.0	0.287	9.5	LOS A	1.2	30.5	0.67	0.67	0.67	31.2
18	R2	35	2.0	46	2.0	0.287	9.5	LOS A	1.2	30.5	0.67	0.67	0.67	30.4
Approach		137	2.0	180	2.0	0.287	9.5	LOS A	1.2	30.5	0.67	0.67	0.67	30.9
East: Campo Road														
1	L2	33	2.0	41	2.0	1.452	221.7	LOS F	211.1	5360.7	1.00	4.30	7.65	8.0
6	T1	1128	2.0	1410	2.0	1.452	221.7	LOS F	211.1	5360.7	1.00	4.30	7.65	8.0
16	R2	106	2.0	133	2.0	1.452	221.7	LOS F	211.1	5360.7	1.00	4.30	7.65	8.0
Approach		1267	2.0	1584	2.0	1.452	221.7	LOS F	211.1	5360.7	1.00	4.30	7.65	8.0
North: Bonita Street														
7	L2	52	2.0	69	2.0	0.422	16.5	LOS C	1.9	49.3	0.79	0.87	1.10	28.7
4	T1	14	2.0	19	2.0	0.422	16.5	LOS C	1.9	49.3	0.79	0.87	1.10	28.7
14	R2	69	2.0	92	2.0	0.422	16.5	LOS C	1.9	49.3	0.79	0.87	1.10	28.1
Approach		135	2.0	180	2.0	0.422	16.5	LOS C	1.9	49.3	0.79	0.87	1.10	28.4
West: Campo Road														
5	L2	57	2.0	66	2.0	0.595	10.4	LOS B	4.9	124.6	0.50	0.30	0.50	31.8
2	T1	519	2.0	597	2.0	0.595	10.4	LOS B	4.9	124.6	0.50	0.30	0.50	31.8
12	R2	40	2.0	46	2.0	0.595	10.4	LOS B	4.9	124.6	0.50	0.30	0.50	31.1
Approach		616	2.0	708	2.0	0.595	10.4	LOS B	4.9	124.6	0.50	0.30	0.50	31.8
All Vehicles		2155	2.0	2652	2.0	1.452	136.9	LOS F	211.1	5360.7	0.83	2.75	4.82	11.4

Site Level of Service (LOS) Method: Delay & v/c (HCM 6). Site LOS Method is specified in the Parameter Settings dialog (Site tab).
Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement.

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 6).

Roundabout Capacity Model: US HCM 6.

Delay Model: HCM Delay Formula (Geometric Delay is not included).

Queue Model: HCM Queue Formula.

Gap-Acceptance Capacity: Traditional M1.

HV (%) values are calculated for All Movement Classes of All Heavy Vehicle Model Designation.

SIDRA INTERSECTION 9.0 | Copyright © 2000-2020 Akcelik and Associates Pty Ltd | sidrasolutions.com

Organisation: MICHAEL BAKER INTERNATIONAL | Licence: NETWORK / 1PC | Processed: Tuesday, July 13, 2021 2:17:18 PM

Project: H:\PDATA\175688_Casa De Oro\Traffic\Analysis\Synchro\3_HY 2035 With Project\HY AM.sip9

SITE LAYOUT


Site: 7 [Int. 7 (Site Folder: General)]

Campo Road / Barcelona Street

Site Category: HY 2035+P AM

Roundabout

Layout pictures are schematic functional drawings reflecting input data. They are not design drawings.



SIDRA INTERSECTION 9.0 | Copyright © 2000-2020 Akcelik and Associates Pty Ltd | sidrasolutions.com

Organisation: MICHAEL BAKER INTERNATIONAL | Licence: NETWORK / 1PC | Created: Tuesday, July 13, 2021 2:24:32 PM

Project: H:\PDATA\175688_Casa De Oro\Traffic\Analysis\Synchro\3_HY 2035 With Project\HY AM.sip9

MOVEMENT SUMMARY

 **Site: 7 [Int. 7 (Site Folder: General)]**

Campo Road / Barcelona Street
Site Category: HY 2035+P AM
Roundabout

Vehicle Movement Performance														
Mov ID	Turn	INPUT VOLUMES [Total HV] veh/h %		DEMAND FLOWS [Total HV] veh/h %		Deg. Satn v/c	Aver. Delay sec	Level of Service	95% BACK OF QUEUE [Veh. Dist] veh ft		Prop. Que	Effective Stop Rate	Aver. No. Cycles	Aver. Speed mph
South: Barcelona Street														
3	L2	334	2.0	407	2.0	0.690	17.8	LOS C	7.6	193.1	0.84	1.11	1.58	27.6
8	T1	38	2.0	46	2.0	0.690	17.8	LOS C	7.6	193.1	0.84	1.11	1.58	27.7
18	R2	65	2.0	79	2.0	0.690	17.8	LOS C	7.6	193.1	0.84	1.11	1.58	27.1
Approach		437	2.0	533	2.0	0.690	17.8	LOS C	7.6	193.1	0.84	1.11	1.58	27.6
East: Campo Road														
1	L2	66	2.0	85	2.0	1.592	286.9	LOS F	176.8	4490.9	1.00	5.66	13.26	6.5
6	T1	914	2.0	1172	2.0	1.592	286.9	LOS F	176.8	4490.9	1.00	5.66	13.26	6.5
16	R2	40	2.0	51	2.0	1.592	286.9	LOS F	176.8	4490.9	1.00	5.66	13.26	6.5
Approach		1020	2.0	1308	2.0	1.592	286.9	LOS F	176.8	4490.9	1.00	5.66	13.26	6.5
North: Barcelona Street														
7	L2	23	2.0	29	2.0	0.192	12.4	LOS B	0.7	17.4	0.75	0.75	0.75	30.3
4	T1	14	2.0	18	2.0	0.192	12.4	LOS B	0.7	17.4	0.75	0.75	0.75	30.3
14	R2	21	2.0	27	2.0	0.192	12.4	LOS B	0.7	17.4	0.75	0.75	0.75	29.6
Approach		58	2.0	74	2.0	0.192	12.4	LOS B	0.7	17.4	0.75	0.75	0.75	30.0
West: Campo Road														
5	L2	15	2.0	19	2.0	0.602	10.4	LOS B	5.1	129.9	0.47	0.27	0.47	31.9
2	T1	392	2.0	484	2.0	0.602	10.4	LOS B	5.1	129.9	0.47	0.27	0.47	32.0
12	R2	182	2.0	225	2.0	0.602	10.4	LOS B	5.1	129.9	0.47	0.27	0.47	31.2
Approach		589	2.0	727	2.0	0.602	10.4	LOS B	5.1	129.9	0.47	0.27	0.47	31.7
All Vehicles		2104	2.0	2642	2.0	1.592	148.8	LOS F	176.8	4490.9	0.82	3.12	7.03	10.8

Site Level of Service (LOS) Method: Delay & v/c (HCM 6). Site LOS Method is specified in the Parameter Settings dialog (Site tab).
Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement.

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 6).

Roundabout Capacity Model: US HCM 6.

Delay Model: HCM Delay Formula (Geometric Delay is not included).

Queue Model: HCM Queue Formula.

Gap-Acceptance Capacity: Traditional M1.

HV (%) values are calculated for All Movement Classes of All Heavy Vehicle Model Designation.

SIDRA INTERSECTION 9.0 | Copyright © 2000-2020 Akcelik and Associates Pty Ltd | sidrasolutions.com

Organisation: MICHAEL BAKER INTERNATIONAL | Licence: NETWORK / 1PC | Processed: Tuesday, July 13, 2021 2:17:18 PM

Project: H:\PDATA\175688_Casa De Oro\Traffic\Analysis\Synchro\3_HY 2035 With Project\HY AM.sip9

Intersection												
Int Delay, s/veh	1.6											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Vol, veh/h	37	461	19	38	920	52	0	0	33	0	0	69
Future Vol, veh/h	37	461	19	38	920	52	0	0	33	0	0	69
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	50	-	-	50	-	-	-	-	0	-	-	0
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	92	92	92	92	92	92	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	40	501	21	41	1000	57	0	0	36	0	0	75
Major/Minor	Major1		Major2			Minor1			Minor2			
Conflicting Flow All	1057	0	0	522	0	0	-	-	512	-	-	1029
Stage 1	-	-	-	-	-	-	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-	-	-	-	-	-	-
Critical Hdwy	4.12	-	-	4.12	-	-	-	-	6.22	-	-	6.22
Critical Hdwy Stg 1	-	-	-	-	-	-	-	-	-	-	-	-
Critical Hdwy Stg 2	-	-	-	-	-	-	-	-	-	-	-	-
Follow-up Hdwy	2.218	-	-	2.218	-	-	-	-	3.318	-	-	3.318
Pot Cap-1 Maneuver	659	-	-	1044	-	-	0	0	562	0	0	284
Stage 1	-	-	-	-	-	-	0	0	-	0	0	-
Stage 2	-	-	-	-	-	-	0	0	-	0	0	-
Platoon blocked, %		-	-		-	-						
Mov Cap-1 Maneuver	659	-	-	1044	-	-	-	-	562	-	-	284
Mov Cap-2 Maneuver	-	-	-	-	-	-	-	-	-	-	-	-
Stage 1	-	-	-	-	-	-	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-	-	-	-	-	-	-
Approach	EB		WB			NB			SB			
HCM Control Delay, s	0.8		0.3			11.8			22.2			
HCM LOS						B			C			
Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1				
Capacity (veh/h)	562	659	-	-	1044	-	-	284				
HCM Lane V/C Ratio	0.064	0.061	-	-	0.04	-	-	0.264				
HCM Control Delay (s)	11.8	10.8	-	-	8.6	-	-	22.2				
HCM Lane LOS	B	B	-	-	A	-	-	C				
HCM 95th %tile Q(veh)	0.2	0.2	-	-	0.1	-	-	1				

SITE LAYOUT


Site: 9 [Int 9 (Site Folder: General)]

Campo / Granada / CDO 1-Lane

Site Category: HY 2035+P AM

Roundabout

Layout pictures are schematic functional drawings reflecting input data. They are not design drawings.



MOVEMENT SUMMARY

 **Site: 9 [Int 9 (Site Folder: General)]**

Campo / Granada / CDO 1-Lane

Site Category: HY 2035+P AM

Roundabout

Vehicle Movement Performance														
Mov ID	Turn	INPUT VOLUMES		DEMAND FLOWS		Deg. Satn	Aver. Delay	Level of Service	95% BACK OF QUEUE		Prop. Que	Effective Stop Rate	Aver. No. Cycles	Aver. Speed
		[Total veh/h	HV] %	[Total veh/h	HV] %				[Veh. veh	Dist] ft				
South: Granada Ave														
3	L2	27	2.0	35	2.0	0.318	10.5	LOS B	1.4	35.5	0.68	0.69	0.72	32.3
8	T1	1	2.0	1	2.0	0.318	10.5	LOS B	1.4	35.5	0.68	0.69	0.72	32.3
18a	R1	29	2.0	37	2.0	0.318	10.5	LOS B	1.4	35.5	0.68	0.69	0.72	32.0
18b	R3	100	2.0	128	2.0	0.318	9.6	LOS A	1.4	35.5	0.68	0.69	0.72	31.1
Approach		157	2.0	201	2.0	0.318	9.9	LOS A	1.4	35.5	0.68	0.69	0.72	31.5
SouthEast: Campo Rd														
3bx	L3	11	2.0	14	2.0	0.991	43.7	LOS E	60.1	1527.0	1.00	1.81	3.14	21.4
3ax	L1	812	2.0	1068	2.0	0.991	43.7	LOS E	60.1	1527.0	1.00	1.81	3.14	21.1
18ax	R1	30	2.0	39	2.0	0.991	43.7	LOS E	60.1	1527.0	1.00	1.81	3.14	21.1
18x	R2	58	2.0	76	2.0	0.062	3.5	LOS A	0.2	6.2	0.26	0.13	0.26	35.0
Approach		911	2.0	1199	2.0	0.991	41.2	LOS E	60.1	1527.0	0.95	1.70	2.96	21.6
NorthEast: Casa De Oro														
1x	L2	56	2.0	79	2.0	0.922	61.0	LOS F	10.3	260.7	0.96	1.58	3.19	18.7
1ax	L1	19	2.0	27	2.0	0.922	61.0	LOS F	10.3	260.7	0.96	1.58	3.19	18.5
16ax	R1	162	2.0	228	2.0	0.922	61.0	LOS F	10.3	260.7	0.96	1.58	3.19	18.6
16bx	R3	16	2.0	23	2.0	0.922	61.0	LOS F	10.3	260.7	0.96	1.58	3.19	18.2
Approach		253	2.0	356	2.0	0.922	61.0	LOS F	10.3	260.7	0.96	1.58	3.19	18.6
North: Granada Ave														
7b	L3	1	2.0	2	2.0	0.340	19.8	LOS C	1.3	33.0	0.84	0.90	1.06	27.9
7a	L1	46	2.0	70	2.0	0.340	19.8	LOS C	1.3	33.0	0.84	0.90	1.06	27.3
4	T1	3	2.0	5	2.0	0.340	19.8	LOS C	1.3	33.0	0.84	0.90	1.06	27.6
14	R2	17	2.0	26	2.0	0.340	19.8	LOS C	1.3	33.0	0.84	0.90	1.06	26.9
Approach		67	2.0	102	2.0	0.340	19.8	LOS C	1.3	33.0	0.84	0.90	1.06	27.3
West: Campo Rd														
5	L2	35	2.0	46	2.0	0.621	11.6	LOS B	5.7	144.0	0.64	0.50	0.69	31.7
5a	L1	77	2.0	101	2.0	0.621	11.6	LOS B	5.7	144.0	0.64	0.50	0.69	31.3
12a	R1	398	2.0	524	2.0	0.621	11.6	LOS B	5.7	144.0	0.64	0.50	0.69	31.4
12	R2	11	2.0	14	2.0	0.621	11.6	LOS B	5.7	144.0	0.64	0.50	0.69	30.8
Approach		521	2.0	686	2.0	0.621	11.6	LOS B	5.7	144.0	0.64	0.50	0.69	31.4
All Vehicles		1909	2.0	2543	2.0	0.991	32.6	LOS D	60.1	1527.0	0.84	1.25	2.12	23.8

Site Level of Service (LOS) Method: Delay & v/c (HCM 6). Site LOS Method is specified in the Parameter Settings dialog (Site tab).

Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement.

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 6).

Roundabout Capacity Model: US HCM 6.

Delay Model: HCM Delay Formula (Geometric Delay is not included).

Queue Model: HCM Queue Formula.

Gap-Acceptance Capacity: Traditional M1.

HV (%) values are calculated for All Movement Classes of All Heavy Vehicle Model Designation.

HCM Signalized Intersection Capacity Analysis

4: Kenwood Dr & Campo Rd

HY 2035+P PM
07/13/2021

	→	↗	↖	←	↘	↙
Movement	EBT	EBR	WBL	WBT	NEL	NER
Lane Configurations	↑↑	↑	↖↗	↑	↖	↗↖
Traffic Volume (vph)	403	124	638	220	119	706
Future Volume (vph)	403	124	638	220	119	706
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900
Total Lost time (s)	5.1	4.0	4.1	4.1	4.4	4.1
Lane Util. Factor	0.95	1.00	0.97	1.00	1.00	0.88
Frt	1.00	0.85	1.00	1.00	1.00	0.85
Flt Protected	1.00	1.00	0.95	1.00	0.95	1.00
Satd. Flow (prot)	3539	1583	3433	1863	1770	2787
Flt Permitted	1.00	1.00	0.95	1.00	0.95	1.00
Satd. Flow (perm)	3539	1583	3433	1863	1770	2787
Peak-hour factor, PHF	0.95	0.95	0.97	0.97	0.96	0.96
Adj. Flow (vph)	424	131	658	227	124	735
RTOR Reduction (vph)	0	0	0	0	0	273
Lane Group Flow (vph)	424	131	658	227	124	462
Turn Type	NA	Free	Split	NA	Prot	pm+ov
Protected Phases	6		5	5	3	5
Permitted Phases		Free				3
Actuated Green, G (s)	34.6	90.0	29.8	29.8	12.0	41.8
Effective Green, g (s)	34.6	90.0	29.8	29.8	12.0	41.8
Actuated g/C Ratio	0.38	1.00	0.33	0.33	0.13	0.46
Clearance Time (s)	5.1		4.1	4.1	4.4	4.1
Vehicle Extension (s)	2.0		2.0	2.0	2.0	2.0
Lane Grp Cap (vph)	1360	1583	1136	616	236	1421
v/s Ratio Prot	c0.12		c0.19	0.12	c0.07	0.11
v/s Ratio Perm		c0.08				0.06
v/c Ratio	0.31	0.08	0.58	0.37	0.53	0.33
Uniform Delay, d1	19.4	0.0	24.9	22.9	36.3	15.2
Progression Factor	1.00	1.00	0.98	0.95	1.00	1.00
Incremental Delay, d2	0.6	0.1	0.4	0.1	1.0	0.0
Delay (s)	20.0	0.1	24.9	21.8	37.3	15.3
Level of Service	B	A	C	C	D	B
Approach Delay (s)	15.3			24.1	18.4	
Approach LOS	B			C	B	
Intersection Summary						
HCM 2000 Control Delay			19.9		HCM 2000 Level of Service	B
HCM 2000 Volume to Capacity ratio			0.46			
Actuated Cycle Length (s)			90.0		Sum of lost time (s)	15.0
Intersection Capacity Utilization			47.3%		ICU Level of Service	A
Analysis Period (min)			15			
c Critical Lane Group						

HCM Signalized Intersection Capacity Analysis

5: New Road A/Conrad Dr & Campo Rd

HY 2035+P PM

07/13/2021

												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (vph)	155	945	95	48	674	60	78	19	46	91	34	181
Future Volume (vph)	155	945	95	48	674	60	78	19	46	91	34	181
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)	4.1	5.1		5.1	5.1		5.1	5.1			5.8	4.1
Lane Util. Factor	1.00	1.00		1.00	0.95		1.00	1.00			1.00	1.00
Frpb, ped/bikes	1.00	1.00		1.00	1.00		1.00	1.00			1.00	1.00
Flpb, ped/bikes	1.00	1.00		1.00	1.00		1.00	1.00			1.00	1.00
Frt	1.00	0.99		1.00	0.99		1.00	0.89			1.00	0.85
Flt Protected	0.95	1.00		0.95	1.00		0.95	1.00			0.96	1.00
Satd. Flow (prot)	1770	1834		1770	3492		1770	1666			1798	1583
Flt Permitted	0.95	1.00		0.12	1.00		0.67	1.00			0.62	1.00
Satd. Flow (perm)	1770	1834		215	3492		1249	1666			1154	1583
Peak-hour factor, PHF	0.93	0.93	0.93	0.96	0.96	0.96	0.92	0.92	0.92	0.93	0.93	0.93
Adj. Flow (vph)	167	1016	102	50	702	62	85	21	50	98	37	195
RTOR Reduction (vph)	0	3	0	0	8	0	0	40	0	0	0	105
Lane Group Flow (vph)	167	1115	0	50	757	0	85	31	0	0	135	90
Confl. Bikes (#/hr)			1			1						
Turn Type	Prot	NA		Perm	NA		Perm	NA		Perm	NA	pm+ov
Protected Phases	1!	8!			2!			4!			7!	1
Permitted Phases				2!			4!			7!		7
Actuated Green, G (s)	11.8	62.2		43.0	43.0		17.6	17.6			20.2	32.0
Effective Green, g (s)	11.8	62.2		43.0	43.0		17.6	17.6			20.2	32.0
Actuated g/C Ratio	0.13	0.69		0.48	0.48		0.20	0.20			0.22	0.36
Clearance Time (s)	4.1	5.1		5.1	5.1		5.1	5.1			5.8	4.1
Vehicle Extension (s)	2.0	2.0		2.0	2.0		2.0	2.0			2.0	2.0
Lane Grp Cap (vph)	232	1267		102	1668		244	325			259	562
v/s Ratio Prot	0.09	c0.61			0.22			0.02				0.02
v/s Ratio Perm				0.23			0.07				c0.12	0.04
v/c Ratio	0.72	0.88		0.49	0.45		0.35	0.09			0.52	0.16
Uniform Delay, d1	37.5	11.0		16.0	15.7		31.2	29.7			30.7	19.8
Progression Factor	1.16	0.84		1.00	1.00		1.00	1.00			1.00	1.00
Incremental Delay, d2	8.2	6.9		15.9	0.9		0.3	0.0			0.9	0.0
Delay (s)	51.7	16.1		31.9	16.6		31.6	29.7			31.5	19.9
Level of Service	D	B		C	B		C	C			C	B
Approach Delay (s)		20.7			17.5			30.7			24.6	
Approach LOS		C			B			C			C	
Intersection Summary												
HCM 2000 Control Delay			20.8				HCM 2000 Level of Service			C		
HCM 2000 Volume to Capacity ratio			0.86									
Actuated Cycle Length (s)			90.0				Sum of lost time (s)			15.0		
Intersection Capacity Utilization			87.3%				ICU Level of Service			E		
Analysis Period (min)			15									
! Phase conflict between lane groups.												
c Critical Lane Group												

SITE LAYOUT


 **Site: A [Int. A (Site Folder: General)]**

Campo Road / Street B

Site Category: HY 2035+P PM

Roundabout

Layout pictures are schematic functional drawings reflecting input data. They are not design drawings.



SIDRA INTERSECTION 9.0 | Copyright © 2000-2020 Akcelik and Associates Pty Ltd | sidrasolutions.com

Organisation: MICHAEL BAKER INTERNATIONAL | Licence: NETWORK / 1PC | Created: Tuesday, July 13, 2021 3:06:08 PM

Project: H:\PDATA\175688_Casa De Oro\Traffic\Analysis\Synchro\3_HY 2035 With Project\HY PM.sip9

MOVEMENT SUMMARY

 **Site: A [Int. A (Site Folder: General)]**

Campo Road / Street B

Site Category: HY 2035+P PM

Roundabout

Vehicle Movement Performance														
Mov ID	Turn	INPUT VOLUMES [Total HV] veh/h %		DEMAND FLOWS [Total HV] veh/h %		Deg. Satn v/c	Aver. Delay sec	Level of Service	95% BACK OF QUEUE [Veh. Dist] veh ft		Prop. Que	Effective Stop Rate	Aver. No. Cycles	Aver. Speed mph
South: Street B														
3	L2	130	2.0	153	2.0	0.473	18.9	LOS C	2.3	57.4	0.81	0.92	1.21	27.2
8	T1	1	2.0	1	2.0	0.473	18.9	LOS C	2.3	57.4	0.81	0.92	1.21	27.3
18	R2	32	2.0	38	2.0	0.473	18.9	LOS C	2.3	57.4	0.81	0.92	1.21	26.7
Approach		163	2.0	192	2.0	0.473	18.9	LOS C	2.3	57.4	0.81	0.92	1.21	27.1
East: Campo Road														
1	L2	32	2.0	38	2.0	0.864	24.2	LOS C	29.9	760.5	1.00	1.29	2.00	26.7
6	T1	749	2.0	881	2.0	0.864	24.2	LOS C	29.9	760.5	1.00	1.29	2.00	26.7
16	R2	16	2.0	19	2.0	0.864	24.2	LOS C	29.9	760.5	1.00	1.29	2.00	26.2
Approach		797	2.0	938	2.0	0.864	24.2	LOS C	29.9	760.5	1.00	1.29	2.00	26.7
North: Street B														
7	L2	16	2.0	19	2.0	0.175	10.7	LOS B	0.6	16.3	0.71	0.71	0.71	31.2
4	T1	1	2.0	1	2.0	0.175	10.7	LOS B	0.6	16.3	0.71	0.71	0.71	31.3
14	R2	49	2.0	58	2.0	0.175	10.7	LOS B	0.6	16.3	0.71	0.71	0.71	30.6
Approach		66	2.0	78	2.0	0.175	10.7	LOS B	0.6	16.3	0.71	0.71	0.71	30.7
West: Campo Road														
5	L2	49	2.0	58	2.0	1.142	89.8	LOS F	193.0	4901.3	1.00	1.31	2.34	15.0
2	T1	1049	2.0	1234	2.0	1.142	89.8	LOS F	193.0	4901.3	1.00	1.31	2.34	15.0
12	R2	130	2.0	153	2.0	1.142	89.8	LOS F	193.0	4901.3	1.00	1.31	2.34	14.9
Approach		1228	2.0	1445	2.0	1.142	89.8	LOS F	193.0	4901.3	1.00	1.31	2.34	15.0
All Vehicles		2254	2.0	2652	2.0	1.142	59.2	LOS F	193.0	4901.3	0.98	1.26	2.09	18.8

Site Level of Service (LOS) Method: Delay & v/c (HCM 6). Site LOS Method is specified in the Parameter Settings dialog (Site tab).
Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement.

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 6).

Roundabout Capacity Model: US HCM 6.

Delay Model: HCM Delay Formula (Geometric Delay is not included).

Queue Model: HCM Queue Formula.

Gap-Acceptance Capacity: Traditional M1.

HV (%) values are calculated for All Movement Classes of All Heavy Vehicle Model Designation.

SIDRA INTERSECTION 9.0 | Copyright © 2000-2020 Akcelik and Associates Pty Ltd | sidrasolutions.com

Organisation: MICHAEL BAKER INTERNATIONAL | Licence: NETWORK / 1PC | Processed: Tuesday, July 13, 2021 3:04:52 PM

Project: H:\PDATA\175688_Casa De Oro\Traffic\Analysis\Synchro\3_HY 2035 With Project\HY PM.sip9

Intersection												
Int Delay, s/veh	1.6											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Vol, veh/h	49	890	97	32	700	16	0	0	52	0	0	65
Future Vol, veh/h	49	890	97	32	700	16	0	0	52	0	0	65
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	0	-	-	0	-	-	-	-	0	-	-	0
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	92	92	92	92	92	92	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	53	967	105	35	761	17	0	0	57	0	0	71
Major/Minor	Major1			Major2			Minor1			Minor2		
Conflicting Flow All	778	0	0	1072	0	0	-	-	1020	-	-	770
Stage 1	-	-	-	-	-	-	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-	-	-	-	-	-	-
Critical Hdwy	4.12	-	-	4.12	-	-	-	-	6.22	-	-	6.22
Critical Hdwy Stg 1	-	-	-	-	-	-	-	-	-	-	-	-
Critical Hdwy Stg 2	-	-	-	-	-	-	-	-	-	-	-	-
Follow-up Hdwy	2.218	-	-	2.218	-	-	-	-	3.318	-	-	3.318
Pot Cap-1 Maneuver	839	-	-	650	-	-	0	0	287	0	0	401
Stage 1	-	-	-	-	-	-	0	0	-	0	0	-
Stage 2	-	-	-	-	-	-	0	0	-	0	0	-
Platoon blocked, %		-	-		-	-						
Mov Cap-1 Maneuver	839	-	-	650	-	-	-	-	287	-	-	401
Mov Cap-2 Maneuver	-	-	-	-	-	-	-	-	-	-	-	-
Stage 1	-	-	-	-	-	-	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-	-	-	-	-	-	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	0.5			0.5			20.6			15.9		
HCM LOS							C			C		
Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1				
Capacity (veh/h)	287	839	-	-	650	-	-	401				
HCM Lane V/C Ratio	0.197	0.063	-	-	0.054	-	-	0.176				
HCM Control Delay (s)	20.6	9.6	-	-	10.9	-	-	15.9				
HCM Lane LOS	C	A	-	-	B	-	-	C				
HCM 95th %tile Q(veh)	0.7	0.2	-	-	0.2	-	-	0.6				

SITE LAYOUT


Site: 7 [Int. 7 (Site Folder: General)]

Campo Road / Barcelona Street

Site Category: HY 2035+P PM

Roundabout

Layout pictures are schematic functional drawings reflecting input data. They are not design drawings.



SIDRA INTERSECTION 9.0 | Copyright © 2000-2020 Akcelik and Associates Pty Ltd | sidrasolutions.com

Organisation: MICHAEL BAKER INTERNATIONAL | Licence: NETWORK / 1PC | Created: Tuesday, July 13, 2021 3:06:10 PM

Project: H:\PDATA\175688_Casa De Oro\Traffic\Analysis\Synchro\3_HY 2035 With Project\HY PM.sip9

MOVEMENT SUMMARY

 **Site: 6 [Int. 6 (Site Folder: General)]**

Campo Road / Bonita Street
Site Category: HY 2035+P PM
Roundabout

Vehicle Movement Performance														
Mov ID	Turn	INPUT VOLUMES [Total HV] veh/h %		DEMAND FLOWS [Total HV] veh/h %		Deg. Satn v/c	Aver. Delay sec	Level of Service	95% BACK OF QUEUE [Veh. Dist] veh ft		Prop. Que	Effective Stop Rate	Aver. No. Cycles	Aver. Speed mph
South: Bonita Street														
3	L2	85	2.0	98	2.0	0.388	13.9	LOS B	1.8	45.8	0.74	0.81	0.98	29.4
8	T1	17	2.0	20	2.0	0.388	13.9	LOS B	1.8	45.8	0.74	0.81	0.98	29.5
18	R2	63	2.0	72	2.0	0.388	13.9	LOS B	1.8	45.8	0.74	0.81	0.98	28.8
Approach		165	2.0	190	2.0	0.388	13.9	LOS B	1.8	45.8	0.74	0.81	0.98	29.2
East: Campo Road														
1	L2	27	2.0	28	2.0	0.584	10.6	LOS B	4.3	110.2	0.59	0.43	0.59	31.8
6	T1	569	2.0	593	2.0	0.584	10.6	LOS B	4.3	110.2	0.59	0.43	0.59	31.8
16	R2	22	2.0	23	2.0	0.584	10.6	LOS B	4.3	110.2	0.59	0.43	0.59	31.1
Approach		618	2.0	644	2.0	0.584	10.6	LOS B	4.3	110.2	0.59	0.43	0.59	31.8
North: Bonita Street														
7	L2	38	2.0	60	2.0	0.262	9.0	LOS A	1.1	27.6	0.66	0.66	0.66	31.8
4	T1	21	2.0	33	2.0	0.262	9.0	LOS A	1.1	27.6	0.66	0.66	0.66	31.8
14	R2	46	2.0	73	2.0	0.262	9.0	LOS A	1.1	27.6	0.66	0.66	0.66	31.1
Approach		105	2.0	167	2.0	0.262	9.0	LOS A	1.1	27.6	0.66	0.66	0.66	31.5
West: Campo Road														
5	L2	66	2.0	72	2.0	0.834	20.2	LOS C	19.1	484.2	0.87	0.67	1.07	27.9
2	T1	778	2.0	846	2.0	0.834	20.2	LOS C	19.1	484.2	0.87	0.67	1.07	28.0
12	R2	64	2.0	70	2.0	0.834	20.2	LOS C	19.1	484.2	0.87	0.67	1.07	27.4
Approach		908	2.0	987	2.0	0.834	20.2	LOS C	19.1	484.2	0.87	0.67	1.07	27.9
All Vehicles		1796	2.0	1987	2.0	0.834	15.6	LOS C	19.1	484.2	0.75	0.61	0.87	29.5

Site Level of Service (LOS) Method: Delay & v/c (HCM 6). Site LOS Method is specified in the Parameter Settings dialog (Site tab).
Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement.

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 6).

Roundabout Capacity Model: US HCM 6.

Delay Model: HCM Delay Formula (Geometric Delay is not included).

Queue Model: HCM Queue Formula.

Gap-Acceptance Capacity: Traditional M1.

HV (%) values are calculated for All Movement Classes of All Heavy Vehicle Model Designation.

SIDRA INTERSECTION 9.0 | Copyright © 2000-2020 Akcelik and Associates Pty Ltd | sidrasolutions.com

Organisation: MICHAEL BAKER INTERNATIONAL | Licence: NETWORK / 1PC | Processed: Tuesday, July 13, 2021 3:04:53 PM


Project: H:\PDATA\175688_Casa De Oro\Traffic\Analysis\Synchro\3_HY 2035 With Project\HY PM.sip9

SITE LAYOUT

 **Site: 6 [Int. 6 (Site Folder: General)]**

Campo Road / Bonita Street
Site Category: HY 2035+P PM
Roundabout

Layout pictures are schematic functional drawings reflecting input data. They are not design drawings.



SIDRA INTERSECTION 9.0 | Copyright © 2000-2020 Akcelik and Associates Pty Ltd | sidrasolutions.com

Organisation: MICHAEL BAKER INTERNATIONAL | Licence: NETWORK / 1PC | Created: Tuesday, July 13, 2021 3:06:09 PM

Project: H:\PDATA\175688_Casa De Oro\Traffic\Analysis\Synchro\3_HY 2035 With Project\HY PM.sip9

MOVEMENT SUMMARY

 **Site: 7 [Int. 7 (Site Folder: General)]**

Campo Road / Barcelona Street
Site Category: HY 2035+P PM
Roundabout

Vehicle Movement Performance														
Mov ID	Turn	INPUT VOLUMES [Total HV] veh/h %		DEMAND FLOWS [Total HV] veh/h %		Deg. Satn v/c	Aver. Delay sec	Level of Service	95% BACK OF QUEUE [Veh. Dist] veh ft		Prop. Que	Effective Stop Rate	Aver. No. Cycles	Aver. Speed mph
South: Barcelona Street														
3	L2	169	2.0	180	2.0	0.386	10.3	LOS B	2.0	50.3	0.69	0.73	0.82	30.6
8	T1	11	2.0	12	2.0	0.386	10.3	LOS B	2.0	50.3	0.69	0.73	0.82	30.6
18	R2	72	2.0	77	2.0	0.386	10.3	LOS B	2.0	50.3	0.69	0.73	0.82	29.9
Approach		252	2.0	268	2.0	0.386	10.3	LOS B	2.0	50.3	0.69	0.73	0.82	30.4
East: Campo Road														
1	L2	98	2.0	101	2.0	0.513	9.3	LOS A	3.4	86.4	0.55	0.40	0.55	32.1
6	T1	419	2.0	432	2.0	0.513	9.3	LOS A	3.4	86.4	0.55	0.40	0.55	32.1
16	R2	23	2.0	24	2.0	0.513	9.3	LOS A	3.4	86.4	0.55	0.40	0.55	31.4
Approach		540	2.0	557	2.0	0.513	9.3	LOS A	3.4	86.4	0.55	0.40	0.55	32.1
North: Barcelona Street														
7	L2	26	2.0	34	2.0	0.169	7.6	LOS A	0.7	16.9	0.63	0.63	0.63	32.5
4	T1	30	2.0	39	2.0	0.169	7.6	LOS A	0.7	16.9	0.63	0.63	0.63	32.6
14	R2	26	2.0	34	2.0	0.169	7.6	LOS A	0.7	16.9	0.63	0.63	0.63	31.8
Approach		82	2.0	108	2.0	0.169	7.6	LOS A	0.7	16.9	0.63	0.63	0.63	32.3
West: Campo Road														
5	L2	12	2.0	12	2.0	0.786	17.8	LOS C	18.4	467.2	0.83	0.85	1.29	28.9
2	T1	570	2.0	588	2.0	0.786	17.8	LOS C	18.4	467.2	0.83	0.85	1.29	28.9
12	R2	272	2.0	280	2.0	0.786	17.8	LOS C	18.4	467.2	0.83	0.85	1.29	28.3
Approach		854	2.0	880	2.0	0.786	17.8	LOS C	18.4	467.2	0.83	0.85	1.29	28.7
All Vehicles		1728	2.0	1813	2.0	0.786	13.5	LOS B	18.4	467.2	0.71	0.68	0.95	30.1

Site Level of Service (LOS) Method: Delay & v/c (HCM 6). Site LOS Method is specified in the Parameter Settings dialog (Site tab).
Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement.

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 6).

Roundabout Capacity Model: US HCM 6.

Delay Model: HCM Delay Formula (Geometric Delay is not included).

Queue Model: HCM Queue Formula.

Gap-Acceptance Capacity: Traditional M1.

HV (%) values are calculated for All Movement Classes of All Heavy Vehicle Model Designation.

SIDRA INTERSECTION 9.0 | Copyright © 2000-2020 Akcelik and Associates Pty Ltd | sidrasolutions.com

Organisation: MICHAEL BAKER INTERNATIONAL | Licence: NETWORK / 1PC | Processed: Tuesday, July 13, 2021 3:04:53 PM

Project: H:\PDATA\175688_Casa De Oro\Traffic\Analysis\Synchro\3_HY 2035 With Project\HY PM.sip9

Intersection												
Int Delay, s/veh	2.1											
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Vol, veh/h	69	408	19	31	421	32	0	0	33	0	0	87
Future Vol, veh/h	69	408	19	31	421	32	0	0	33	0	0	87
Conflicting Peds, #/hr	0	0	0	0	0	0	0	0	0	0	0	0
Sign Control	Free	Free	Free	Free	Free	Free	Stop	Stop	Stop	Stop	Stop	Stop
RT Channelized	-	-	None	-	-	None	-	-	None	-	-	None
Storage Length	0	-	-	0	-	-	-	-	0	-	-	0
Veh in Median Storage, #	-	0	-	-	0	-	-	0	-	-	0	-
Grade, %	-	0	-	-	0	-	-	0	-	-	0	-
Peak Hour Factor	92	92	92	92	92	92	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	75	443	21	34	458	35	0	0	36	0	0	95
Major/Minor	Major1			Major2			Minor1			Minor2		
Conflicting Flow All	493	0	0	464	0	0	-	-	454	-	-	476
Stage 1	-	-	-	-	-	-	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-	-	-	-	-	-	-
Critical Hdwy	4.12	-	-	4.12	-	-	-	-	6.22	-	-	6.22
Critical Hdwy Stg 1	-	-	-	-	-	-	-	-	-	-	-	-
Critical Hdwy Stg 2	-	-	-	-	-	-	-	-	-	-	-	-
Follow-up Hdwy	2.218	-	-	2.218	-	-	-	-	3.318	-	-	3.318
Pot Cap-1 Maneuver	1071	-	-	1097	-	-	0	0	606	0	0	589
Stage 1	-	-	-	-	-	-	0	0	-	0	0	-
Stage 2	-	-	-	-	-	-	0	0	-	0	0	-
Platoon blocked, %	-	-	-	-	-	-	-	-	-	-	-	-
Mov Cap-1 Maneuver	1071	-	-	1097	-	-	-	-	606	-	-	589
Mov Cap-2 Maneuver	-	-	-	-	-	-	-	-	-	-	-	-
Stage 1	-	-	-	-	-	-	-	-	-	-	-	-
Stage 2	-	-	-	-	-	-	-	-	-	-	-	-
Approach	EB			WB			NB			SB		
HCM Control Delay, s	1.2			0.5			11.3			12.3		
HCM LOS							B			B		
Minor Lane/Major Mvmt	NBLn1	EBL	EBT	EBR	WBL	WBT	WBR	SBLn1				
Capacity (veh/h)	606	1071	-	-	1097	-	-	589				
HCM Lane V/C Ratio	0.059	0.07	-	-	0.031	-	-	0.161				
HCM Control Delay (s)	11.3	8.6	-	-	8.4	-	-	12.3				
HCM Lane LOS	B	A	-	-	A	-	-	B				
HCM 95th %tile Q(veh)	0.2	0.2	-	-	0.1	-	-	0.6				

SITE LAYOUT


Site: 9 [Int 9 (Site Folder: General)]

Campo / Granada / CDO 1-Lane

Site Category: HY 2035+P PM

Roundabout

Layout pictures are schematic functional drawings reflecting input data. They are not design drawings.



MOVEMENT SUMMARY

 **Site: 9 [Int 9 (Site Folder: General)]**

Campo / Granada / CDO 1-Lane

Site Category: HY 2035+P PM

Roundabout

Vehicle Movement Performance														
Mov ID	Turn	INPUT VOLUMES		DEMAND FLOWS		Deg. Satn	Aver. Delay	Level of Service	95% BACK OF QUEUE		Prop. Que	Effective Stop Rate	Aver. No. Cycles	Aver. Speed
		[Total veh/h	HV] %	[Total veh/h	HV] %				[Veh. veh	Dist] ft				
South: Granada Ave														
3	L2	15	2.0	19	2.0	0.189	9.8	LOS A	0.7	18.5	0.67	0.67	0.67	32.6
8	T1	1	2.0	1	2.0	0.189	9.8	LOS A	0.7	18.5	0.67	0.67	0.67	32.6
18a	R1	8	2.0	10	2.0	0.189	9.8	LOS A	0.7	18.5	0.67	0.67	0.67	32.3
18b	R3	56	2.0	72	2.0	0.189	8.8	LOS A	0.7	18.5	0.67	0.67	0.67	31.4
Approach		80	2.0	103	2.0	0.189	9.1	LOS A	0.7	18.5	0.67	0.67	0.67	31.7
SouthEast: Campo Rd														
3bx	L3	22	2.0	29	2.0	0.438	7.6	LOS A	2.6	64.9	0.43	0.29	0.43	32.2
3ax	L1	359	2.0	472	2.0	0.438	7.6	LOS A	2.6	64.9	0.43	0.29	0.43	31.5
18ax	R1	13	2.0	17	2.0	0.438	7.6	LOS A	2.6	64.9	0.43	0.29	0.43	31.5
18x	R2	51	2.0	67	2.0	0.055	3.4	LOS A	0.2	5.4	0.25	0.13	0.25	35.0
Approach		445	2.0	586	2.0	0.438	7.1	LOS A	2.6	64.9	0.41	0.27	0.41	31.9
NorthEast: Casa De Oro														
1x	L2	45	2.0	63	2.0	0.267	7.8	LOS A	1.2	30.0	0.62	0.60	0.62	33.0
1ax	L1	5	2.0	7	2.0	0.267	7.8	LOS A	1.2	30.0	0.62	0.60	0.62	32.6
16ax	R1	90	2.0	127	2.0	0.267	7.8	LOS A	1.2	30.0	0.62	0.60	0.62	32.7
16bx	R3	4	2.0	6	2.0	0.267	7.8	LOS A	1.2	30.0	0.62	0.60	0.62	31.7
Approach		144	2.0	203	2.0	0.267	7.8	LOS A	1.2	30.0	0.62	0.60	0.62	32.7
North: Granada Ave														
7b	L3	1	2.0	2	2.0	0.111	6.9	LOS A	0.4	10.9	0.61	0.60	0.61	33.1
7a	L1	32	2.0	48	2.0	0.111	6.9	LOS A	0.4	10.9	0.61	0.60	0.61	32.4
4	T1	3	2.0	5	2.0	0.111	6.9	LOS A	0.4	10.9	0.61	0.60	0.61	32.7
14	R2	11	2.0	17	2.0	0.111	6.9	LOS A	0.4	10.9	0.61	0.60	0.61	31.8
Approach		47	2.0	71	2.0	0.111	6.9	LOS A	0.4	10.9	0.61	0.60	0.61	32.3
West: Campo Rd														
5	L2	12	2.0	16	2.0	0.759	16.0	LOS C	13.7	348.6	0.77	0.66	0.99	29.9
5a	L1	96	2.0	126	2.0	0.759	16.0	LOS C	13.7	348.6	0.77	0.66	0.99	29.6
12a	R1	546	2.0	718	2.0	0.759	16.0	LOS C	13.7	348.6	0.77	0.66	0.99	29.7
12	R2	11	2.0	14	2.0	0.759	16.0	LOS C	13.7	348.6	0.77	0.66	0.99	29.1
Approach		665	2.0	875	2.0	0.759	16.0	LOS C	13.7	348.6	0.77	0.66	0.99	29.7
All Vehicles		1381	2.0	1837	2.0	0.759	11.5	LOS B	13.7	348.6	0.63	0.53	0.73	30.9

Site Level of Service (LOS) Method: Delay & v/c (HCM 6). Site LOS Method is specified in the Parameter Settings dialog (Site tab).

Roundabout LOS Method: Same as Sign Control.

Vehicle movement LOS values are based on average delay and v/c ratio (degree of saturation) per movement.

LOS F will result if v/c > 1 irrespective of movement delay value (does not apply for approaches and intersection).

Intersection and Approach LOS values are based on average delay for all movements (v/c not used as specified in HCM 6).

Roundabout Capacity Model: US HCM 6.

Delay Model: HCM Delay Formula (Geometric Delay is not included).

Queue Model: HCM Queue Formula.

Gap-Acceptance Capacity: Traditional M1.

HV (%) values are calculated for All Movement Classes of All Heavy Vehicle Model Designation.