



Custom Soil Resource Report Map—Farmland Classification (Tomlinson)



Custom Soil Resource Report









MAP LEGEND








Area of Interest (AOI)

-  Area of Interest (AOI)




Soils








Soil Rating Polygons






-  Not prime farmland
-  All areas are prime farmland
-  Prime farmland if drained
-  Prime farmland if protected from flooding or not frequently flooded during the growing season
-  Prime farmland if irrigated
-  Prime farmland if drained and either protected from flooding or not frequently flooded during the growing season
-  Prime farmland if irrigated and drained
-  Prime farmland if irrigated and either protected from flooding or not frequently flooded during the growing season

-  Prime farmland if subsoiled, completely removing the root inhibiting soil layer
-  Prime farmland if irrigated and the product of I (soil erodibility) x C (climate factor) does not exceed 60
-  Prime farmland if irrigated and reclaimed of excess salts and sodium
-  Farmland of statewide importance
-  Farmland of local importance
-  Farmland of unique importance
-  Not rated or not available







Soil Rating Lines










-  Not prime farmland
-  All areas are prime farmland
-  Prime farmland if drained

-  Prime farmland if protected from flooding or not frequently flooded during the growing season
-  Prime farmland if irrigated
-  Prime farmland if drained and either protected from flooding or not frequently flooded during the growing season
-  Prime farmland if irrigated and drained
-  Prime farmland if irrigated and either protected from flooding or not frequently flooded during the growing season
-  Prime farmland if subsoiled, completely removing the root inhibiting soil layer
-  Prime farmland if irrigated and the product of I (soil erodibility) x C (climate factor) does not exceed 60

-  Prime farmland if irrigated and reclaimed of excess salts and sodium
-  Farmland of statewide importance
-  Farmland of local importance
-  Farmland of unique importance
-  Not rated or not available

Soil Rating Points

-  Not prime farmland
-  All areas are prime farmland
-  Prime farmland if drained
-  Prime farmland if protected from flooding or not frequently flooded during the growing season
-  Prime farmland if irrigated
-  Prime farmland if drained and either protected from flooding or not frequently flooded during the growing season

-  Prime farmland if irrigated and drained
-  Prime farmland if irrigated and either protected from flooding or not frequently flooded during the growing season
-  Prime farmland if subsoiled, completely removing the root inhibiting soil layer
-  Prime farmland if irrigated and the product of I (soil erodibility) x C (climate factor) does not exceed 60
-  Prime farmland if irrigated and reclaimed of excess salts and sodium
-  Farmland of statewide importance
-  Farmland of local importance
-  Farmland of unique importance
-  Not rated or not available

Water Features

MAP INFORMATION

 Streams and Canals

Transportation

 Rails


 Interstate Highways

 US Routes

 Major Roads

 Local Roads

Background

 Aerial Photography

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
Web Soil Survey URL: <http://websoilsurvey.nrcs.usda.gov>
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: San Diego County Area, California
Survey Area Data: Version 8, Sep 17, 2014

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: May 3, 2010—Jun 19, 2010

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Table—Farmland Classification (Tomlinson)

Farmland Classification— Summary by Map Unit — San Diego County Area, California (CA638)				
Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
EsC	Escondido very fine sandy loam, 5 to 9 percent slopes	Farmland of statewide importance	5.4	34.7%
EsE2	Escondido very fine sandy loam, 15 to 30 percent slopes , eroded	Not prime farmland	0.0	0.0%
HrC	Huerhuero loam, 2 to 9 percent slopes	Farmland of statewide importance	10.0	64.4%
WmC	Wyman loam, 5 to 9 percent slopes	Farmland of statewide importance	0.1	0.9%
Totals for Area of Interest			15.5	100.0%

Rating Options—Farmland Classification (Tomlinson)

Aggregation Method: No Aggregation Necessary

Aggregation is the process by which a set of component attribute values is reduced to a single value that represents the map unit as a whole.

A map unit is typically composed of one or more "components". A component is either some type of soil or some nonsoil entity, e.g., rock outcrop. For the attribute being aggregated, the first step of the aggregation process is to derive one attribute value for each of a map unit's components. From this set of component attributes, the next step of the aggregation process derives a single value that represents the map unit as a whole. Once a single value for each map unit is derived, a thematic map for soil map units can be rendered. Aggregation must be done because, on any soil map, map units are delineated but components are not.

For each of a map unit's components, a corresponding percent composition is recorded. A percent composition of 60 indicates that the corresponding component typically makes up approximately 60% of the map unit. Percent composition is a critical factor in some, but not all, aggregation methods.

The majority of soil attributes are associated with a component of a map unit, and such an attribute has to be aggregated to the map unit level before a thematic map can be rendered. Map units, however, also have their own attributes. An attribute of a map unit does not have to be aggregated in order to render a corresponding thematic map. Therefore, the "aggregation method" for any attribute of a map unit is referred to as "No Aggregation Necessary".

Tie-break Rule: Lower


The tie-break rule indicates which value should be selected from a set of multiple candidate values, or which value should be selected in the event of a percent composition tie.

Farmland Classification (Tomlinson)

Farmland classification identifies map units as prime farmland, farmland of statewide importance, farmland of local importance, or unique farmland. It identifies the location and extent of the soils that are best suited to food, feed, fiber, forage, and oilseed crops. NRCS policy and procedures on prime and unique farmlands are published in the "Federal Register," Vol. 43, No. 21, January 31, 1978.

Custom Soil Resource Report


Map—Farmland Classification (Tomlinson)



Custom Soil Resource Report









MAP LEGEND








Area of Interest (AOI)

-  Area of Interest (AOI)




Soils








Soil Rating Polygons






-  Not prime farmland
-  All areas are prime farmland
-  Prime farmland if drained
-  Prime farmland if protected from flooding or not frequently flooded during the growing season
-  Prime farmland if irrigated
-  Prime farmland if drained and either protected from flooding or not frequently flooded during the growing season
-  Prime farmland if irrigated and drained
-  Prime farmland if irrigated and either protected from flooding or not frequently flooded during the growing season

-  Prime farmland if subsoiled, completely removing the root inhibiting soil layer
-  Prime farmland if irrigated and the product of I (soil erodibility) x C (climate factor) does not exceed 60
-  Prime farmland if irrigated and reclaimed of excess salts and sodium
-  Farmland of statewide importance
-  Farmland of local importance
-  Farmland of unique importance
-  Not rated or not available







Soil Rating Lines










-  Not prime farmland
-  All areas are prime farmland
-  Prime farmland if drained

-  Prime farmland if protected from flooding or not frequently flooded during the growing season
-  Prime farmland if irrigated
-  Prime farmland if drained and either protected from flooding or not frequently flooded during the growing season
-  Prime farmland if irrigated and drained
-  Prime farmland if irrigated and either protected from flooding or not frequently flooded during the growing season
-  Prime farmland if subsoiled, completely removing the root inhibiting soil layer
-  Prime farmland if irrigated and the product of I (soil erodibility) x C (climate factor) does not exceed 60

-  Prime farmland if irrigated and reclaimed of excess salts and sodium
-  Farmland of statewide importance
-  Farmland of local importance
-  Farmland of unique importance
-  Not rated or not available


Soil Rating Points

-  Not prime farmland
-  All areas are prime farmland
-  Prime farmland if drained
-  Prime farmland if protected from flooding or not frequently flooded during the growing season
-  Prime farmland if irrigated
-  Prime farmland if drained and either protected from flooding or not frequently flooded during the growing season


-  Prime farmland if irrigated and drained
-  Prime farmland if irrigated and either protected from flooding or not frequently flooded during the growing season
-  Prime farmland if subsoiled, completely removing the root inhibiting soil layer
-  Prime farmland if irrigated and the product of I (soil erodibility) x C (climate factor) does not exceed 60
-  Prime farmland if irrigated and reclaimed of excess salts and sodium
-  Farmland of statewide importance
-  Farmland of local importance
-  Farmland of unique importance
-  Not rated or not available


Water Features

MAP INFORMATION

 Streams and Canals

Transportation

 Rails


 Interstate Highways

 US Routes

 Major Roads

 Local Roads

Background

 Aerial Photography

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
Web Soil Survey URL: <http://websoilsurvey.nrcs.usda.gov>
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: San Diego County Area, California
Survey Area Data: Version 8, Sep 17, 2014

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: May 3, 2010—Jun 19, 2010

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Table—Farmland Classification (Tomlinson)

Farmland Classification— Summary by Map Unit — San Diego County Area, California (CA638)				
Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
EsC	Escondido very fine sandy loam, 5 to 9 percent slopes	Farmland of statewide importance	5.4	34.7%
EsE2	Escondido very fine sandy loam, 15 to 30 percent slopes , eroded	Not prime farmland	0.0	0.0%
HrC	Huerhuero loam, 2 to 9 percent slopes	Farmland of statewide importance	10.0	64.4%
WmC	Wyman loam, 5 to 9 percent slopes	Farmland of statewide importance	0.1	0.9%
Totals for Area of Interest			15.5	100.0%

Rating Options—Farmland Classification (Tomlinson)

Aggregation Method: No Aggregation Necessary

Aggregation is the process by which a set of component attribute values is reduced to a single value that represents the map unit as a whole.

A map unit is typically composed of one or more "components". A component is either some type of soil or some nonsoil entity, e.g., rock outcrop. For the attribute being aggregated, the first step of the aggregation process is to derive one attribute value for each of a map unit's components. From this set of component attributes, the next step of the aggregation process derives a single value that represents the map unit as a whole. Once a single value for each map unit is derived, a thematic map for soil map units can be rendered. Aggregation must be done because, on any soil map, map units are delineated but components are not.

For each of a map unit's components, a corresponding percent composition is recorded. A percent composition of 60 indicates that the corresponding component typically makes up approximately 60% of the map unit. Percent composition is a critical factor in some, but not all, aggregation methods.

The majority of soil attributes are associated with a component of a map unit, and such an attribute has to be aggregated to the map unit level before a thematic map can be rendered. Map units, however, also have their own attributes. An attribute of a map unit does not have to be aggregated in order to render a corresponding thematic map. Therefore, the "aggregation method" for any attribute of a map unit is referred to as "No Aggregation Necessary".

Tie-break Rule: Lower

The tie-break rule indicates which value should be selected from a set of multiple candidate values, or which value should be selected in the event of a percent composition tie.

Soil Properties and Qualities

The Soil Properties and Qualities section includes various soil properties and qualities displayed as thematic maps with a summary table for the soil map units in the selected area of interest. A single value or rating for each map unit is generated by aggregating the interpretive ratings of individual map unit components. This aggregation process is defined for each property or quality.

Soil Physical Properties

Soil Physical Properties are measured or inferred from direct observations in the field or laboratory. Examples of soil physical properties include percent clay, organic matter, saturated hydraulic conductivity, available water capacity, and bulk density.

Saturated Hydraulic Conductivity (Ksat), Standard Classes (Tomlinson)

Saturated hydraulic conductivity (Ksat) refers to the ease with which pores in a saturated soil transmit water. The estimates are expressed in terms of micrometers per second. They are based on soil characteristics observed in the field, particularly structure, porosity, and texture. Saturated hydraulic conductivity is considered in the design of soil drainage systems and septic tank absorption fields.

For each soil layer, this attribute is actually recorded as three separate values in the database. A low value and a high value indicate the range of this attribute for the soil component. A "representative" value indicates the expected value of this attribute for the component. For this soil property, only the representative value is used.

The numeric Ksat values have been grouped according to standard Ksat class limits. The classes are:

Very low: 0.00 to 0.01

Low: 0.01 to 0.1


Moderately low: 0.1 to 1.0

Moderately high: 1 to 10

High: 10 to 100


Very high: 100 to 705

Custom Soil Resource Report
 Map—Saturated Hydraulic Conductivity (Ksat), Standard Classes (Tomlinson)










MAP LEGEND

Area of Interest (AOI)








 Area of Interest (AOI)

Soils







Soil Rating Polygons


 Very Low (0.0 - 0.01)
 Low (0.01 - 0.1)
 Moderately Low (0.1 - 1)
 Moderately High (1 - 10)
 High (10 - 100)
 Very High (100 - 705)
 Not rated or not available

Soil Rating Lines


 Very Low (0.0 - 0.01)
 Low (0.01 - 0.1)
 Moderately Low (0.1 - 1)
 Moderately High (1 - 10)
 High (10 - 100)
 Very High (100 - 705)
 Not rated or not available

Soil Rating Points






 Very Low (0.0 - 0.01)
 Low (0.01 - 0.1)
 Moderately Low (0.1 - 1)
 Moderately High (1 - 10)
 High (10 - 100)
 Very High (100 - 705)

 Not rated or not available


Water Features

 Streams and Canals

Transportation

 Rails
 Interstate Highways
 US Routes
 Major Roads
 Local Roads

Background

 Aerial Photography

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:24,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
 Web Soil Survey URL: <http://websoilsurvey.nrcs.usda.gov>
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: San Diego County Area, California
 Survey Area Data: Version 8, Sep 17, 2014

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: May 3, 2010—Jun 19, 2010

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Table—Saturated Hydraulic Conductivity (Ksat), Standard Classes (Tomlinson)

Saturated Hydraulic Conductivity (Ksat), Standard Classes— Summary by Map Unit — San Diego County Area, California (CA638)				
Map unit symbol	Map unit name	Rating (micrometers per second)	Acres in AOI	Percent of AOI
EsC	Escondido very fine sandy loam, 5 to 9 percent slopes	9.0000	5.4	34.7%
EsE2	Escondido very fine sandy loam, 15 to 30 percent slopes , eroded	9.0000	0.0	0.0%
HrC	Huerhuero loam, 2 to 9 percent slopes	9.0000	10.0	64.4%
WmC	Wyman loam, 5 to 9 percent slopes	9.0000	0.1	0.9%
Totals for Area of Interest			15.5	100.0%

Rating Options—Saturated Hydraulic Conductivity (Ksat), Standard Classes (Tomlinson)

Units of Measure: micrometers per second

Aggregation Method: Dominant Component

Component Percent Cutoff: None Specified

Tie-break Rule: Fastest

Interpret Nulls as Zero: No

Layer Options (Horizon Aggregation Method): Depth Range (Weighted Average)

Top Depth: 0

Bottom Depth: 12

Units of Measure: Inches

References

American Association of State Highway and Transportation Officials (AASHTO). 2004. Standard specifications for transportation materials and methods of sampling and testing. 24th edition.

American Society for Testing and Materials (ASTM). 2005. Standard classification of soils for engineering purposes. ASTM Standard D2487-00.

Cowardin, L.M., V. Carter, F.C. Golet, and E.T. LaRoe. 1979. Classification of wetlands and deep-water habitats of the United States. U.S. Fish and Wildlife Service FWS/OBS-79/31.

Federal Register. July 13, 1994. Changes in hydric soils of the United States.

Federal Register. September 18, 2002. Hydric soils of the United States.

Hurt, G.W., and L.M. Vasilas, editors. Version 6.0, 2006. Field indicators of hydric soils in the United States.

National Research Council. 1995. Wetlands: Characteristics and boundaries.

Soil Survey Division Staff. 1993. Soil survey manual. Soil Conservation Service. U.S. Department of Agriculture Handbook 18. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_054262

Soil Survey Staff. 1999. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. 2nd edition. Natural Resources Conservation Service, U.S. Department of Agriculture Handbook 436. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053577

Soil Survey Staff. 2010. Keys to soil taxonomy. 11th edition. U.S. Department of Agriculture, Natural Resources Conservation Service. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053580

Tiner, R.W., Jr. 1985. Wetlands of Delaware. U.S. Fish and Wildlife Service and Delaware Department of Natural Resources and Environmental Control, Wetlands Section.

United States Army Corps of Engineers, Environmental Laboratory. 1987. Corps of Engineers wetlands delineation manual. Waterways Experiment Station Technical Report Y-87-1.

United States Department of Agriculture, Natural Resources Conservation Service. National forestry manual. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/home/?cid=nrcs142p2_053374

United States Department of Agriculture, Natural Resources Conservation Service. National range and pasture handbook. <http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/landuse/rangepasture/?cid=stelprdb1043084>


Custom Soil Resource Report

United States Department of Agriculture, Natural Resources Conservation Service. National soil survey handbook, title 430-VI. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/soils/scientists/?cid=nrcs142p2_054242

United States Department of Agriculture, Natural Resources Conservation Service. 2006. Land resource regions and major land resource areas of the United States, the Caribbean, and the Pacific Basin. U.S. Department of Agriculture Handbook 296. http://www.nrcs.usda.gov/wps/portal/nrcs/detail/national/soils/?cid=nrcs142p2_053624

United States Department of Agriculture, Soil Conservation Service. 1961. Land capability classification. U.S. Department of Agriculture Handbook 210. http://www.nrcs.usda.gov/Internet/FSE_DOCUMENTS/nrcs142p2_052290.pdf

APPENDIX F
LABORATORY DATA



Sample	Depth/EI.	Visual Classification	γ_d	MC	MC	H2O
			Initial	Initial	Final	
● TP- 3	3.0	Sandy Clay	118.1	10.7	15.8	1000

Stress at which water was added: 1000 psf
 Strain Difference: _ _ _ _ -1.62%



GeoSoils, Inc.
 5741 Palmer Way
 Carlsbad, CA 92008
 Telephone: (760) 438-3155
 Fax: (760) 931-0915


CONSOLIDATION TEST

Project: TOMLINSON

Number: 6814-A-SC

Date: February 2015

Plate: F - 1



Sample	Depth/EI.	Visual Classification	γ_d	MC	MC	H2O
			Initial	Initial	Final	
● TP- 4	7.0	Clayey Sand	112.4	7.9	16.8	1000

Stress at which water was added: 1000 psf
 Strain Difference: _ _ _ _ -0.05%



GeoSoils, Inc.
 5741 Palmer Way
 Carlsbad, CA 92008
 Telephone: (760) 438-3155
 Fax: (760) 931-0915


CONSOLIDATION TEST

Project: TOMLINSON

Number: 6814-A-SC

Date: February 2015

Plate: F - 2



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Sample	Depth	Range	Visual Classification/USCS CLASSIFICATION	LL	PL	PI	Cc	Cu
● TP-10	3.0		Sand w/ Silt				2.32	15.03

Sample	Depth	D100	D60	D30	D10	%Gravel	%Sand	%Silt	%Clay
● TP-10	3.0	25	1.618	0.636	0.108	3.8	88.1	8.1	

GeoSoils, Inc.

GeoSoils, Inc.
5741 Palmer Way
Carlsbad, CA 92008
Telephone: (760) 438-3155
Fax: (760) 931-0915


GRAIN SIZE DISTRIBUTION

Project: TOMLINSON

Number: 6814-A-SC

Date: February 2015

Plate: F - 3



Sample	Depth/EI.	LL	PL	PI	Fines	USCS CLASSIFICATION
● TP- 3	3.0	27	18	9		Sandy Clay



GeoSoils, Inc.
 5741 Palmer Way
 Carlsbad, CA 92008
 Telephone: (760) 438-3155
 Fax: (760) 931-0915

ATTERBERG LIMITS' RESULTS

Project: TOMLINSON

Number: 6814-A-SC

Date: February 2015

Plate: F - 4

SUMMARY OF LABORATORY TEST DATA

GeoSoils, Inc.
5741 Palmer Way, Suite D
Carlsbad, CA 92010

QCI Project No.: 14-029-012d
Date: December 22, 2014
Summarized by: KA

Client: Tomlinson
Project Name: N/A
W.O. 6814-A-SC

Corrosivity Test Results

Sample ID	Sample Depth	pH CT-532 (643)	Chloride CT-422 (ppm)	Sulfate CT-417 % By Weight	Resistivity CT-532 (643) (ohm-cm)
TP-3	0.5-3'	7.11	140	0.0060	2100

APPENDIX G

GENERAL EARTHWORK AND GRADING GUIDELINES

GENERAL EARTHWORK, GRADING GUIDELINES, AND PRELIMINARY CRITERIA

General

These guidelines present general procedures and requirements for earthwork and grading as shown on the approved grading plans, including preparation of areas to be filled, placement of fill, installation of subdrains, excavations, and appurtenant structures or flatwork. The recommendations contained in the geotechnical report are part of these earthwork and grading guidelines and would supercede the provisions contained hereafter in the case of conflict. Evaluations performed by the consultant during the course of grading may result in new or revised recommendations which could supercede these guidelines or the recommendations contained in the geotechnical report. Generalized details follow this text.

The contractor is responsible for the satisfactory completion of all earthwork in accordance with provisions of the project plans and specifications and latest adopted Code. In the case of conflict, the most onerous provisions shall prevail. The project geotechnical engineer and engineering geologist (geotechnical consultant), and/or their representatives, should provide observation and testing services, and geotechnical consultation during the duration of the project.

EARTHWORK OBSERVATIONS AND TESTING

Geotechnical Consultant

Prior to the commencement of grading, a qualified geotechnical consultant (soil engineer and engineering geologist) should be employed for the purpose of observing earthwork procedures and testing the fills for general conformance with the recommendations of the geotechnical report(s), the approved grading plans, and applicable grading codes and ordinances.

The geotechnical consultant should provide testing and observation so that an evaluation may be made that the work is being accomplished as specified. It is the responsibility of the contractor to assist the consultants and keep them apprised of anticipated work schedules and changes, so that they may schedule their personnel accordingly.

All remedial removals, clean-outs, prepared ground to receive fill, key excavations, and subdrain installation should be observed and documented by the geotechnical consultant prior to placing any fill. It is the contractor's responsibility to notify the geotechnical consultant when such areas are ready for observation.

Laboratory and Field Tests

Maximum dry density tests to determine the degree of compaction should be performed in accordance with American Standard Testing Materials test method ASTM designation D 1557. Random or representative field compaction tests should be performed in accordance with test methods ASTM designation D 1556, D 2937 or D 2922, and D 3017, at intervals of approximately ± 2 feet of fill height or approximately every 1,000 cubic yards placed. These criteria would vary depending on the soil conditions and the size of the project. The location and frequency of testing would be at the discretion of the geotechnical consultant.

Contractor's Responsibility

All clearing, site preparation, and earthwork performed on the project should be conducted by the contractor, with observation by a geotechnical consultant, and staged approval by the governing agencies, as applicable. It is the contractor's responsibility to prepare the ground surface to receive the fill, to the satisfaction of the geotechnical consultant, and to place, spread, moisture condition, mix, and compact the fill in accordance with the recommendations of the geotechnical consultant. The contractor should also remove all non-earth material considered unsatisfactory by the geotechnical consultant.

Notwithstanding the services provided by the geotechnical consultant, it is the sole responsibility of the contractor to provide adequate equipment and methods to accomplish the earthwork in strict accordance with applicable grading guidelines, latest adopted Codes or agency ordinances, geotechnical report(s), and approved grading plans. Sufficient watering apparatus and compaction equipment should be provided by the contractor with due consideration for the fill material, rate of placement, and climatic conditions. If, in the opinion of the geotechnical consultant, unsatisfactory conditions such as questionable weather, excessive oversized rock or deleterious material, insufficient support equipment, etc., are resulting in a quality of work that is not acceptable, the consultant will inform the contractor, and the contractor is expected to rectify the conditions, and if necessary, stop work until conditions are satisfactory.

During construction, the contractor shall properly grade all surfaces to maintain good drainage and prevent ponding of water. The contractor shall take remedial measures to control surface water and to prevent erosion of graded areas until such time as permanent drainage and erosion control measures have been installed.

SITE PREPARATION

All major vegetation, including brush, trees, thick grasses, organic debris, and other deleterious material, should be removed and disposed of off-site. These removals must be concluded prior to placing fill. In-place existing fill, soil, alluvium, colluvium, or rock materials, as evaluated by the geotechnical consultant as being unsuitable, should be removed prior to any fill placement. Depending upon the soil conditions, these materials

may be reused as compacted fills. Any materials incorporated as part of the compacted fills should be approved by the geotechnical consultant.

Any underground structures such as cesspools, cisterns, mining shafts, tunnels, septic tanks, wells, pipelines, or other structures not located prior to grading, are to be removed or treated in a manner recommended by the geotechnical consultant. Soft, dry, spongy, highly fractured, or otherwise unsuitable ground, extending to such a depth that surface processing cannot adequately improve the condition, should be overexcavated down to firm ground and approved by the geotechnical consultant before compaction and filling operations continue. Overexcavated and processed soils, which have been properly mixed and moisture conditioned, should be re-compacted to the minimum relative compaction as specified in these guidelines.

Existing ground, which is determined to be satisfactory for support of the fills, should be scarified (ripped) to a minimum depth of 6 to 8 inches, or as directed by the geotechnical consultant. After the scarified ground is brought to optimum moisture content, or greater and mixed, the materials should be compacted as specified herein. If the scarified zone is greater than 6 to 8 inches in depth, it may be necessary to remove the excess and place the material in lifts restricted to about 6 to 8 inches in compacted thickness.

Existing ground which is not satisfactory to support compacted fill should be overexcavated as required in the geotechnical report, or by the on-site geotechnical consultant. Scarification, disc harrowing, or other acceptable forms of mixing should continue until the soils are broken down and free of large lumps or clods, until the working surface is reasonably uniform and free from ruts, hollows, hummocks, mounds, or other uneven features, which would inhibit compaction as described previously.

Where fills are to be placed on ground with slopes steeper than 5:1 (horizontal to vertical [h:v]), the ground should be stepped or benched. The lowest bench, which will act as a key, should be a minimum of 15 feet wide and should be at least 2 feet deep into firm material, and approved by the geotechnical consultant. In fill-over-cut slope conditions, the recommended minimum width of the lowest bench or key is also 15 feet, with the key founded on firm material, as designated by the geotechnical consultant. As a general rule, unless specifically recommended otherwise by the geotechnical consultant, the minimum width of fill keys should be equal to $\frac{1}{2}$ the height of the slope.

Standard benching is generally 4 feet (minimum) vertically, exposing firm, acceptable material. Benching may be used to remove unsuitable materials, although it is understood that the vertical height of the bench may exceed 4 feet. Pre-stripping may be considered for unsuitable materials in excess of 4 feet in thickness.

All areas to receive fill, including processed areas, removal areas, and the toes of fill benches, should be observed and approved by the geotechnical consultant prior to placement of fill. Fills may then be properly placed and compacted until design grades (elevations) are attained.

COMPACTED FILLS

Any earth materials imported or excavated on the property may be utilized in the fill provided that each material has been evaluated to be suitable by the geotechnical consultant. These materials should be free of roots, tree branches, other organic matter, or other deleterious materials. All unsuitable materials should be removed from the fill as directed by the geotechnical consultant. Soils of poor gradation, undesirable expansion potential, or substandard strength characteristics may be designated by the consultant as unsuitable and may require blending with other soils to serve as a satisfactory fill material.

Fill materials derived from benching operations should be dispersed throughout the fill area and blended with other approved material. Benching operations should not result in the benched material being placed only within a single equipment width away from the fill/bedrock contact.

Oversized materials defined as rock, or other irreducible materials, with a maximum dimension greater than 12 inches, should not be buried or placed in fills unless the location of materials and disposal methods are specifically approved by the geotechnical consultant. Oversized material should be taken offsite, or placed in accordance with recommendations of the geotechnical consultant in areas designated as suitable for rock disposal. GSI anticipates that soils to be utilized as fill material for the subject project may contain some rock. Appropriately, the need for rock disposal may be necessary during grading operations on the site. From a geotechnical standpoint, the depth of any rocks, rock fills, or rock blankets, should be a sufficient distance from finish grade. This depth is generally the same as any overexcavation due to cut-fill transitions in hard rock areas, and generally facilitates the excavation of structural footings and substructures. Should deeper excavations be proposed (i.e., deepened footings, utility trenching, swimming pools, spas, etc.), the developer may consider increasing the hold-down depth of any rocky fills to be placed, as appropriate. In addition, some agencies/jurisdictions mandate a specific hold-down depth for oversize materials placed in fills. The hold-down depth, and potential to encounter oversize rock, both within fills, and occurring in cut or natural areas, would need to be disclosed to all interested/affected parties. Once approved by the governing agency, the hold-down depth for oversized rock (i.e., greater than 12 inches) in fills on this project is provided as 10 feet, unless specified differently in the text of this report. The governing agency may require that these materials need to be deeper, crushed, or reduced to less than 12 inches in maximum dimension, at their discretion.

To facilitate future trenching, rock (or oversized material), should not be placed within the hold-down depth feet from finish grade, the range of foundation excavations, future utilities, or underground construction unless specifically approved by the governing agency, the geotechnical consultant, and/or the developer's representative.

If import material is required for grading, representative samples of the materials to be utilized as compacted fill should be analyzed in the laboratory by the geotechnical consultant to evaluate its physical properties and suitability for use onsite. Such testing should be performed three (3) days prior to importation. If any material other than that

previously tested is encountered during grading, an appropriate analysis of this material should be conducted by the geotechnical consultant as soon as possible.

Approved fill material should be placed in areas prepared to receive fill in near horizontal layers, that when compacted, should not exceed about 6 to 8 inches in thickness. The geotechnical consultant may approve thick lifts if testing indicates the grading procedures are such that adequate compaction is being achieved with lifts of greater thickness. Each layer should be spread evenly and blended to attain uniformity of material and moisture suitable for compaction.

Fill layers at a moisture content less than optimum should be watered and mixed, and wet fill layers should be aerated by scarification, or should be blended with drier material. Moisture conditioning, blending, and mixing of the fill layer should continue until the fill materials have a uniform moisture content at, or above, optimum moisture.

After each layer has been evenly spread, moisture conditioned, and mixed, it should be uniformly compacted to a minimum of 90 percent of the maximum density as evaluated by ASTM test designation D 1557, or as otherwise recommended by the geotechnical consultant. Compaction equipment should be adequately sized and should be specifically designed for soil compaction, or of proven reliability to efficiently achieve the specified degree of compaction.

Where tests indicate that the density of any layer of fill, or portion thereof, is below the required relative compaction, or improper moisture is in evidence, the particular layer or portion shall be re-worked until the required density and/or moisture content has been attained. No additional fill shall be placed in an area until the last placed lift of fill has been tested and found to meet the density and moisture requirements, and is approved by the geotechnical consultant.

In general, per the latest adopted Code, fill slopes should be designed and constructed at a gradient of 2:1 (h:v), or flatter. Compaction of slopes should be accomplished by over-building a minimum of 3 feet horizontally, and subsequently trimming back to the design slope configuration. Testing shall be performed as the fill is elevated to evaluate compaction as the fill core is being developed. Special efforts may be necessary to attain the specified compaction in the fill slope zone. Final slope shaping should be performed by trimming and removing loose materials with appropriate equipment. A final evaluation of fill slope compaction should be based on observation and/or testing of the finished slope face. Where compacted fill slopes are designed steeper than 2:1 (h:v), prior approval from the governing agency, specific material types, a higher minimum relative compaction, special reinforcement, and special grading procedures will be recommended.

If an alternative to over-building and cutting back the compacted fill slopes is selected, then special effort should be made to achieve the required compaction in the outer 10 feet of each lift of fill by undertaking the following:

1. An extra piece of equipment consisting of a heavy, short-shanked sheepfoot should be used to roll (horizontal) parallel to the slopes continuously as fill is placed. The sheepfoot roller should also be used to roll perpendicular to the slopes, and extend out over the slope to provide adequate compaction to the face of the slope.
2. Loose fill should not be spilled out over the face of the slope as each lift is compacted. Any loose fill spilled over a previously completed slope face should be trimmed off or be subject to re-rolling.
3. Field compaction tests will be made in the outer (horizontal) ± 2 to ± 8 feet of the slope at appropriate vertical intervals, subsequent to compaction operations.
4. After completion of the slope, the slope face should be shaped with a small tractor and then re-rolled with a sheepfoot to achieve compaction to near the slope face. Subsequent to testing to evaluate compaction, the slopes should be grid-rolled to achieve compaction to the slope face. Final testing should be used to evaluate compaction after grid rolling.
5. Where testing indicates less than adequate compaction, the contractor will be responsible to rip, water, mix, and recompact the slope material as necessary to achieve compaction. Additional testing should be performed to evaluate compaction.

SUBDRAIN INSTALLATION

Subdrains should be installed in approved ground in accordance with the approximate alignment and details indicated by the geotechnical consultant. Subdrain locations or materials should not be changed or modified without approval of the geotechnical consultant. The geotechnical consultant may recommend and direct changes in subdrain line, grade, and drain material in the field, pending exposed conditions. The location of constructed subdrains, especially the outlets, should be recorded/surveyed by the project civil engineer. Drainage at the subdrain outlets should be provided by the project civil engineer.

EXCAVATIONS

Excavations and cut slopes should be examined during grading by the geotechnical consultant. If directed by the geotechnical consultant, further excavations or overexcavation and refilling of cut areas should be performed, and/or remedial grading of cut slopes should be performed. When fill-over-cut slopes are to be graded, unless otherwise approved, the cut portion of the slope should be observed by the geotechnical consultant prior to placement of materials for construction of the fill portion of the slope.

The geotechnical consultant should observe all cut slopes, and should be notified by the contractor when excavation of cut slopes commence.

If, during the course of grading, unforeseen adverse or potentially adverse geologic conditions are encountered, the geotechnical consultant should investigate, evaluate, and make appropriate recommendations for mitigation of these conditions. The need for cut slope buttressing or stabilizing should be based on in-grading evaluation by the geotechnical consultant, whether anticipated or not.

Unless otherwise specified in geotechnical and geological report(s), no cut slopes should be excavated higher or steeper than that allowed by the ordinances of controlling governmental agencies. Additionally, short-term stability of temporary cut slopes is the contractor's responsibility.

Erosion control and drainage devices should be designed by the project civil engineer and should be constructed in compliance with the ordinances of the controlling governmental agencies, and/or in accordance with the recommendations of the geotechnical consultant.

COMPLETION

Observation, testing, and consultation by the geotechnical consultant should be conducted during the grading operations in order to state an opinion that all cut and fill areas are graded in accordance with the approved project specifications. After completion of grading, and after the geotechnical consultant has finished observations of the work, final reports should be submitted, and may be subject to review by the controlling governmental agencies. No further excavation or filling should be undertaken without prior notification of the geotechnical consultant or approved plans.

All finished cut and fill slopes should be protected from erosion and/or be planted in accordance with the project specifications and/or as recommended by a landscape architect. Such protection and/or planning should be undertaken as soon as practical after completion of grading.

PRELIMINARY OUTDOOR POOL/SPA DESIGN RECOMMENDATIONS

The following preliminary recommendations are provided for consideration in pool/spa design and planning. Actual recommendations should be provided by a qualified geotechnical consultant, based on site specific geotechnical conditions, including a subsurface investigation, differential settlement potential, expansive and corrosive soil potential, proximity of the proposed pool/spa to any slopes with regard to slope creep and lateral fill extension, as well as slope setbacks per Code, and geometry of the proposed improvements. Recommendations for pools/spas and/or deck flatwork underlain by expansive soils, or for areas with differential settlement greater than ¼-inch over 40 feet horizontally, will be more onerous than the preliminary recommendations presented below.

The 1:1 (h:v) influence zone of any nearby retaining wall site structures should be delineated on the project civil drawings with the pool/spa. This 1:1 (h:v) zone is defined as a plane up from the lower-most heel of the retaining structure, to the daylight grade of the nearby building pad or slope. If pools/spas or associated pool/spa improvements are constructed within this zone, they should be re-positioned (horizontally or vertically) so that they are supported by earth materials that are outside or below this 1:1 plane. If this is not possible given the area of the building pad, the owner should consider eliminating these improvements or allow for increased potential for lateral/vertical deformations and associated distress that may render these improvements unusable in the future, unless they are periodically repaired and maintained. The conditions and recommendations presented herein should be disclosed to all homeowners and any interested/affected parties.

General

1. The equivalent fluid pressure to be used for the pool/spa design should be 60 pounds per cubic foot (pcf) for pool/spa walls with level backfill, and 75 pcf for a 2:1 sloped backfill condition. In addition, backdrains should be provided behind pool/spa walls subjacent to slopes.
2. Passive earth pressure may be computed as an equivalent fluid having a density of 150 pcf, to a maximum lateral earth pressure of 1,000 pounds per square foot (psf).
3. An allowable coefficient of friction between soil and concrete of 0.30 may be used with the dead load forces.
4. When combining passive pressure and frictional resistance, the passive pressure component should be reduced by one-third.
5. Where pools/spas are planned near structures, appropriate surcharge loads need to be incorporated into design and construction by the pool/spa designer. This includes, but is not limited to landscape berms, decorative walls, footings, built-in barbeques, utility poles, etc.
6. All pool/spa walls should be designed as “free standing” and be capable of supporting the water in the pool/spa without soil support. The shape of pool/spa in cross section and plan view may affect the performance of the pool, from a geotechnical standpoint. Pools and spas should also be designed in accordance with the latest adopted Code. Minimally, the bottoms of the pools/spas, should maintain a distance $H/3$, where H is the height of the slope (in feet), from the slope face. This distance should not be less than 7 feet, nor need not be greater than 40 feet.
7. The soil beneath the pool/spa bottom should be uniformly moist with the same stiffness throughout. If a fill/cut transition occurs beneath the pool/spa bottom, the cut portion should be overexcavated to a minimum depth of 48 inches, and

replaced with compacted fill, such that there is a uniform blanket that is a minimum of 48 inches below the pool/spa shell. If very low expansive soil is used for fill, the fill should be placed at a minimum of 95 percent relative compaction, at optimum moisture conditions. This requirement should be 90 percent relative compaction at over optimum moisture if the pool/spa is constructed within or near expansive soils. The potential for grading and/or re-grading of the pool/spa bottom, and attendant potential for shoring and/or slot excavation, needs to be considered during all aspects of pool/spa planning, design, and construction.

8. If the pool/spa is founded entirely in compacted fill placed during rough grading, the deepest portion of the pool/spa should correspond with the thickest fill on the lot.
9. Hydrostatic pressure relief valves should be incorporated into the pool and spa designs. A pool/spa under-drain system is also recommended, with an appropriate outlet for discharge.
10. All fittings and pipe joints, particularly fittings in the side of the pool or spa, should be properly sealed to prevent water from leaking into the adjacent soils materials, and be fitted with slip or expandable joints between connections transecting varying soil conditions.
11. An elastic expansion joint (flexible waterproof sealant) should be installed to prevent water from seeping into the soil at all deck joints.
12. A reinforced grade beam should be placed around skimmer inlets to provide support and mitigate cracking around the skimmer face.
13. In order to reduce unsightly cracking, deck slabs should minimally be 4 inches thick, and reinforced with No. 3 reinforcing bars at 18 inches on-center. All slab reinforcement should be supported to ensure proper mid-slab positioning during the placement of concrete. Wire mesh reinforcing is specifically not recommended. Deck slabs should not be tied to the pool/spa structure. Pre-moistening and/or pre-soaking of the slab subgrade is recommended, to a depth of 12 inches (optimum moisture content), or 18 inches (120 percent of the soil's optimum moisture content, or 3 percent over optimum moisture content, whichever is greater), for very low to low, and medium expansive soils, respectively. This moisture content should be maintained in the subgrade soils during concrete placement to promote uniform curing of the concrete and minimize the development of unsightly shrinkage cracks. Slab underlayment should consist of a 1- to 2-inch leveling course of sand (S.E. >30) and a minimum of 4 to 6 inches of Class 2 base compacted to 90 percent. Deck slabs within the H/3 zone, where H is the height of the slope (in feet), will have an increased potential for distress relative to other areas outside of the H/3 zone. If distress is undesirable, improvements, deck slabs or flatwork should not be constructed closer than H/3 or 7 feet (whichever is greater) from the slope face, in order to reduce, but not eliminate, this potential.

14. Pool/spa bottom or deck slabs should be founded entirely on competent bedrock, or properly compacted fill. Fill should be compacted to achieve a minimum 90 percent relative compaction, as discussed above. Prior to pouring concrete, subgrade soils below the pool/spa decking should be thoroughly watered to achieve a moisture content that is at least 2 percent above optimum moisture content, to a depth of at least 18 inches below the bottom of slabs. This moisture content should be maintained in the subgrade soils during concrete placement to promote uniform curing of the concrete and minimize the development of unsightly shrinkage cracks.
15. In order to reduce unsightly cracking, the outer edges of pool/spa decking to be bordered by landscaping, and the edges immediately adjacent to the pool/spa, should be underlain by an 8-inch wide concrete cutoff shoulder (thickened edge) extending to a depth of at least 12 inches below the bottoms of the slabs to mitigate excessive infiltration of water under the pool/spa deck. These thickened edges should be reinforced with two No. 4 bars, one at the top and one at the bottom. Deck slabs may be minimally reinforced with No. 3 reinforcing bars placed at 18 inches on-center, in both directions. All slab reinforcement should be supported on chairs to ensure proper mid-slab positioning during the placement of concrete.
16. Surface and shrinkage cracking of the finish slab may be reduced if a low slump and water-cement ratio are maintained during concrete placement. Concrete utilized should have a minimum compressive strength of 4,000 psi. Excessive water added to concrete prior to placement is likely to cause shrinkage cracking, and should be avoided. Some concrete shrinkage cracking, however, is unavoidable.
17. Joint and sawcut locations for the pool/spa deck should be determined by the design engineer and/or contractor. However, spacings should not exceed 6 feet on center.
18. Considering the nature of the onsite earth materials, it should be anticipated that caving or sloughing could be a factor in subsurface excavations and trenching. Shoring or excavating the trench walls/backcuts at the angle of repose (typically 25 to 45 degrees), should be anticipated. All excavations should be observed by a representative of the geotechnical consultant, including the project geologist and/or geotechnical engineer, prior to workers entering the excavation or trench, and minimally conform to Cal/OSHA ("Type C" soils may be assumed), state, and local safety codes. Should adverse conditions exist, appropriate recommendations should be offered at that time by the geotechnical consultant. GSI does not consult in the area of safety engineering and the safety of the construction crew is the responsibility of the pool/spa builder.
19. It is imperative that adequate provisions for surface drainage are incorporated by the homeowners into their overall improvement scheme. Ponding water, ground saturation and flow over slope faces, are all situations which must be avoided to enhance long term performance of the pool/spa and associated improvements, and reduce the likelihood of distress.

20. Regardless of the methods employed, once the pool/spa is filled with water, should it be emptied, there exists some potential that if emptied, significant distress may occur. Accordingly, once filled, the pool/spa should not be emptied unless evaluated by the geotechnical consultant and the pool/spa builder.
21. For pools/spas built within (all or part) of the Code setback and/or geotechnical setback, as indicated in the site geotechnical documents, special foundations are recommended to mitigate the affects of creep, lateral fill extension, expansive soils and settlement on the proposed pool/spa. Most municipalities or County reviewers do not consider these effects in pool/spa plan approvals. As such, where pools/spas are proposed on 20 feet or more of fill, medium or highly expansive soils, or rock fill with limited “cap soils” and built within Code setbacks, or within the influence of the creep zone, or lateral fill extension, the following should be considered during design and construction:
- OPTION A: Shallow foundations with or without overexcavation of the pool/spa “shell,” such that the pool/spa is surrounded by 5 feet of very low to low expansive soils (without irreducible particles greater than 6 inches), and the pool/spa walls closer to the slope(s) are designed to be free standing. GSI recommends a pool/spa under-drain or blanket system (see attached Typical Pool/Spa Detail). The pool/spa builders and owner in this optional construction technique should be generally satisfied with pool/spa performance under this scenario; however, some settlement, tilting, cracking, and leakage of the pool/spa is likely over the life of the project.
- OPTION B: Pier supported pool/spa foundations with or without overexcavation of the pool/spa shell such that the pool/spa is surrounded by 5 feet of very low to low expansive soils (without irreducible particles greater than 6 inches), and the pool/spa walls closer to the slope(s) are designed to be free standing. The need for a pool/spa under-drain system may be installed for leak detection purposes. Piers that support the pool/spa should be a minimum of 12 inches in diameter and at a spacing to provide vertical and lateral support of the pool/spa, in accordance with the pool/spa designers recommendations current applicable Codes. The pool/spa builder and owner in this second scenario construction technique should be more satisfied with pool/spa performance. This construction will reduce settlement and creep effects on the pool/spa; however, it will not eliminate these potentials, nor make the pool/spa “leak-free.”
22. The temperature of the water lines for spas and pools may affect the corrosion properties of site soils, thus, a corrosion specialist should be retained to review all spa and pool plans, and provide mitigative recommendations, as warranted. Concrete mix design should be reviewed by a qualified corrosion consultant and materials engineer.

23. All pool/spa utility trenches should be compacted to 90 percent of the laboratory standard, under the full-time observation and testing of a qualified geotechnical consultant. Utility trench bottoms should be sloped away from the primary structure on the property (typically the residence).
24. Pool and spa utility lines should not cross the primary structure's utility lines (i.e., not stacked, or sharing of trenches, etc.).
25. The pool/spa or associated utilities should not intercept, interrupt, or otherwise adversely impact any area drain, roof drain, or other drainage conveyances. If it is necessary to modify, move, or disrupt existing area drains, subdrains, or tightlines, then the design civil engineer should be consulted, and mitigative measures provided. Such measures should be further reviewed and approved by the geotechnical consultant, prior to proceeding with any further construction.
26. The geotechnical consultant should review and approve all aspects of pool/spa and flatwork design prior to construction. A design civil engineer should review all aspects of such design, including drainage and setback conditions. Prior to acceptance of the pool/spa construction, the project builder, geotechnical consultant and civil designer should evaluate the performance of the area drains and other site drainage pipes, following pool/spa construction.
27. All aspects of construction should be reviewed and approved by the geotechnical consultant, including during excavation, prior to the placement of any additional fill, prior to the placement of any reinforcement or pouring of any concrete.
28. Any changes in design or location of the pool/spa should be reviewed and approved by the geotechnical and design civil engineer prior to construction. Field adjustments should not be allowed until written approval of the proposed field changes are obtained from the geotechnical and design civil engineer.
29. Disclosure should be made to homeowners and builders, contractors, and any interested/affected parties, that pools/spas built within about 15 feet of the top of a slope, and/or $H/3$, where H is the height of the slope (in feet), will experience some movement or tilting. While the pool/spa shell or coping may not necessarily crack, the levelness of the pool/spa will likely tilt toward the slope, and may not be esthetically pleasing. The same is true with decking, flatwork and other improvements in this zone.
30. Failure to adhere to the above recommendations will significantly increase the potential for distress to the pool/spa, flatwork, etc.
31. Local seismicity and/or the design earthquake will cause some distress to the pool/spa and decking or flatwork, possibly including total functional and economic loss.

32. The information and recommendations discussed above should be provided to any contractors and/or subcontractors, or homeowners, interested/affected parties, etc., that may perform or may be affected by such work.

JOB SAFETY

General

At GSI, getting the job done safely is of primary concern. The following is the company's safety considerations for use by all employees on multi-employer construction sites. On-ground personnel are at highest risk of injury, and possible fatality, on grading and construction projects. GSI recognizes that construction activities will vary on each site, and that site safety is the prime responsibility of the contractor; however, everyone must be safety conscious and responsible at all times. To achieve our goal of avoiding accidents, cooperation between the client, the contractor, and GSI personnel must be maintained.

In an effort to minimize risks associated with geotechnical testing and observation, the following precautions are to be implemented for the safety of field personnel on grading and construction projects:

Safety Meetings: GSI field personnel are directed to attend contractor's regularly scheduled and documented safety meetings.

Safety Vests: Safety vests are provided for, and are to be worn by GSI personnel, at all times, when they are working in the field.

Safety Flags: Two safety flags are provided to GSI field technicians; one is to be affixed to the vehicle when on site, the other is to be placed atop the spoil pile on all test pits.

Flashing Lights: All vehicles stationary in the grading area shall use rotating or flashing amber beacons, or strobe lights, on the vehicle during all field testing. While operating a vehicle in the grading area, the emergency flasher on the vehicle shall be activated.

In the event that the contractor's representative observes any of our personnel not following the above, we request that it be brought to the attention of our office.

Test Pits Location, Orientation, and Clearance

The technician is responsible for selecting test pit locations. A primary concern should be the technician's safety. Efforts will be made to coordinate locations with the grading contractor's authorized representative, and to select locations following or behind the established traffic pattern, preferably outside of current traffic. The contractor's authorized

representative (supervisor, grade checker, dump man, operator, etc.) should direct excavation of the pit and safety during the test period. Of paramount concern should be the soil technician's safety, and obtaining enough tests to represent the fill.

Test pits should be excavated so that the spoil pile is placed away from oncoming traffic, whenever possible. The technician's vehicle is to be placed next to the test pit, opposite the spoil pile. This necessitates the fill be maintained in a driveable condition. Alternatively, the contractor may wish to park a piece of equipment in front of the test holes, particularly in small fill areas or those with limited access.

A zone of non-encroachment should be established for all test pits. No grading equipment should enter this zone during the testing procedure. The zone should extend approximately 50 feet outward from the center of the test pit. This zone is established for safety and to avoid excessive ground vibration, which typically decreases test results.

When taking slope tests, the technician should park the vehicle directly above or below the test location. If this is not possible, a prominent flag should be placed at the top of the slope. The contractor's representative should effectively keep all equipment at a safe operational distance (e.g., 50 feet) away from the slope during this testing.

The technician is directed to withdraw from the active portion of the fill as soon as possible following testing. The technician's vehicle should be parked at the perimeter of the fill in a highly visible location, well away from the equipment traffic pattern. The contractor should inform our personnel of all changes to haul roads, cut and fill areas or other factors that may affect site access and site safety.

In the event that the technician's safety is jeopardized or compromised as a result of the contractor's failure to comply with any of the above, the technician is required, by company policy, to immediately withdraw and notify his/her supervisor. The grading contractor's representative will be contacted in an effort to affect a solution. However, in the interim, no further testing will be performed until the situation is rectified. Any fill placed can be considered unacceptable and subject to reprocessing, recompaction, or removal.

In the event that the soil technician does not comply with the above or other established safety guidelines, we request that the contractor bring this to the technician's attention and notify this office. Effective communication and coordination between the contractor's representative and the soil technician is strongly encouraged in order to implement the above safety plan.

Trench and Vertical Excavation


It is the contractor's responsibility to provide safe access into trenches where compaction testing is needed. Our personnel are directed not to enter any excavation or vertical cut which: 1) is 5 feet or deeper unless shored or laid back; 2) displays any evidence of instability, has any loose rock or other debris which could fall into the trench; or 3) displays any other evidence of any unsafe conditions regardless of depth.

All trench excavations or vertical cuts in excess of 5 feet deep, which any person enters, should be shored or laid back. Trench access should be provided in accordance with Cal/OSHA and/or state and local standards. Our personnel are directed not to enter any trench by being lowered or “riding down” on the equipment.


If the contractor fails to provide safe access to trenches for compaction testing, our company policy requires that the soil technician withdraw and notify his/her supervisor. The contractor’s representative will be contacted in an effort to affect a solution. All backfill not tested due to safety concerns or other reasons could be subject to reprocessing and/or removal.

If GSI personnel become aware of anyone working beneath an unsafe trench wall or vertical excavation, we have a legal obligation to put the contractor and owner/developer on notice to immediately correct the situation. If corrective steps are not taken, GSI then has an obligation to notify Cal/OSHA and/or the proper controlling authorities.


TYPE A




TYPE B



Selection of alternate subdrain details, location, and extent of subdrains should be evaluated by the geotechnical consultant during grading.



A-1



B-1

Filter material: Minimum volume of 9 cubic feet per lineal foot of pipe.


Perforated pipe: 6-inch-diameter ABS or PVC pipe or approved substitute with minimum 8 perforations ($\frac{1}{4}$ -inch diameter) per lineal foot in bottom half of pipe (ASTM D-2751, SDR-35, or ASTM D-1527, Schd. 40).

For continuous run in excess of 500 feet, use 8-inch-diameter pipe (ASTM D-3034, SDR-35, or ASTM D-1785, Schd. 40).


FILTER MATERIAL

Sieve Size	Percent Passing
1 inch	100
$\frac{3}{4}$ inch	90-100
$\frac{3}{8}$ inch	40-100
No. 4	25-40
No. 8	18-33
No. 30	5-15
No. 50	0-7
No. 200	0-3

ALTERNATE 1: PERFORATED PIPE AND FILTER MATERIAL



A-2



B-2


Gravel Material: 9 cubic feet per lineal foot.

Perforated Pipe: See Alternate 1


Gravel: Clean $\frac{3}{4}$ -inch rock or approved substitute.


Filter Fabric: Mirafi 140 or approved substitute.


ALTERNATE 2: PERFORATED PIPE, GRAVEL, AND FILTER FABRIC



Provide a 1:1 (H:V) minimum projection from toe of slope as shown on grading plan to the recommended removal depth. Slope height, site conditions, and/or local conditions could dictate flatter projections.







Filter Material: Minimum of 5 cubic feet per lineal foot of pipe or 4 cubic feet per lineal foot of pipe when placed in square cut trench.

Alternative in Lieu of Filter Material: Gravel may be encased in approved filter fabric. Filter fabric shall be Mirafi 140 or equivalent. Filter fabric shall be lapped a minimum of 12 inches in all joints.

Minimum 4-Inch-Diameter Pipe: ABS-ASTM D-2751, SDR 35; or ASTM D-1527 Schedule 40, PVC-ASTM D-3034, SDR 35; or ASTM D-1785 Schedule 40 with a crushing strength of 1,000 pounds minimum, and a minimum of 8 uniformly-spa per foot of pipe. Must be installed with perforations down at bottom of pipe. Provide cap at upstream end of pipe. Slope at 2 percent to outlet pipe. Outlet pipe to be connected to subdrain pipe with tee or elbow.


- Notes:**
1. Trench for outlet pipes to be backfilled and compacted with onsite soil.
 2. Backdrains and lateral drains shall be located at elevation of every bench drain. First drain located at elevation just above lower lot grade. Additional drains may be required at the discretion of the geotechnical consultant.

Filter Material shall be of the following specification or an approved equivalent.

Sieve Size	Percent Passing
1 inch	100
¾ inch	90-100
⅜ inch	40-100
No. 4	25-40
No. 8	18-33
No. 30	5-15
No. 50	0-7
No. 200	0-3


Gravel shall be of the following specification or an approved equivalent.

Sieve Size	Percent Passing
1½ inch	100
No. 4	50
No. 200	8




NOTES:

1. Where the natural slope approaches or exceeds the design slope ratio, special recommendations would be provided by the geotechnical consultant.
2. The need for and disposition of drains should be evaluated by the geotechnical consultant, based upon exposed conditions.




NOTE: The cut portion of the slope should be excavated and evaluated by the geotechnical consultant prior to construction of the fill portion.




NOTES: 1. Subdrains may be required as specified by the geotechnical consultant.


2. W shall be equipment width (15 feet) for slope heights less than 25 feet. For slopes greater than 25 feet, W shall be evaluated by the geotechnical consultant. At no time, shall W be less than $H/2$, where H is the height of the slope.




- NOTES:
1. 15-foot minimum to be maintained from proposed finish slope face to backcut.
 2. The need and disposition of drains will be evaluated by the geotechnical consultant based on field conditions.
 3. Pad overexcavation and recompaction should be performed if evaluated to be necessary by the geotechnical consultant.



- NOTES:
1. Subdrain and key width requirements will be evaluated based on exposed subsurface conditions and thickness of overburden.
 2. Pad overexcavation and recompaction should be performed if evaluated necessary by the geotechnical consultant.




CUT LOT OR MATERIAL-TYPE TRANSITION




CUT-FILL LOT (DAYLIGHT TRANSITION)

VIEW NORMAL TO SLOPE FACE



VIEW PARALLEL TO SLOPE FACE




NOTES:

- A. One equipment width or a minimum of 15 feet between rows (or windrows).
- B. Height and width may vary depending on rock size and type of equipment. Length of windrow shall be no greater than 100 feet.
- C. If approved by the geotechnical consultant, windrows may be placed directly on competent material or bedrock, provided adequate space is available for compaction.
- D. Orientation of windrows may vary but should be as recommended by the geotechnical engineer and/or engineering geologist. Staggering of windrows is not necessary unless recommended.
- E. Clear area for utility trenches, foundations, and swimming pools; Hold-down depth as specified in text of report, subject to governing agency approval.
- F. All fill over and around rock windrow shall be compacted to at least 95% compaction or as recommended.
- G. After fill between windrows is placed and compacted, with the lift of fill covering windrow, windrow should be proof rolled with a D-9 dozer or equivalent.


VIEWS ARE DIAGRAMMATIC ONLY AND MAY BE SUPERSEDED BY REPORT RECOMMENDATIONS OR CODE
ROCK SHOULD NOT TOUCH AND VOIDS SHOULD BE COMPLETELY FILLED

ROCK DISPOSAL PITS

Fill lifts compacted over rock after embedment







ROCK DISPOSAL LAYERS




* Hold-down depth or below lowest utility as specified in text of report, subject to governing agency approval.

** Clear zone for utility trenches, foundations, and swimming pools, as specified in text of report.

VIEWS ARE DIAGRAMMATIC ONLY AND MAY BE SUPERSEDED BY REPORT RECOMMENDATIONS OR CODE
ROCK SHOULD NOT TOUCH AND VOIDS SHOULD BE COMPLETELY FILLED IN




NOT TO SCALE



Gabion impact or diversion wall should be constructed at the base of the ascending slope subject to rock fall. Walls need to be constructed with high segments that sustain impact and mitigate potential for overtopping, and low segment that provides channelization of sediments and debris to desired depositional area for subsequent clean-out. Additional subdrain may be recommended by geotechnical consultant.


From GSA, 1987

NOT TO SCALE
SEE NOTES




CROSS SECTION VIEW

NOT TO SCALE
SEE NOTES




NOTES:

1. 6-inch-thick, clean gravel ($\frac{3}{4}$ to $1\frac{1}{2}$ inch) sub-base encapsulated in Mirafi 140N or equivalent, underlain by a 15-mil vapor retarder, with 4-inch-diameter perforated pipe longitudinal connected to 4-inch-diameter perforated pipe transverse. Connect transverse pipe to 4-inch-diameter nonperforated pipe at low point and outlet or to sump pump area.
2. Pools on fills thicker than 20 feet should be constructed on deep foundations; otherwise, distress (tilting, cracking, etc.) should be expected.
3. Design does not apply to infinity-edge pools/spas.




NOTES:

1. Locations of settlement plates should be clearly marked and readily visible (red flagged) to equipment operators.
2. Contractor should maintain clearance of a 5-foot radius of plate base and within 5 feet (vertical) for heavy equipment. Fill within clearance area should be hand compacted to project specifications or compacted by alternative approved method by the geotechnical consultant (in writing, prior to construction).
3. After 5 feet (vertical) of fill is in place, contractor should maintain a 5-foot radius equipment clearance from riser.
4. Place and mechanically hand compact initial 2 feet of fill prior to establishing the initial reading.
5. In the event of damage to the settlement plate or extension resulting from equipment operating within the specified clearance area, contractor should immediately notify the geotechnical consultant and should be responsible for restoring the settlement plates to working order.
6. An alternate design and method of installation may be provided at the discretion of the geotechnical consultant.



SIDE VIEW



TOP VIEW

